UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	ISSUE DATE	PATENT NO.	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	09/13/2016	9441453	SAFO/0012USP1	9598

26290 7590 08/24/2016

PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

ISSUE NOTIFICATION

The projected patent number and issue date are specified above.

Determination of Patent Term Adjustment under 35 U.S.C. 154 (b)
(application filed on or after May 29, 2000)

The Patent Term Adjustment is 177 day(s). Any patent to issue from the above-identified application will include an indication of the adjustment on the front page.

If a Continued Prosecution Application (CPA) was filed in the above-identified application, the filing date that determines Patent Term Adjustment is the filing date of the most recent CPA.

Applicant will be able to obtain more detailed information by accessing the Patent Application Information Retrieval (PAIR) WEB site (http://pair.uspto.gov).

Any questions regarding the Patent Term Extension or Adjustment determination should be directed to the Office of Patent Legal Administration at (571)-272-7702. Questions relating to issue and publication fee payments should be directed to the Application Assistance Unit (AAU) of the Office of Data Management (ODM) at (571)-272-4200.

APPLICANT(s) (Please see PAIR WEB site http://pair.uspto.gov for additional applicants):

David Lymberopoulos, Houston, TX;
Benjamin R. Matthews, Missouri City, TX;

The United States represents the largest, most dynamic marketplace in the world and is an unparalleled location for business investment, innovation, and commercialization of new technologies. The USA offers tremendous resources and advantages for those who invest and manufacture goods here. Through SelectUSA, our nation works to encourage and facilitate business investment. To learn more about why the USA is the best country in the world to develop technology, manufacture products, and grow your business, visit SelectUSA.gov.

IR103 (Rev. 10/09)

Doc Code: IFEE PTOL/85B-EFS

Document Description: Issue Fee Payment (PTO-85B)

Issue Fee Transmittal Form

Application Number	Filing Date	First Named Inventor	Atty. Docket No.	Confirmation No.
13480704	25-May-2012	David Lymberopoulos	SAFO/0012USP1	9598

TITLE OF INVENTION :

SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

Entity Status	Application Type	Art Unit	Class - Subclass	EXAMINER
Small	Utility under 35 USC 111(a)	3753	485000	WILLIAM MCCALISTER

Issue Fee Due	Publication Due	Total Fee(s) Due	Date Due	Prev. Paid Fee
$480	$0	$480	28-Sep-2016	$0

1.Change of Correspondence Address and/or Indication Of Fee Address (37 CFR 1.33 & 1.363)

Current Correspondence Address:	Current Indicated Fee Address :
26290 PATTERSON & SHERIDAN, L.L.P. 24 Greenway Plaza, Suite 1600 Houston TX 77046 UNITED STATES 713-623-4844 PSDocketing@pattersonsheridan.com	
☐ Change of correspondence address requested, system generated AIA/122-EFS form attached	☐ Fee Address indication requested, system generated SB/47-EFS form attached

2.Entity Status

Change in Entity Status

○ Applicant certifying micro entity status; system generated Micro Entity certification form attached. See 37 CFR 1.29.
Note: Absent a valid certification of micro entity status, issue fee payment in the micro entity amount will not be accepted at the risk of application abandonment. If this box is checked, you will be prompted to choose a micro entity status on the gross income basis (37 CFR 1.29(a)) or the institution of higher education basis (37 CFR 1.29(d)), and make the applicable certification online.

◉ Applicant asserting small entity status. See 37 CFR 1.27.
Note: If the application was previously under micro entity status, checking this box will be taken to be a notification of loss of entitlement to micro entity status.

○ Applicant changing to regular undiscounted fee status.
Note: Checking this box will be taken to be a notification of loss of entitlement to small or micro entity status, as applicable.

Doc Code: IFEE PTOL/85B-EFS

Document Description: Issue Fee Payment (PTO-85B)

3.The Following Fee(s) Are Submitted:

☒ Issue Fee	☐ I authorize USPTO to apply my previously paid issue fee to the current fees due
☐ Publication Fee	☐ The Director is hereby authorized to apply my previously paid issue fee to the current fee due and to charge deficient fees to Deposit Account Number _____
☐ Advance Order - # of copies _____	☒ If **in addition to** the payment of the issue fee amount submitted with this form, there are any discrepancies in any amount(s) due, the Director is authorized to charge any deficiency, or credit any overpayment, to Deposit Account Number 200782/SAFO0012U . The **issue fee must be submitted** with this form. **If payment of the issue fee does not accompany this form, checking this box and providing a deposit account number will NOT be effective to satisfy full payment of the fee(s) due.**

4.Firm and/or Attorney Names To Be Printed

NOTE: If no name is listed, no name will be printed
For printing on the patent front page, list to be displayed as entered

1.

2.

3.

5.Assignee Name(s) and Residence Data To Be Printed

PLEASE NOTE: Unless an assignee is identified below, no assignee data will appear on the patent. If an assignee is identified below, the document has been filed for recordation as set forth in 37 CFR 3.11. Completion of this form is NOT a substitute for filing an assignment.

Name	City	State	Country	Category
SAFOCO, INC.	Houston	TEXAS	united states	corporation

6.Signature

I certify, in accordance with 37 CFR 1.4(d)(4) that I am an attorney or agent registered to practice before the Patent and Trademark Office who has filed and has been granted power of attorney in this application. I also certify that this Fee(s) Transmittal form is being transmitted to the USPTO via EFS-WEB on the date indicated below.

Signature	/Jessie D. Herrera/	**Date**	08-10-2016
Name	Jessie D. Herrera	**Registration Number**	63799

WEB IFEE 1.0

Electronic Patent Application Fee Transmittal

Application Number:	13480704
Filing Date:	25-May-2012
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Filer:	Jessie D. Herrera/Stephanie Dominguez
Attorney Docket Number:	SAFO/0012USP1

Filed as Small Entity

Filing Fees for Utility under 35 USC 111(a)

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Basic Filing:				
Utility Appl Issue Fee	2501	1	480	480
Publ. Fee- Early, Voluntary, or Normal	1504	1	0	0
Pages:				
Claims:				
Miscellaneous-Filing:				
Petition:				
Patent-Appeals-and-Interference:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				
Miscellaneous:				
		Total in USD ($)		**480**

Electronic Acknowledgement Receipt	
EFS ID:	26599766
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Stephanie Dominguez
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	10-AUG-2016
Filing Date:	25-MAY-2012
Time Stamp:	12:29:59
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	CARD
Payment was successfully received in RAM	$480
RAM confirmation Number	081016INTEFSW12295600
Deposit Account	1101
Authorized User	Stephanie Dominguez
The Director of the USPTO is hereby authorized to charge indicated fees and credit any overpayment as follows:	

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Issue Fee Payment (PTO-85B)	Web85b.pdf	46156 051da5218e1d1e0ae143a3d836f44c9888d4bcdb	no	2
Warnings:					
Information:					
2	Fee Worksheet (SB06)	fee-info.pdf	32035 04baa9bef632c3aa8b8ebdeb5b0b86b1f4f9f2a7	no	2
Warnings:					
Information:					
		Total Files Size (in bytes):	78191		

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

NOTICE OF ALLOWANCE AND FEE(S) DUE

26290 7590 06/28/2016

PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

EXAMINER
MCCALISTER, WILLIAM M

ART UNIT	PAPER NUMBER
3753	

DATE MAILED: 06/28/2016

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

TITLE OF INVENTION: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

APPLN. TYPE	ENTITY STATUS	ISSUE FEE DUE	PUBLICATION FEE DUE	PREV. PAID ISSUE FEE	TOTAL FEE(S) DUE	DATE DUE
nonprovisional	SMALL	$480	$0	$0	$480	09/28/2016

THE APPLICATION IDENTIFIED ABOVE HAS BEEN EXAMINED AND IS ALLOWED FOR ISSUANCE AS A PATENT. PROSECUTION ON THE MERITS IS CLOSED. THIS NOTICE OF ALLOWANCE IS NOT A GRANT OF PATENT RIGHTS. THIS APPLICATION IS SUBJECT TO WITHDRAWAL FROM ISSUE AT THE INITIATIVE OF THE OFFICE OR UPON PETITION BY THE APPLICANT. SEE 37 CFR 1.313 AND MPEP 1308.

THE ISSUE FEE AND PUBLICATION FEE (IF REQUIRED) MUST BE PAID WITHIN THREE MONTHS FROM THE MAILING DATE OF THIS NOTICE OR THIS APPLICATION SHALL BE REGARDED AS ABANDONED. THIS STATUTORY PERIOD CANNOT BE EXTENDED. SEE 35 U.S.C. 151. THE ISSUE FEE DUE INDICATED ABOVE DOES NOT REFLECT A CREDIT FOR ANY PREVIOUSLY PAID ISSUE FEE IN THIS APPLICATION. IF AN ISSUE FEE HAS PREVIOUSLY BEEN PAID IN THIS APPLICATION (AS SHOWN ABOVE), THE RETURN OF PART B OF THIS FORM WILL BE CONSIDERED A REQUEST TO REAPPLY THE PREVIOUSLY PAID ISSUE FEE TOWARD THE ISSUE FEE NOW DUE.

HOW TO REPLY TO THIS NOTICE:

I. Review the ENTITY STATUS shown above. If the ENTITY STATUS is shown as SMALL or MICRO, verify whether entitlement to that entity status still applies.

If the ENTITY STATUS is the same as shown above, pay the TOTAL FEE(S) DUE shown above.

If the ENTITY STATUS is changed from that shown above, on PART B - FEE(S) TRANSMITTAL, complete section number 5 titled "Change in Entity Status (from status indicated above)".

For purposes of this notice, small entity fees are 1/2 the amount of undiscounted fees, and micro entity fees are 1/2 the amount of small entity fees.

II. PART B - FEE(S) TRANSMITTAL, or its equivalent, must be completed and returned to the United States Patent and Trademark Office (USPTO) with your ISSUE FEE and PUBLICATION FEE (if required). If you are charging the fee(s) to your deposit account, section "4b" of Part B - Fee(s) Transmittal should be completed and an extra copy of the form should be submitted. If an equivalent of Part B is filed, a request to reapply a previously paid issue fee must be clearly made, and delays in processing may occur due to the difficulty in recognizing the paper as an equivalent of Part B.

III. All communications regarding this application must give the application number. Please direct all communications prior to issuance to Mail Stop ISSUE FEE unless advised to the contrary.

IMPORTANT REMINDER: Utility patents issuing on applications filed on or after Dec. 12, 1980 may require payment of maintenance fees. It is patentee's responsibility to ensure timely payment of maintenance fees when due.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 8

PART B - FEE(S) TRANSMITTAL

Complete and send this form, together with applicable fee(s), to: Mail **Mail Stop ISSUE FEE**
Commissioner for Patents
P.O. Box 1450
Alexandria, Virginia 22313-1450
or Fax (571)-273-2885

INSTRUCTIONS: This form should be used for transmitting the ISSUE FEE and PUBLICATION FEE (if required). Blocks 1 through 5 should be completed where appropriate. All further correspondence including the Patent, advance orders and notification of maintenance fees will be mailed to the current correspondence address as indicated unless corrected below or directed otherwise in Block 1, by (a) specifying a new correspondence address; and/or (b) indicating a separate "FEE ADDRESS" for maintenance fee notifications.

CURRENT CORRESPONDENCE ADDRESS (Note: Use Block 1 for any change of address)

26290 7590 06/28/2016
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

Note: A certificate of mailing can only be used for domestic mailings of the Fee(s) Transmittal. This certificate cannot be used for any other accompanying papers. Each additional paper, such as an assignment or formal drawing, must have its own certificate of mailing or transmission.

Certificate of Mailing or Transmission
I hereby certify that this Fee(s) Transmittal is being deposited with the United States Postal Service with sufficient postage for first class mail in an envelope addressed to the Mail Stop ISSUE FEE address above, or being facsimile transmitted to the USPTO (571) 273-2885, on the date indicated below.

(Depositor's name)
(Signature)
(Date)

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

TITLE OF INVENTION: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

APPLN. TYPE	ENTITY STATUS	ISSUE FEE DUE	PUBLICATION FEE DUE	PREV. PAID ISSUE FEE	TOTAL FEE(S) DUE	DATE DUE
nonprovisional	SMALL	$480	$0	$0	$480	09/28/2016

EXAMINER	ART UNIT	CLASS-SUBCLASS
MCCALISTER, WILLIAM M	3753	137-485000

1. Change of correspondence address or indication of "Fee Address" (37 CFR 1.363).
- ❑ Change of correspondence address (or Change of Correspondence Address form PTO/SB/122) attached.
- ❑ "Fee Address" indication (or "Fee Address" Indication form PTO/SB/47; Rev 03-02 or more recent) attached. **Use of a Customer Number is required.**

2. For printing on the patent front page, list
(1) The names of up to 3 registered patent attorneys or agents OR, alternatively,
(2) The name of a single firm (having as a member a registered attorney or agent) and the names of up to 2 registered patent attorneys or agents. If no name is listed, no name will be printed.
1 _____
2 _____
3 _____

3. ASSIGNEE NAME AND RESIDENCE DATA TO BE PRINTED ON THE PATENT (print or type)

PLEASE NOTE: Unless an assignee is identified below, no assignee data will appear on the patent. If an assignee is identified below, the document has been filed for recordation as set forth in 37 CFR 3.11. Completion of this form is NOT a substitute for filing an assignment.

(A) NAME OF ASSIGNEE (B) RESIDENCE: (CITY and STATE OR COUNTRY)

Please check the appropriate assignee category or categories (will not be printed on the patent) : ❑ Individual ❑ Corporation or other private group entity ❑ Government

4a. The following fee(s) are submitted:
- ❑ Issue Fee
- ❑ Publication Fee (No small entity discount permitted)
- ❑ Advance Order - # of Copies _____

4b. Payment of Fee(s): **(Please first reapply any previously paid issue fee shown above)**
- ❑ A check is enclosed.
- ❑ Payment by credit card. Form PTO-2038 is attached.
- ❑ The director is hereby authorized to charge the required fee(s), any deficiency, or credits any overpayment, to Deposit Account Number _____ (enclose an extra copy of this form).

5. **Change in Entity Status** (from status indicated above)
- ❑ Applicant certifying micro entity status. See 37 CFR 1.29 — NOTE: Absent a valid certification of Micro Entity Status (see forms PTO/SB/15A and 15B), issue fee payment in the micro entity amount will not be accepted at the risk of application abandonment.
- ❑ Applicant asserting small entity status. See 37 CFR 1.27 — NOTE: If the application was previously under micro entity status, checking this box will be taken to be a notification of loss of entitlement to micro entity status.
- ❑ Applicant changing to regular undiscounted fee status. — NOTE: Checking this box will be taken to be a notification of loss of entitlement to small or micro entity status, as applicable.

NOTE: This form must be signed in accordance with 37 CFR 1.31 and 1.33. See 37 CFR 1.4 for signature requirements and certifications.

Authorized Signature _____ Date _____

Typed or printed name _____ Registration No. _____

PTOL-85 Part B (10-13) Approved for use through 10/31/2013. OMB 0651-0033 U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 9

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

26290 7590 06/28/2016
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

EXAMINER	
MCCALISTER, WILLIAM M	
ART UNIT	PAPER NUMBER
3753	

DATE MAILED: 06/28/2016

Determination of Patent Term Adjustment under 35 U.S.C. 154 (b)
(Applications filed on or after May 29, 2000)

The Office has discontinued providing a Patent Term Adjustment (PTA) calculation with the Notice of Allowance.

Section 1(h)(2) of the AIA Technical Corrections Act amended 35 U.S.C. 154(b)(3)(B)(i) to eliminate the requirement that the Office provide a patent term adjustment determination with the notice of allowance. See Revisions to Patent Term Adjustment, 78 Fed. Reg. 19416, 19417 (Apr. 1, 2013). Therefore, the Office is no longer providing an initial patent term adjustment determination with the notice of allowance. The Office will continue to provide a patent term adjustment determination with the Issue Notification Letter that is mailed to applicant approximately three weeks prior to the issue date of the patent, and will include the patent term adjustment on the patent. Any request for reconsideration of the patent term adjustment determination (or reinstatement of patent term adjustment) should follow the process outlined in 37 CFR 1.705.

Any questions regarding the Patent Term Extension or Adjustment determination should be directed to the Office of Patent Legal Administration at (571)-272-7702. Questions relating to issue and publication fee payments should be directed to the Customer Service Center of the Office of Patent Publication at 1-(888)-786-0101 or (571)-272-4200.

OMB Clearance and PRA Burden Statement for PTOL-85 Part B

The Paperwork Reduction Act (PRA) of 1995 requires Federal agencies to obtain Office of Management and Budget approval before requesting most types of information from the public. When OMB approves an agency request to collect information from the public, OMB (i) provides a valid OMB Control Number and expiration date for the agency to display on the instrument that will be used to collect the information and (ii) requires the agency to inform the public about the OMB Control Number's legal significance in accordance with 5 CFR 1320.5(b).

The information collected by PTOL-85 Part B is required by 37 CFR 1.311. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, Virginia 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, Virginia 22313-1450. Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether disclosure of these records is required by the Freedom of Information Act.
2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.
3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.
4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).
5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.
6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).
7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.
8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspection or an issued patent.
9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

Notice of Allowability	Application No. 13/480,704	Applicant(s) LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	AIA (First Inventor to File) Status No

-- The MAILING DATE of this communication appears on the cover sheet with the correspondence address--

All claims being allowable, PROSECUTION ON THE MERITS IS (OR REMAINS) CLOSED in this application. If not included herewith (or previously mailed), a Notice of Allowance (PTOL-85) or other appropriate communication will be mailed in due course. **THIS NOTICE OF ALLOWABILITY IS NOT A GRANT OF PATENT RIGHTS.** This application is subject to withdrawal from issue at the initiative of the Office or upon petition by the applicant. See 37 CFR 1.313 and MPEP 1308.

1. ☒ This communication is responsive to *the amendment of 5/4/16*.
   ☐ A declaration(s)/affidavit(s) under **37 CFR 1.130(b)** was/were filed on_____.
2. ☐ An election was made by the applicant in response to a restriction requirement set forth during the interview on _____; the restriction requirement and election have been incorporated into this action.
3. ☒ The allowed claim(s) is/are *1-6,8-15 and 17-20*. As a result of the allowed claim(s), you may be eligible to benefit from the **Patent Prosecution Highway** program at a participating intellectual property office for the corresponding application. For more information, please see http://www.uspto.gov/patents/init_events/pph/index.jsp or send an inquiry to PPHfeedback@uspto.gov .
4. ☐ Acknowledgment is made of a claim for foreign priority under 35 U.S.C. § 119(a)-(d) or (f).

   Certified copies:

   a) ☐ All b) ☐ Some *c) ☐ None of the:
      1. ☐ Certified copies of the priority documents have been received.
      2. ☐ Certified copies of the priority documents have been received in Application No. _____ .
      3. ☐ Copies of the certified copies of the priority documents have been received in this national stage application from the International Bureau (PCT Rule 17.2(a)).

   * Certified copies not received: _____.

Applicant has THREE MONTHS FROM THE "MAILING DATE" of this communication to file a reply complying with the requirements noted below. Failure to timely comply will result in ABANDONMENT of this application.
THIS THREE-MONTH PERIOD IS NOT EXTENDABLE.

5. ☐ CORRECTED DRAWINGS (as "replacement sheets") must be submitted.
   ☐ including changes required by the attached Examiner's Amendment / Comment or in the Office action of Paper No./Mail Date _____.

   Identifying indicia such as the application number (see 37 CFR 1.84(c)) should be written on the drawings in the front (not the back) of each sheet. Replacement sheet(s) should be labeled as such in the header according to 37 CFR 1.121(d).
6. ☐ DEPOSIT OF and/or INFORMATION about the deposit of BIOLOGICAL MATERIAL must be submitted. Note the attached Examiner's comment regarding REQUIREMENT FOR THE DEPOSIT OF BIOLOGICAL MATERIAL.

Attachment(s)

1. ☐ Notice of References Cited (PTO-892)
2. ☐ Information Disclosure Statements (PTO/SB/08), Paper No./Mail Date _____
3. ☐ Examiner's Comment Regarding Requirement for Deposit of Biological Material
4. ☐ Interview Summary (PTO-413), Paper No./Mail Date _____ .
5. ☒ Examiner's Amendment/Comment
6. ☐ Examiner's Statement of Reasons for Allowance
7. ☐ Other _____.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

The present application is being examined under the pre-AIA first to invent provisions.

EXAMINER'S AMENDMENT

An examiner's amendment to the record appears below. Should the changes and/or additions be unacceptable to applicant, an amendment may be filed as provided by 37 CFR 1.312. To ensure consideration of such an amendment, it MUST be submitted no later than the payment of the issue fee.

Authorization for this examiner's amendment was given in a telephone interview with Jessie Herrera on 6/9/16.

The application has been amended as follows:

IN THE CLAIMS:

Claim 21 is cancelled.

Claim 21 is cancelled to place the application in condition for allowance by obviating a restriction requirement between claim 21 and the remaining claims.

Election/Restrictions

Claims 1 and 12 are allowable. The restriction requirement between fluid species, as set forth in the Office action mailed on 3/18/14, has been reconsidered in

view of the allowability of claims to the elected invention pursuant to MPEP § 821.04(a). **The restriction requirement is hereby withdrawn as to any claim that requires all the limitations of an allowable claim.** Claims 4, 9, 13 and 17, directed to a non-elected species are no longer withdrawn from consideration because the claim(s) requires all the limitations of an allowable claim.

In view of the above noted withdrawal of the restriction requirement, applicant is advised that if any claim presented in a continuation or divisional application is anticipated by, or includes all the limitations of, a claim that is allowable in the present application, such claim may be subject to provisional statutory and/or nonstatutory double patenting rejections over the claims of the instant application.

Once a restriction requirement is withdrawn, the provisions of 35 U.S.C. 121 are no longer applicable. See In re Ziegler, 443 F.2d 1211, 1215, 170 USPQ 129, 131-32 (CCPA 1971). See also MPEP § 804.01.

(Regarding the present restriction requirement, claim 21 as amended on 5/4/16 is two-way distinct from the remaining claims as amended on 5/4/16, in that only claim 21 requires a positively-recited step of pumping fluid to a well, and only the remaining claims require a fluid supply, first fluid line, pump, and second fluid line. Also a serious search burden exists because of different fields of search, including separate classes, subclasses and key words directed to the distinct features.)

Any inquiry concerning this communication or earlier communications from the examiner should be directed to **William McCalister**, whose telephone number **571-270-1869**. The examiner can normally be reached on Monday-Friday (7:00AM-5:30PM EST).

If attempts to reach the examiner by telephone are unsuccessful, the examiner's supervisors can be reached by phone. Craig Schneider can be reached at 571-272-3607, John Fristoe can be reached at 571-272-4926 and Mary McManmon can be reached at 571-272-6007. The fax phone number for the organization where this application or proceeding is assigned is 571-273-8300.

Information regarding the status of an application may be obtained from the Patent Application Information Retrieval (PAIR) system. Status information for published applications may be obtained from either Private PAIR or Public PAIR. Status information for unpublished applications is available through Private PAIR only. For more information about the PAIR system, see http://pair-direct.uspto.gov. Should you have questions on access to the Private PAIR system, contact the Electronic Business Center (EBC) at 866-217-9197 (toll-free). If you would like assistance from a USPTO Customer Service Representative or access to the automated information system, call 800-786-9199 (IN USA OR CANADA) or 571-272-1000.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

6/9/16

EAST Search History

EAST Search History (Prior Art)

Ref #	Hits	Search Query	DBs	Default Operator	Plurals	Time Stamp
L1	13041	E21B34/06,02,10,16.CPC.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2016/06/09 10:52
L2	2505	y10t137/7761.cpc.	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/09 10:57
L3	4130	e21b34/02,10,16,06.cpc.	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/09 10:57
L4	272	f15b20/00,31576,6303,665,7052,0091,1262.cpc.	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/09 10:58
L5	6886	l1 or l2 or l3 or l4	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/09 10:58
L6	1	13/480704	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/09 11:03
S1	1	13/480704	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 12:52
S2	626	137/492.5.ccls.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:17
S3	170	S2 and (pump or compressor)	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:17
S5	138	S2 and pump	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:18

S6	44	("6349772" | "20100154894" | "20020108747" | "20020112632" | "20060159569" | "20110036415" | "20110240126" | "5275086" | "6772718" | "4082147" | "6199629" | "3741116" | "5335730" | "6435282" | "20100025045" | "20110094752" | "20020124889" | "4213480" | "5273113" | "5526883" | "6854704" | "7004445" | "20130008519" | "20130008519" | "20120031494" | "20050236594" | "4667570" | "5490564" | "6412510" | "RE39583" | "6296052" | "4215746" | "5684451" | "20050087712" | "3788341" | "4527429" | "5097857" | "5132904" | "6450477" | "7231971" | "20100154894" | "20090126798" | "4461449" | "20040135112" | "20110094752" | "6633236" | "7635029").PN.	US-PGPUB; USPAT	OR	OFF	2014/07/02 13:18
S7	15	S2 and (pump near3 (command$4 or control$4)) and (pressure near3 (sens$4 or transduc$4))	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:25
S8	626	137/492.5.ccls.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 16:51
S9	72	S8 and pump and hydraulic	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 16:51
S10	12	("3788341" | "4335744" | "4337788" | "4461450" | "4503878").PN. OR ("4774980").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/02 17:00
S11	21	("1223326" | "3225785" | "4037619" | "4414882" | "4431159" | "4585205" | "4613111" | "4774980" | "4778351" | "5094267" | "5158108" | "5158230" | "5197328" | "5318272" | "5431182" | "5460196").PN. OR ("6202681").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/02 17:01
S12	3	("2010/0154894").URPN.	USPAT	OR	OFF	2014/07/03 13:51
S13	19	("2132132" | "2203243" | "3227171" | "3367355" | "3467129").PN. OR ("3788341").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/03 13:53
S14	11	("3788341" | "4186766" | "4240463" | "4319603" | "5293910" | "5396923").PN. OR ("7044156").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/03 13:54
S15	18	(US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-	US-PGPUB; USPAT	OR	OFF	2014/07/03 14:01

		7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.				
S16	6	S15 and control$4 near4 pump	US-PGPUB; USPAT	OR	OFF	2014/07/03 14:01
S17	18	(US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.	US-PGPUB; USPAT	OR	OFF	2014/07/07 07:40
S18	7	S17 and pump	USPAT	OR	OFF	2014/07/07 07:40
S19	10	S17 and pump	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/07 07:40
S20	12	("3788341" | "4335744" | "4337788" | "4461450" | "4503878").PN. OR ("4774980").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 08:55
S21	8	("5341837" | "5526883").PN. OR ("6116268").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:01
S22	313	137/492,492.5.ccls. and well	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:06
S23	61	137/492,492.5.ccls. and well and controller	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:06
S24	5	11/426109	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:10
S25	10	("2006/0219299").URPN.	USPAT	OR	OFF	2014/07/07 09:12
S26	10	"6450477"	USPAT	OR	OFF	2014/07/07 09:19
S27	20	(US-20060219299-$ or US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6056008-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.	US-PGPUB; USPAT	OR	OFF	2014/07/07 12:21
S28	9	S27 and pump with control$4	US-PGPUB; USPAT	OR	OFF	2014/07/07 12:21
S29	12	S27 and housing	US-PGPUB; USPAT	OR	OFF	2014/07/07 12:25
S30	20	(US-20060219299-$ or US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6056008-$ or US-	US-PGPUB; USPAT	OR	OFF	2014/07/07 14:46

		6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.				
S31	16	S30 and hydraulic	US-PGPUB; USPAT	OR	OFF	2014/07/07 14:46
S32	9	S30 and hydraulic and pump	US-PGPUB; USPAT	OR	OFF	2014/07/07 15:12
S33	592	g05d16/2086.cpc.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/07 15:44
S34	2283	f16k17/00.cpc.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/07 15:55
S35	20	(US-20060219299-$ or US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6056008-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.	US-PGPUB; USPAT	OR	OFF	2015/03/19 08:04
S36	10	S35 and gate	USPAT	OR	OFF	2015/03/19 08:05
S37	13	S35 and gate	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/03/19 08:05
S38	30	("1893462" | "1918891" | "2203243" | "2278952" | "2637946" | "2707483" | "3227171" | "3788341" | "3991784").PN. OR ("4240463").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:09
S39	5	S38 and gate	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:10
S40	21	("2132132" | "2203243" | "3227171" | "3367355" | "3467129").PN. OR ("3788341").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:11
S41	5	S40 and gate	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:12
S42	432	137/487.5,488.ccls. and safety and (oil or gas or pipeline or well or wellhead)	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:16
S43	80	137/487.5,488.ccls. and safety and (oil or gas or pipeline or well or wellhead) and gate	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:17

S44	38	("3198207" | "3252476" | "3338302" | "3389718" | "3452592" | "3712129" | "3898877" | "3920040" | "3963050" | "4046006" | "Re29638").PN. OR ("4230187").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:26
S45	0	S44 and gate	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:26
S46	1	13/480704	US-PGPUB; USPAT; USOCR	OR	OFF	2015/03/19 08:56
S47	1	"5335730".pn.	USPAT	OR	OFF	2015/03/19 08:58
S48	0	"20030051881"	USPAT	OR	OFF	2015/03/19 08:59
S49	11	"20030051881"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/03/19 08:59
S50	1	"5335730".pn.	USPAT	OR	OFF	2015/03/19 09:46
S51	39	137/488,492,492.5.ccls. and @pd>"20141215"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/03/19 13:09
S52	0	g05d16/2086.ccls. and @pd>"20141215"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/03/19 13:10
S53	0	g05d17/00.ccls. and @pd>"20141215"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/03/19 13:10
S54	651	137/492.5.ccls.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/25 12:35
S55	50	S54 and (bias$3 near4 open$3)	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/25 12:36
S56	30	("1893462" | "1918891" | "2203243" | "2278952" | "2637946" | "2707483" | "3227171"	US-PGPUB; USPAT;	OR	OFF	2015/06/25 13:01

		| "3788341" | "3991784").PN. OR ("4240463").URPN.	USOCR			
S57	14	("4240463" | "4285362" | "4319603" | "4328672" | "4617958" | "4671319" | "5029609" | "5425396" | "5590685" | "5687759").PN. OR ("5758686").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/06/25 13:39
S58	30	("1893462" | "1918891" | "2203243" | "2278952" | "2637946" | "2707483" | "3227171" | "3788341" | "3991784").PN. OR ("4240463").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/06/25 13:42
S59	9	("3613070" | "4087073" | "4240463" | "4649704" | "4687014" | "6332315").PN. OR ("6729130").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/06/25 13:42
S60	12	("3788341" | "4186766" | "4240463" | "4319603" | "5293910" | "5396923").PN. OR ("7044156").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/06/25 13:43
S61	11	("4091832" | "4240463").PN. OR ("4319603").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2015/06/25 13:44
S62	77	S54 and (normal$3 near4 open$3)	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/25 13:49
S63	41	137/488,492,492.5.ccls. and @pd>"20150301"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/26 14:10
S64	0	g05d16/2086.ccls. and @pd>"20150301"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/26 14:11
S65	0	g05d17/00.ccls. and @pd>"20150301"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/26 14:11
S66	0	Hoogerhyde.in. near2 Eric.in.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/29 08:45
S67	0	14/277478	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT	OR	OFF	2015/06/29 08:51

			IBM_TDB			
S68	4	"5271428".pn.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/29 10:10
S69	1	13/480704	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/12/29 10:46
S70	81	(G05D16/2086.CPC. OR F16K17/00.CPC.) AND @PD>"20150601"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/12/29 14:01
S71	1	13/345660	USPAT	OR	OFF	2016/06/06 13:10
S72	2	13/345660	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2016/06/06 13:10
S73	1	13/645660	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2016/06/06 13:11
S74	1627	g05d16/2086.cpc. or f16k17/00.cpc. or 137/488,492,492.5.ccls. and @pd>"20140707"	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/08 12:32
S75	2377	y10t137/7762,7769,777.cpc.	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/08 12:33
S76	2377	y10t137/7762,7769,777.cpc.	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/08 13:36
S77	279	S76 not 137/488,492,492.5.ccls.	US-PGPUB; USPAT; USOCR	OR	OFF	2016/06/08 13:36

EAST Search History (Interference)

Ref #	Hits	Search Query	DBs	Default Operator	Plurals	Time Stamp
L7	0	(fluid and supply and first and line and pump and second and downstream and return and safety and valve and controller and actuator and drive and gate).clm.	US-PGPUB; USPAT	OR	OFF	2016/06/09 11:43

6/9/2016 12:25:08 PM
C:\Users\wmccalister\Documents\EAST\Workspaces\13480704.wsp

Issue Classification	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	**Art Unit**
	WILLIAM MCCALISTER	3753

CPC							
Symbol						**Type**	**Version**
E21B		34	/	06		F	2013-01-01
Y10T		137	/	7761		A	2015-04-01
Y10T		137	/	0318		A	2015-04-01
Y10T		137	/	7762		A	2015-04-01
Y10T		137	/	7769		A	2015-04-01
Y10T		137	/	777		A	2015-04-01
E21B		34	/	02		I	2013-01-01
E21B		34	/	10		I	2013-01-01
E21B		34	/	16		I	2013-01-01
F15B		20	/	00		I	2013-01-01
F15B		2211	/	31576		A	2013-01-01
F15B		2211	/	6303		A	2013-01-01
F15B		2211	/	665		A	2013-01-01
F15B		2211	/	7052		A	2013-01-01
F16K		37	/	0091		I	2013-01-01
F16K		31	/	1262		I	2013-01-01

CPC Combination Sets								
Symbol					**Type**	**Set**	**Ranking**	**Version**
			/					
			/					

NONE		Total Claims Allowed:	
(Assistant Examiner)	(Date)	18	
/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753	06/09/2016	O.G. Print Claim(s)	O.G. Print Figure
(Primary Examiner)	(Date)	1	14

Issue Classification	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	**Art Unit**
	WILLIAM MCCALISTER	3753

US ORIGINAL CLASSIFICATION		INTERNATIONAL CLASSIFICATION										
CLASS	SUBCLASS	CLAIMED					NON-CLAIMED					
		E	2	1	B	34 / 06 (2006.01.01)						
CROSS REFERENCE(S)												
CLASS	SUBCLASS (ONE SUBCLASS PER BLOCK)											

NONE		Total Claims Allowed:	
(Assistant Examiner)	(Date)	18	
/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753	06/09/2016	O.G. Print Claim(s)	O.G. Print Figure
(Primary Examiner)	(Date)	1	14

U.S. Patent and Trademark Office

Part of Paper No. 20160606

Issue Classification	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	**Art Unit**
	WILLIAM MCCALISTER	3753

☒ Claims renumbered in the same order as presented by applicant ☐ CPA ☐ T.D. ☐ R.1.47

Final	Original	Final	Original	Final	Original	Final	Original	Final	Original	Final	Original	Final	Original	Final	Original

NONE (Assistant Examiner)	(Date)	**Total Claims Allowed:** 18	
/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753 (Primary Examiner)	06/09/2016 (Date)	O.G. Print Claim(s) 1	O.G. Print Figure 14

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 26

Search Notes	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	Art Unit
	WILLIAM MCCALISTER	3753

CPC- SEARCHED		
Symbol	Date	Examiner
G05D 16/2086 good for electrical controls for a fluid pilot valve that controls a main valve	7/7/2014	WM
F16K 17/00 this invention meets the definition of "safety" but this subclass is very large and includes a lot of irrelevant art	7/7/2014	WM
E21B34/02,06,10,16	6/9/2016	WM
Y10T137/7761, 7762, 7769, 777, 0318	6/9/2016	WM
F15B 20/00; 2211/31576, 6303, 665, 7052	6/9/2016	WM
F16K 37/0091; 31/1262	6/9/2016	WM

CPC COMBINATION SETS - SEARCHED		
Symbol	Date	Examiner

US CLASSIFICATION SEARCHED			
Class	Subclass	Date	Examiner
137	488, 492, 492.5	7/7/2014	wm

SEARCH NOTES		
Search Notes	Date	Examiner
updated ccls and cpc searches	3/19/2015	WM
UPDATED SEARCH	6/26/2015	WM
UPDATED SEARCH	12/29/2015	WM
UPDATED SEARCH, additional cpc indicated above	6/9/2016	WM

INTERFERENCE SEARCH			
US Class/ CPC Symbol	US Subclass / CPC Group	Date	Examiner
F16K	17/00; 37/0091; 31/1262	6/9/2016	WM
G05D	16/2086	6/9/2016	WM

	/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 27

INTERFERENCE SEARCH			
US Class/ CPC Symbol	**US Subclass / CPC Group**	**Date**	**Examiner**
Y10T	137/7761, 7762, 7769, 777, 0318	6/9/2016	WM
F15B	20/00; 2211/31576, 6303, 665, 7052	6/9/2016	WM
E21B	34/02,06,10,16	6/9/2016	WM
	see interference search history		

	/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753

PTO/SB/06 (09-11)
Approved for use through 1/31/2014. OMB 0651-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PATENT APPLICATION FEE DETERMINATION RECORD Substitute for Form PTO-875	Application or Docket Number 13/480,704	Filing Date 05/25/2012	☐ To be Mailed

ENTITY: ☐ LARGE ☒ SMALL ☐ MICRO

APPLICATION AS FILED – PART I

FOR	(Column 1) NUMBER FILED	(Column 2) NUMBER EXTRA	RATE ($)	FEE ($)
☐ BASIC FEE (37 CFR 1.16(a), (b), or (c))	N/A	N/A	N/A	
☐ SEARCH FEE (37 CFR 1.16(k), (i), or (m))	N/A	N/A	N/A	
☐ EXAMINATION FEE (37 CFR 1.16(o), (p), or (q))	N/A	N/A	N/A	
TOTAL CLAIMS (37 CFR 1.16(i))	minus 20 =	*	X $ =	
INDEPENDENT CLAIMS (37 CFR 1.16(h))	minus 3 =	*	X $ =	
☐ APPLICATION SIZE FEE (37 CFR 1.16(s))	If the specification and drawings exceed 100 sheets of paper, the application size fee due is $310 ($155 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).			
☐ MULTIPLE DEPENDENT CLAIM PRESENT (37 CFR 1.16(j))				
* If the difference in column 1 is less than zero, enter "0" in column 2.			TOTAL	

APPLICATION AS AMENDED – PART II

AMENDMENT 05/04/2016	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
Total (37 CFR 1.16(i))	* 19	Minus	** 20	= 0	X $40 =	0
Independent (37 CFR 1.16(h))	* 3	Minus	*** 3	= 0	X $210 =	0
☐ Application Size Fee (37 CFR 1.16(s))						
☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
					TOTAL ADD'L FEE	0

AMENDMENT	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
Total (37 CFR 1.16(i))	*	Minus	**	=	X $ =	
Independent (37 CFR 1.16(h))	*	Minus	***	=	X $ =	
☐ Application Size Fee (37 CFR 1.16(s))						
☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
					TOTAL ADD'L FEE	

* If the entry in column 1 is less than the entry in column 2, write "0" in column 3.

** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 20, enter "20".

*** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 3, enter "3".

The "Highest Number Previously Paid For" (Total or Independent) is the highest number found in the appropriate box in column 1.

LIE
/MARCUS MONROE/

This collection of information is required by 37 CFR 1.16. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

PTO/SB/30EFS (07-14)
Approved for use through 07/31/2016. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

REQUEST FOR CONTINUED EXAMINATION(RCE)TRANSMITTAL
(Submitted Only via EFS-Web)

Application Number	13480704	Filing Date	2012-05-25	Docket Number (if applicable)	SAFO/0012USP1	Art Unit	3753
First Named Inventor	David LYMBEROPOULOS			Examiner Name	W. M. McCalister		

This is a Request for Continued Examination (RCE) under 37 CFR 1.114 of the above-identified application.
Request for Continued Examination (RCE) practice under 37 CFR 1.114 does not apply to any utility or plant application filed prior to June 8, 1995, to any international application that does not comply with the requirements of 35 U.S.C. 371, or to any design application. The Instruction Sheet for this form is located at WWW.USPTO.GOV.

SUBMISSION REQUIRED UNDER 37 CFR 1.114

Note: If the RCE is proper, any previously filed unentered amendments and amendments enclosed with the RCE will be entered in the order in which they were filed unless applicant instructs otherwise. If applicant does not wish to have any previously filed unentered amendment(s) entered, applicant must request non-entry of such amendment(s).

☐ Previously submitted. If a final Office action is outstanding, any amendments filed after the final Office action may be considered as a submission even if this box is not checked.

- ☐ Consider the arguments in the Appeal Brief or Reply Brief previously filed on _____
- ☐ Other _____

☒ Enclosed

- ☒ Amendment/Reply
- ☐ Information Disclosure Statement (IDS)
- ☐ Affidavit(s)/ Declaration(s)
- ☐ Other _____

MISCELLANEOUS

☐ Suspension of action on the above-identified application is requested under 37 CFR 1.103(c) for a period of months _____ (Period of suspension shall not exceed 3 months; Fee under 37 CFR 1.17(i) required)

☐ Other _____

FEES

☒ **The RCE fee under 37 CFR 1.17(e) is required by 37 CFR 1.114 when the RCE is filed.**
The Director is hereby authorized to charge any underpayment of fees, or credit any overpayments, to Deposit Account No 20-0782

SIGNATURE OF APPLICANT, ATTORNEY, OR AGENT REQUIRED

☒ Patent Practitioner Signature

Applicant Signature

PTO/SB/30EFS (07-14)
Approved for use through 07/31/2016. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

Signature of Registered U.S. Patent Practitioner			
Signature	/Jessie D. Herrera/	Date (YYYY-MM-DD)	2016-05-04
Name	Jessie D. Herrera	Registration Number	63799

This collection of information is required by 37 CFR 1.114. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.11 and 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450.

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these records.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: David Lymberopoulos et al.	§	
Serial No.: 13/480,704	§	Group Art Unit: 3753
Filed: May 25, 2012	§	Examiner: McCalister, William M.
Confirmation No.: 9598	§	
For: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE	§	

MAIL STOP AF
Commissioner for Patents
P.O. Box 1450
Alexandria, VA 22313-1450

Dear Sir:

RESPONSE TO FINAL OFFICE ACTION DATED JANUARY 4, 2016

In response to the Final Office Action dated January 4, 2016, please enter this response and reconsider the claims pending in the application for the reasons discussed below. Although Applicant believes that no additional fees are due in connection with this response, the Commissioner is hereby authorized to charge counsel's Deposit Account No. 20-0782/SAFO/0012USP1/JDH for any fees required to make this response timely and acceptable to the Office.

Amendments to the Claims begin on page 2 of this paper.

Remarks begin on page 7 of this paper.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 33

AMENDMENTS TO THE CLAIMS

1. (Currently Amended) A control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a fluid supply;

a first fluid line in fluid communication with the fluid supply;

a pump in fluid communication with the first fluid line and configured to pump fluid from the fluid supply to one or more wellheads through the first fluid line;

a second fluid line in fluid communication with the first fluid line at a location downstream of the pump and configured to return fluid from the first fluid line to the fluid supply;

a safety valve in-line with the second fluid line and having a gate normally maintained in a closed positon to close fluid flow through the ~~flow~~ second fluid line;

a valve actuator configured to move the gate into the closed position by fluid supplied into the valve actuator and configured to move the gate into an open position by a biasing member disposed in the valve actuator;

an electronic controller assembly programmed with a predetermined condition and configured to receive a signal from a transducer connected to the ~~flow~~ first fluid line, wherein the signal corresponds to a measured physical property;

a valve assembly in communication with the controller assembly; and

a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid into the valve actuator to move the gate into the closed position, and wherein the controller assembly is operable to actuate the valve assembly in response to a comparison of the measured physical property to the predetermined condition to release the fluid from the valve actuator so that the biasing member moves the gate into the open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the ~~flow~~ second fluid line to return fluid in the first fluid line back to the fluid supply.

2. (Original) The system of claim 1, further comprising a housing for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

3. (Previously Presented) The system of claim 2, wherein the fluid supplied into the valve actuator by the fluid drive assembly is supplied from a reservoir disposed outside of the housing.

4. (Withdrawn) The system of claim 1, wherein the fluid drive assembly is a compressor and the fluid is a pneumatic fluid.

5. (Previously Presented) The system of claim 1, wherein the fluid drive assembly is a pump and the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid.

6. (Original) The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly.

7. (Canceled)

8. (Original) The system of claim 1, further comprising a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly.

9. (Withdrawn-Currently Amended) The system of claim 1, wherein the fluid supplied into the valve actuator by the fluid drive assembly is ambient air.

10. (Original) The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system.

11. (Previously Presented) The system of claim 1, wherein the controller assembly is a programmable logic controller.

12. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising:

a fluid supply;

a first fluid line in fluid communication with the fluid supply;

a pump in fluid communication with the first fluid line and configured to pump fluid from the fluid supply to one or more wellheads through the first fluid line;

a second fluid line in fluid communication with the first fluid line at a location downstream of the pump and configured to return fluid from the first fluid line to the fluid supply;

a safety valve in-line with the second fluid line and having a gate,

a valve actuator configured to move the gate,

a housing,

an electronic controller assembly,

a fluid drive assembly, and

a valve assembly;

supplying fluid into the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into a closed position~~, wherein the gate is normally maintained in the closed position to close fluid flow through the flow line~~;

maintaining the gate in the closed position to close fluid flow through the second fluid line;

monitoring a physical property in the ~~flow~~ first fluid line using the controller assembly; and

actuating the valve assembly using the controller assembly to release the fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the ~~flow~~ second fluid line based upon a comparison of the

monitored physical property to a predetermined condition to return fluid from the first fluid line back to the fluid supply.

13. (Withdrawn-Currently Amended) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a pneumatic fluid disposed external to the housing, and further comprising filtering the pneumatic fluid as it enters the housing by the fluid drive assembly.

14. (Previously Presented) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid disposed in a reservoir within the housing that is in fluid communication with the fluid drive assembly.

15. (Original) The method of claim 12, further comprising measuring the physical property using a transducer configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. (Canceled)

17. (Withdrawn-Currently Amended) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a pneumatic fluid, and wherein the fluid drive assembly is a compressor.

18. (Previously Presented) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid, and wherein the fluid drive assembly is a pump.

19. (Original) The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve.

20. (Original) The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly.

21. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a pump, a reservoir, a safety valve having a gate in-line with the flow line, a valve actuator configured to move the gate, and a sensor;

actuating the valve actuator to move the gate into a closed position by ~~supplying~~ pumping actuator fluid from the reservoir into the valve actuator using the pump~~, wherein the gate is normally maintained in the closed position to close fluid flow through the flow line~~;

maintaining the gate in the closed position to close fluid flow through the flow line;

pumping fluid through the flow line to at least one wellhead of a well to conduct a fracturing operation;

monitoring fluid pressure in the flow line using the sensor while maintaining the gate in the closed position; and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position, forces the actuator fluid out of the valve actuator and back into the reservoir, and thereby ~~opens~~ dumps fluid flowing through the flow line to relieve fluid pressure in the flow line.

REMARKS

This is intended as a full and complete response to the Office Action dated January 4, 2016. Claims 1-6, 8-15, and 17-21 are pending in the application. Claims 4, 9, 13, and 17 stand withdrawn. Claims 1-3, 5-6, 8, 10-12, 14-15, and 18-21 stand rejected. Reconsideration of the rejected claims is requested for the reasons presented below.

Claim Rejections Under 35 U.S.C. § 103

Claims 1, 5, 6, 12, 15, 18, and 21 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Wailes* (US 3,776,249) in view of *Moore* (US 4,240,463).

Claims 1, 5, 6, 12, 15, 18, and 21 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Moore* in view of *Wailes*.

Claims 2, 3, 14, and 20 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Wailes* in view of *Moore* (alternatively, over *Moore* in view of *Wailes*) as applied to claims 1 and 12 above, and further in view of *Vinegar* (US 2003/0051881).

Claims 8 and 11 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Wailes* in view of *Moore* (alternatively, over *Moore* in view of *Wailes*) as applied to claims 1 above, and further in view of *Cotham* (US 5,335,730).

Claims 1, 6, 10, 12, 15, and 19 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Ohtsuka* (US 5,758,686) in view of *Etheridge* (US 4,774,980).

Independent claim 1 has been amended to recite “a fluid supply; a first fluid line in fluid communication with the fluid supply; a pump in fluid communication with the first fluid line and configured to pump fluid from the fluid supply to one or more wellheads through the first fluid line; a second fluid line in fluid communication with the first fluid line at a location downstream of the pump and configured to return fluid from the first fluid line to the fluid supply; a safety valve in-line with the second fluid line and having a gate normally maintained in a closed positon to close fluid flow through the second fluid

line…wherein the controller assembly is operable to actuate the valve assembly in response to a comparison of the measured physical property to the predetermined condition to release the fluid from the valve actuator so that the biasing member moves the gate into the open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the second fluid line to return fluid in the first fluid line back to the fluid supply."

Independent claim 12 has been amended to recite "providing a control system comprising: a fluid supply; a first fluid line in fluid communication with the fluid supply; a pump in fluid communication with the first fluid line and configured to pump fluid from the fluid supply to one or more wellheads through the first fluid line; a second fluid line in fluid communication with the first fluid line at a location downstream of the pump and configured to return fluid from the first fluid line to the fluid supply; a safety valve in-line with the second fluid line and having a gate…maintaining the gate in the closed position to close fluid flow through the second fluid line;…and actuating the valve assembly using the controller assembly to release the fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the second fluid line based upon a comparison of the monitored physical property to a predetermined condition to return fluid from the first fluid line back to the fluid supply.

Independent claim 21 has been amended to recite "providing a control system comprising a pump, a reservoir, a safety valve having a gate in-line with the flow line, a valve actuator configured to move the gate, and a sensor; actuating the valve actuator to move the gate into a closed position by pumping actuator fluid from the reservoir into the valve actuator using the pump; maintaining the gate in the closed position to close fluid flow through the flow line; pumping fluid through the flow line to at least one wellhead of a well to conduct a fracturing operation;…and actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position, forces the actuator fluid out of the valve actuator and back into the reservoir,

and thereby dumps fluid flowing through the flow line to relieve fluid pressure in the flow line.

Wailes discloses a flow control system configured to close a gate valve 11 to thereby close fluid flow in a pipeline 12 to isolate a break in the pipeline 12. See Abstract. *Moore* discloses a safety valve actuator and pilot system for emergency closure of a flow line. See Abstract. *Ohtsuka* discloses an abnormality detection system for a valve 21 that is normally maintained in an open positon. See Abstract, Figure 1. *Etheridge* discloses a "positive shut-off" system configured to close a control valve 10 that is normally maintained in an open positon to completely close flow of product from a wellhead through a flow line. See Col. 7, lines 23-35. However, *Wailes*, *Moore*, *Ohtsuka*, and *Etheridge* fail to disclose each and every element of amended independent claims 1, 12, and 21 shown above. *Vinegar* and *Cotham* fail to cure the deficiencies of *Wailes*, *Moore*, *Ohtsuka*, and *Etheridge*. Applicant respectfully requests withdrawal of the rejections and allowance of claims 1, 12, and 21, and claims dependent therefrom.

Conclusion

Having addressed all issues set out in the final office action, Applicant respectfully submits that the claims are in condition for allowance and respectfully requests that the claims be allowed.

Respectfully submitted,

/Jessie D. Herrera/
Jessie D. Herrera
Registration No. 63,799
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046
Telephone: (713) 623-4844
Facsimile: (713) 623-4846
Attorney for Applicant

Electronic Patent Application Fee Transmittal

Application Number:	13480704
Filing Date:	25-May-2012
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Filer:	Jessie D. Herrera/Stephanie Dominguez
Attorney Docket Number:	SAFO/0012USP1

Filed as Small Entity

Filing Fees for Utility under 35 USC 111(a)

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Basic Filing:				
Pages:				
Claims:				
Miscellaneous-Filing:				
Petition:				
Patent-Appeals-and-Interference:				
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Extension - 1 month with $0 paid	2251	1	100	100
Miscellaneous:				
RCE- 2nd and Subsequent Request	2820	1	850	850
		Total in USD ($)		**950**

Electronic Acknowledgement Receipt	
EFS ID:	25679735
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Stephanie Dominguez
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	04-MAY-2016
Filing Date:	25-MAY-2012
Time Stamp:	11:47:00
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	Credit Card
Payment was successfully received in RAM	$950
RAM confirmation Number	9418
Deposit Account	
Authorized User	
The Director of the USPTO is hereby authorized to charge indicated fees and credit any overpayment as follows:	

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Request for Continued Examination (RCE)	RCE.PDF	1349994 2c6e1d5dd157d3deeee7a3e28c9452ee4d38a203	no	3
Warnings:					
Information:					
2		Response.pdf	91347 d257af6eb4c531ff861285f5d13fd509e976fce1	yes	9

	Multipart Description/PDF files in .zip description		
	Document Description	**Start**	**End**
	Response After Final Action	1	1
	Claims	2	6
	Applicant Arguments/Remarks Made in an Amendment	7	9

Warnings:					
Information:					
3	Fee Worksheet (SB06)	fee-info.pdf	32424 3b77ab2b27ad1b6e9074201f02dc153e56c8a979	no	2
Warnings:					
Information:					
		Total Files Size (in bytes):	1473765		

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111

If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371

If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office

If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

26290 7590 01/04/2016
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

EXAMINER	
MCCALISTER, WILLIAM M	

ART UNIT	PAPER NUMBER
3753	

NOTIFICATION DATE	DELIVERY MODE
01/04/2016	ELECTRONIC

Please find below and/or attached an Office communication concerning this application or proceeding.

The time period for reply, if any, is set in the attached communication.

Notice of the Office communication was sent electronically on above-indicated "Notification Date" to the following e-mail address(es):

PSDocketing@pattersonsheridan.com
pair_eofficeaction@pattersonsheridan.com
jcardenas@pattersonsheridan.com

Office Action Summary	Application No. 13/480,704	Applicant(s) LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	AIA (First Inventor to File) Status No

-- The MAILING DATE of this communication appears on the cover sheet with the correspondence address --

Period for Reply

A SHORTENED STATUTORY PERIOD FOR REPLY IS SET TO EXPIRE 3 MONTHS FROM THE MAILING DATE OF THIS COMMUNICATION.

- Extensions of time may be available under the provisions of 37 CFR 1.136(a). In no event, however, may a reply be timely filed after SIX (6) MONTHS from the mailing date of this communication.
- If NO period for reply is specified above, the maximum statutory period will apply and will expire SIX (6) MONTHS from the mailing date of this communication.
- Failure to reply within the set or extended period for reply will, by statute, cause the application to become ABANDONED (35 U.S.C. § 133). Any reply received by the Office later than three months after the mailing date of this communication, even if timely filed, may reduce any earned patent term adjustment. See 37 CFR 1.704(b).

Status

1)☒ Responsive to communication(s) filed on *10/27/15*.

☐ A declaration(s)/affidavit(s) under **37 CFR 1.130(b)** was/were filed on _____.

2a)☒ This action is **FINAL**. 2b)☐ This action is non-final.

3)☐ An election was made by the applicant in response to a restriction requirement set forth during the interview on _____; the restriction requirement and election have been incorporated into this action.

4)☐ Since this application is in condition for allowance except for formal matters, prosecution as to the merits is closed in accordance with the practice under *Ex parte Quayle*, 1935 C.D. 11, 453 O.G. 213.

Disposition of Claims*

5)☒ Claim(s) *1-6,8-15 and 17-21* is/are pending in the application.

5a) Of the above claim(s) *4,9,13 and 17* is/are withdrawn from consideration.

6)☐ Claim(s) _____ is/are allowed.

7)☒ Claim(s) *1-3,5,6,8,10-12,14,15 and 18-21* is/are rejected.

8)☐ Claim(s) _____ is/are objected to.

9)☐ Claim(s) _____ are subject to restriction and/or election requirement.

* If any claims have been determined allowable, you may be eligible to benefit from the **Patent Prosecution Highway** program at a participating intellectual property office for the corresponding application. For more information, please see http://www.uspto.gov/patents/init_events/pph/index.jsp or send an inquiry to PPHfeedback@uspto.gov.

Application Papers

10)☐ The specification is objected to by the Examiner.

11)☐ The drawing(s) filed on _____ is/are: a)☐ accepted or b)☐ objected to by the Examiner.

Applicant may not request that any objection to the drawing(s) be held in abeyance. See 37 CFR 1.85(a).

Replacement drawing sheet(s) including the correction is required if the drawing(s) is objected to. See 37 CFR 1.121(d).

Priority under 35 U.S.C. § 119

12)☐ Acknowledgment is made of a claim for foreign priority under 35 U.S.C. § 119(a)-(d) or (f).

Certified copies:

a)☐ All b)☐ Some** c)☐ None of the:

1.☐ Certified copies of the priority documents have been received.

2.☐ Certified copies of the priority documents have been received in Application No. _____.

3.☐ Copies of the certified copies of the priority documents have been received in this National Stage application from the International Bureau (PCT Rule 17.2(a)).

** See the attached detailed Office action for a list of the certified copies not received.

Attachment(s)

1) ☐ Notice of References Cited (PTO-892)

2) ☐ Information Disclosure Statement(s) (PTO/SB/08a and/or PTO/SB/08b) Paper No(s)/Mail Date _____.

3) ☐ Interview Summary (PTO-413) Paper No(s)/Mail Date. _____ .

4) ☐ Other: _____.

The present application is being examined under the pre-AIA first to invent provisions.

Claims 7 and 16 have been cancelled. Claims 4, 9, 13 and 17 have been withdrawn. Claims 1-3, 5, 6, 8, 10-12, 14, 15 and 18-21 will be treated on the merits.

Claim Rejections - 35 USC § 103

The text of those sections of Title 35, U.S. Code not included in this action can be found in a prior Office action.

Claims 1, 5, 6, 12, 15, 18 and 21 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Wailes (US 3,776,249) in view of Moore (US 4,240,463).

Regarding claim 1, Wailes discloses a control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve (11) having a gate (11 is a "gate valve") normally maintained in a closed position to close fluid flow through the valve (this is seen as an intended use recitation, and Wailes safety valve is ***capable of*** being normally maintained in a closed position; under a second alternative reading, the gate is normally maintained in the closed position for a time delay determined by relay 83 after supplying fluid into to the valve actuator to close the gate);

a valve actuator (16) configured to move the gate into the closed position by fluid supplied into the valve actuator;

an electronic controller assembly (122) programmed with a predetermined condition (the “predetermined minimum level” at low pressure detector 68) and configured to receive a signal from a transducer (41) connected to the flow line, wherein the signal corresponds to a measured physical property (41 is a pressure transducer);

a valve assembly (111) in (indirect) communication with the controller assembly; and

a fluid drive assembly (119, 121) in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid into the valve actuator to move the gate into the closed position (via 81 and 119), and wherein the controller assembly is operable to actuate the valve assembly in response to a comparison of the measured physical property to the predetermined condition to release the fluid from the valve actuator and thereby open fluid flow through the flow line (see Abstract: "pressure sensing continues and if after closing certain predetermined requirements are met, the valves are automatically opened”; more specifically, time delay relay 83 opens the valve via 86 and 121 only after the “inhibit input” on circuit 82 ceases, which occurs when the alarm relay 66 stops the signal to 78, which occurs when the low pressure detector stops a signal to 66).

Wailes does not disclose a biasing member disposed in the valve actuator that moves the gate into the open position and forces the fluid out of the valve actuator.

Moore teaches that it was known in the art at the time of invention to use a biasing member 35 disposed in a similar valve actuator to move a similar gate into an open position and force fluid out of the similar valve actuator. To help prevent the valve from sticking closed, it would have been obvious to use a biasing member disposed in Wailes' valve actuator so that the biasing member helps to move the gate open and to force fluid out of the valve actuator, as taught by Moore.

Regarding claim 5, Wailes discloses the fluid to be hydraulic fluid, and it would have been obvious to use a well-known pump to provide the pressure required of Wailes' hydraulic pilot system.

Regarding claim 6, Wailes discloses the system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly (a power source is inherent).

Regarding claim 12, Wailes discloses a method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve (11) having a gate, a valve actuator (16) configured to move the gate, a housing (13), an electronic controller assembly (122), a fluid drive assembly (119 and 121; alternatively 112), and a valve assembly (111);

supplying fluid into the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into a closed position (the closed position described at col. 7 lines 22-62), wherein the gate is normally maintained in the closed position to close fluid flow through the flow line (the gate is normally maintained in the closed position for a time delay determined by relay 83 after supplying fluid into to the valve actuator to close the gate; under a second alternative reading, in an especially leak-prone environment such as the river crossing described at col. 1, it could be considered normal (i.e., regular, natural, etc., see Dictionary.com) for the gate valve to be maintained closed);

monitoring a physical property in the flow line using the controller assembly (via 41).

Wailes also discloses opening the valve *based on* a comparison of the monitored physical property to a predetermined condition (see Abstract: "pressure sensing continues and if after closing certain predetermined requirements are met, the valves are automatically opened"; more specifically, see col. 5 line 45 to col. 6 line 30: time delay relay 83 opens the valve via 86 and 121 only after the "inhibit input" on circuit 82 ceases, which occurs when the alarm relay 66 stops the signal to 78, which occurs when the low pressure detector stops a signal to 66).

Wailes does not disclose a biasing member disposed in the valve actuator which moves the gate into the open position and forces the fluid out of the valve actuator. Moore teaches that it was known in the art at the time of invention to use a biasing

member 35 disposed in a similar valve actuator to move a similar gate into an open position and force fluid out of the similar valve actuator. To help prevent the valve from sticking closed, it would have been obvious to use a biasing member disposed in Wailes' valve actuator so that the biasing member helps to move the gate open and to force fluid out of the valve actuator, as taught by Moore.

Regarding claim 15, Wailes discloses the method of claim 12, further comprising measuring the physical property using a transducer (41) configured to communicate a signal corresponding to the measured physical property to the controller assembly.

Regarding claim 18, Wailes discloses the method of claim 12, wherein the fluid is a hydraulic fluid, and wherein the fluid drive assembly (112) is a pump.

Regarding claim 21, the claimed method would necessarily be performed during the normal and usual operation of the device set forth in the obviousness analysis above (where the claimed method steps are seen as clearly corresponding to the recited features and capabilities of the apparatus as mapped above).

Claims 1, 5, 6, 12, 15, 18 and 21 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Moore in view of Wailes.

Moore discloses a gate valve and actuator with a biasing member in the actuator as claimed, but does not disclose the other claimed details of the control system. Wailes teaches that it was known in the art at the time of invention to control a similar gate valve using a control system as claimed connected to a similar actuator (see the analyses of Wailes set forth above). To control Moore's gate valve, it would have been obvious to use a control system and corresponding method as claimed and as taught by Wailes.

Claims 2, 3, 14 and 20 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Wailes in view of Moore (alternatively, over Moore in view of Wailes) as applied to claims 1 and 12 above, and further in view of Vinegar (US 2003/0051881).

Regarding claims 2, 3 and 14, Wailes discloses the fluid to be a hydraulic fluid, but does not disclose the hydraulic fluid to be disposed in a reservoir within a housing for supporting the controller assembly, valve assembly and fluid drive assembly. Vinegar teaches that it was known in the art at the time of invention to dispose hydraulic fluid in a reservoir 80 within a housing 72 for supporting a similar controller assembly, valve assembly and fluid drive assembly. To secure a source of Wailes' hydraulic fluid, it would have been obvious to use a reservoir within a housing for supporting the controller assembly, valve assembly and fluid drive assembly, as taught by Vinegar. Specifically regarding claim 3, the fluid is inherently supplied from outside of the housing during assembly of the system.

Regarding claim 20, Vinegar discloses actuating the safety valve by communicating a signal from a remote computer system to the controller assembly (paragraph 0043, 2nd sentence), and it would have been obvious to actuate Wailes' safety valve using such a signal for example if an emergency were detected at the remote computer system.

Claims 8 and 11 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Wailes in view of Moore (alternatively, over Moore in view of Wailes) as applied to claim 1 above, and further in view of Cotham (US 5,335,730).

Regarding claim 8, Wailes does not disclose a filter as claimed. Cotham teaches that it was known to use a filter ("D" at the bottom of FIG 6) attached to a similar housing for filtering fluid entering the housing by a similar fluid drive assembly. To remove debris from Wailes' fluid, it would have been obvious to use a filter as claimed.

Regarding claim 11, Wailes does not disclose the controller to be a PLC. Cotham teaches that PLCs were known in the art at the time of invention (col. 8 line 49), and it would have been obvious to embody Wailes' controller as a PLC in order to increase it's adaptability (via programmability).

Claims 1, 6, 10, 12, 15 and 19 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Ohtsuka (US 5,758,686) in view of Etheridge (US 4,774,980).

Regarding claim 1, Ohtsuka discloses a control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve (21) having a gate (1) normally maintained in a closed position to close fluid flow through the valve (this is seen as an intended use recitation, and Ohtsuka's safety valve is ***capable of*** being normally maintained in a closed position; under a second alternative reading, the gate is normally maintained in the closed position for a period of time until it is reopened);

a valve actuator (3, 6, 9) configured to move the gate into a closed position by fluid supplied into the valve actuator and configured to move the gate into an open position by a biasing member (9) disposed in the valve actuator;

an electronic controller assembly (221, 222, 224, 23, 24, 231, 237) programmed with a predetermined condition (the "desired value" from 221) configured to receive a signal from a transducer (224) connected to the flow line (all components are connected), wherein the signal corresponds to a measured physical property (it is a displacement sensor), and wherein the controller assembly is operable to actuate the valve assembly in response to a comparison of the measured physical property to the predetermined condition to release the fluid from the valve actuator so that the biasing member moves the gate into the open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the fluid line (col. 6 lines 30-35); and

a pressure generating section (223) in communication with the electronic controller which supplies fluid into the valve actuator to move the gate to the closed position and which releases fluid from the valve actuator so that the biasing member moves the gate into the open position and forces the fluid out of the valve actuator.

Ohtsuka does not disclose the pressure generating section (223) to include a valve assembly and fluid drive assembly as claimed. Etheridge teaches that it was known in the art at the time of invention to embody a pressure generating section by using a valve assembly (250) and a fluid drive assembly (208). To embody Ohtsuka's generically disclosed pressure generating section, it would have been obvious to use a valve assembly and a fluid drive assembly as claimed, and as taught by Etheridge.

Regarding claim 6, a power source is seen as inherent.

Regarding claim 10, the controller can communicate an alarm signal to a remote location 24.

Regarding claims 12 and 15, the claimed method would necessarily be performed during the normal and usual operation of the obvious device (the controller allows the valve plug to "retreat" only when there is no abnormality detected).

Regarding claim 19, members 23 and 24 are together read as the "remote computer system" (23 is not read as part of the controller for the purposes of claim 19).

Response to Arguments

Applicant's arguments have been considered but they are not persuasive. Wailes' disclosure that "it is assumed that the gate valve 11 is open" is insufficient to prevent the claims from being read on Wailes. As explained above, Wailes' gate valve is normally maintained closed for a predetermined period after the valve is closed, and before it is reopened. Similarly, Ohtsuka's and Moore's valves are normally maintained closed for a time period after valve closure, and before re-opening.

Conclusion

Applicant's amendment necessitated the new ground(s) of rejection presented in this Office action. Accordingly, **THIS ACTION IS MADE FINAL**. See MPEP § 706.07(a). Applicant is reminded of the extension of time policy as set forth in 37 CFR 1.136(a).

A shortened statutory period for reply to this final action is set to expire THREE MONTHS from the mailing date of this action. In the event a first reply is filed within TWO MONTHS of the mailing date of this final action and the advisory action is not mailed until after the end of the THREE-MONTH shortened statutory period, then the shortened statutory period will expire on the date the advisory action is mailed, and any extension fee pursuant to 37 CFR 1.136(a) will be calculated from the mailing date of

the advisory action. In no event, however, will the statutory period for reply expire later than SIX MONTHS from the date of this final action.

Any inquiry concerning this communication or earlier communications from the examiner should be directed to **William McCalister**, whose telephone number **571-270-1869**. The examiner can normally be reached on Monday-Friday (7:00AM-5:30PM EST).

If attempts to reach the examiner by telephone are unsuccessful, the examiner's supervisors can be reached by phone. Craig Schneider can be reached at 571-272-3607 or John Fristoe can be reached at 571-272-4926. The fax phone number for the organization where this application or proceeding is assigned is 571-273-8300.

Information regarding the status of an application may be obtained from the Patent Application Information Retrieval (PAIR) system. Status information for published applications may be obtained from either Private PAIR or Public PAIR. Status information for unpublished applications is available through Private PAIR only. For more information about the PAIR system, see http://pair-direct.uspto.gov. Should you have questions on access to the Private PAIR system, contact the Electronic Business Center (EBC) at 866-217-9197 (toll-free). If you would like assistance from a USPTO Customer Service Representative or access to the automated information system, call 800-786-9199 (IN USA OR CANADA) or 571-272-1000.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

12/29/15

EAST Search History

EAST Search History (Prior Art)

Ref #	Hits	Search Query	DBs	Default Operator	Plurals	Time Stamp
L1	81	(G05D16/2086.CPC. OR F16K17/00.CPC.) AND @PD>"20150601"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/12/29 14:01

EAST Search History (Interference)

< This search history is empty>

12/ 29/ 2015 2:03:24 PM
C:\ Users\ wmccalister\ Documents\ EAST\ Workspaces\ 13480704.wsp

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 61

Search Notes	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	Art Unit
	WILLIAM MCCALISTER	3753

CPC- SEARCHED		
Symbol	Date	Examiner
G05D 16/2086 good for electrical controls for a fluid pilot valve that controls a main valve	7/7/2014	wm
F16K 17/00 this invention meets the definition of "safety" but this subclass is very large and includes a lot of irrelevant art	7/7/2014	wm

CPC COMBINATION SETS - SEARCHED		
Symbol	Date	Examiner

US CLASSIFICATION SEARCHED			
Class	Subclass	Date	Examiner
137	488, 492, 492.5	7/7/2014	wm

SEARCH NOTES		
Search Notes	Date	Examiner
updated ccls and cpc searches	3/19/2015	wm
UPDATED SEARCH	6/26/2015	WM
UPDATED SEARCH	12/29/2015	WM

INTERFERENCE SEARCH			
US Class/ CPC Symbol	US Subclass / CPC Group	Date	Examiner

	/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 62

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: David Lymberopoulos et al.	§	
Serial No.: 13/480,704	§	Group Art Unit: 3753
Filed: May 25, 2012	§	Examiner: McCalister, William M.
Confirmation No.: 9598	§	
For: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE	§	

MAIL STOP Amendment
Commissioner for Patents
P.O. Box 1450
Alexandria, VA 22313-1450

Dear Sir:

RESPONSE TO OFFICE ACTION DATED JULY 2, 2015

In response to the Office Action dated July 2, 2015, please enter this response and reconsider the claims pending in the application for the reasons discussed below. Although Applicant believes that no additional fees are due in connection with this response, the Commissioner is hereby authorized to charge counsel's Deposit Account No. 20-0782/SAFO/0012USP1/JDH for any fees required to make this response timely and acceptable to the Office.

Amendments to the Claims begin on page 2 of this paper.

Remarks begin on page 6 of this paper.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 63

AMENDMENTS TO THE CLAIMS

1. (Currently Amended) A control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve having a gate normally maintained in a closed positon to close fluid flow through the flow line;

a valve actuator configured to move the gate into [[a]] the closed position by fluid supplied into the valve actuator and configured to move the gate into an open position by a biasing member disposed in the valve actuator;

an electronic controller assembly programmed with a predetermined condition and configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property;

a valve assembly in communication with the controller assembly; and

a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid into the valve actuator to move the gate into the closed position, and wherein the controller assembly is operable to actuate the valve assembly in response to a comparison of the measured physical property to the predetermined condition to release the fluid from the valve actuator so that the biasing member moves the gate into the open position, ~~and~~ forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line.

2. (Original) The system of claim 1, further comprising a housing for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

3. (Previously Presented) The system of claim 2, wherein the fluid supplied into the valve actuator by the fluid drive assembly is supplied from a reservoir disposed outside of the housing.

4. (Withdrawn) The system of claim 1, wherein the fluid drive assembly is a compressor and the fluid is a pneumatic fluid.

5. (Previously Presented) The system of claim 1, wherein the fluid drive assembly is a pump and the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid.

6. (Original) The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly.

7. (Canceled)

8. (Original) The system of claim 1, further comprising a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly.

9. (Withdrawn) The system of claim 1, wherein the fluid is ambient air.

10. (Original) The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system.

11. (Previously Presented) The system of claim 1, wherein the controller assembly is a programmable logic controller.

12. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve having a gate, a valve actuator configured to move the gate, a housing, an electronic controller assembly, a fluid drive assembly, and a valve assembly;

supplying fluid into the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into a closed position, wherein the gate is normally maintained in the closed position to close fluid flow through the flow line;

monitoring a physical property in the flow line using the controller assembly; and

actuating the valve assembly using the controller assembly to release the fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position, ~~and~~ forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line based upon a comparison of the monitored physical property to a predetermined condition.

13. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid disposed external to the housing, and further comprising filtering the pneumatic fluid as it enters the housing by the fluid drive assembly.

14. (Previously Presented) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid disposed in a reservoir within the housing that is in fluid communication with the fluid drive assembly.

15. (Original) The method of claim 12, further comprising measuring the physical property using a transducer configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. (Canceled)

17. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid, and wherein the fluid drive assembly is a compressor.

18. (Previously Presented) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid, and wherein the fluid drive assembly is a pump.

19. (Original) The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve.

20. (Original) The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly.

21. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve having a gate, a valve actuator configured to move the gate, and a sensor;

actuating the valve actuator to move the gate into a closed position by supplying actuator fluid into the valve actuator, wherein the gate is normally maintained in the closed position to close fluid flow through the flow line;

monitoring fluid pressure in the flow line using the sensor while maintaining the gate in the closed position; and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position, ~~and~~ forces the actuator fluid out of the valve actuator, and thereby opens fluid flow through the flow line to relieve fluid pressure in the flow line.

REMARKS

This is intended as a full and complete response to the Office Action dated July 2, 2015. Claims 1-6, 8-15, and 17-21 are pending in the application. Claims 4, 9, 13, and 17 stand withdrawn. Claims 1-3, 5-6, 8, 10-12, 14-15, and 18-21 stand rejected. Reconsideration of the rejected claims is requested for the reasons presented below.

Claim Rejections Under 35 USC § 103

Claims 1, 5, 6, 12, 15, 18, and 21 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Wailes* (US 3,776,249) in view of *Moore* (US 4,240,463).

Independent claims 1, 12, and 21 have been amended to recite a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line. *Wailes* and *Moore* fail to disclose these elements.

Wailes discloses a flow control system configured to close a gate valve 11 to thereby close fluid flow in a pipeline 12 to isolate a break in the pipeline 12. See Abstract. During normal operation, "it is assumed that the gate valve 11 is open" and gas is flowing normally through the pipeline 12. See Col. 5, lines 47-49. The gate valve 11 remains open unless a pressure drop is detected, in response to which the gate valve 11 is closed to close fluid flow through the pipeline 12. See Col. 5, lines 59-64. *Wailes* does not disclose a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line, as recited in claims 1, 12, and 21.

Moore discloses a safety valve actuator and pilot system for emergency closure of a flow line. See Abstract. "During normal operation of the valve system 10 the safety valve member 22 is open." Col. 3, lines 37-38. The "safety valve will remain open until the pressure in the flow line exceeds the predetermined value at which the safety valve is set to be closed." Col. 3, lines 60-62. *Moore* does not disclose a safety valve having

a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line, as recited in claims 1, 12, and 21.

Based on the foregoing, *Wailes* and *Moore* fail to disclose each and every element of claims 1, 12, and 21, and claims dependent therefrom. Applicant respectfully requests withdrawal of the rejection.

Claims 1, 5, 6, 12, 15, 18, and 21 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Moore* in view of *Wailes*.

Independent claims 1, 12, and 21 have been amended to recite a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line. *Wailes* and *Moore* fail to disclose these elements.

Wailes discloses a flow control system configured to close a gate valve 11 to thereby close fluid flow in a pipeline 12 to isolate a break in the pipeline 12. See Abstract. During normal operation, "it is assumed that the gate valve 11 is open" and gas is flowing normally through the pipeline 12. See Col. 5, lines 47-49. The gate valve 11 remains open unless a pressure drop is detected, in response to which the gate valve 11 is closed to close fluid flow through the pipeline 12. See Col. 5, lines 59-64. *Wailes* does not disclose a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line, as recited in claims 1, 12, and 21.

Moore discloses a safety valve actuator and pilot system for emergency closure of a flow line. See Abstract. "During normal operation of the valve system 10 the safety valve member 22 is open." Col. 3, lines 37-38. The "safety valve will remain open until the pressure in the flow line exceeds the predetermined value at which the safety valve is set to be closed." Col. 3, lines 60-62. *Moore* does not disclose a safety valve having

a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line, as recited in claims 1, 12, and 21.

Based on the foregoing, *Wailes* and *Moore* fail to disclose each and every element of claims 1, 12, and 21, and claims dependent therefrom. Applicant respectfully requests withdrawal of the rejection.

Claims 2, 3, 14, and 20 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Wailes* in view of *Moore* (alternatively, over *Moore* in view of *Wailes*) as applied to claims 1 and 12 above, and further in view of *Vinegar* (US 2003/0051881).

Claims 2, 3, 14, and 20 depend from one of claims 1 and 12 and are therefore allowable for at least the same reasons. *Vinegar* fails to cure the deficiencies of *Wailes* and *Moore*. Applicant respectfully requests withdrawal of the rejection.

Claims 8 and 11 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Wailes* in view of *Moore* (alternatively, over *Moore* in view of *Wailes*) as applied to claims 1 above, and further in view of *Cotham* (US 5,335,730).

Claims 8 and 11 depend from claim 1 and are therefore allowable for at least the same reasons. *Cotham* fails to cure the deficiencies of *Wailes* and *Moore*. Applicant respectfully requests withdrawal of the rejection.

Claims 1, 6, 10, 12, 15, and 19 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Ohtsuka* (US 5,758,686) in view of *Etheridge* (US 4,774,980).

Independent claims 1 and 12 have been amended to recite a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line. *Ohtsuka* and *Etheridge* fail to disclose these elements.

Ohtsuka discloses an abnormality detection system for a valve 21 that is normally maintained in an open positon. See Abstract, Figure 1. The abnormality detection system uses three factors to detect an abnormality, one of which is a fluid force C which acts on the valve plug 1 as fluid is flowing through the valve 21. See Col. 3, lines 13-19 and 55-61. Therefore, *Ohtsuka* does not disclose a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line, as recited in claims 1 and 12.

Etheridge discloses a "positive shut-off" system configured to close a control valve 10 that is normally maintained in an open positon to completely close flow of product from a wellhead through a flow line. See Col. 7, lines 23-35. *Etheridge* does not disclose a safety valve having a gate normally maintained in a closed positon to close fluid flow through a flow line, and releasing fluid from a valve actuator so that a biasing member moves the gate into an open position, forces the fluid out of the valve actuator, and thereby opens fluid flow through the flow line, as recited in claims 1 and 12.

Based on the foregoing, *Ohtsuka* and *Etheridge* fail to disclose each and every element of claims 1 and 12, and claims dependent therefrom. Applicant respectfully requests withdrawal of the rejection.

Conclusion

Having addressed all issues set out in the office action, Applicant respectfully submits that the claims are in condition for allowance and respectfully requests that the claims be allowed.

Respectfully submitted,

/Jessie D. Herrera/
Jessie D. Herrera
Registration No. 63,799
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046
Telephone: (713) 623-4844
Facsimile: (713) 623-4846
Attorney for Applicant(s)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 72

Electronic Patent Application Fee Transmittal

Application Number:	13480704
Filing Date:	25-May-2012
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Filer:	Jessie D. Herrera/Stephanie Dominguez
Attorney Docket Number:	SAFO/0012USP1

Filed as Small Entity

Filing Fees for Utility under 35 USC 111(a)

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Basic Filing:				
Pages:				
Claims:				
Miscellaneous-Filing:				
Petition:				
Patent-Appeals-and-Interference:				
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Extension - 1 month with $0 paid	2251	1	100	100
Miscellaneous:				
		Total in USD ($)		**100**

Electronic Acknowledgement Receipt	
EFS ID:	23906647
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Stephanie Dominguez
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	27-OCT-2015
Filing Date:	25-MAY-2012
Time Stamp:	16:44:25
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	Credit Card
Payment was successfully received in RAM	$100
RAM confirmation Number	3448
Deposit Account	
Authorized User	
The Director of the USPTO is hereby authorized to charge indicated fees and credit any overpayment as follows:	

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1		Response.pdf	92242 2e925487aac0e46f4e3eb1504ea987f0d0861237	yes	10

Multipart Description/PDF files in .zip description		
Document Description	**Start**	**End**
Amendment/Req. Reconsideration-After Non-Final Reject	1	1
Claims	2	7
Applicant Arguments/Remarks Made in an Amendment	8	10

Warnings:

Information:

2	Fee Worksheet (SB06)	fee-info.pdf	30657 1b975dcb2571e07d83318949af361a895b016cb3	no	2

Warnings:

Information:

Total Files Size (in bytes):	122899

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

PTO/SB/06 (09-11)
Approved for use through 1/31/2014. OMB 0651-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PATENT APPLICATION FEE DETERMINATION RECORD Substitute for Form PTO-875	Application or Docket Number 13/480,704	Filing Date 05/25/2012	☐ To be Mailed

ENTITY: ☐ LARGE ☒ SMALL ☐ MICRO

APPLICATION AS FILED – PART I

FOR	(Column 1) NUMBER FILED	(Column 2) NUMBER EXTRA	RATE ($)	FEE ($)
☐ BASIC FEE (37 CFR 1.16(a), (b), or (c))	N/A	N/A	N/A	
☐ SEARCH FEE (37 CFR 1.16(k), (i), or (m))	N/A	N/A	N/A	
☐ EXAMINATION FEE (37 CFR 1.16(o), (p), or (q))	N/A	N/A	N/A	
TOTAL CLAIMS (37 CFR 1.16(i))	minus 20 =	*	X $ =	
INDEPENDENT CLAIMS (37 CFR 1.16(h))	minus 3 =	*	X $ =	
☐ APPLICATION SIZE FEE (37 CFR 1.16(s))	If the specification and drawings exceed 100 sheets of paper, the application size fee due is $310 ($155 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).			
☐ MULTIPLE DEPENDENT CLAIM PRESENT (37 CFR 1.16(j))				
* If the difference in column 1 is less than zero, enter "0" in column 2.			TOTAL	

APPLICATION AS AMENDED – PART II

AMENDMENT	10/27/2015	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
	Total (37 CFR 1.16(i))	* 19	Minus	** 21	= 0	X $40 =	0
	Independent (37 CFR 1.16(h))	* 3	Minus	*** 3	= 0	X $210 =	0
	☐ Application Size Fee (37 CFR 1.16(s))						
	☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
						TOTAL ADD'L FEE	0

AMENDMENT		(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
	Total (37 CFR 1.16(i))	*	Minus	**	=	X $ =	
	Independent (37 CFR 1.16(h))	*	Minus	***	=	X $ =	
	☐ Application Size Fee (37 CFR 1.16(s))						
	☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
						TOTAL ADD'L FEE	

* If the entry in column 1 is less than the entry in column 2, write "0" in column 3.
** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 20, enter "20".
*** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 3, enter "3".
The "Highest Number Previously Paid For" (Total or Independent) is the highest number found in the appropriate box in column 1.

LIE
/SHARAIN MORELAND/

This collection of information is required by 37 CFR 1.16. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**
If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

26290 7590 07/02/2015
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

EXAMINER	
MCCALISTER, WILLIAM M	

ART UNIT	PAPER NUMBER
3753	

NOTIFICATION DATE	DELIVERY MODE
07/02/2015	ELECTRONIC

Please find below and/or attached an Office communication concerning this application or proceeding.

The time period for reply, if any, is set in the attached communication.

Notice of the Office communication was sent electronically on above-indicated "Notification Date" to the following e-mail address(es):

PSDocketing@pattersonsheridan.com
pair_eofficeaction@pattersonsheridan.com
jcardenas@pattersonsheridan.com

Office Action Summary	Application No. 13/480,704	Applicant(s) LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	AIA (First Inventor to File) Status No

-- The MAILING DATE of this communication appears on the cover sheet with the correspondence address --

Period for Reply

A SHORTENED STATUTORY PERIOD FOR REPLY IS SET TO EXPIRE *3* MONTHS FROM THE MAILING DATE OF THIS COMMUNICATION.

- Extensions of time may be available under the provisions of 37 CFR 1.136(a). In no event, however, may a reply be timely filed after SIX (6) MONTHS from the mailing date of this communication.
- If NO period for reply is specified above, the maximum statutory period will apply and will expire SIX (6) MONTHS from the mailing date of this communication.
- Failure to reply within the set or extended period for reply will, by statute, cause the application to become ABANDONED (35 U.S.C. § 133). Any reply received by the Office later than three months after the mailing date of this communication, even if timely filed, may reduce any earned patent term adjustment. See 37 CFR 1.704(b).

Status

1)☒ Responsive to communication(s) filed on *6/18/15*.

☐ A declaration(s)/affidavit(s) under **37 CFR 1.130(b)** was/were filed on _____.

2a)☐ This action is **FINAL**. 2b)☒ This action is non-final.

3)☐ An election was made by the applicant in response to a restriction requirement set forth during the interview on _____; the restriction requirement and election have been incorporated into this action.

4)☐ Since this application is in condition for allowance except for formal matters, prosecution as to the merits is closed in accordance with the practice under *Ex parte Quayle*, 1935 C.D. 11, 453 O.G. 213.

Disposition of Claims*

5)☒ Claim(s) *1-6,8-15 and 17-21* is/are pending in the application.

5a) Of the above claim(s) *4,9,13 and 17* is/are withdrawn from consideration.

6)☐ Claim(s) _____ is/are allowed.

7)☒ Claim(s) *1-3,5,6,8,10-12,14,15 and 18-21* is/are rejected.

8)☐ Claim(s) _____ is/are objected to.

9)☐ Claim(s) _____ are subject to restriction and/or election requirement.

* If any claims have been determined allowable, you may be eligible to benefit from the **Patent Prosecution Highway** program at a participating intellectual property office for the corresponding application. For more information, please see http://www.uspto.gov/patents/init_events/pph/index.jsp or send an inquiry to PPHfeedback@uspto.gov.

Application Papers

10)☐ The specification is objected to by the Examiner.

11)☐ The drawing(s) filed on _____ is/are: a)☐ accepted or b)☐ objected to by the Examiner.

Applicant may not request that any objection to the drawing(s) be held in abeyance. See 37 CFR 1.85(a).

Replacement drawing sheet(s) including the correction is required if the drawing(s) is objected to. See 37 CFR 1.121(d).

Priority under 35 U.S.C. § 119

12)☐ Acknowledgment is made of a claim for foreign priority under 35 U.S.C. § 119(a)-(d) or (f).

Certified copies:

a)☐ All b)☐ Some** c)☐ None of the:

1.☐ Certified copies of the priority documents have been received.

2.☐ Certified copies of the priority documents have been received in Application No. _____.

3.☐ Copies of the certified copies of the priority documents have been received in this National Stage application from the International Bureau (PCT Rule 17.2(a)).

** See the attached detailed Office action for a list of the certified copies not received.

Attachment(s)

1) ☒ Notice of References Cited (PTO-892)

2) ☒ Information Disclosure Statement(s) (PTO/SB/08a and/or PTO/SB/08b) Paper No(s)/Mail Date _____.

3) ☐ Interview Summary (PTO-413) Paper No(s)/Mail Date. _____ .

4) ☐ Other: _____.

The present application is being examined under the pre-AIA first to invent provisions.

Claims 7 and 16 have been cancelled. Claims 4, 9, 13 and 17 have been withdrawn. Claims 1-3, 5, 6, 8, 10-12, 14, 15 and 18-21 will be treated on the merits.

Claim Rejections - 35 USC § 103

The following is a quotation of pre-AIA 35 U.S.C. 103(a) which forms the basis for all obviousness rejections set forth in this Office action:

> (a) A patent may not be obtained though the invention is not identically disclosed or described as set forth in section 102 of this title, if the differences between the subject matter sought to be patented and the prior art are such that the subject matter as a whole would have been obvious at the time the invention was made to a person having ordinary skill in the art to which said subject matter pertains. Patentability shall not be negatived by the manner in which the invention was made.

The factual inquiries set forth in *Graham v. John Deere Co.*, 383 U.S. 1, 148 USPQ 459 (1966), that are applied for establishing a background for determining obviousness under pre-AIA 35 U.S.C. 103(a) are summarized as follows:

1. Determining the scope and contents of the prior art.

2. Ascertaining the differences between the prior art and the claims at issue.

3. Resolving the level of ordinary skill in the pertinent art.

4. Considering objective evidence present in the application indicating obviousness or nonobviousness.

This application currently names joint inventors. In considering patentability of the claims under pre-AIA 35 U.S.C. 103(a), the examiner presumes that the subject matter

of the various claims was commonly owned at the time any inventions covered therein were made absent any evidence to the contrary. Applicant is advised of the obligation under 37 CFR 1.56 to point out the inventor and invention dates of each claim that was not commonly owned at the time a later invention was made in order for the examiner to consider the applicability of pre-AIA 35 U.S.C. 103(c) and potential pre-AIA 35 U.S.C. 102(e), (f) or (g) prior art under pre-AIA 35 U.S.C. 103(a).

Claims 1, 5, 6, 12, 15, 18 and 21 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Wailes (US 3,776,249) in view of Moore (US 4,240,463).

Regarding claim 1, Wailes discloses a control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve (11) having a gate (11 is a “gate valve”);

a valve actuator (16) configured to move the gate into a closed position by fluid supplied into the valve actuator;

an electronic controller assembly (122) configured to receive a signal from a transducer (41) connected to the flow line, wherein the signal corresponds to a measured physical property (41 is a pressure transducer);

a valve assembly (111) in (indirect) communication with the controller assembly; and

a fluid drive assembly (119, 121) in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid into the valve actuator to move the gate into the closed position.

Wailes does not disclose a biasing member disposed in the valve actuator that moves the gate into the open position and forces the fluid out of the valve actuator. Moore teaches that it was known in the art at the time of invention to use a biasing member 35 disposed in a similar valve actuator to move a similar gate into an open position and force fluid out of the similar valve actuator. To help prevent the valve from sticking closed, it would have been obvious to use a biasing member disposed in Wailes' valve actuator so that the biasing member helps to move the gate open and to force fluid out of the valve actuator, as taught by Moore.

Regarding claim 5, Wailes discloses the fluid to be hydraulic fluid, and it would have been obvious to use a well-known pump to provide the pressure required of Wailes' hydraulic pilot system.

Regarding claim 6, Wailes discloses the system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly (a power source is inherent).

Regarding claim 12, Wailes discloses a method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve (11) having a gate, a valve actuator (16) configured to move the gate, a housing (13), an electronic controller assembly (122), a fluid drive assembly (119 and 121; alternatively 112), and a valve assembly (111);

supplying fluid into the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into a closed position (the closed position described at col. 7 lines 22-62);

monitoring a physical property in the flow line using the controller assembly (via 41).

Wailes also discloses opening the valve *based on* a comparison of the monitored physical property to a predetermined condition (col. 5 line 45 to col. 6 line 30), but does not disclose a biasing member disposed in the valve actuator which moves the gate into the open position and forces the fluid out of the valve actuator. Moore teaches that it was known in the art at the time of invention to use a biasing member 35 disposed in a similar valve actuator to move a similar gate into an open position and force fluid out of the similar valve actuator. To help prevent the valve from sticking closed, it would have been obvious to use a biasing member disposed in Wailes' valve actuator so that the biasing member helps to move the gate open and to force fluid out of the valve actuator, as taught by Moore.

Regarding claim 15, Wailes discloses the method of claim 12, further comprising measuring the physical property using a transducer (41) configured to communicate a signal corresponding to the measured physical property to the controller assembly.

Regarding claim 18, Wailes discloses the method of claim 12, wherein the fluid is a hydraulic fluid, and wherein the fluid drive assembly (112) is a pump.

Regarding claim 21, the claimed method would necessarily be performed during the normal and usual operation of the device set forth in the obviousness analysis above (where the claimed method steps are seen as clearly corresponding to the recited features and capabilities of the apparatus as mapped above).

Claims 1, 5, 6, 12, 15, 18 and 21 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Moore in view of Wailes.

Moore discloses a gate valve and actuator with a biasing member in the actuator as claimed, but does not disclose the other claimed details of the control system. Wailes teaches that it was known in the art at the time of invention to control a similar gate valve using a control system as claimed connected to a similar actuator (see the analyses of Wailes set forth above). To control Moore's gate valve, it would have been obvious to use a control system as claimed and as taught by Wailes.

Claims 2, 3, 14 and 20 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Wailes in view of Moore (alternatively, over Moore in view of Wailes) as applied to claims 1 and 12 above, and further in view of Vinegar (US 2003/0051881).

Regarding claims 2, 3 and 14, Wailes discloses the fluid to be a hydraulic fluid, but does not disclose the hydraulic fluid to be disposed in a reservoir within a housing for supporting the controller assembly, valve assembly and fluid drive assembly. Vinegar teaches that it was known in the art at the time of invention to dispose hydraulic fluid in a reservoir 80 within a housing 72 for supporting a similar controller assembly, valve assembly and fluid drive assembly. To secure a source of Wailes' hydraulic fluid, it would have been obvious to use a reservoir within a housing for supporting the controller assembly, valve assembly and fluid drive assembly, as taught by Vinegar. Specifically regarding claim 3, the fluid is inherently supplied from outside of the housing during assembly of the system.

Regarding claim 20, Vinegar discloses actuating the safety valve by communicating a signal from a remote computer system to the controller assembly (paragraph 0043, 2nd sentence), and it would have been obvious to actuate Wailes' safety valve using such a signal for example if an emergency were detected at the remote computer system.

Claims 8 and 11 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Wailes in view of Moore (alternatively, over Moore in view of Wailes) as applied to claim 1 above, and further in view of Cotham (US 5,335,730).

Regarding claim 8, Wailes does not disclose a filter as claimed. Cotham teaches that it was known to use a filter ("D" at the bottom of FIG 6) attached to a similar housing for filtering fluid entering the housing by a similar fluid drive assembly. To remove debris from Wailes' fluid, it would have been obvious to use a filter as claimed.

Regarding claim 11, Wailes does not disclose the controller to be a PLC. Cotham teaches that PLCs were known in the art at the time of invention (col. 8 line 49), and it would have been obvious to embody Wailes' controller as a PLC in order to increase it's adaptability (via programmability).

Claims 1, 6, 10, 12, 15 and 19 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Ohtsuka (US 5,758,686) in view of Etheridge (US 4,774,980).

Regarding claim 1, Ohtsuka discloses a control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve (21) having a gate (1);

a valve actuator (3, 6, 9) configured to move the gate into a closed position by fluid supplied into the valve actuator and configured to move the gate into an open position by a biasing member (9) disposed in the valve actuator;

an electronic controller assembly (221, 222, 224, 23, 24, 231, 237) configured to receive a signal from a transducer (232) connected to the flow line, wherein the signal corresponds to a measured physical property (232 is a flow rate sensor); and

a pressure generating section (223) in communication with the electronic controller which supplies fluid into the valve actuator to move the gate to the closed position and which releases fluid from the valve actuator so that the biasing member moves the gate into the open position and forces the fluid out of the valve actuator.

Ohtsuka does not disclose the pressure generating section (223) to include a valve assembly and fluid drive assembly as claimed. Etheridge teaches that it was known in the art at the time of invention to embody a pressure generating section by using a valve assembly (250) and a fluid drive assembly (208). To embody Ohtsuka's generically disclosed pressure generating section, it would have been obvious to use a valve assembly and a fluid drive assembly as claimed, and as taught by Etheridge.

Regarding claim 6, a power source is seen as inherent.

Regarding claim 10, the controller can communicate an alarm signal to a remote location 24.

Regarding claims 12 and 15, the claimed method would necessarily be performed during the normal and usual operation of the obvious device (the controller allows the valve plug to “retreat” only when there is no abnormality detected).

Regarding claim 19, members 23 and 24 are together read as the "remote computer system" (23 is not read as part of the controller for the purposes of claim 19).

Response to Arguments

Applicant’s arguments with respect to the previous 102 and 103 rejections have been considered but are moot because the arguments do not apply to any of the references being used in the current rejection. Ohtsuka and Moore disclose the claimed features (i.e., the biasing member).

Conclusion

Applicant's amendment necessitated the new ground(s) of rejection presented in this Office action. Accordingly, **THIS ACTION IS MADE FINAL**. See MPEP § 706.07(a). Applicant is reminded of the extension of time policy as set forth in 37 CFR 1.136(a).

A shortened statutory period for reply to this final action is set to expire THREE MONTHS from the mailing date of this action. In the event a first reply is filed within TWO MONTHS of the mailing date of this final action and the advisory action is not

mailed until after the end of the THREE-MONTH shortened statutory period, then the shortened statutory period will expire on the date the advisory action is mailed, and any extension fee pursuant to 37 CFR 1.136(a) will be calculated from the mailing date of the advisory action. In no event, however, will the statutory period for reply expire later than SIX MONTHS from the date of this final action.

Any inquiry concerning this communication or earlier communications from the examiner should be directed to **William McCalister**, whose telephone number **571-270-1869**. The examiner can normally be reached on Monday-Friday (7:00AM-5:30PM EST).

If attempts to reach the examiner by telephone are unsuccessful, the examiner's supervisors can be reached by phone. Craig Schneider can be reached at 571-272-3607 or John Fristoe can be reached at 571-272-4926. The fax phone number for the organization where this application or proceeding is assigned is 571-273-8300.

Information regarding the status of an application may be obtained from the Patent Application Information Retrieval (PAIR) system. Status information for published applications may be obtained from either Private PAIR or Public PAIR. Status information for unpublished applications is available through Private PAIR only. For more information about the PAIR system, see http://pair-direct.uspto.gov. Should you have questions on access to the Private PAIR system, contact the Electronic Business Center (EBC) at 866-217-9197 (toll-free). If you would like assistance from a USPTO Customer Service Representative or access to the

automated information system, call 800-786-9199 (IN USA OR CANADA) or 571-272-

1000.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

3/19/15

Notice of References Cited	Application/Control No. 13/480,704	Applicant(s)/Patent Under Reexamination LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	Page 1 of 1

U.S. PATENT DOCUMENTS

*		Document Number Country Code-Number-Kind Code	Date MM-YYYY	Name	Classification
*	A	US-4,240,463 A	12-1980	Moore, Allen D.	137/492.5
*	B	US-5,758,686 A	06-1998	Ohtsuka et al.	137/492.5
	C	US-			
	D	US-			
	E	US-			
	F	US-			
	G	US-			
	H	US-			
	I	US-			
	J	US-			
	K	US-			
	L	US-			
	M	US-			

FOREIGN PATENT DOCUMENTS

*		Document Number Country Code-Number-Kind Code	Date MM-YYYY	Country	Name	Classification
	N					
	O					
	P					
	Q					
	R					
	S					
	T					

NON-PATENT DOCUMENTS

*		Include as applicable: Author, Title Date, Publisher, Edition or Volume, Pertinent Pages)
	U	
	V	
	W	
	X	

*A copy of this reference is not being furnished with this Office action. (See MPEP § 707.05(a).)
Dates in MM-YYYY format are publication dates. Classifications may be US or foreign.

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS						Remove
Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	3922111		1975-11-25	Deters	
If you wish to add additional U.S. Patent citation information please click the Add button.						Add

U.S.PATENT APPLICATION PUBLICATIONS						Remove
Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20060219299	A1	2006-10-05	Snowbarger	
	2	20100236790	A1	2010-09-23	SMITHSON	
If you wish to add additional U.S. Published Application citation information please click the Add button.						Add

FOREIGN PATENT DOCUMENTS								Remove
Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	2391880	GB	A	2004-02-18	Reeves Wireline Technologies Limited		☐
If you wish to add additional Foreign Patent Document citation information please click the Add button								Add

NON-PATENT LITERATURE DOCUMENTS	Remove

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Receipt date: 06/18/2015	Application Number	13480704 13480704 - GAU: 3753
INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	Singapore Search Report and Written Opinion for Patent Application No. 2013007943, dated October 17, 2014.	☒
	2	Australian Examination Report for Patent Application No. 2011285979, dated February 13, 2015.	☒

If you wish to add additional non-patent literature document citation information please click the Add button **Add**

EXAMINER SIGNATURE

Examiner Signature	/William Mccalister/	Date Considered	06/26/2015

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

EFS Web 2.1.17 ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

EAST Search History

EAST Search History (Prior Art)

Ref #	Hits	Search Query	DBs	Default Operator	Plurals	Time Stamp
L1	41	137/488,492,492.5.ccls. and @pd>"20150301"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/26 14:10
L2	0	g05d16/2086.ccls. and @pd>"20150301"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/26 14:11
L3	0	g05d17/00.ccls. and @pd>"20150301"	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2015/06/26 14:11

EAST Search History (Interference)

< This search history is empty>

6/ 26/ 2015 2:12:18 PM
C:\ Users\ wmccalister\ Documents\ EAST\ Workspaces\ 13480704.wsp

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198

Search Notes	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	Art Unit
	WILLIAM MCCALISTER	3753

CPC- SEARCHED		
Symbol	Date	Examiner
G05D 16/2086 good for electrical controls for a fluid pilot valve that controls a main valve	7/7/2014	wm
F16K 17/00 this invention meets the definition of "safety" but this subclass is very large and includes a lot of irrelevant art	7/7/2014	wm

CPC COMBINATION SETS - SEARCHED		
Symbol	Date	Examiner

US CLASSIFICATION SEARCHED			
Class	Subclass	Date	Examiner
137	488, 492, 492.5	7/7/2014	wm

SEARCH NOTES		
Search Notes	Date	Examiner
updated ccls and cpc searches	3/19/2015	wm
UPDATED SEARCH	6/26/2015	WM

INTERFERENCE SEARCH			
US Class/ CPC Symbol	US Subclass / CPC Group	Date	Examiner

	/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753

PTO/SB/30EFS (07-14)
Approved for use through 07/31/2016. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

REQUEST FOR CONTINUED EXAMINATION(RCE)TRANSMITTAL
(Submitted Only via EFS-Web)

Application Number	13/480,704	Filing Date	2012-05-25	Docket Number (if applicable)	SAFO/0012USP1	Art Unit	3753
First Named Inventor	David LYMBEROPOULOS			Examiner Name	W. M. McCalister		

This is a Request for Continued Examination (RCE) under 37 CFR 1.114 of the above-identified application.
Request for Continued Examination (RCE) practice under 37 CFR 1.114 does not apply to any utility or plant application filed prior to June 8, 1995, to any international application that does not comply with the requirements of 35 U.S.C. 371, or to any design application. The Instruction Sheet for this form is located at WWW.USPTO.GOV.

SUBMISSION REQUIRED UNDER 37 CFR 1.114

Note: If the RCE is proper, any previously filed unentered amendments and amendments enclosed with the RCE will be entered in the order in which they were filed unless applicant instructs otherwise. If applicant does not wish to have any previously filed unentered amendment(s) entered, applicant must request non-entry of such amendment(s).

☐ Previously submitted. If a final Office action is outstanding, any amendments filed after the final Office action may be considered as a submission even if this box is not checked.

- ☐ Consider the arguments in the Appeal Brief or Reply Brief previously filed on _____
- ☐ Other _____

☒ Enclosed

- ☒ Amendment/Reply
- ☒ Information Disclosure Statement (IDS)
- ☐ Affidavit(s)/ Declaration(s)
- ☐ Other _____

MISCELLANEOUS

☐ Suspension of action on the above-identified application is requested under 37 CFR 1.103(c) for a period of months _____ (Period of suspension shall not exceed 3 months; Fee under 37 CFR 1.17(i) required)

☐ Other _____

FEES

☒ **The RCE fee under 37 CFR 1.17(e) is required by 37 CFR 1.114 when the RCE is filed.**
The Director is hereby authorized to charge any underpayment of fees, or credit any overpayments, to Deposit Account No 20-0782

SIGNATURE OF APPLICANT, ATTORNEY, OR AGENT REQUIRED

☒ Patent Practitioner Signature

☐ Applicant Signature

PTO/SB/30EFS (07-14)
Approved for use through 07/31/2016. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

Signature of Registered U.S. Patent Practitioner			
Signature	/Jessie D. Herrera/	Date (YYYY-MM-DD)	2015-06-18
Name	Jessie D. Herrera	Registration Number	63799

This collection of information is required by 37 CFR 1.114. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.11 and 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450.

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these records.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	3922111		1975-11-25	Deters	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20060219299	A1	2006-10-05	Snowbarger	
	2	20100236790	A1	2010-09-23	SMITHSON	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	2391880	GB	A	2004-02-18	Reeves Wireline Technologies Limited		☐

If you wish to add additional Foreign Patent Document citation information please click the Add button Add

NON-PATENT LITERATURE DOCUMENTS Remove

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	Singapore Search Report and Written Opinion for Patent Application No. 2013007943, dated October 17, 2014.	☒
	2	Australian Examination Report for Patent Application No. 2011285979, dated February 13, 2015.	☒

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/Jessie D. Herrera/	Date (YYYY-MM-DD)	2015-06-18
Name/Print	Jessie D. Herrera	Registration Number	63799

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 102

(12) UK Patent Application (19) GB (11) 2 391 880 (13) A

(43) Date of A Publication 18.02.2004

(21) Application No: 0218784.7

(22) Date of Filing: 13.08.2002

(51) INT CL[7]:
E21B 47/12 23/00

(52) UK CL (Edition W):
E1F FKU

(56) Documents Cited:
EP 0551163 A
WO 1994/029572 A
US 6105690 A
WO 1999/054591 A
US 6310829 B
US 4896722 A

(58) Field of Search:
UK CL (Edition T) E1F FHK FHU FKD FKE FKF FKG FKU
INT CL[7] E21B 23/00 23/04 47/12 47/14 47/16 47/18
Other: Online: WPI EPODOC JAPIO

(71) Applicant(s):
Reeves Wireline Technologies Limited
(Incorporated in the United Kingdom)
Gotham Road, East Leake,
LOUGHBOROUGH, Leicester, LE12 6JX,
United Kingdom

(72) Inventor(s):
Michael Charles Spencer
Michael John Chaplin
Charles Richard Easter

(74) Agent and/or Address for Service:
Eric Potter Clarkson
Park View House, 58 The Ropewalk,
NOTTINGHAM, NG1 5DD, United Kingdom

(54) Abstract Title: **Apparatuses and methods for deploying logging tools and signalling in boreholes**

(57) In the field of tools for use in boreholes, an apparatus (10) which includes a pump (11) for circulating fluid under pressure in a wellbore (12).

A control device (13) controls the speed of the pump (11). A conduit (17) interconnects the pump and the wellbore (12).

Within the wellbore a downhole transducer (21) that is capable of detecting changes in the pressure of fluid at a downhole location and generating signals indicative thereof.

A processor (23) generates actuator commands in dependence on the generated signals.

One or more actuators (24) is operable to activate at least part of a downhole tool in dependence on a said actuator command.

A modulating valve (26) is capable of modulating the pressure of fluid in the conduit.

A remote transducer (27) that may be eg. at a surface location, is capable of detecting pressure of fluid in the conduit at a location remote from the downhole transducer (21).

The control device causes the pump to generate one or more digital acoustic signals in the fluid, the wave forms of which are detectable by the downhole transducer (21).

The modulating valve (26) is capable of generating digital or analogue wave forms in the fluid.

In operation the control device sends control signals via the fluid that are detected by the downhole transducer (21). Consequently the processor (23) causes actuation of one or more tools.

Following correct actuation the modulating valve (26) generates signals in the form of pressure changes in the fluid. The remote transducer (17) detects and displays such signals, to indicate at a surface location whether deployment of the tool has occurred successfully.




Fig. 1

GB 2 391 880 A

At least one drawing originally filed was informal and the print reproduced here is taken from a later filed formal copy.




28
29
27
17
31
18a
16
14
18
11
12
10
13
24
26
32
34
36
21
19
23
24
18b
32
63
36
22


Fig. 1



2/11


Fig. 2A

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 105



3/11

Fig. 2B



4/11

Fig. 2C

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 107




Fig. 2D




Fig. 2E

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 109



Data Transmission to Tool String
Standpipe Pressure
Tool string running into openhole
30 Secs
30 Secs
30 Secs
30 Secs
Time

Fig. 3



Tool Response
Tools landed in openhole, pressure relief valve opens
Tools Released
Control valve opens in tool to indicate power on, calipers open, data recording and tools functional
Standpipe Pressure
Time
Tools pumped into openhole

Fig. 4

Pressure Tester Responses




Fig. 5




Fig. 6




Fig. 7

Good Test




Fig. 8




Fig. 9




Fig. 10

APPARATUSES AND METHODS FOR DEPLOYING LOGGING TOOLS AND SIGNALLING IN BOREHOLES

This invention relates to apparatuses and methods for deploying logging tools and signalling in boreholes.

The logging of boreholes hitherto has used techniques that are well known in the oil and gas industries. The advantages of such an activity are known to those skilled in the art of oil and gas production.

When a borehole is drilled, it is seldom smooth and regular. Sections of the borehole sometimes cave in. Sometimes there are other sections of rock, in particular shales and clays, that squeeze into the borehole as a result of pressure exerted by overlying strata.

Traditionally, borehole logging has involved the use of a so-called wireline logging tool. The wireline logging tool is lowered on a wireline or pushed on drillpipe into the borehole to a downhole, logging location. The wireline logging tool is connected by a wireline to eg. data processing and recording apparatus at a surface location external of the borehole.

Wireline logging tools are of comparatively large diameter. Consequently it is difficult to push or lower a wireline logging tool into a borehole having caved in or squeezed sections as aforesaid.

In recent years it has become known to employ, for the logging of boreholes, a so-called compact logging tool comprising logging tool sections and battery / memory sections. This logging tool typically is of considerably less diameter than a conventional wireline logging tool. It includes a self-contained power supply in the form of a series of batteries; and one or more memory devices, whose function is to record data logged

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 115

by the logging tool.

Battery / memory logging tools in many circumstances offer advantages over traditional, wireline tools.

It is now known to deploy such a battery / memory logging tool using a so-called "garaging" technique, in which the tool lies retracted within one or more joints of drillpipe during running in of the drillpipe at tripping speed. Once the drillpipe reaches the total depth ("TD") of the well, a mechanism is actuated to cause delatching of a delatchable running sub that during running in of the drillpipe causes retention of the battery / memory logging tool within the drillpipe.

Delatching of the running sub causes deployment of the logging tool to a location protruding from the downhole end of the drillpipe, at which location the logging tool is available for logging operations. Such operations then occur as the drillpipe is withdrawn upwardly from the wellbore. The battery / memory logging tool logs data on the open hole well as it travels upwards towards an uphole location, supported on the end of the drillpipe.

Following withdrawal of all the joints of drillpipe in the wellbore, the memory section of the battery / memory logging tool is recovered. The data recorded therein is downloaded, enhanced and/or analysed as desired.

The known technique for deploying the logging tool includes circulating the well with fluid under pressure, by means of a positive displacement pump connected to the drillpipe at an uphole (surface) location.

This permits the insertion into the drillpipe of a messenger sub. Such a sub is pumpable within the drillpipe to the downhole end thereof, where it

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 116

operates a release tool. Operation of the release tool causes delatching of the running sub and deployment of the logging tool as aforesaid.

The above-described method has proved highly successful in the data logging art.

Nonetheless there is a need for further improvements in the efficiency of deployment of logging tools.

Rig time is costed at several hundred or thousand dollars per hour. Therefore it is strongly desirable to complete data logging operations in as short a time as possible. However the time taken to pump the messenger sub from an uphole location to approximately the TD of the well can be significant, not least because most oil wells are many hundreds or thousands of metres long.

The drillpipe must be of the correct diameter, and drifted, to ensure that the messenger will pass through the drillpipe and any bottom hole restrictions. Such preparation of the drillpipe is also time-consuming.

The known garaging technique for the deployment of logging tools includes method steps aimed at signalling from a downhole location to an uphole location whether deployment of the logging tool has commenced. There is however a greater need for communication between downhole and uphole locations in oil wells as the logging tools become more complex.

There have been numerous proposals in the past aimed at providing such communication without resorting to wireline connections between the downhole and uphole ends of a drillpipe. In the main such prior art proposals attempt to provide encoded communication between the downhole and uphole locations, by means of acoustic signals generated as

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 117

pressure pulses in the fluid circulating in the well.

The approach in the prior art has been to develop a language using which it is possible digitally to transmit packets of data within the drillpipe.

This approach suffers from several disadvantages.

Principal among these is the use in the prior art of electromechanical pulsing techniques to generate fluid pressure signals at downhole locations. Typically such techniques involve the use of electrically actuated, mechanical valving members to interrupt the flow of mud (or other fluid) thereby creating pulses of sufficient amplitude to be detectable at a surface location. Since the mass of mud typically requiring to be arrested by the valving members is several thousand kilogrammes the service lives and general reliability of the prior art devices are poor.

A further disadvantage of the prior art techniques is that the speed of data transmission is poor, because of the limited bandwidth of the transmission medium (mud). This problem is acute when attempting to multiplex data transmissions.

According to a first aspect of the invention there is provided apparatus for remotely activating a tool in a wellbore, the apparatus comprising:

a positive displacement pump for causing circulation of a fluid under pressure in the wellbore;

a control device for controlling the speed of operation of the pump;

a conduit that is operatively connected to the pump and extends into the wellbore for conveying the fluid thereinto on operation of the pump;

a downhole transducer, that is capable of detecting changes in the pressure of the fluid and generating one or more detected pressure signals indicative thereof;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 118

a processor that is capable of generating one or more actuator commands in dependence on detected pressure signals generated by the downhole transducer;

one or more actuators that are each operable to activate at least a part of a tool in dependence on a said actuator command;

an activatable tool at a downhole location;

a modulating valve for modulating the pressure of fluid in the conduit; and

a remote transducer that is operatively connected to detect pressure of the fluid in the conduit at a location remote from the downhole pressure transducer, wherein operation of the modulating valve is dependent on a downhole event.

Advantageously the apparatus of the invention allows the practising of the garaging method for the rapid deployment of logging tools without the need to pump a messenger sub to a downhole location to initiate releasing of the tool.

The downhole transducer and the processor are capable of initiating a tool deployment operation following the generation of an acoustic signal at a remote location that preferably is a surface location.

The transmission of such an acoustic signal occurs more rapidly than the pumping of the messenger sub to the downhole location. On the other hand, the data requiring transmission to the downhole location in order to initiate tool deployment can be simple. Consequently it can be transmitted in digital or analogue form.

There is no need for multiplexing of data in the acoustic signals, since the presence of the processor at the downhole location means that the acoustic signals need only initiate a further, more complex process that occurs under

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 119

the control of the processor that is appropriately programmed.

The presence of the modulating valve allows the apparatus to signal from the downhole location to eg. an uphole location that a particular event (such as but not limited to correct deployment of a logging tool) has occurred.

The data necessary for such signalling also are simple, and hence suitable for propagation as analogue or digital acoustic signals in wellbore fluids.

As is explained in more detail below, within the scope of the invention there is no need to attempt the transmission of complex borehole log data by means of acoustic signals.

Conveniently the control device is operable to cause the pump to generate one or more analogue acoustic signals, in the fluid, the waveforms of which are detectable by the downhole transducer.

Preferably the control device is operable to cause the pump to generate one or more digital acoustic signals, in the fluid, the waveforms of which are detectable by the downhole transducer; and the modulating valve is operable to generate one or more analogue or digital acoustic signals, in the fluid, the waveforms of which are detectable by the remote transducer.

Thus the operation of the apparatus according to the invention may if desired be a hybrid of digital and analogue signalling techniques. This confers maximum flexibility on the data transmission, with digital signals being used when there is a need to transmit simple data with a high degree of reliability; and analogue signals being used when it is necessary to transmit from the downhole end of a drillpipe to a remote location an indication of instantaneously prevailing conditions at the downhole end of the wellbore. There may be a short delay of a few seconds, as a result of

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 120

propagation of the acoustic signal along the drillpipe, before the indication is detectable at the remote location; but this delay is within acceptable limits.

A further advantageous feature of the apparatus of the invention is that it permits timebase modulation of the data generated at the downhole location. This allows matching of the data transmission rate to the bandwidth of the transmission medium (the mud or other fluid).

Preferably the conduit is a drillpipe that is moveable within the wellbore; the activatable tool is moveable relative to the drillpipe; and the drillpipe and the activatable tool include mutually engageable latch parts that, when mutually engaged, retain at least part, or all, of the activatable tool in a retracted position relative to the drillpipe and when disengaged permit movement of the tool to an advanced position in which at least part of the tool protrudes or protrudes further from the downhole end of the drillpipe, the apparatus including a release tool activator that is operable to cause disengagement of the latch parts from one another.

The release tool activator preferably includes or is controlled by a programmable device that is programmed to cause disengagement of the latch parts on the downhole transducer detecting a predetermined sequence of pressure changes in the fluid.

As a consequence the apparatus of the invention is able to detect an encoded, digital signal indicative of a need to deploy a logging tool; and cause releasing of the tool.

The foregoing features of the apparatus of the invention suit it for use in a garaging technique similar to the prior art method outlined hereinabove.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 121

Conveniently the drillpipe when present includes on its interior surface one or more landing stops and the activatable tool includes protruding from an exterior surface one or more landing dogs that are each engageable with a said landing stop on the activatable tool moving to its advanced position relative to the drillpipe.

Even more preferably the landing stop is or includes an annular landing collar extending about the interior surface of the drillpipe.

The foregoing features assist in the deployment of the activatable tool (that in preferred embodiments is a logging tool), since it is desirable for release of the tool from a retracted position to be limited so that the drillpipe and the tool remain in contact with one another. This in turn permits travel of the tool along the wellbore protruding from the drillpipe, during logging operations.

Preferably the operation of the release tool activator to cause disengagement of the latch parts also causes the modulating valve to close whereby movement of the tool to its advanced position causes dethrottling of the flow of fluid at the downhole location, such dethrottling being detectable at the remote location as a period of reduced fluid pressure.

Thus the apparatus of the invention advantageously is capable of signalling to an uphole location the commencement of deployment of an activatable tool or a part thereof.

In preferred embodiments of the invention the apparatus includes a pressure relief valve, whose opening threshold is predetermined; and the engagement of the or each said landing dog with a said landing stop causes the pressure relief valve to generate an analogue, acoustic signal that is indicative of landing of the tool in its advanced position relative to the drillpipe.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 122

The foregoing features assure that the signals generated by the movement of the toolstring and pressure relief valve on initiation of tool release and tool landing are easily detected at a surface or other remote location and are distinctive of the tool deployment action.

The modulating valve optionally is a proportional valve including a valve needle and a valve seat; and acoustic signals generated thereby conveniently are fluid pressure decreases that are proportional to the displacement of the valve needle relative to the seat.

The modulating valve preferably is a proportional valve including a valve needle and a seat therefor; and the acoustic signal is an increase in pressure that is proportional to the displacement of the valve needle relative to the seat.

It is further preferable that the apparatus includes an actuator member that is common to the release tool and the modulating valve whereby operation of the release tool causes movement of the modulating valve.

In a particularly preferred embodiment of the invention the common actuator member is a rod extending centrally within a toolstring, mutually spaced parts of the rod being secured respectively to the release tool, the valve member of the modulating valve and a servomechanism (ie. a speed- and position-controllable device) that moves the rod longitudinally in the toolstring in dependence on one or more said actuator commands.

Connection of the rod to a servomechanism conveniently permits the generation of actuator commands within a processor or other programmable device forming part of the apparatus at a downhole location; and conversion of such commands into an acoustic signal that is detectable at an uphole or

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 123

other location that is remote from the downhole one.

In other words the apparatus is capable of generating an acoustic signal, that is transmissible to eg. an uphole location, that is distinctive of landing of the activatable tool in its deployed position. Thus the apparatus clearly signals correct deployment of the tool. A surface-located engineer, or software programmed in a microprocessor forming part of or connected to the apparatus, may then know that it is possible to commence logging operations (or other operations carried out by the activatable tool, if the latter is other than a logging tool), without fear that the operations would be a waste of valuable rig time as a result of failed deployment of the tool. In the event of the engineer, or the software, identifying sub-optimal deployment, it is possible under some circumstances promptly to take corrective action such as but not limited to relocating the tool in the borehole.

Preferably the activatable tool includes one or more reaction surfaces against which fluid pressure in the conduit acts.

The presence of such surfaces advantageously permits the pumping, using pressure of fluid in the wellbore, of the activatable tool from its retracted position to its deployed position following releasing thereof.

Preferably the reaction surfaces include one or more flexible, annular sealing members encircling a cylindrical part of the activatable tool so as to seal between the exterior of the tool and the interior of the conduit. The or each reaction surface conveniently is moveable longitudinally of the activatable tool relative to the landing dogs; and the apparatus includes a resiliently deformable member operatively interconnecting the or each reaction surface and a said landing dog.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 124

The resiliently deformable member, that in preferred embodiments of the invention is a coiled spring encircling a cylindrical part of the apparatus of the invention, causes gradual deceleration of the reaction surfaces and the mass of equipment and drilling fluid supported thereby on landing of the tool.

Such controlled deceleration minimises the risk of damage to components of the apparatus on engagement of the landing dogs with the landing stops.

Preferably the logging toolstring includes a cylindrical member that is moveable relative to a chamber, the chamber including one or more ports providing communication between the interior and the exterior of the chamber and the cylindrical member closing the or each said port during deployment of the toolstring, the or each reaction surface being operatively connected to the cylindrical member such that on landing of the tool the cylindrical member moves to open the or each said port to limit the pressure of fluid in the chamber.

It is also preferable that the chamber has formed therein an orifice, the orifice providing fluid communication between the chamber and a further chamber the volume of which changes on movement of the cylindrical member.

Conveniently the coiled spring interconnects the or each reaction member and the cylindrical member.

The foregoing feature permits the forcing of fluid via the orifice into the variable volume chamber. This damps the motion of the reaction surfaces, the components of the apparatus connected thereto and the mass of drilling fluid supported thereby and consequently prevents unwanted oscillations.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 125

It is also preferable that the said chamber includes a wall member having defined therein each said port, the wall member including a perforated sleeve that is releasably secured on the chamber. This feature advantageously permits modification of the port size, by changing of the sleeve to suit the density and viscosity of the fluid in the drillpipe so as to provide for the correct acoustic signal waveform shape.

The apparatus of the invention also conveniently includes a pressure relief valve that opens to vent fluid pressure from within a hollow part of the activatable tool should the pressure within the hollow part exceed a predetermined threshold.

Preferably the apparatus includes a first pressure balancer for balancing fluid pressure on the uphole and downhole sides of the modulating valve.

In practical embodiments of the invention the first pressure balancer is such as to equalise pressures in the chambers on either side of the modulating valve.

The pressure balancer is such that the modulating valve when operating does not have to act against the full pressure, that may be up to several thousand psi, of fluid in the wellbore.

Preferably the apparatus also includes a further pressure balancer that in use lies downhole of the modulating valve and is operatively connected to equalise pressures acting on the uphole and downhole sides of the servomechanism. The purpose of the further pressure balancer is to maintain the loadings on the servomechanism within acceptable values, so that the servomechanism does not have to overcome the borehole pressure during its operation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 126

In one embodiment of the invention the activatable tool is or includes a formation pressure tester; and the processor is programmed to generate one or more actuator commands for causing operation of the formation pressure tester.

The apparatus of the invention is particularly suitable for use in the deployment of a formation pressure tester.

More specifically, when the apparatus includes the servomechanism as aforesaid the processor is preferably connected and programmed to generate commands for causing one or more of:

(i) operation of the servomechanism to cause unlatching of the mutually engageable latch parts and thereby cause movement of the toolstring that generates an acoustic signal that is indicative of tool release; followed by

(ii) operation of the pressure relief valve to signal landing of one or more landing dogs in a landing stop;

(iii) deployment of one or more deployable components of the formation pressure tester;

(iv) powering up and/or self-testing of one or more tools in a toolstring.

When the apparatus of the invention includes the servomechanism as aforesaid, conveniently the activatable tool includes a logging device and a memory device capable of recording data logged by the logging device, the processor being programmed to generate actuator commands for commanding the servomechanism to operate the modulating valve to generate fluid pressure signals in dependence on the recorded, logged data.

Thus the apparatus of the invention is suitable for use with a "wireless" battery / memory logging tool.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 127

In the preferred embodiment of the invention the logged data that is the subject of the signals generated by the programmed device are indicative of the conditions prevailing in the vicinity of the formation pressure tester, rather than entire borehole plots (that preferably are stored in the memory device and subsequently downloaded or otherwise manipulated, following recovery of the formation pressure tester or at least the memory device to a surface location at the end of a logging operation).

Conveniently the apparatus includes a remote transducer that detects pressure of the fluid in the conduit at a location remote from the downhole pressure transducer and generates signals indicative thereof.

More specifically, the remote transducer preferably detects fluid pressure in a standpipe that interconnects the outlet of the pump and the interior of the conduit.

The remote transducer may be, but is not limited to, a pressure gauge, a piezoelectric transducer operatively connected to a display device such as a computer monitor or a pen recorder; a strain gauge; or any of a range of other transducing devices from which a pressure signal may be generated.

In preferred embodiments of the invention at least an output device forming part of or connected to the pressure transducer is located such that a human operator may view it. Consequently the pressure transducer may provide an immediately visible indication of the signals generated by operation of the modulating valve at a downhole location.

Conveniently the apparatus includes an on-board source of electrical power.

Preferably this is in the form of a sub, forming part of a toolstring, that

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 128

includes a plurality of batteries connected for powering the various components of the apparatus.

According to a second aspect of the invention there is provided apparatus for signalling between a downhole location in a wellbore and a further location that is remote from the downhole location, the apparatus comprising a conduit extending into the wellbore; a pump connected to supply fluid under pressure in the conduit; a modulating valve, at a downhole location, for modulating the pressure of fluid in the conduit; a programmable processor for controlling operation of the modulating valve; a memory device; and a remote transducer for detecting fluid pressure at the further location.

This apparatus contrasts with prior art signalling apparatuses in that it is capable of transmitting analogue data to the further location that preferably is a surface location at which computers, processing apparatus and/or human operators may be located.

Preferably the memory device includes stored therein data logged in the wellbore; and the programmable processor is programmed to cause the modulating valve to modulate the pressure of fluid in the conduit in a fashion that is characteristic of the logged data.

In use of the apparatus the stored data that is transmitted by means of the apparatus of the invention is not, generally, an entire log of a wellbore. On the contrary, the stored data so transmitted preferably relates to instantaneously prevailing conditions in the vicinity of eg. an activatable tool at the time of its activation. Such data are used to confirm successful activation and/or deployment of a tool.

Conveniently the programmable processor is programmed to cause the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 129

modulating valve to modulate the pressure of fluid in the conduit in a fashion that is characteristic of two types of data logs (eg. gamma ray and formation pressure logs) carried out at different times.

It is also preferable that the earlier of the two logs is a low frequency Gamma log.

Such features of the apparatus allow for example the use of an accurate Gamma log of a borehole to confirm the position of a formation pressure tester during use, with signals indicative of the position of the formation pressure tester being transmitted via the borehole fluid to an uphole location.

Since the accurate positioning of formation pressure testers (and some other logging tools) is known potentially to consume large amounts of logging time, the foregoing features are highly advantageous.

In preferred embodiments of the invention the formation pressure tester is conventional and of a *per se* known kind. The formation pressure tester logs and transmits data in a *per se* conventional manner. A key difference however between the arrangement of the invention and those of prior art devices is that the formation log *per se* is stored in a downhole memory device. Typically the data transmitted via the medium of the borehole fluid are indicative eg. of whether the formation pressure tester has deployed correctly.

Preferably the modulating valve includes a valve member; a valve seat on which the valve is seatable to raise fluid pressure in the conduit and from which the valve member is removable to reduce fluid pressure in the conduit; a servomechanism connected to operate in dependence on signals generated by the programmable processor; and an actuator member

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 130

operatively interconnecting the servomechanism and the valve member whereby the valve is openable and closeable in dependence on the signals generated by the programmable processor.

Such an arrangement advantageously is simple and reliable. Operation of this arrangement results in the instantaneous generation of modulating signals in the borehole fluid, on the occurrence of a downhole event.

Conveniently the apparatus includes a logging tool that is capable of logging data characteristic of the wellbore and/or a formation proximate thereto, the logging tool and the memory device being connectable one to the other so that the memory device stores data logged by the logging tool.

The use of such a tool and memory combination conveniently permits the downloading of logged data following completion of logging operations and the recovery of the logging tool to an uphole location, for example as a result of withdrawal of drillpipe from the borehole.

More specifically the logging tool preferably is a formation pressure tester that is deployable against the wellbore in dependence on commands generated by the programmable device.

The programmable device may be programmed to generate signals that cause the modulating valve to generate analogue pressure changes in the fluid in the conduit, the pressure changes mimicking pressure changes experienced by the formation pressure tester in use.

Such signals may be used to signify at an uphole location the correct deployment of a formation pressure tester forming part of the apparatus of the invention.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 131

In a preferred embodiment of the invention the pressure changes generated by the modulating valve include, in the case of a good test carried out by the formation pressure tester:

an initial pressure increase that mimics sealing of the formation pressure tester pad against the borehole;

a subsequent pressure decrease caused by operation of the pretest piston of the formation pressure tester that mimics exposure of the formation pressure tester transducer to formation fluid pressure; and

a subsequent pressure recovery that mimics the building up of formation fluid pressure within the formation pressure tester when the pretest is halted.

Another possibility is for the pressure generated by the modulating valve to include, in the case of the formation pressure tester experiencing a so-called "no seal" condition, a period of substantially invariant fluid pressure that mimics the fluid pressure exerted on the formation pressure tester when carrying out a no-seal test.

Yet a further possibility is for the pressure generated by the modulating valve to include, in the case of the formation pressure tester engaging a so-called "tight formation", a pressure drop (that mimics the fluid pressure experienced by the formation pressure tester when carrying out a pressure test on a tight formation); and a subsequent period without a substantial pressure recovery.

Each of the aforementioned types of pressure modulation generated by the modulating valve is distinctive of a particular instantaneously prevailing downhole condition.

Of the three conditions specified, the "no-seal" and "tight formation" indications would suggest to a human operator that the formation pressure

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 132

tester is incorrectly located for the acquisition of useful data. It is therefore a highly significant advantage of the apparatus of the invention to be able to signal to a human operator whether the formation pressure tester is incorrectly located. The human operator would then be able as necessary to adjust the position of the formation pressure tester (for example by running in or withdrawing a few inches of drillpipe at a time), with the aim of obtaining from the apparatus of the invention a transmitted indication that a good test has resulted.

The aforementioned formation type data are the kinds of data (that may either be transmitted in real time or stored in the memory device, when present, and subsequently transmitted) that it is envisaged to signal to an uphole location using the apparatus of the invention. The actual formation logs (that typically are highly complex and require detailed analysis and/or manipulation) would be fed from the formation pressure tester to the memory device and stored in the latter. On retrieval of the formation pressure tester and memory device to an uphole location the formation log data could be downloaded in a *per se* known manner.

Conveniently the apparatus of the invention includes a source of electrical power operatively connected to power as necessary the programmable device, the modulating valve and the logging tool. Consequently the apparatus is of the wireless type, that is associated with significant advantages.

Preferably the programmable device, the modulating valve, the logging tool and the source of electrical power are secured one to another in a discrete toolstring.

Thus the toolstring may be assembled at a surface location and deployed according to a modified version of the so-called garaging technique. The

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 133

apparatus of the invention may then signal to the uphole location whether the tool is correctly deployed and operating (and hence whether formation logging operations should commence).

According to a third aspect of the invention there is provided a method of deploying a logging tool in a wellbore using an apparatus as defined herein, the method comprising the steps of:

(i) running the downhole transducer, the processor, the release tool actuator, the activatable tool and the modulating valve to a downhole location on a length of drillpipe defining the conduit;

(ii) operating the pump under control of the control device to:

(a) circulate the wellbore; and

(b) generate one or more changes in fluid pressure, in the conduit, that are detectable by the downhole transducer whereby the downhole transducer generates one or more detected pressure signals that are indicative of the generated fluid pressure changes such that the processor generates one or more actuator commands that cause operation of the tool actuator so as to activate at least part of the activatable tool at the downhole location, activation of the activatable tool causing the modulating valve to modulate the pressure of fluid in the conduit; and

(iii) detecting the modulation of fluid pressure in the conduit at the remote location by means of the remote transducer.

Advantages of the apparatuses of the invention described hereinabove inure to the aforementioned method.

Preferably the sub-step of operating the pump to generate one or more changes in fluid pressure in the conduit includes the further sub-step of generating a waveform, in the fluid in the conduit, that is detectable at the remote location.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 134

Conveniently the sub-step of operating the pump to generate one or more changes in fluid pressure in the conduit includes the further sub-step of generating a sequence of digital pressure pulses in the fluid in the conduit; and the operation of the modulating valve includes the generation of one or more analogue pressure changes in the fluid in the conduit.

In other words the method of the invention preferably involves a combination of digital and analogue signals generated in wellbore fluid. The digital signals are employed when it is appropriate to do so (for example when transmitting simple data intended to initiate deployment of a logging tool). The analogue signals are used to indicate prevailing conditions at a downhole location.

Conveniently the step (i) includes the step of running mutually engaged latch parts, that secure at least part of the activatable tool and the drillpipe together, to the downhole location. This aspect of the method permits the use of a modified version of the *per se* known garaging tool deployment technique.

Preferably during the step of running the mutually engaged latch parts to the downhole location at least part of the activatable tool is retained in the retracted position relative to the drillpipe; and on operation of the release tool actuator at least part or all of the activatable tool moves relative to the drillpipe so as to protrude from the downhole end thereof.

It is also preferable that operation of the release tool actuator causes disengagement of the mutually engageable latch parts from one another.

The method of the invention also advantageously includes engagement of a landing dog secured to the activatable tool with a landing stop secured on the drillpipe.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 135

Such engagement of a landing stop and a landing dog ensures that the activatable tool does not detach from the drillpipe in which it is conveyed to a downhole location.

Conveniently, following engagement of the landing dog and the landing stop, one part of the activatable tool moves relative to another part, such relative movement between parts of the tool being subject to one or more of:

deceleration by virtue of deformation of a resiliently deformable member and/or

damping by forcing of a fluid via an orifice into an expandable chamber.

As noted hereinabove, these aspects of the method prevent potential damage to the components of apparatus carrying out the method of the invention by virtue of sudden deceleration of a large mass of borehole fluid and toolstring components. The damping using the orifice additionally helps to prevent the generation of spurious acoustic signals in the borehole fluid.

In addition the aforesaid damping and deceleration assist in the generation of the tool release and landing signals.

The method of the invention preferably includes operation of a servomechanism to move an actuator member to cause operation of the modulating valve, operation of the servomechanism being dependent on the generation of signals by the processor.

The use of a servomechanism to operate a modulating valve ensures accuracy of such operation. It also allows the use of a self-contained apparatus for carrying out the steps of the method, including an on-board

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 136

power supply for powering the servomechanism.

Preferably the method of the invention includes the sub-step of pumping at least part of the activatable tool between retracted and protruding positions relative to the downhole end of the drillpipe, using the pressure of fluid circulating in the wellbore.

More specifically the pumping of at least part of the activatable tool includes causing fluid under pressure in the conduit to act on at least one flexible, annular sealing member encircling a cylindrical part of the activatable tool so as slidingly to seal between the exterior of the tool and the interior of the conduit.

These aspects of the method of the invention advantageously make use of the circulating borehole fluid pressure to cause deployment of a logging tool.

Optionally the method also includes opening of a pressure release valve to vent fluid pressure from within a hollow part of the activatable tool if the pressure within the hollow part exceeds a predetermined threshold value.

Preferably the method of the invention includes balancing of fluid pressure in the hollow portion and fluid pressure in the conduit. Such balancing reduces the energy demand of the components needed to carry out the method steps.

In a particularly preferred embodiment of the invention activation of the activatable tool includes activation and operation of a formation pressure tester.

Conveniently activation of the formation pressure tester includes:

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 137

(iv) unlatching of the mutually engageable latch parts;

(v) landing of one or more landing dogs in a landing stop;

(vi) deployment of one or more deployable components of the formation pressure tester; and

(vii) powering up and/or self testing of the formation pressure tester

and wherein the method includes causing the modulating valve to generate signals in the fluid in the conduit that are indicative of one or more of (iv) to (vii).

Consequently the method of the invention is capable of signalling correct deployment of a logging tool.

The method of the invention also typically includes logging of data characteristic of a wellbore using a downhole logging tool; and recording of logged data using a downhole memory device. Subsequently the method typically includes the step of recovering the downhole memory device to an uphole location following the recording of data; and the subsequent analysis, modification, display and/or transmission of the recorded data.

Such steps highlight the versatility of the method of the invention, since the use of a downhole memory device obviates the need to try and transmit large amounts of complex formation data in digital form to an uphole location.

The method also preferably includes the steps of detecting changes in the pressure of fluid in the conduit, using a transducer at a location remote from the downhole transducer; the method further including generating one or more signals indicative of such detections of pressure changes. Consequently the method of the invention is capable of indicating to eg. a surface-located, human operator the initiation or completion of various

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 138

actions at a downhole location.

In a preferred embodiment of the invention the method includes as necessary powering the downhole transducer, the processor, the release tool actuator, the modulating valve and the activatable tool using a power source conveyed to the downhole location.

According to a fourth aspect of the invention there is provided a method of signalling between a downhole location in a wellbore and a further location that is remote therefrom, the method comprising the steps of:

pumping fluid, using a pump, in a conduit extending into the wellbore so as to pressurise fluid in the conduit;

operating a modulating valve at the downhole location to modulate the pressure of fluid in dependence on signals generated by a processor at the downhole location, the signals being characteristic of conditions at the downhole location; and

detecting modulations in the pressure of fluid in the conduit, resulting from operation of the modulating valve, at the further location.

More specifically the modulations caused by operation of the modulating valve are analogue mimics of data logged by the logging tool, especially data indicative of prevailing wellbore conditions. Such data are readily transmissible as narrow bandwidth signals that do not require a complex or high level transmission language.

Conveniently the processor is operatively connected to a servomechanism that when activated causes operation of the modulating valve by means of an actuator member, the method including causing the processor to operate the modulating valve.

Preferably the method includes the step of storing data logged by the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 139

logging tool in a memory device at the downhole location.

Even more specifically, the method includes the step of logging data indicative of the pressure of fluid proximate the wellbore at the downhole location, using a formation pressure tester.

Advantages of steps as aforesaid are set out herein in relation to other aspects of the apparatus and method of the invention.

Conveniently the modulations effected by the modulating valve in the case of a good pressure test include:

an initial pressure increase that mimics sealing of the formation pressure tester pad against the borehole;

a subsequent pressure decrease caused by operation of the pretest piston of the formation pressure tester that mimics exposure of the formation pressure tester transducer to formation fluid pressure; and

a subsequent pressure recovery that mimics the building up of formation fluid pressure within the formation pressure tester.

Another possibility is for the modulations effected by the modulating valve in the case of the formation pressure tester experiencing a "no-seal" formation to include:

a period of substantially invariant fluid pressure that mimics the fluid pressure experienced by the formation pressure tester when carrying out a test that fails to seal.

Yet a further possibility is for the modulations effected by the modulating valve in the case of the pressure tests encountering a tight formation to include:

a pressure drop that mimics the fluid pressure experienced by the formation pressure tester when carrying out a pressure test on a tight

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 140

formation; and a subsequent period without a substantial pressure recovery.

Thus the method of the invention is suitable for signifying whether a pressure test is correctly deployed to obtain good test data; or whether an operator or a control device should act to adjust the position of the formation pressure tester away from a no-seal or tight formation area of the wellbore.

The method of the invention may optionally include powering the modulating valve, the processor and the logging tool using a source of electrical power at the downhole location. Thus the method of the invention is suited to being carried out by a wireless, compact, battery / memory logging tool of a kind that is in general known.

There now follows a description of preferred embodiments of the invention, by way of non-limiting example, with reference being made to the accompanying drawings in which:

Figure 1 is a schematic overview of apparatus according to the invention;

Figures 2a-2e are a longitudinally sectioned view of a toolstring forming part of the Figure 1 apparatus;

Figure 3 is a plot of standpipe pressure against time in apparatus according to the invention, illustrating a series of acoustic signals that are transmissible in accordance with the method of the invention;

Figure 4 is a plot of standpipe pressure against time, illustrating the response of a toolstring such as shown in Figures 2a-2e to a series of acoustic signals as illustrated by Figure 3, the response being detected at an uphole location;

Figure 5 shows the typical response of a *per se* known formation pressure tester when carrying out a so-called "no-seal" test;

Figure 6 shows the response of a *per se* known formation pressure

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 141

tester when testing a so-called "tight formation";

Figure 7 shows the response of a *per se* known formation pressure tester when carrying out a good test; and

Figures 8 to 10 are plots of standpipe pressure against time to illustrate the signalling of formation pressure tester responses as shown in Figures 4 to 7 at an uphole location using the apparatuses and methods of the invention.

Referring to Figure 1, apparatus 10 according to the invention includes a positive displacement pump 11 of a *per se* known kind for circulating fluid under pressure in a wellbore 12. A control device such as a microprocessor or other programmable device 13 controls the speed at which pump 11 pumps fluid in the wellbore 12.

Pump 11 is connected via appropriately valved connections 14, 16 in a *per se* known manner for circulating fluid in wellbore 12.

Programmable device 13 is in the embodiment of the invention shown capable of adjusting the output of pump 11 to provide a constant flow rate regardless of the fluid pressure in the wellbore 12. Techniques for achieving a constant flow rate pump output are known to those skilled in the relevant art.

The connections 14, 16 are connected as shown in Figure 1 to a standpipe 17 that in the embodiment shown is at surface level, such that it is possible to gain physical access to the pressure in standpipe 17.

The end of standpipe 17 remote from pump 11 is connected in a fluid-transmitting, pressure-tight manner to a conduit in the form of drillpipe 18.

As shown schematically in Figure 1, drillpipe 18 extends into the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 142

wellbore 12.

It is known in the oil and gas production art that the extent to which a drillpipe protrudes into a wellbore is controllable, by virtue of the addition and/or removal of drillpipe joints at the uphole (surface) end 18a thereof. As a result it is common for the downhole end 18b of the drillpipe to be several hundreds or thousands of metres removed from the uphole end 18a.

As represented schematically in Figure 1, the wellbore 12 is unlikely to be straight, parallel sided and of constant diameter along its entire length.

The use of drillpipe as part of the apparatus of the invention is preferred; but it is possible for the conduit represented by reference numeral 18 in Figure 1 to take other forms if desired.

For example conduit 18 could in alternative embodiments of the invention be a length of so-called "coiled tubing" techniques for the deployment of which are known to those skilled in the oil and gas production arts.

At its downhole end 18b drillpipe 18 supports several components, forming part of the apparatus of the invention, that are for convenience shown in schematic form. Several of such components 21, 23 are in practical embodiments of the invention constituted as part of a logging toolstring 19

Toolstring 19 includes a transducer 21 that in use of the apparatus 10 is near the downhole end 18b of drillpipe 18, but that is moveable towards uphole end 18a of drillpipe 18 during and following data logging operations.

Transducer 21 is a pressure transducer such as, but not limited to, a strain gauge that is capable of detecting changes in the pressure of fluid surrounding it within drillpipe 18.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 143

An electronics section 23 of toolstring 19 contains various electronic components including a processor that is capable of generating one or more actuator commands, whereby to control one or more actuators located at the downhole end 18b of drillpipe 18; and a memory device such as a flash memory that is capable of logging data relating to the geological formations that the wellbore 12 perforates.

The downhole components constituting the toolstring 19 include a source of electrical power, in the form of a battery section 63.

An actuator represented schematically by reference numeral 24 is shown supported on the interior of drillpipe 18, a short distance uphole from end 18b.

In practice the apparatus of the invention may include more than one actuator. The actuators may be variously located on the drillpipe and/or the toolstring, depending on their precise function. For the purpose of the overview represented by Figure 1, a single pair of fixed latching detents 24 and corresponding, moveable dogs 32 represent the actuator function in the apparatus 10. In a practical embodiment of the invention, such as the arrangement shown in Figure 2, there might typically be three latching detents that are equi-spaced about the hollow interior of the drillpipe for example by means of a sleeve 51 inserted into the drillpipe end, and in which the detents 24 are formed as angled perforations.

Toolstring 19 exemplifies an activatable tool that in use of the apparatus occupies a downhole position.

Shown schematically in the drillpipe between latching arms 24 and downhole end 18b is a modulating valve 26. Modulating valve 26 is

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 144

capable of modulating the pressure of fluid in the drillpipe 18 in a manner described in more detail below.

Operation of modulating valve 26 to modulate fluid pressure in the drillpipe depends on the occurrence of one or more downhole events such as commencement of the deployment of toolstring 19; completion of the deployment of toolstring 19; and commencement of operation of a logging tool such as a formation pressure tester that is not visible in Figure 1.

Apparatus 10 additionally includes a remote transducer that is connected to detect pressure of fluid in the conduit at a location remote from downhole transducer 21.

The remote transducer is shown in Figure 1 as a pressure gauge 27 connected to indicate the pressure of fluid in standpipe 17. In practical embodiments of the invention the remote transducing function would additionally be provided by a processor such as laptop computer 28 shown connected via a suitable data cable 29 to a transducing device such as but not limited to a piezoelectric transducer or strain gauge 31, the various components being schematically shown operatively connected to measure and record fluid pressures in standpipe 17.

As is known in the relevant art, it is a common practice when carrying out operations at a downhole location to circulate the wellbore 12 with a pressurised fluid intended to perform various functions in the wellbore.

The composition and nature of wellbore fluids varies greatly from wellbore to wellbore. Methods within the scope of the invention include the use of a great variety of such fluids.

Control device 13 is programmable and in accordance with the invention is

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 145

programmed to cause pump 11 to circulate wellbore 12 with fluid under pressure.

The precise fluid pressure is dictated by numerous factors such as the nature of the wellbore fluid and the conditions prevailing at various downhole locations in wellbore 12. It is typical for the pressure of fluid circulating in wellbore 12 to be for example several thousand pounds per square inch (psi). The precise fluid pressure is chosen to permit circulation of the particular well under investigation.

Pump 11 is capable of generating such pressures in the wellbore fluid.

Control device 13 is programmed in accordance with the invention to cause the pump 11 to generate digital or analogue acoustic signals, in the form of pressure pulses, by way of modulation of the prevailing fluid pressure in wellbore 12.

Figure 3 shows a sequence of pressure pulses that pump 11 under the control of device 13 is capable of generating in the wellbore fluid.

Figure 3 plots the pressure detected in standpipe 17 against time. As shown, the pressure pulses are in the preferred embodiment of the invention digital pulses each having a timebase of 30 seconds.

Other sequences of pressure pulses are possible within the scope of the invention.

Figure 3 shows the modulating effect of the control device 13 on the fluid pressure. Figure 3 is not intended to indicate absolute wellbore fluid pressure values.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 146

In contrast to pump 11, modulating valve 26 is capable of producing analogue acoustic signals in the form of pressure pulses in a manner described in more detail hereinbelow.

As noted, drillpipe 18 is moveable within wellbore 12. Various techniques are known for adding and removing joints of drillpipe so as to vary the extent to which drillpipe 18 protrudes into wellbore 12.

Toolstring 19 includes at its uphole end one or more latching dogs 32 that during running in of the drillpipe 18 into wellbore 12 engage with the latching detents 24 so as to retain toolstring 19 in a retracted position in which it lies completely within drillpipe 18.

Movement of the latching dogs 32 in a predetermined manner causes them to disengage from latching detents 24. This allows the toolstring 19 to be pumped in a downhole direction by the pressurised fluid within drillpipe 18, so that the major part of toolstring 19 protrudes from the downhole end 18b thereof as shown in Figure 1.

Latching dogs (ie. arms) 32 operate under the control of a release tool activator 33 that is not visible in Figure 1 but is described in more detail hereinbelow.

The release tool activator 33 is in turn controlled by the programmable device represented schematically by electronics section 23 of toolstring 19. The programmable part of electronics section 23 is in accordance with the invention programmed to cause disengagement of the latching dogs 32 from the latching detents 24, in the event of the downhole transducer 21 detecting a predetermined sequence of acoustic signals in the borehole fluid. Preferably the predetermined sequence of acoustic signals is that shown in Figure 3, that is a simple series of digital pressure pulses the number of

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 147

which is controlled.

The simple sequence represented by Figure 3 may be simply and reliably generated by the pump 11, and does not require a complicated communications protocol or language.

Downhole end 18b of drillpipe 18 includes on its interior surface a landing stop in the form of an annular landing collar 34. Toolstring 19 includes a further annular landing collar 36. The landing collars 34 and 36 are mutually engageable upon the toolstring 19 being pumped beyond its position shown in Figure 1 protruding from downhole end 18b of drillpipe 18. The primary purpose of such engagement is to prevent the toolstring 19 from separating completely from the end of drillpipe 18.

The overview of the structure of apparatus 10 represented by Figure 1 indicates that in simple terms the apparatus performs a modified version of the garaging technique for the deployment and use of logging tools.

The essence of such use of the apparatus lies in part in the running in of drillpipe with the latching detents 24 serving to retain the toolstring 19 within downhole end 18b. This allows the running in over the majority of the depth of the well at tripping speed, thereby minimising rig time. Additionally the latching of the toolstring within the drillpipe allows rotation of the latter. This assists the running in operation.

When the downhole end 18b of drillpipe 18 approaches the TD of the well the rate of running in is reduced and then stopped as the TD is tagged. Throughout this process the pump 11 circulates the well in accordance with commands from control device 13.

Various methods of determining the drillpipe depth are possible within the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 148

scope of the invention. Regardless of the precise drillpipe depth measuring technique adopted, the next stage in operation of the apparatus involves the generation of digital pressure pulses as exemplified by Figure 3.

Transducer 21 detects the pressure pulses at the downhole end of the wellbore 12. Assuming that the electronics section 23 identifies the sequence of pressure pulses, according to its programming, as being indicative of a need to deploy the toolstring 19, the latching dogs 32 are withdrawn temporarily to free them from the detents 24 and allow them to pass through the drillpipe 18. The toolstring 19 is then pumped out of the downhole end 18b into the openhole section 22 of wellbore 12, until the landing collar 36 engages the landing collar 34 in order to retain the toolstring 19 in position ready to log the formation in the vicinity of open hole section 22.

Referring now to Figures 2a to 2e, there is shown an embodiments of apparatus according to the invention that illustrates the above-described principles in more detail and additionally includes numerous further features that are within the scope of the invention.

Figure 2 shows a toolstring 19 prior to its deployment from the drillpipe 18.

The uphole end of toolstring 19 includes a hollow, cylindrical body 37 that is open at its uphole end 38 to allow the circulation of fluid within cylindrical body 37.

The downhole end 39 of toolstring 19 is constituted by an essentially non-hollow cylinder supporting a plurality of toolstring sections.

At its extreme downhole end downhole section 39 may include a formation pressure tester. The formation pressure tester is, for simplicity, omitted

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 149

from Figure 2. However the formation pressure tester preferably is of a *per se* known design. As noted, the formation pressure tester could be augmented or replaced by one or more other logging tools.

The formation pressure tester is deployable from a compact configuration, in which all the parts of the formation pressure tester lie within an annular housing at downhole end 39 of toolstring 19; and an active position.

In the latter position of the formation pressure tester, one or more calliper arms protrudes radially outwardly therefrom to press an annular pad against the wall of wellbore 12 (that is omitted from Figure 2 for clarity). The formation pressure tester includes for this purpose a further pressure transducer (that is omitted from Figure 2).

The formation pressure tester includes an electronics section that is known *per se*.

A further electronics section 23, whose function is to control operation of modulating valve 26 that is described in more detail below, includes a programmable device in the form of a microprocessor; a memory device arranged to store data logged by the formation pressure tester; and an on-board power source in the form of a plurality of series- and parallel-connected batteries. The formation pressure tester and the components of the electronics section 23 are appropriately wired to one another so as to permit acquisition of data generated by the transducer in the formation pressure tester and its storage in the memory device.

Electronics section 23 is connected at its uphole end to a servomechanism consisting, in the embodiment shown, of an electric motor 42 whose rotary output shaft 43 is connected via an uphole gearbox 44 to a threaded lead screw 46 and ball nut 46a that convert the rotary output motion of motor 42

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 150

to linear form. At least the microprocessor of electronics section 23 is wired to the servomechanism such that the servomechanism operates under the command of the microprocessor. In practical embodiments of the invention it also is desirable for the memory device to be directly or indirectly connectable to the inputs of the servomechanism, so that (as desired) the servomechanism is operable in dependence on logged data stored in the memory device.

An actuator shaft 47 is secured to the uphole end of ball nut 46a and extends longitudinally through the hollow part 38 of the cylindrical body 37. Consequently actuator shaft 47 is moveable longitudinally in body section 38.

Downhole pressure transducer 21 is located adjacent the downhole end of electric motor 42. Transducer 21 is mounted within hollow body section 38 on the downhole side of a pressure balancer 48 described in more detail below.

At the uphole end of actuator shaft 47 the latching arms 32 pivotably secured thereto are, in the position of the apparatus shown in Figure 2, engaged with latching detent perforations 24 described schematically in relation to Figure 1. The perforations 24 are formed in the aforementioned sleeve 51 that is secured eg. 3 or 4 drillpipe joints uphole of the downhole end of the drillpipe 18. As is visible in Figure 2a the perforations 24 are angled relative to the longitudinal axis of the apparatus. The latching arms 32 include similarly angled protuberances 32a so that the arms 32 are capable of, before its deployment, retaining the toolstring 19 in the drillpipe 18 in a harpoon-like manner as shown.

At its uphole end, actuator shaft 47 terminates in a release tool 49 comprising the hollow sleeve 51 within which the free, uphole end 52 of

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 151

actuator shaft 47 is longitudinally slideable. The uphole end 52 of shaft 47 protrudes into sleeve 51. Within sleeve 51 shaft 47 terminates in an activator cam 33 that is engageable with the latching arms 32 to cause their release from the detent perforations 24.

Operation of the electric motor 42 under the control of the processor in the electronics section 23 causes shaft 43 to rotate. Lead screw 46 and ball nut 46a convert such motion into longitudinal, linear motion of actuator shaft 47.

Upon the processor sending an appropriate command to motor 42, cam 33 therefore moves longitudinally within sleeve 51 towards the latching arms 32.

The three release arms 32 are pivotably secured within the release sleeve 51. On such movement of cam 33 towards latching arms 32 the cam 33 engages the arms 24 and causes them to pivot out of engagement with the latching perforations 24, following shearing of shear pins 56 that retain the latching arms 24 in place until such movement of cam 33 as aforesaid.

On the cam 33 engaging the latching arms 32 the toolstring 19 is released with the result that it is free to slide towards the right of Figure 2.

At its uphole end the exterior of cylindrical portion 38 is encircled by a pair of *per se* known swab cups 57, 58. On such releasing of toolstring 19 following withdrawal of the latching arms 24 and release arms 56 the pressure of fluid in the drillpipe 18 acts on the swab cups 57, 58 and drives the toolstring 19 towards the right of Figure 2 so that the downhole components 39 protrude from the end of the drillpipe 18 in the manner outlined in connection with Figure 1.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 152

Intermediate its two ends actuator shaft 47 has secured thereon a valving member 59 including a circular, conical valving surface 61 that is seatable in a valve seat 62. Member 59 and seat 61 constitute the modulating valve 26 shown schematically in Figure 1. Conical valving surface 61 constitutes a somewhat large diameter, proportional valve needle.

Valving member 59 is rigidly secured to the exterior of actuator shaft 47. Consequently the longitudinal movement of actuator shaft 47 to the left and right in Figure 2 respectively causes unseating and re-seating of the valving member 59 in the seat 61.

As is evident from Figure 2, unseating of the valve surface 61 from the seat 62 opens a fluid flow path via a chamber 64, whence the fluid under pressure vents from within the tool via one or more radial ports 66 perforating cylindrical body 37.

Consequently opening of the modulating valve 26 causes a drop in the fluid pressure in the drillpipe 18. Such a pressure drop is detectable by the remote transducer 27 or 31 at the standpipe 17, and is proportional to the extent of unseating of the valve 26.

On re-seating of the valving member 59 on the seat 62 the flow of fluid via port 66 is blocked. Consequently the pressure in the drillpipe 18 increases, again in a proportional manner. This too is detectable by means of the transducer 27/31 at the uphole, standpipe location.

Movement of the toolstring 19 to the right of Figure 2 (ie. release of the toolstring as aforesaid) also causes a detectable pressure drop in the drillpipe 18, by virtue of removal of the blockage in drillpipe 18 caused by the presence of the toolstring in its latched position. Such a pressure drop is indicative of tool release.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 153

In Figure 2 the landing dogs 36 are shown as an annular collar encircling cylindrical body 37 near its uphole end 38 in the region between the swab cups 57, 58 and the modulating valve 26.

Immediately uphole of the landing dogs 36 hollow, cylindrical portion 38 is of reduced diameter as signified by reference numeral 69 and is encircled by a coiled spring 71.

At its uphole end spring 71 is retained by a further annular collar 72 encircling the cylindrical body 37. Collar 72 is secured to a hollow cylinder 73 on which the swab cups 57, 58 are secured.

Reduced diameter portion 69 is slideable in the manner of a telescope section within cylinder 73, against the resilience of coiled spring 71.

As a consequence of the landing dogs 36 engaging the drillpipe landing collar 34 (that is not visible in Figure 2), cylinder 73 slides towards landing dogs 36 against the resilience of coiled spring 71. This action gradually decelerates the mass of the toolstring 19 that is, in effect, supported by cylinder 73 during delatching and deployment operations; and also the mass of drillpipe fluid acting on the swab cups 57, 58. The mass of the fluid may be several tonnes, so it is important that the rate of the spring 71 is correctly chosen.

On the downhole side of the landing dogs 36 there is defined, by concentric, hollow, external cylindrical parts 74, 76 and cylindrical body 37 an annular chamber 77. Cylinder 74 is rigidly secured to collar 36.

The cylindrical parts 74, 76 are slideable one relative to another so that the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 154

length of chamber 77 is variable.

Adjacent the landing dogs 36 chamber 77 includes an annulus of (in the preferred embodiment) six damper ports 78.

In use of the apparatus annular chamber 77 is charged with drillpipe fluid via the damper ports 78. Upon the landing dogs engaging the landing collar chamber 77 elongates longitudinally by virtue of relative movement between the cylindrical parts 74 and 76, with the result that its volume increases.

As a consequence, fluid is drawn into chamber 77 via the damper ports 78 thereby damping the spring – mass – damper system defined by:

the mass of toolstring 19 and of the fluid acting uphole of the swab cups 57, 58;

the spring 67; and

the damper represented by the damper ports 78.

Consequently on landing of the landing dogs 36 in the landing collar (not shown) there is little or no likelihood of oscillation of the toolstring 18 in the drillpipe 18. Consequently the likelihood of spurious, acoustic signals being generated in the drillpipe is reduced or eliminated.

The apparatus of the invention additionally includes a pressure relief arrangement 79 valve that is openable to vent pressure from within a hollow part of the activatable tool should the pressure exceed a predetermined threshold such as 500 psi. In the embodiment shown the pressure relief valve is constituted by features of cylinders 74 and 76. As is evident from Figure 2, following landing of the landing dogs 36 in the landing collar pressure within the hollow, cylindrical section 37 continues to act on the swab cups 57, 58 tending to drive the toolstring 19 to the right of Figure 2.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 155

This causes sliding of cylinder 76 relative to (by then fixed) cylinder 74. Mutually aligned pressure relief ports 80, 81 perforate cylinders 37 and 74. The pressure acting on swab cups 57, 58 causes the cylinder 76 to move to the right of Figure 2 to expose pressure relief ports 81 via which pressure within body 37 may vent.

Thus pressure relief valve is arranged to open when landing of the landing dogs in the landing collar occurs. This curtails the increase of pressure within hollow section 37 following landing, in a way that is detectable in standpipe 17.

A secondary pressure relief valve 101 is present downhole of relief valve 79 to allow valve 26 to be disabled and to prevent the drillpipe pulling "wet". The resulting pressures cause a sleeve 102 that is secured to toolstring 19 by means of shear pins 103 to move to the right of Figure 2 and open one or more normally closed vent ports 104 to allow venting of fluid from within toolstring 19.

The swab cups 57, 58 are, as illustrated, of conventional design. In an alternative arrangement the swab cups may each be effectively a pair of conventional swab cups arranged "back-to-back" in a siamesed frustoconical shape so as to create a flexible, annular bulge encircling the cylindrical part of the drillstring and defining a sliding seal against the interior wall of the drillpipe 18.

Optionally a fishing neck, may be secured at the uphole end of toolstring 19 to permit retrieval of toolstring 19 from the borehole.

Such a fishing neck is when required secured to toolstring 19 before running in of the drillpipe 18.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 156

The fishing neck is perforated whereby to permit circulation of fluid via the hollow interior 37 of uphole section 38 of toolstring 19.

As shown in Figure 3, the typical digital acoustic signal generated by pump 11 under the control of controller 13 is a series of two pressure pulses each of 30 seconds duration and spaced by pressure decreases each of 30 seconds duration.

The pressure transducer 21 in the toolstring 19 detects such pulses and generates signals indicative thereof. By virtue of the wiring of the transducer such signals pass to the processor in the electronics section 23. Since the processor is programmed to recognise the sequence of pulses it generates commands to the electric servomotor 42 to cause the actuator shaft 47 to move to the left in Figures 2 to 5 and initiate release of the toolstring 19 from its retracted position to its operative position.

The diameter of the valving member 59 is such that it is moveable longitudinally in chamber 64 while still maintaining its seated condition. During running in of the drillpipe modulating valve 26 is in its open position (ie. with member 59 unseated from seat 62). On operation of the motor 42 as aforesaid member 59 seats in seat 62 to close modulating valve 26.

The motor 42 then continues to drive the valving member 59 to the left of Figure 2, causing it to pass more fully into chamber 64. By virtue of the rigid connection of cam 33 to member 59 (by means of shaft 47) this action causes cam 33 to engage the latching arm 32, shear the shear pins 56 and allow release of the toolstring 19.

As illustrated in Figure 4 by "tools released", this causes a drop in the drillpipe fluid pressure that is detectable at the standpipe 17, as the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 157

toolstring 19 commences its movement to the right and consequently dethrottles the fluid in drillpipe 18.

Figure 4 shows that the pressure reduction continues while the fluid pressure acts to pump the toolstring 19 to its deployed position. This period is signified by "tools pumped into openhole" in Figure 4.

On landing of the landing dogs 36 in the landing collar (not shown) halting of the toolstring causes a pressure build up in the hollow part 38 of toolstring 19 and hence in the standpipe 17. The pressure build up is visible in Figure 4, as signified by "tools landed in openhole,".

Once the pressure within hollow portion 38 of toolstring 19 exceeds the threshold pressure set for the pressure relief valve 79, the latter opens with the result that the standpipe pressure stabilises.

The pressure transducer 21 is capable of detecting this condition. It consequently generates a further signal that is interpreted by the processor in the electronics section 23 to initiate an activation procedure for a logging tool such as but not limited to a formation pressure tester.

The initiation routine of the formation pressure tester can include deployment of a calliper having a pad secured thereto; powering up of the electronic parts of the formation pressure tester; a self-testing routine.

On completion of such activities, such that the formation pressure tester is ready for use, the processor generates commands to the servomechanism causing the valve member 59 to unseat from seat 62 thereby causing a further pressure drop (signified by "control valve opens in tool to indicate power on, callipers open, data recorded and tools functional" in Figure 4) that is also detectable in standpipe 17.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 158

It follows from the foregoing that in use of the apparatus of the invention it is possible to initiate deployment of downhole components using signals generated at an uphole location. It is subsequently possible for the downhole components to signal correct deployment to the uphole location represented by standpipe 17.

Figure 5 shows the pressure response of the formation pressure tester in the event of it encountering a no-seal condition. In such circumstances the pad fails to seal adequately, for example because of excessive porosity of the surrounding strata.

As indicated in Figure 5, this leads to a constant pressure response within the formation pressure tester.

Figure 6 shows the pressure response of the formation pressure tester when encountering a so-called tight formation.

In this circumstance the pad seals correctly against the surrounding strata, and the pretest causes an initial pressure drop with the formation pressure tester. The pressure detected by the formation pressure tester however remains at a lower value thereafter.

A good pressure test is illustrated in Figure 7. In this circumstance the initial pressure drop is followed a short time later by a build up of formation pressure within the active chamber of the formation pressure tester. Such a pressure response in the formation pressure tester represents good data.

The apparatus of the invention is arranged such that the processor in the electronics section 23 analyses the pressure responses of the formation pressure tester, either in real time or following recording of the pressure

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 159

responses in the memory device forming part of the electronics section. The processor then is capable of commanding the servomotor 42 to open and close the modulating valve 26 in dependence on the formation pressure tester responses. This causes analogue modulation of the drillpipe fluid pressure with the result that the fluid pressure in the standpipe 17 modulates similarly.

Figures 8 to 10 show the standpipe pressures resulting from such operation of the processor, servomotor 42 and modulating valve 26. As is clear from Figures 8 to 10 in use of the apparatus of the invention the standpipe pressures closely mimic the actual formation pressure tester responses at the downhole location. Consequently an operator at a surface location (or indeed appropriately programmed software in a control computer) may interpret the standpipe pressure indications in order to ascertain whether conditions are correct for operation of the formation pressure tester.

In the event of the standpipe pressure indication signifying either a no-seal or a tight formation, the operator can run in or withdraw a short length of drillpipe 18 in order to reposition the formation pressure tester (following withdrawal of the pad thereof from the borehole wall) until a region of good formation quality is encountered, as signified by a pressure indication like that of Figure 10.

Modulating valve 26 is pressure balanced by virtue of conduit 83 providing drillpipe pressure on both the uphole and downhole ends of valving member 59. Conduit 83 connects to drillpipe pressure via ports 84 as shown in Figure 2c.

A further pressure balancer 48 balances the fluid pressures exerted on lead screw (ball screw) 46.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 160

Pressure balancer 48 includes a hollowed portion 63 of an end cap 46b secured on lead screw 46. Hollowed portion 63 is slightly downhole of solid end cap 46b that connects to rigid shaft 47. The threaded portion of lead screw 46 is threadedly received in hollow portion 63.

Annular O-ring seal 53a seals the uphole end of end cap 46b relative to an encircling cylinder 54. A further O-ring seal 53b uphole of end cap 40b, on shaft 47, defines an annular chamber 67 that is filled with air at atmospheric pressure. Downhole of end cap 46b the exterior of chamber 63 is sealed by a third O-ring 53c to the wall of toolstring 19.

The hollow portion 63 also contains air at atmospheric pressure. Consequently the borehole pressure acting in an annular chamber 67 encircling end cap 46b confers no net force on lead screw 46, as a result of atmospheric pressure acting on the components to either side thereof.

Thus a further annular chamber 86 lies, externally of end cap 46b, between O-rings 53a and 53c. Chamber 86 is connected via ports 87 to conduit 83. Hence borehole (drillpipe) pressure acts in chamber 86.

Conduit 83 extends further downhole to beyond the seals 53c.

Conduit 83 terminates at a pressure bulkhead 88 of *per se* known design. A pair of capillary tubes 89 connect the pressure transducer 21 to the bulkhead 88, whereby transducer 21 is able to detect the various pressure changes in the drillpipe 18.

One mode of use of the device of the invention, is following completion of a natural Gamma log of a borehole. The results of the Gamma log can be stored in the memory device of electronics section 23 before deployment thereof. The electronics section 23 can then cause operation of the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 161

modulating valve 26 partly in dependence on the Gamma log data. Consequently the apparatus is able to transmit to the uphole transducer 27 an absolute indication of the position of the toolstring 19 in the borehole at any given time.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 162

CLAIMS

1. Apparatus for remotely activating a tool in a wellbore, the apparatus comprising:

a positive displacement pump for causing circulation of a fluid under pressure in the wellbore;

a control device for controlling the speed of operation of the pump;

a conduit that is operatively connected to the pump and extends into the wellbore for conveying the fluid thereinto on operation of the pump;

a downhole transducer, that is capable of detecting changes in the pressure of the fluid and generating one or more detected pressure signals indicative thereof;

a processor that is capable of generating one or more actuator commands in dependence on detected pressure signals generated by the downhole transducer;

one or more actuators that are each operable to activate at least a part of a tool in dependence on a said actuator command;

an activatable tool at a downhole location;

a modulating valve for modulating the pressure of fluid in the conduit; and

a remote transducer that is operatively connected to detect pressure of the fluid in the conduit at a location remote from the downhole transducer, wherein operation of the modulating valve is dependent on a downhole event.

2. Apparatus according to Claim 1 wherein the control device is operable to cause the pump to generate one or more analogue acoustic signals, in the fluid, the waveforms or which are detectable by the downhole transducer.

3. Apparatus according to Claim 1 wherein the control device is

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 163

operable to cause the pump to generate one or more digital acoustic signals, in the fluid, the waveforms of which are detectable by the downhole transducer; and wherein the modulating valve is operable to generate one or more analogue or digital acoustic signals, in the fluid, that are detectable by the remote transducer.

4. Apparatus according to any of Claims 1 to 3 wherein the conduit is a drillpipe that is moveable within the wellbore; wherein the activatable tool is moveable relative to the drillpipe; and wherein the drillpipe and the activatable tool include mutually engageable latch parts that, when mutually engaged, retain at least part, or all, of the activatable tool in a retracted position relative to the drillpipe and when disengaged permit movement of the tool to an advanced position in which at least part of the tool protrudes or protrudes further from the downhole end of the drillpipe, the apparatus including a release tool activator that is operable to cause disengagement of the latch parts from one another.

5. Apparatus according to Claim 4 wherein the release tool activator includes or is controlled by a programmable device that is programmed to cause disengagement of the latch parts on the downhole transducer detecting a predetermined sequence of pressure changes in the fluid.

6. Apparatus according to Claim 4 or Claim 5 wherein the drillpipe includes on its interior surface one or more landing stops and the activatable tool includes protruding from an exterior surface one or more landing dogs that are each engageable with a said landing stop on the activatable tool moving to its advanced position relative to the drillpipe.

7. Apparatus according to Claim 5 or Claim 6 wherein the landing stop is or includes an annular landing collar extending about the interior surface of the drillpipe.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 164

8. Apparatus according to any of Claims 4 to 7 wherein operation of the release tool activator to cause disengagement of the latch parts also causes the modulating valve to close whereby movement of the tool to its advanced position causes dethrottling of the flow of fluid at the downhole location, such dethrottling being detectable at the remote location as a period of reduced fluid pressure.

9. Apparatus according to any of Claims 6 to 8 wherein the apparatus includes a pressure relief valve, whose opening threshold is predetermined; and the engagement of the or each said landing dog with a said landing stop causes the pressure relief valve to generate an analogue, acoustic signal that is indicative of landing of the tool in its advanced position relative to the drillpipe.

10. Apparatus according to Claim 8 or Claim 9 when dependent from Claim 8 wherein the modulating valve optionally is a proportional valve including a valve needle and a valve seat; and acoustic signals generated thereby conveniently are fluid pressure decreases that are proportional to the displacement of the valve needle relative to the seat.

11. Apparatus according to Claim 8 or Claim 9 when dependent from Claim 8 wherein the modulating valve preferably is a proportional valve including a valve needle and a seat therefor; and the acoustic signal is an increase in pressure that is proportional to the displacement of the valve needle relative to the seat.

12. Apparatus according to Claim 8 or any preceding claim dependent therefrom including an actuator member that is common to the release tool and the modulating valve whereby operation of the release tool causes movement of the modulating valve.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 165

13. Apparatus according to Claim 10 when dependent from Claim 9 wherein the common actuator member is a rod extending centrally within a toolstring, mutually spaced parts of the rod being secured respectively to the release tool, the valve member of the modulating valve and a servomechanism that moves the rod longitudinally in the toolstring in dependence on one or more said actuator commands.

14. Apparatus according to Claim 4 or any preceding claim dependent therefrom, the activatable tool including one or more reaction surfaces against which fluid pressure in the conduit acts.

15. Apparatus according to Claim 14 wherein the reaction surfaces include one or more flexible, annular sealing members encircling a cylindrical part of the activatable tool so as to seal between the exterior of the tool and the interior of the conduit.

16. Apparatus according to Claim 14 or Claim 15 when dependent from Claim 5 wherein the or each reaction surface is moveable longitudinally of the activatable tool relative to the landing dogs; and the apparatus includes a resiliently deformable member operatively interconnecting the or each reaction surface and a said landing dog.

17. Apparatus according to Claim 14 or any preceding claim dependent therefrom, wherein the logging toolstring includes a cylindrical member that is moveable relative to a chamber, the chamber including one or more ports providing communication between the interior and the exterior of the chamber and the cylindrical member closing the or each said port during deployment of the toolstring, the or each reaction surface being operatively connected to the cylindrical member such that on landing of the tool the cylindrical member moves to open the or each said port to limit the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 166

pressure of fluid in the chamber.

18. Apparatus according to Claim 17 wherein the chamber has formed therein an orifice, the orifice providing fluid communication between the conduit and a further chamber the volume of which changes on movement of the cylindrical member.

19. Apparatus according to Claim 17 or any preceding claim dependent therefrom wherein the resiliently deformable member is a coiled spring interconnecting the or each reaction member and the cylindrical member.

20. Apparatus according to Claim 17 or any preceding claim dependent therefrom wherein the chamber includes a wall member having defined therein each said port, the wall member including a perforated sleeve that is releasably secured on the chamber.

21. Apparatus according to Claim 18 or any preceding claim that depends therefrom including a pressure relief valve that opens to vent fluid pressure from within a hollow part of the activatable tool should the pressure within the hollow part exceed a predetermined threshold.

22. Apparatus according to Claim 21 including a first pressure balancer for balancing fluid pressure in the uphole and downhole sides of the modulating valve.

23. Apparatus according to Claim 22 including a further pressure balancer that in use lies downhole of the modulating valve and is operatively connected to equalise pressures acting on the uphole and downhole sides of the servomechanism.

24. Apparatus according to any preceding claim wherein the activatable

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 167

tool includes a formation pressure tester; and wherein the processor is programmed to generate one or more actuator commands for causing operation of the formation pressure tester.

25. Apparatus according to Claim 24 when dependent from Claim 13 wherein the processor is connected and programmed to generate commands for causing one or more of:

(i) operation of the servomechanism to cause unlatching of the mutually engageable latch parts and thereby cause movement of the toolstring, that generates an acoustic signal that is indicative of tool release; followed by

(ii) operation of the pressure relief valve;

(iii) deployment of one or more deployable components of the formation pressure tester; and

(iv) powering up and/or self-testing or one or more tools in a toolstring.

26. Apparatus according to Claim 13 or any preceding claim depending therefrom wherein the activatable tool includes a logging device and a memory device capable of recording data logged by the logging device, the processor being programmed to generate actuator commands for commanding the servomechanism to operate the modulating valve to generate fluid pressure signals in dependence on the recorded, logged data.

27. Apparatus according to any preceding claim, including a remote transducer that detects pressure of the fluid in the conduit at a location remote from the downhole pressure transducer and generates signals indicative thereof.

28. Apparatus according to Claim 27 wherein the remote transducer detects fluid pressure in a standpipe that interconnects the outlet of the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 168

pump and the interior of the conduit.

29. Apparatus according to any preceding claim including an on-board source of electrical power.

30. Apparatus for signalling between a downhole location in a wellbore and a further location that is remote from the downhole location, the apparatus comprising a conduit extending into the wellbore; a pump connected to supply fluid under pressure in the conduit; a modulating valve, at a downhole location, for modulating the pressure of fluid in the conduit; a programmable processor for controlling operation of the modulating valve; a memory device; and a remote transducer for detecting fluid pressure at the further location.

31. Apparatus according to Claim 30 wherein the memory device includes stored therein data logged in the wellbore; and wherein the programmable processor is programmed to cause the modulating valve to modulate the pressure of fluid in the conduit in a fashion that is characteristic of the logged data.

32. Apparatus according to Claim 31 wherein the programmable processor is programmed to cause the modulating valve to modulate the pressure of fluid in the conduit in a fashion that is characteristic of two data logs carried out at different times.

33. Apparatus according to Claim 32 wherein the earlier of the two logs is a low frequency Gamma log.

34. Apparatus according to any of Claims 30 to 33 wherein the modulating valve includes a valve member; a valve seat on which the valve is seatable to raise fluid pressure in the conduit and from which the valve

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 169

member is removable to reduce fluid pressure in the conduit; a servomechanism connected to operate in dependence on signals generated by the programmable processor; and an actuator member operatively interconnecting the servomechanism and the valve member whereby the valve is openable and closeable in dependence on the signals generated by the programmable processor.

35. Apparatus according to any of Claims 31 to 34 including a logging tool that is capable of logging data characteristic of the wellbore and/or a formation proximate thereto, the logging tool and the memory device being connectable one to the other so that the memory device stores data logged by the logging tool.

36. Apparatus according to Claim 35 wherein the logging tool is a formation pressure tester that is deployable against the wellbore in dependence on commands generated by the programmable device.

37. Apparatus according to Claim 36 wherein the programmable device is programmed to generate signals that cause the modulating valve to generate analogue pressure changes in the fluid in the conduit, the pressure changes mimicking pressure changes experienced by the formation pressure tester in use.

38. Apparatus according to Claim 37 wherein the pressure changes generated by the modulating valve include, in the case of a good test carried out by the formation pressure tester:

an initial pressure increase that mimics sealing of the formation pressure tester pad against the borehole;

a subsequent pressure decrease caused by operation of the pretest piston of the formation pressure tester that mimics exposure of the formation pressure tester transducer to formation fluid pressure; and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 170

a subsequent pressure recovery that mimics the building up of formation fluid pressure within the formation pressure tester when the pretest is halted.

39. Apparatus according to Claim 37 wherein the pressure changes generated by the modulating valve includes, in the case of the formation pressure tester experiencing a no-seal condition, a period of substantially invariant fluid pressure that mimics the fluid pressure exerted on the formation pressure tester when carrying out a no-seal test.

40. Apparatus according to Claim 37 wherein the pressure generated by the modulating valve includes, in the case of the formation pressure tester engaging a tight formation, an initial pressure drop; and a subsequent period without a substantial pressure recovery.

41. Apparatus according to any of Claims 30 to 40 including a source of electrical power operatively connected to power as necessary the programmable device, the modulating valve and the logging tool.

42. Apparatus according to Claim 41 wherein the programmable device, the modulating valve, the logging tool and the source of electrical power are secured one to another in a discrete toolstring.

43. A method of deploying a logging tool in a wellbore using an apparatus according to any of Claims 1 to 42, the method comprising the steps of:

(i) running the downhole transducer, the processor, the release tool actuator, the activatable tool and the modulating valve to a downhole location on a length of drillpipe defining the conduit;

(ii) operating the pump under control of the control device to:

(a) circulate the wellbore; and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 171

(b) generate one or more changes in fluid pressure, in the conduit, that are detectable by the downhole transducer whereby the downhole transducer generates one or more detected pressure signals that are indicative of the generated fluid pressure changes such that the processor generates one or more actuator commands that cause operation of the tool actuator so as to activate at least part of the activatable tool at the downhole location, activation of the activatable tool causing the modulating valve to modulate the pressure of fluid in the conduit; and

(iii) detecting the modulation of fluid pressure in the conduit at the remote location of means of the remote transducer.

44. A method according to Claim 43 wherein the sub-step of operating the pump to generate one or more changes in fluid pressure in the conduit includes the further sub-step of generating a waveform, in the fluid in the conduit, that is detectable at the remote location.

45. A method according to Claim 43 wherein the sub-step of operating the pump to generate one or more changes in fluid pressure in the conduit includes the further sub-step of generating a sequence of digital pressure pulses in the fluid in the conduit; and wherein the operation of the modulating valve includes the generation of one or more analogue pressure changes in the fluid in the conduit.

46. A method according to any of Claims 43 to 45 wherein the step (i) includes the step of running mutually engaged latch parts, that secure at least part of the activatable tool and the drillpipe together, to the downhole location.

47. A method according to Claim 46 wherein during the step of running the mutually engaged latch parts to the downhole location at least part of the activatable tool is retained in the retracted position relative to the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 172

drillpipe; and wherein on operation of the release tool actuator at least part, or all, of the activatable tool moves relative to the drillpipe so as to protrude from the downhole end thereof.

48. A method according to Claim 47 wherein operation of the release tool actuator causes disengagement of the mutually engageable latch parts from one another.

49. A method according to Claim 47 or Claim 48 including engagement of a landing dog secured to the activatable tool with a landing stop secured on the drillpipe.

50. A method according to Claim 49 wherein following engagement of the landing dog and the landing stop one part of the activatable tool moves relative to another part, such relative movement between parts of the tool being subject to one or more of:

deceleration by virtue of deformation of a resiliently deformable member and/or

damping by forcing of a fluid via an orifice into an expandable chamber.

51. A method according to any of Claims 43 to 50 including operation of a servomechanism to move an actuator member to cause operation of the modulating valve, operation of the servomechanism being dependent on the generation of signals by the processor.

52. A method according to any of Claims 43 to 51 including the sub-step of pumping at least part of the activatable tool between retracted and protruding positions relative to the downhole end of the drillpipe, using the pressure of fluid circulating in the wellbore.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 173

53. A method according to Claim 52 wherein the pumping of at least part of the activatable tool includes causing fluid under pressure in the conduit to act on at least one flexible, annular sealing member encircling a cylindrical part of the activatable tool so as slidingly to seal between the exterior of the tool and the interior of the conduit.

54. A method according to any of Claims 43 to 53 including opening of a pressure relief valve to vent fluid pressure from within a hollow part of the activatable tool if the pressure within the hollow part exceeds a predetermined threshold value.

55. A method according to Claim 54 including balancing of fluid pressure in the hollow portion and fluid pressure in the conduit.

56. A method according to any of Claims 43 to 55 wherein activation of the activatable tool includes activation and operation of a formation pressure tester.

57. A method according to Claim 56 wherein activation of the formation pressure tester includes:

(iv) unlatching of the mutually engageable latch parts;

(v) landing of one or more landing dogs in a landing stop;

(vi) deployment of one or more deployable components of the formation pressure tester; and

(vii) powering up and/or self testing of the formation pressure tester

and wherein the method includes causing the modulating valve to generate signals in the fluid in the conduit that are indicative of one or more of (iv) to (vii).

58. A method according to any of Claims 43 to 57 including logging of

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 174

data characteristic of a formation perforated by a wellbore using a downhole logging tool; and recording of logged data using a downhole memory device.

59. A method according to Claim 58 including the step of recovering the downhole memory device to an uphole location following the recording of data; and the subsequent analysis, modification, display and/or transmission of the recorded data.

60. A method according to any of Claims 43 to 59 including the detecting of changes in the pressure of fluid in the conduit, using a transducer at a location remote from the downhole transducer; the method further including generating one or more signals indicative of such detections of pressure changes.

61. A method according to any of Claims 43 to 60 including the sub-step of as necessary powering the downhole transducer, the processor, the release tool actuator, the modulating valve and the activatable tool using a power source conveyed to the downhole location.

62. A method of signalling between a downhole location in a wellbore and a further location that is remote therefrom, the method comprising the steps of:

pumping fluid, using a pump, in a conduit extending into the wellbore so as to pressurise fluid in the conduit;

operating a modulating valve at the downhole location to modulate the pressure of fluid in dependence on signals generated by a processor at the downhole location, the signals being characteristic of conditions at the downhole location; and

detecting modulations in the pressure of fluid in the conduit, resulting from operation of the modulating valve, at the further location.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 175

63. A method according to Claim 62 wherein the modulations caused by operation of the modulating valve are analogue mimics of data logged by the logging tool.

64. A method according to Claim 62 or Claim 63 wherein the processor is operatively connected to a servomechanism that when activated causes operation of the modulating valve by means of an actuator member, the method including causing the processor to operate the modulating valve.

65. A method according to any of Claims 62 to 64 including the step of storing data logged by the logging tool in a memory device at the downhole location.

66. A method according to any of Claims 62 to 65 including the step of logging data on the pressure of fluid proximate the wellbore at the downhole location, using a formation pressure tester.

67. A method according to Claim 66 wherein the modulations effected by the modulating valve in the case of a good pressure test include:

an initial pressure increase that mimics sealing of the formation pressure tester pad against the borehole;

a subsequent pressure decrease caused by operation of the pretest piston of the formation pressure tester that mimics exposure of the formation pressure tester transducer to formation fluid pressure; and

a subsequent pressure recovery that mimics the building up of formation fluid pressure within the formation pressure tester.

68. A method according to Claim 66 wherein modulations effected by the modulating valve in the case of the formation pressure tester experiencing a "no-seal" formation include:

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 176

a period of substantially invariant fluid pressure that mimics the fluid pressure experienced by the formation pressure tester when carrying out a test that fails to seal.

69. A method according to Claim 66 wherein modulations effected by the modulating valve in the case of the pressure tests encountering a tight formation include:

a pressure drop that mimics the fluid pressure experienced by the formation pressure tester when carrying out a pressure test on a tight formation; and a subsequent period without a substantial pressure recovery.

70. A method according to any of Claims 62 to 69 including powering the modulating valve, the processor and the logging tool using a source of electrical power at the downhole location.

71. A method according to any of Claims 43 to 61 or any of Claims 62 to 70 including the step of modulating acoustic signals generated in the borehole fluid with one or more waveforms that are characteristic of a low frequency Gamma log of the borehole.

72. A method according to any of Claims 43 to 61 including the step of causing operation of one or more pressure relief valves generally to equalise uphole and downhole fluid pressures acting on one or more components of the apparatus.

73. Apparatus generally as herein described, with reference to and/or as illustrated in the accompanying drawings.

74. Methods generally as herein described, with reference to and/or as illustrated in the accompanying drawings.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 177

Amendments to the claims have been filed as follows

1. Apparatus for remotely activating a tool in a wellbore, the apparatus comprising:

a positive displacement pump for causing circulation of a fluid under pressure in the wellbore;

a control device for controlling the speed of operation of the pump;

a conduit that is operatively connected to the pump and extends into the wellbore for conveying the fluid thereinto on operation of the pump;

a downhole transducer, that is capable of detecting changes in the pressure of the fluid and generating one or more detected pressure signals indicative thereof;

a processor that is capable of generating one or more actuator commands in dependence on detected pressure signals generated by the downhole transducer;

one or more actuators that are each operable to activate at least a part of a tool in dependence on a said actuator command;

an activatable tool at a downhole location;

a modulating valve for modulating the pressure of fluid in the conduit; and

a remote transducer that is operatively connected to detect pressure of the fluid in the conduit at a location remote from the downhole transducer; wherein operation of the modulating valve is dependent on a downhole event, wherein the control device is operable to cause the pump to generate one or more digital acoustic signals, in the fluid, the waveforms of which are detectable by the downhole transducer; and wherein the modulating valve is operable to generate one or more analogue acoustic signals, in the fluid, that are detectable by the remote transducer.

2. Apparatus according to Claim 1 wherein the control device is operable to cause the pump to generate one or more analogue acoustic

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 178

signals, in the fluid, the waveforms or which are detectable by the downhole transducer.

3. Apparatus according to Claim 1 or Claim 2 wherein the conduit is a drillpipe that is moveable within the wellbore; wherein the activatable tool is moveable relative to the drillpipe; and wherein the drillpipe and the activatable tool include mutually engageable latch parts that, when mutually engaged, retain at least part, or all, of the activatable tool in a retracted position relative to the drillpipe and when disengaged permit movement of the tool to an advanced position in which at least part of the tool protrudes or protrudes further from the downhole end of the drillpipe, the apparatus including a release tool activator that is operable to cause disengagement of the latch parts from one another.

4. Apparatus according to Claim 3 wherein the release tool activator includes or is controlled by a programmable device that is programmed to cause disengagement of the latch parts on the downhole transducer detecting a predetermined sequence of pressure changes in the fluid.

5. Apparatus according to Claim 3 or Claim 4 wherein the drillpipe includes on its interior surface one or more landing stops and the activatable tool includes protruding from an exterior surface one or more landing dogs that are each engageable with a said landing stop on the activatable tool moving to its advanced position relative to the drillpipe.

6. Apparatus according to Claim 4 or Claim 5 wherein the landing stop is or includes an annular landing collar extending about the interior surface of the drillpipe.

7. Apparatus according to any of Claims 3 to 6 wherein operation of the release tool activator to cause disengagement of the latch parts also

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 179

causes the modulating valve to close whereby movement of the tool to its advanced position causes dethrottling of the flow of fluid at the downhole location, such dethrottling being detectable at the remote location as a period of reduced fluid pressure.

8. Apparatus according to any of Claims 5 to 7 wherein the apparatus includes a pressure relief valve, whose opening threshold is predetermined; and the engagement of the or each said landing dog with a said landing stop causes the pressure relief valve to generate an analogue, acoustic signal that is indicative of landing of the tool in its advanced position relative to the drillpipe.

9. Apparatus according to Claim 7 or Claim 8 when dependent from Claim 8 wherein the modulating valve optionally is a proportional valve including a valve needle and a valve seat; and acoustic signals generated thereby conveniently are fluid pressure decreases that are proportional to the displacement of the valve needle relative to the seat.

10. Apparatus according to Claim 7 or Claim 8 when dependent from Claim 8 wherein the modulating valve preferably is a proportional valve including a valve needle and a seat therefor; and the acoustic signal is an increase in pressure that is proportional to the displacement of the valve needle relative to the seat.

11. Apparatus according to Claim 7 or any preceding claim dependent therefrom including an actuator member that is common to the release tool and the modulating valve whereby operation of the release tool causes movement of the modulating valve.

12. Apparatus according to Claim 9 when dependent from Claim 8 wherein the common actuator member is a rod extending centrally within a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 180

toolstring, mutually spaced parts of the rod being secured respectively to the release tool, the valve member of the modulating valve and a servomechanism that moves the rod longitudinally in the toolstring in dependence on one or more said actuator commands.

13. Apparatus according to Claim 3 or any preceding claim dependent therefrom, the activatable tool including one or more reaction surfaces against which fluid pressure in the conduit acts.

14. Apparatus according to Claim 13 wherein the reaction surfaces include one or more flexible, annular sealing members encircling a cylindrical part of the activatable tool so as to seal between the exterior of the tool and the interior of the conduit.

15. Apparatus according to Claim 13 or Claim 14 when dependent from Claim 4 wherein the or each reaction surface is moveable longitudinally of the activatable tool relative to the landing dogs; and the apparatus includes a resiliently deformable member operatively interconnecting the or each reaction surface and a said landing dog.

16. Apparatus according to Claim 13 or any preceding claim dependent therefrom, wherein the logging toolstring includes a cylindrical member that is moveable relative to a chamber, the chamber including one or more ports providing communication between the interior and the exterior of the chamber and the cylindrical member closing the or each said port during deployment of the toolstring, the or each reaction surface being operatively connected to the cylindrical member such that on landing of the tool the cylindrical member moves to open the or each said port to limit the pressure of fluid in the chamber.

17. Apparatus according to Claim 16 wherein the chamber has formed

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 181

therein an orifice, the orifice providing fluid communication between the conduit and a further chamber the volume of which changes on movement of the cylindrical member.

18. Apparatus according to Claim 16 or any preceding claim dependent therefrom wherein the resiliently deformable member is a coiled spring interconnecting the or each reaction member and the cylindrical member.

19. Apparatus according to Claim 16 or any preceding claim dependent therefrom wherein the chamber includes a wall member having defined therein each said port, the wall member including a perforated sleeve that is releasably secured on the chamber.

20. Apparatus according to Claim 17 or any preceding claim that depends therefrom including a pressure relief valve that opens to vent fluid pressure from within a hollow part of the activatable tool should the pressure within the hollow part exceed a predetermined threshold.

21. Apparatus according to Claim 20 including a first pressure balancer for balancing fluid pressure in the uphole and downhole sides of the modulating valve.

22. Apparatus according to Claim 21 including a further pressure balancer that in use lies downhole of the modulating valve and is operatively connected to equalise pressures acting on the uphole and downhole sides of the servomechanism.

23. Apparatus according to any preceding claim wherein the activatable tool includes a formation pressure tester; and wherein the processor is programmed to generate one or more actuator commands for causing operation of the formation pressure tester.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 182

24. Apparatus according to Claim 23 when dependent from Claim 12 wherein the processor is connected and programmed to generate commands for causing one or more of:

(i) operation of the servomechanism to cause unlatching of the mutually engageable latch parts and thereby cause movement of the toolstring, that generates an acoustic signal that is indicative of tool release; followed by

(ii) operation of the pressure relief valve;

(iii) deployment of one or more deployable components of the formation pressure tester; and

(iv) powering up and/or self-testing or one or more tools in a toolstring.

25. Apparatus according to Claim 12 or any preceding claim depending therefrom wherein the activatable tool includes a logging device and a memory device capable of recording data logged by the logging device, the processor being programmed to generate actuator commands for commanding the servomechanism to operate the modulating valve to generate fluid pressure signals in dependence on the recorded, logged data.

26. Apparatus according to any preceding claim, including a remote transducer that detects pressure of the fluid in the conduit at a location remote from the downhole pressure transducer and generates signals indicative thereof.

27. Apparatus according to Claim 26 wherein the remote transducer detects fluid pressure in a standpipe that interconnects the outlet of the pump and the interior of the conduit.

28. Apparatus according to any preceding claim including an on-board

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 183

source of electrical power.

29. Apparatus for signalling between a downhole location in a wellbore and a further location that is remote from the downhole location, the apparatus comprising a conduit extending into the wellbore; a pump connected to supply fluid under pressure in the conduit; a modulating valve, at a downhole location, for modulating the pressure of fluid in the conduit; a programmable processor for controlling operation of the modulating valve; a memory device; and a remote transducer for detecting fluid pressure at the further location.

30. Apparatus according to Claim 29 wherein the memory device includes stored therein data logged in the wellbore; and wherein the programmable processor is programmed to cause the modulating valve to modulate the pressure of fluid in the conduit in a fashion that is characteristic of the logged data.

31. Apparatus according to Claim 30 wherein the programmable processor is programmed to cause the modulating valve to modulate the pressure of fluid in the conduit in a fashion that is characteristic of two data logs carried out at different times.

32. Apparatus according to Claim 31 wherein the earlier of the two logs is a low frequency Gamma log.

33. Apparatus according to any of Claims 29 to 32 wherein the modulating valve includes a valve member; a valve seat on which the valve is seatable to raise fluid pressure in the conduit and from which the valve member is removable to reduce fluid pressure in the conduit; a servomechanism connected to operate in dependence on signals generated by the programmable processor; and an actuator member operatively

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 184

interconnecting the servomechanism and the valve member whereby the valve is openable and closeable in dependence on the signals generated by the programmable processor.

34. Apparatus according to any of Claims 30 to 33 including a logging tool that is capable of logging data characteristic of the wellbore and/or a formation proximate thereto, the logging tool and the memory device being connectable one to the other so that the memory device stores data logged by the logging tool.

35. Apparatus according to Claim 34 wherein the logging tool is a formation pressure tester that is deployable against the wellbore in dependence on commands generated by the programmable device.

36. Apparatus according to Claim 35 wherein the programmable device is programmed to generate signals that cause the modulating valve to generate analogue pressure changes in the fluid in the conduit, the pressure changes mimicking pressure changes experienced by the formation pressure tester in use.

37. Apparatus according to Claim 36 wherein the pressure changes generated by the modulating valve include, in the case of a good test carried out by the formation pressure tester:

an initial pressure increase that mimics sealing of the formation pressure tester pad against the borehole;

a subsequent pressure decrease caused by operation of the pretest piston of the formation pressure tester that mimics exposure of the formation pressure tester transducer to formation fluid pressure; and

a subsequent pressure recovery that mimics the building up of formation fluid pressure within the formation pressure tester when the pretest is halted.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 185

38. Apparatus according to Claim 36 wherein the pressure changes generated by the modulating valve includes, in the case of the formation pressure tester experiencing a no-seal condition, a period of substantially invariant fluid pressure that mimics the fluid pressure exerted on the formation pressure tester when carrying out a no-seal test.

39. Apparatus according to Claim 36 wherein the pressure generated by the modulating valve includes, in the case of the formation pressure tester engaging a tight formation, an initial pressure drop; and a subsequent period without a substantial pressure recovery.

40. Apparatus according to any of Claims 29 to 39 including a source of electrical power operatively connected to power as necessary the programmable device, the modulating valve and the logging tool.

41. Apparatus according to Claim 40 wherein the programmable device, the modulating valve, the logging tool and the source of electrical power are secured one to another in a discrete toolstring.

42. A method of deploying a logging tool in a wellbore using an apparatus according to any of Claims 1 to 41, the method comprising the steps of:

(i) running the downhole transducer, the processor, the release tool actuator, the activatable tool and the modulating valve to a downhole location on a length of drillpipe defining the conduit;

(ii) operating the pump under control of the control device to:

(a) circulate the wellbore; and

(b) generate one or more changes in fluid pressure, in the conduit, that are detectable by the downhole transducer whereby the downhole transducer generates one or more detected pressure signals that

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 186

are indicative of the generated fluid pressure changes such that the processor generates one or more actuator commands that cause operation of the tool actuator so as to activate at least part of the activatable tool at the downhole location, activation of the activatable tool causing the modulating valve to modulate the pressure of fluid in the conduit; and

(iii) detecting the modulation of fluid pressure in the conduit at the remote location of means of the remote transducer, wherein the sub-step of operating the pump to generate one or more changes in fluid pressure in the conduit includes the further sub-step of generating a sequence of digital pressure pulses in the fluid in the conduit; and wherein the operation of the modulating valve includes the generation of one or more analogue pressure changes in the fluid in the conduit.

43. A method according to Claim 42 wherein the sub-step of operating the pump to generate one or more changes in fluid pressure in the conduit includes the further sub-step of generating a waveform, in the fluid in the conduit, that is detectable at the remote location.

44. A method according to Claim 42 or Claim 43 wherein the step (i) includes the step of running mutually engaged latch parts, that secure at least part of the activatable tool and the drillpipe together, to the downhole location.

45. A method according to Claim 44 wherein during the step of running the mutually engaged latch parts to the downhole location at least part of the activatable tool is retained in the retracted position relative to the drillpipe; and wherein on operation of the release tool actuator at least part, or all, of the activatable tool moves relative to the drillpipe so as to protrude from the downhole end thereof.

46. A method according to Claim 45 wherein operation of the release

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 187

tool actuator causes disengagement of the mutually engageable latch parts from one another.

47. A method according to Claim 45 or Claim 46 including engagement of a landing dog secured to the activatable tool with a landing stop secured on the drillpipe.

48. A method according to Claim 47 wherein following engagement of the landing dog and the landing stop one part of the activatable tool moves relative to another part, such relative movement between parts of the tool being subject to one or more of:

deceleration by virtue of deformation of a resiliently deformable member and/or

damping by forcing of a fluid via an orifice into an expandable chamber.

49. A method according to any of Claims 42 to 48 including operation of a servomechanism to move an actuator member to cause operation of the modulating valve, operation of the servomechanism being dependent on the generation of signals by the processor.

50. A method according to any of Claims 42 to 49 including the sub-step of pumping at least part of the activatable tool between retracted and protruding positions relative to the downhole end of the drillpipe, using the pressure of fluid circulating in the wellbore.

51. A method according to Claim 50 wherein the pumping of at least part of the activatable tool includes causing fluid under pressure in the conduit to act on at least one flexible, annular sealing member encircling a cylindrical part of the activatable tool so as slidingly to seal between the exterior of the tool and the interior of the conduit.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 188

52. A method according to any of Claims 42 to 51 including opening of a pressure relief valve to vent fluid pressure from within a hollow part of the activatable tool if the pressure within the hollow part exceeds a predetermined threshold value.

53. A method according to Claim 52 including balancing of fluid pressure in the hollow portion and fluid pressure in the conduit.

54. A method according to any of Claims 42 to 53 wherein activation of the activatable tool includes activation and operation of a formation pressure tester.

55. A method according to Claim 54 wherein activation of the formation pressure tester includes:

(iv) unlatching of the mutually engageable latch parts;

(v) landing of one or more landing dogs in a landing stop;

(vi) deployment of one or more deployable components of the formation pressure tester; and

(vii) powering up and/or self testing of the formation pressure tester

and wherein the method includes causing the modulating valve to generate signals in the fluid in the conduit that are indicative of one or more of (iv) to (vii).

56. A method according to any of Claims 42 to 55 including logging of data characteristic of a formation perforated by a wellbore using a downhole logging tool; and recording of logged data using a downhole memory device.

57. A method according to Claim 56 including the step of recovering the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 189

downhole memory device to an uphole location following the recording of data; and the subsequent analysis, modification, display and/or transmission of the recorded data.

58. A method according to any of Claims 42 to 57 including the step of detecting of changes in the pressure of fluid in the conduit, using a transducer at a location remote from the downhole transducer; the method further including generating one or more signals indicative of such detections of pressure changes.

59. A method according to any of Claims 42 to 58 including the sub-step of as necessary powering the downhole transducer, the processor, the release tool actuator, the modulating valve and the activatable tool using a power source conveyed to the downhole location.

60. A method of signalling between a downhole location in a wellbore and a further location that is remote therefrom, the method comprising the steps of:

pumping fluid, using a pump, in a conduit extending into the wellbore so as to pressurise fluid in the conduit;

operating a modulating valve at the downhole location to modulate the pressure of fluid in dependence on signals generated by a processor at the downhole location, the signals being characteristic of conditions at the downhole location; and

detecting modulations in the pressure of fluid in the conduit, resulting from operation of the modulating valve, at the further location.

61. A method according to Claim 60 wherein the modulations caused by operation of the modulating valve are analogue mimics of data logged by the logging tool.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 190

62. A method according to Claim 60 or Claim 61 wherein the processor is operatively connected to a servomechanism that when activated causes operation of the modulating valve by means of an actuator member, the method including causing the processor to operate the modulating valve.

63. A method according to any of Claims 60 to 62 including the step of storing data logged by the logging tool in a memory device at the downhole location.

64. A method according to any of Claims 60 to 63 including the step of logging data on the pressure of fluid proximate the wellbore at the downhole location, using a formation pressure tester.

65. A method according to Claim 64 wherein the modulations effected by the modulating valve in the case of a good pressure test include:

an initial pressure increase that mimics sealing of the formation pressure tester pad against the borehole;

a subsequent pressure decrease caused by operation of the pretest piston of the formation pressure tester that mimics exposure of the formation pressure tester transducer to formation fluid pressure; and

a subsequent pressure recovery that mimics the building up of formation fluid pressure within the formation pressure tester.

66. A method according to Claim 65 wherein modulations effected by the modulating valve in the case of the formation pressure tester experiencing a "no-seal" formation include:

a period of substantially invariant fluid pressure that mimics the fluid pressure experienced by the formation pressure tester when carrying out a test that fails to seal.

67. A method according to Claim 64 wherein modulations effected by

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 191

the modulating valve in the case of the pressure tests encountering a tight formation include:

a pressure drop that mimics the fluid pressure experienced by the formation pressure tester when carrying out a pressure test on a tight formation; and a subsequent period without a substantial pressure recovery.

68. A method according to any of Claims 60 to 67 including powering the modulating valve, the processor and the logging tool using a source of electrical power at the downhole location.

69. A method according to any of Claims 42 to 59 or any of Claims 60 to 68 including the step of modulating acoustic signals generated in the borehole fluid with one or more waveforms that are characteristic of a low frequency Gamma log of the borehole.

70. A method according to any of Claims 42 to 59 including the step of causing operation of one or more pressure relief valves generally to equalise uphole and downhole fluid pressures acting on one or more components of the apparatus.

71. Apparatus generally as herein described, with reference to and/or as illustrated in the accompanying drawings.

72. Methods generally as herein described, with reference to and/or as illustrated in the accompanying drawings.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 192

Application No: GB 0218784.7 **Examiner:** Nicholas Mole
Claims searched: 1-29, 43-61, 71-72 **Date of search:** 18 November 2002

Patents Act 1977
Search Report under Section 17

Databases searched:

UK Patent Office collections, including GB, EP, WO & US patent specifications, in:

UK Cl (Ed.T): E1F FKU FHK FHU FKD FKE FKF FKG

Int Cl (Ed.7): E21B 23/00 23/04 47/12 47/14 47/16 47/18

Other: Online: WPI EPODOC JAPIO

Documents considered to be relevant:

Category	Identity of document and relevant passage		Relevant to claims
A	EP 0551163 A	(HALLIBURTON)	
X	WO 1999/054591 A	(SCHLUMBERGER) see esp. abstract	1 at least
X	WO 1994/029572 A	(BAKER HUGHES) see esp. page 25 line 13 to page 30 line 19 and claim 50	1 at least
A	US 6310829 B	(GREEN)	
X	US 6105690	(BIGLIN) see esp. col. 5 lines 26-39 and col. 6 lines 44-67	1 at least
X	US 4896722	(UPCHURCH) see esp. col. 13 line 66 to col. 15 line 10	1 at least

X Document indicating lack of novelty or inventive step
Y Document indicating lack of inventive step if combined with one or more other documents of same category.
& Member of the same patent family
A Document indicating technological background and/or state of the art.
P Document published on or after the declared priority date but before the filing date of this invention.
E Patent document published on or after, but with priority date earlier than, the filing date of this application.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 193

Electronic Patent Application Fee Transmittal

Application Number:	13480704
Filing Date:	25-May-2012
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Filer:	Jessie D. Herrera/Stephanie Dominguez
Attorney Docket Number:	SAFO/0012USP1

Filed as Small Entity

Filing Fees for Utility under 35 USC 111(a)

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Basic Filing:				
Pages:				
Claims:				
Miscellaneous-Filing:				
Petition:				
Patent-Appeals-and-Interference:				
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Miscellaneous:				
Request for Continued Examination	2801	1	600	600
		Total in USD ($)		**600**

Electronic Acknowledgement Receipt	
EFS ID:	22669651
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Stephanie Dominguez
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	18-JUN-2015
Filing Date:	25-MAY-2012
Time Stamp:	12:44:19
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	Credit Card
Payment was successfully received in RAM	$600
RAM confirmation Number	13262
Deposit Account	
Authorized User	
The Director of the USPTO is hereby authorized to charge indicated fees and credit any overpayment as follows:	

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1		Response.pdf	86963 74ab15dc46e0388f9d197825c691270f6b3ad05d	yes	8

Multipart Description/PDF files in .zip description

Document Description	Start	End
Response After Final Action	1	1
Claims	2	5
Applicant Arguments/Remarks Made in an Amendment	6	8

Warnings:					
Information:					
2	Request for Continued Examination (RCE)	RCE.pdf	1350028 979ad6c510731c5700ca4e117c7b66371bee83a0	no	3
Warnings:					
Information:					
3	Information Disclosure Statement (IDS) Form (SB08)	IDS.pdf	612419 61114b8f708b9fffef8d6d99c74101ff1810b64d	no	4
Warnings:					
Information:					
4	Foreign Reference	GB2391880A.pdf	3368845 615e037391e453ef4882780dd328b1db1ddada1a	no	91
Warnings:					
Information:					
5	Non Patent Literature	AU_Exam_Rep_2014Feb13.pdf	250232 042c5da3e91b8efbc98ff6529e5216300e7320b1	no	4
Warnings:					
Information:					
6	Non Patent Literature	SG_SearchRep_2014Oct17-.pdf	360567 336c08655d97e21e2c6fdd1d7d883bd16ff96e18	no	19

Warnings:					
Information:					
7	Fee Worksheet (SB06)	fee-info.pdf	30760 80a478877ea8e59508c4cee5b40504a628c60e36	no	2
Warnings:					
Information:					
		Total Files Size (in bytes):	6059814		

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: David Lymberopoulos	§	
Serial No.: 13/480,704	§	Group Art Unit: 3753
Filed: May 25, 2012	§	Examiner: McCalister, William M.
Confirmation No.: 9598	§	
For: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE	§	

MAIL STOP AF
Commissioner for Patents
P.O. Box 1450
Alexandria, VA 22313-1450

Dear Sir:

RESPONSE TO FINAL OFFICE ACTION DATED MARCH 24, 2015

In response to the Office Action dated March 24, 2015, please enter this response and reconsider the claims pending in the application for the reasons discussed below. Although Applicant believes that no additional fees are due in connection with this response, the Commissioner is hereby authorized to charge counsel's Deposit Account No. 20-0782/SAFO/0012USP1/JDH for any fees required to make this response timely and acceptable to the Office.

Amendments to the Claims begin on page 2 of this paper.

Remarks begin on page 6 of this paper.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 199

AMENDMENTS TO THE CLAIMS

Please cancel claims 7 and 16, and amend the claims as follows:

1. (Currently Amended) A control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve having a gate;

a valve actuator configured to move the gate into a closed position by fluid supplied into the valve actuator and configured to move the gate into an open position by a biasing member disposed in the valve actuator;

an electronic controller assembly configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property;

a valve assembly in communication with the controller assembly; and

a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid ~~to~~ into the valve actuator to move the gate ~~to a first~~ into the closed position, and wherein the controller assembly is operable to actuate the valve assembly to ~~actuate~~ release the fluid from the valve actuator ~~to move~~ so that the biasing member moves the gate ~~to a second position~~ into the open position and forces the fluid out of the valve actuator.

2. (Original) The system of claim 1, further comprising a housing for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

3. (Currently Amended) The system of claim 2, wherein the fluid supplied into the valve actuator by the fluid drive assembly is supplied from a reservoir disposed outside of the housing.

4. (Withdrawn) The system of claim 1, wherein the fluid drive assembly is a compressor and the fluid is a pneumatic fluid.

5. (Currently Amended) The system of claim 1, wherein the fluid drive assembly is a pump and the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid.

6. (Original) The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly.

7. (Canceled)

8. (Original) The system of claim 1, further comprising a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly.

9. (Withdrawn) The system of claim 1, wherein the fluid is ambient air.

10. (Original) The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system.

11. (Currently Amended) The system of claim 1, wherein the controller assembly is a programmable logic controller~~, and wherein the valve assembly is operable to release or return fluid from the safety valve for actuating the safety valve to the second position~~.

12. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve having a gate, a valve actuator configured to move the gate, a housing, an electronic controller assembly, a fluid drive assembly, and a valve assembly;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 201

supplying fluid ~~to~~ into the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into ~~a first~~ a closed position;

monitoring a physical property in the flow line using the controller assembly; and

actuating the valve assembly using the controller assembly to release the fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position and forces the fluid out of the valve actuator ~~actuate the valve actuator to move the gate into a second position~~ based upon a comparison of the monitored physical property to a predetermined condition.

13. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid disposed external to the housing, and further comprising filtering the pneumatic fluid as it enters the housing by the fluid drive assembly.

14. (Currently Amended) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid disposed in a reservoir within the housing that is in fluid communication with the fluid drive assembly.

15. (Original) The method of claim 12, further comprising measuring the physical property using a transducer configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. (Canceled)

17. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid, and wherein the fluid drive assembly is a compressor.

18. (Currently Amended) The method of claim 12, wherein the fluid supplied into the valve actuator by the fluid drive assembly is a hydraulic fluid, and wherein the fluid drive assembly is a pump.

19. (Original) The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve.

20. (Original) The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly.

21. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve having a gate, a valve actuator configured to move the gate, and a sensor;

actuating the valve actuator to move the gate into a closed position by supplying actuator fluid ~~to~~ into the valve actuator;

monitoring fluid pressure in the flow line using the sensor while maintaining the gate in the closed position; and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator ~~and moving~~ so that a biasing member disposed in the valve actuator moves the gate into an open position and forces the actuator fluid out of the valve actuator to relieve fluid pressure in the flow line.

REMARKS

This is intended as a full and complete response to the Office Action dated March 24, 2015. Claims 1-21 are pending in the application. Claims 4, 9, 13, and 17 stand withdrawn. Claims 1-3, 5-8, 10-12, 14-16, and 18-21 stand rejected. Claims 7 and 16 have been canceled. Reconsideration of the rejected claims is requested for the reasons presented below.

Claim Rejections Under 35 USC § 112

Claims 3, 5, 14 and 18 stand rejected under 35 U.S.C. § 112(b) or 35 U.S.C. 112 (pre-AIA), second paragraph. In response, claims 3, 5, 14, and 18 have been amended to clarify the antecedent basis for the "fluid" as noted by the Examiner. Applicant respectfully requests withdrawal of the rejection.

Claim Rejections Under 35 USC § 102

Claims 1, 6, 7, 12, 15, 16, and 18 stand rejected under pre-AIA 35 U.S.C. § 102(b) as being anticipated by *Wailes* (US 3,776,249). Claims 7 and 16 have been canceled.

Claim 1 has been amended to recite "wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid into the valve actuator to move the gate into the closed position, and wherein the controller assembly is operable to actuate the valve assembly to release the fluid from the valve actuator so that the biasing member moves the gate into the open position and forces the fluid out of the valve actuator." Claim 12 has been amended to recite "actuating the valve assembly using the controller assembly to release the fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position and forces the fluid out of the valve actuator based upon a comparison of the monitored physical property to a predetermined condition." *Wailes* fails to disclose these elements of claims 1 and 12.

Wailes discloses a control apparatus having a hydraulic system 17 that directs fluid through separate fluid lines 18, 19 into a power operator 16 (such as a double-acting piston and cylinder assembly) to open and close a valve. See Col. 3, lines 1-8.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 204

Since the valve is opened and closed by fluid supplied into the power operator 16 via separate fluid lines 18, 19, *Wailes* does not disclose a controller assembly operable to actuate a valve assembly to release fluid from a valve actuator so that a biasing member disposed in the valve actuator moves a gate of a safety valve into an open position and forces the fluid out of the valve actuator, as recited in claims 1 and 12. *Wailes* thus fails to disclose or suggest each and every element of claims 1 and 12, and claims dependent therefrom. Applicant respectfully requests withdrawal of the rejection and allowance of the claims.

Claim Rejections Under 35 USC § 103

Claims 1-3, 5-8, 10-12, 14-16, and 18-21 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Vinegar* (US 2003/0051881) in view of *Cotham* (US 5,335,730). Claims 7 and 16 have been canceled.

Claim 1 has been amended to recite "wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid into the valve actuator to move the gate into the closed position, and wherein the controller assembly is operable to actuate the valve assembly to release the fluid from the valve actuator so that the biasing member moves the gate into the open position and forces the fluid out of the valve actuator." Claim 12 has been amended to recite "actuating the valve assembly using the controller assembly to release the fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position and forces the fluid out of the valve actuator based upon a comparison of the monitored physical property to a predetermined condition." Claim 21 has been amended to recite "actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator so that a biasing member disposed in the valve actuator moves the gate into an open position and forces the actuator fluid out of the valve actuator to relieve fluid pressure in the flow line." *Vinegar* and *Cotham* fail to disclose these elements of claims 1, 12, and 21.

Vinegar discloses a system 70, as shown in Figures 4 and 6, which includes a pilot valve 82 that simultaneously directs fluid into an upper chamber of an actuator 84 while directing fluid out of a lower chamber of the actuator 84 (or vice versa) through

separate fluid lines to open and close a valve 74. Since the valve 74 is opened and closed by fluid supplied into the actuator 84 via separate fluid lines 18, 19, *Vinegar* does not disclose a controller assembly operable to actuate a valve assembly to release fluid from a valve actuator so that a biasing member disposed in the valve actuator moves a gate of a safety valve into an open position and forces the fluid out of the valve actuator, as recited in claims 1, 12, and 21. *Cotham* discloses a wellhead control system but fails to cure the deficiency of *Vinegar*. *Vinegar* in view of *Cotham* thus fails to disclose or suggest each and every element of claims 1, 12, and 21, and claims dependent therefrom. Applicant respectfully requests withdrawal of the rejection and allowance of the claims.

Conclusion

Having addressed all issues set out in the final office action, Applicant respectfully submits that the claims are in condition for allowance and respectfully requests that the claims be allowed.

Respectfully submitted,

/Jessie D. Herrera/
Jessie D. Herrera
Registration No. 63,799
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046
Telephone: (713) 623-4844
Facsimile: (713) 623-4846
Attorney for Applicant(s)

PTO/SB/06 (09-11)
Approved for use through 1/31/2014. OMB 0651-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PATENT APPLICATION FEE DETERMINATION RECORD Substitute for Form PTO-875	Application or Docket Number 13/480,704	Filing Date 05/25/2012	☐ To be Mailed

ENTITY: ☐ LARGE ☒ SMALL ☐ MICRO

APPLICATION AS FILED – PART I

FOR	(Column 1) NUMBER FILED	(Column 2) NUMBER EXTRA	RATE ($)	FEE ($)
☐ BASIC FEE (37 CFR 1.16(a), (b), or (c))	N/A	N/A	N/A	
☐ SEARCH FEE (37 CFR 1.16(k), (i), or (m))	N/A	N/A	N/A	
☐ EXAMINATION FEE (37 CFR 1.16(o), (p), or (q))	N/A	N/A	N/A	
TOTAL CLAIMS (37 CFR 1.16(i))	minus 20 =	*	X $ =	
INDEPENDENT CLAIMS (37 CFR 1.16(h))	minus 3 =	*	X $ =	
☐ APPLICATION SIZE FEE (37 CFR 1.16(s))	If the specification and drawings exceed 100 sheets of paper, the application size fee due is $310 ($155 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).			
☐ MULTIPLE DEPENDENT CLAIM PRESENT (37 CFR 1.16(j))				
* If the difference in column 1 is less than zero, enter "0" in column 2.			TOTAL	

APPLICATION AS AMENDED – PART II

AMENDMENT 06/18/2015

	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
Total (37 CFR 1.16(i))	* 19	Minus	** 21	= 0	X $40 =	0
Independent (37 CFR 1.16(h))	* 3	Minus	*** 3	= 0	X $210 =	0
☐ Application Size Fee (37 CFR 1.16(s))						
☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
					TOTAL ADD'L FEE	0

AMENDMENT

	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
Total (37 CFR 1.16(i))	*	Minus	**	=	X $ =	
Independent (37 CFR 1.16(h))	*	Minus	***	=	X $ =	
☐ Application Size Fee (37 CFR 1.16(s))						
☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
					TOTAL ADD'L FEE	

* If the entry in column 1 is less than the entry in column 2, write "0" in column 3.

** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 20, enter "20".

*** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 3, enter "3".

The "Highest Number Previously Paid For" (Total or Independent) is the highest number found in the appropriate box in column 1.

LIE
/POLIN ANG/

This collection of information is required by 37 CFR 1.16. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

26290 7590 03/24/2015

PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

EXAMINER	
MCCALISTER, WILLIAM M	

ART UNIT	PAPER NUMBER
3753	

NOTIFICATION DATE	DELIVERY MODE
03/24/2015	ELECTRONIC

Please find below and/or attached an Office communication concerning this application or proceeding.

The time period for reply, if any, is set in the attached communication.

Notice of the Office communication was sent electronically on above-indicated "Notification Date" to the following e-mail address(es):

PSDocketing@pattersonsheridan.com
pair_eofficeaction@pattersonsheridan.com
jcardenas@pattersonsheridan.com

Office Action Summary	Application No. 13/480,704	Applicant(s) LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	AIA (First Inventor to File) Status No

-- The MAILING DATE of this communication appears on the cover sheet with the correspondence address --

Period for Reply

A SHORTENED STATUTORY PERIOD FOR REPLY IS SET TO EXPIRE *3* MONTHS FROM THE MAILING DATE OF THIS COMMUNICATION.

- Extensions of time may be available under the provisions of 37 CFR 1.136(a). In no event, however, may a reply be timely filed after SIX (6) MONTHS from the mailing date of this communication.
- If NO period for reply is specified above, the maximum statutory period will apply and will expire SIX (6) MONTHS from the mailing date of this communication.
- Failure to reply within the set or extended period for reply will, by statute, cause the application to become ABANDONED (35 U.S.C. § 133). Any reply received by the Office later than three months after the mailing date of this communication, even if timely filed, may reduce any earned patent term adjustment. See 37 CFR 1.704(b).

Status

1)☒ Responsive to communication(s) filed on *12/29/14*.

☐ A declaration(s)/affidavit(s) under **37 CFR 1.130(b)** was/were filed on _____.

2a)☒ This action is **FINAL**. 2b)☐ This action is non-final.

3)☐ An election was made by the applicant in response to a restriction requirement set forth during the interview on _____; the restriction requirement and election have been incorporated into this action.

4)☐ Since this application is in condition for allowance except for formal matters, prosecution as to the merits is closed in accordance with the practice under *Ex parte Quayle*, 1935 C.D. 11, 453 O.G. 213.

Disposition of Claims*

5)☒ Claim(s) *1-21* is/are pending in the application.

5a) Of the above claim(s) *4,9,13 and 17* is/are withdrawn from consideration.

6)☐ Claim(s) _____ is/are allowed.

7)☒ Claim(s) *1-3, 5-8, 10-12, 14-16 and 18-21* is/are rejected.

8)☐ Claim(s) _____ is/are objected to.

9)☐ Claim(s) _____ are subject to restriction and/or election requirement.

* If any claims have been determined allowable, you may be eligible to benefit from the **Patent Prosecution Highway** program at a participating intellectual property office for the corresponding application. For more information, please see http://www.uspto.gov/patents/init_events/pph/index.jsp or send an inquiry to PPHfeedback@uspto.gov.

Application Papers

10)☐ The specification is objected to by the Examiner.

11)☒ The drawing(s) filed on *5/25/12* is/are: a)☒ accepted or b)☐ objected to by the Examiner.

Applicant may not request that any objection to the drawing(s) be held in abeyance. See 37 CFR 1.85(a).

Replacement drawing sheet(s) including the correction is required if the drawing(s) is objected to. See 37 CFR 1.121(d).

Priority under 35 U.S.C. § 119

12)☐ Acknowledgment is made of a claim for foreign priority under 35 U.S.C. § 119(a)-(d) or (f).

Certified copies:

a)☐ All b)☐ Some** c)☐ None of the:

1.☐ Certified copies of the priority documents have been received.

2.☐ Certified copies of the priority documents have been received in Application No. _____.

3.☐ Copies of the certified copies of the priority documents have been received in this National Stage application from the International Bureau (PCT Rule 17.2(a)).

** See the attached detailed Office action for a list of the certified copies not received.

Attachment(s)

1) ☒ Notice of References Cited (PTO-892)

2) ☒ Information Disclosure Statement(s) (PTO/SB/08a and/or PTO/SB/08b) Paper No(s)/Mail Date *10/14/14, 12/29/14*.

3) ☐ Interview Summary (PTO-413) Paper No(s)/Mail Date. _____ .

4) ☐ Other: _____.

The present application is being examined under the pre-AIA first to invent provisions.

Claims 4, 9, 13 and 17 have been withdrawn. Claims 1-3, 5-8, 10-12, 14-16 and 18-21 will be treated on the merits.

Claim Rejections - 35 USC § 112

The following is a quotation of 35 U.S.C. 112(b):
(b) CONCLUSION.—The specification shall conclude with one or more claims particularly pointing out and distinctly claiming the subject matter which the inventor or a joint inventor regards as the invention.

The following is a quotation of 35 U.S.C. 112 (pre-AIA), second paragraph:
The specification shall conclude with one or more claims particularly pointing out and distinctly claiming the subject matter which the applicant regards as his invention.

Claims 3, 5, 14 and 18 are rejected under 35 U.S.C. 112(b) or 35 U.S.C. 112 (pre-AIA), second paragraph, as being indefinite for failing to particularly point out and distinctly claim the subject matter which the inventor or a joint inventor, or for pre-AIA the applicant regards as the invention. Claim 1 introduces a plurality of fluids (see the preambles and the bodies), and it cannot be determined to which of these fluids claims 3 and 5 refer back. Claim 12 similarly introduces a plurality of fluids, and it cannot be determined to which of these fluids claims 14 and 18 refer back.

Claim Rejections - 35 USC § 102

The text of those sections of Title 35, U.S. Code not included in this action can be found in a prior Office action.

Claims 1, 6, 7, 12, 15, 16 and 18 are rejected under pre-AIA 35 U.S.C. 102(b) as being anticipated by Wailes (US 3,776,249).

Wailes discloses:

1. A control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve (11) having a gate (11 is a “gate valve”);

a valve actuator (16) configured to move the gate;

an electronic controller assembly (122) configured to receive a signal from a transducer (41) connected to the flow line, wherein the signal corresponds to a measured physical property (41 is a pressure transducer);

a valve assembly (111) in (indirect) communication with the controller assembly; and

a fluid drive assembly (119, 121) in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the valve actuator to move the gate to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the valve actuator to move the gate to a second position (the controller controls the position of the safety valve by controlling the position of 111, in turn by controlling the positions of 119 and 121).

6. The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly (a power source is inherent).

7. The system of claim 1, wherein the first position is a closed position and the second position is an open position (both positions are obtained via the operation of 111, 119 and 121).

12. A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve (11) having a gate, a valve actuator (16) configured to move the gate, a housing (13), an electronic controller assembly (122), a fluid drive assembly (119 and 121; alternatively 112), and a valve assembly (111);

supplying fluid to the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into a first position (the closed position described at col. 7 lines 22-62);

monitoring a physical property in the flow line using the controller assembly (via 41); and

actuating the valve assembly using the controller assembly to actuate the valve actuator to move the gate into a second position *based upon* a comparison of the

monitored physical property to a predetermined condition (the open position described at described at col. 7 lines 22-62; note that the term “based upon” is seen as broad enough to read on the relationship disclosed at col. 5 line 65 to col. 6 line 1).

15. The method of claim 12, further comprising measuring the physical property using a transducer (41) configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. The method of claim 12, wherein the first position is a closed position and the second position is an open position (as mapped above).

18. The method of claim 12, wherein the fluid is a hydraulic fluid, and wherein the fluid drive assembly (112) is a pump.

Claim Rejections - 35 USC § 103

The following is a quotation of pre-AIA 35 U.S.C. 103(a) which forms the basis for all obviousness rejections set forth in this Office action:

> (a) A patent may not be obtained though the invention is not identically disclosed or described as set forth in section 102 of this title, if the differences between the subject matter sought to be patented and the prior art are such that the subject matter as a whole would have been obvious at the time the invention was made to a person having ordinary skill in the art to which said subject matter pertains. Patentability shall not be negatived by the manner in which the invention was made.

The factual inquiries set forth in *Graham v. John Deere Co.*, 383 U.S. 1, 148 USPQ 459 (1966), that are applied for establishing a background for determining obviousness under pre-AIA 35 U.S.C. 103(a) are summarized as follows:

1. Determining the scope and contents of the prior art.

2. Ascertaining the differences between the prior art and the claims at issue.

3. Resolving the level of ordinary skill in the pertinent art.

4. Considering objective evidence present in the application indicating obviousness or nonobviousness.

This application currently names joint inventors. In considering patentability of the claims under pre-AIA 35 U.S.C. 103(a), the examiner presumes that the subject matter of the various claims was commonly owned at the time any inventions covered therein were made absent any evidence to the contrary. Applicant is advised of the obligation under 37 CFR 1.56 to point out the inventor and invention dates of each claim that was not commonly owned at the time a later invention was made in order for the examiner to consider the applicability of pre-AIA 35 U.S.C. 103(c) and potential pre-AIA 35 U.S.C. 102(e), (f) or (g) prior art under pre-AIA 35 U.S.C. 103(a).

Claims 1-3, 5-8, 10-12, 14-16 and 18-21 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Vinegar (US 2003/0051881) in view of Cotham (US 5,335,730).

Regarding claim 1, Vinegar discloses a control system for controlling fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve (12) having a gate (see paragraph 0023);

a valve actuator (84) configured to move the gate;

an electronic controller assembly (90);

a valve assembly (82) in communication with the controller assembly; and

a fluid drive assembly (76, 78) in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the valve actuator to move the gate to a first position (closed), and wherein the controller assembly is operable to actuate the valve assembly to actuate the valve actuator to move the gate to a second position (open) (paragraph 0043).

Vinegar does not disclose the controller to be configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property. Cotham teaches that it was known in the art at the time of invention to protect against over- and under-pressures by configuring a similar controller (114) to receive a signal from a transducer (135) connected to a similar flow line, wherein the signal corresponds to a measured physical property (135 is a pressure transducer) (see col. 8 lines 6-25). To protect against over- and under-pressure in Vinegar's system, it would have been obvious to configure the controller to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property, as taught by Cotham.

Regarding claim 2, Vinegar discloses the system of claim 1, further comprising a housing (72 and 28 together form a housing) for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

Regarding claim 3, Vinegar discloses the system of claim 2, wherein the fluid is supplied from a reservoir disposed outside of the housing (as understood, during assembly, or during filling of the system with fluid).

Regarding claim 5, Vinegar discloses the system of claim 1, wherein the fluid drive assembly (76, 78) is a pump and the fluid is a hydraulic fluid (mentioned throughout the specification).

Regarding claim 6, Vinegar discloses the system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly (a power source is inherent).

Regarding claim 7, Vinegar discloses the system of claim 1, wherein the first position is a closed position and the second position is an open position (as mapped in the analysis above).

Regarding claim 8, Vinegar discloses the system of claim 1, further comprising a housing (72, 26) for supporting the fluid drive assembly. Vinegar does not disclose a filter as claimed. Cotham teaches that it was known to use a filter ("D" at the bottom of FIG 6) attached to a similar housing for filtering fluid entering the housing by a similar fluid drive assembly. To remove debris from Vinegar's fluid, it would have been obvious to use a filter as claimed.

Regarding claim 10, Vinegar discloses the claimed communications capability of the controller, via the presence of modems 89 and 48. Alternatively, should it be determined that Vinegar does not disclose the claimed communication capability, then consider that it was well-known in the art at the time of invention to communicate sensor readings to a master control panel so that users can monitor the sensed parameters, and it would have been obvious to create such a capability in Vinegar's controller assembly so that users of Vinegar's system can remotely monitor Vinegar's sensed pressure.

Regarding claim 11, Vinegar does not disclose the controller to be a PLC. Cotham teaches that PLCs were known in the art at the time of invention (col. 8 line 49), and it would have been obvious to embody Vinegar's controller as a PLC in order to increase it's adaptability (via programmability). Vinegar discloses the safety valve to release fluid for returning it to the second position (the safety valve actuator both receives and expels fluid when it moves in either direction).

Regarding claim 12, Vinegar discloses method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve (74) having a gate, a valve actuator (84) configured to move the gate, a housing (26, 72), an electronic controller assembly (90), a fluid drive assembly (76, 78), and a valve assembly (82);

supplying fluid to the valve actuator using the fluid drive assembly to actuate the valve actuator to move the gate into a first position (paragraph 0043).

Vinegar does not disclose monitoring a physical property in the flow line using the controller assembly and actuating the valve assembly to move the gate into a second position *based upon* a comparison of the monitored physical property to a predetermined condition. Cotham teaches that it was known in the art to monitor a physical property in the flow line using the controller assembly and actuating the valve assembly to move the gate into a second position *based upon* a comparison of the monitored physical property to a predetermined condition (col. 8 lines 6-26). To void extremely high and low pressures in Vinegar's pipeline, it would have been obvious to monitor a physical property in the flow line using the controller assembly and actuating the valve assembly to move the gate into a second position *based upon* a comparison of the monitored physical property to a predetermined condition, as taught by Cotham.

Regarding claims 14-16, 18 and 19, see the analyses of the corresponding apparatus claims set forth above.

Regarding claim 20, Vinegar discloses actuating the safety valve by communicating a signal from a remote computer system to the controller assembly (paragraph 0043, 2nd sentence).

Regarding claim 21, the claimed method would necessarily be performed during the normal and usual operation of the device set forth in the obviousness analysis above (where the claimed method steps are seen as clearly corresponding to the recited features and capabilities of the apparatus as mapped above).

Response to Arguments

Applicant's arguments regarding the previous 112 rejections and drawing objections are persuasive and these rejections are withdrawn. Applicant's arguments with respect to the previous 102 and 103 rejections have been considered but are moot because the arguments do not apply to any of the references being used in the current rejection. Vinegar, Cotham, and Wailes disclose the claimed features (i.e., the gate and fluid drive assembly).

Conclusion

Applicant's amendment necessitated the new ground(s) of rejection presented in this Office action. Accordingly, **THIS ACTION IS MADE FINAL**. See MPEP § 706.07(a). Applicant is reminded of the extension of time policy as set forth in 37 CFR 1.136(a).

A shortened statutory period for reply to this final action is set to expire THREE MONTHS from the mailing date of this action. In the event a first reply is filed within TWO MONTHS of the mailing date of this final action and the advisory action is not mailed until after the end of the THREE-MONTH shortened statutory period, then the shortened statutory period will expire on the date the advisory action is mailed, and any extension fee pursuant to 37 CFR 1.136(a) will be calculated from the mailing date of the advisory action. In no event, however, will the statutory period for reply expire later than SIX MONTHS from the date of this final action.

Any inquiry concerning this communication or earlier communications from the examiner should be directed to **William McCalister**, whose telephone number **571-270-1869**. The examiner can normally be reached on Monday-Friday (7:00AM-5:30PM EST).

If attempts to reach the examiner by telephone are unsuccessful, the examiner's supervisors can be reached by phone. Craig Schneider can be reached at 571-272-3607 or John Fristoe can be reached at 571-272-4926. The fax phone number for the organization where this application or proceeding is assigned is 571-273-8300.

Information regarding the status of an application may be obtained from the Patent Application Information Retrieval (PAIR) system. Status information for

published applications may be obtained from either Private PAIR or Public PAIR. Status information for unpublished applications is available through Private PAIR only. For more information about the PAIR system, see http://pair-direct.uspto.gov. Should you have questions on access to the Private PAIR system, contact the Electronic Business Center (EBC) at 866-217-9197 (toll-free). If you would like assistance from a USPTO Customer Service Representative or access to the automated information system, call 800-786-9199 (IN USA OR CANADA) or 571-272-1000.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

3/19/15

Notice of References Cited	Application/Control No. 13/480,704	Applicant(s)/Patent Under Reexamination LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	Page 1 of 1

U.S. PATENT DOCUMENTS

*		Document Number Country Code-Number-Kind Code	Date MM-YYYY	Name	Classification
*	A	US-3,776,249 A	12-1973	Wailes et al.	137/14
*	B	US-5,335,730 A	08-1994	Cotham, III, Heman C.	166/374
*	C	US-2003/0051881 A1	03-2003	Vinegar et al.	166/374
	D	US-			
	E	US-			
	F	US-			
	G	US-			
	H	US-			
	I	US-			
	J	US-			
	K	US-			
	L	US-			
	M	US-			

FOREIGN PATENT DOCUMENTS

*		Document Number Country Code-Number-Kind Code	Date MM-YYYY	Country	Name	Classification
	N					
	O					
	P					
	Q					
	R					
	S					
	T					

NON-PATENT DOCUMENTS

*		Include as applicable: Author, Title Date, Publisher, Edition or Volume, Pertinent Pages)
	U	
	V	
	W	
	X	

*A copy of this reference is not being furnished with this Office action. (See MPEP § 707.05(a).)
Dates in MM-YYYY format are publication dates. Classifications may be US or foreign.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99**)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS						Remove
Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					
If you wish to add additional U.S. Patent citation information please click the Add button.						Add

U.S.PATENT APPLICATION PUBLICATIONS						Remove
Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					
If you wish to add additional U.S. Published Application citation information please click the Add button.						Add

FOREIGN PATENT DOCUMENTS							Remove	
Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐
If you wish to add additional Foreign Patent Document citation information please click the Add button							Add	

NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Receipt date: 10/14/2014	Application Number	13480704 13480704 - GAU: 3753
INFORMATION DISCLOSURE STATEMENT BY APPLICANT	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
(**Not for submission under 37 CFR 1.99)**	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

	1	Canadian Office Action for Canadian Patent Applicaton Number 2,806,849, dated August 29, 2014.	☐

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature	/William Mccalister/	Date Considered	03/19/2015

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Search Notes	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	Art Unit
	WILLIAM MCCALISTER	3753

CPC- SEARCHED		
Symbol	Date	Examiner
G05D 16/2086 good for electrical controls for a fluid pilot valve that controls a main valve	7/7/2014	wm
F16K 17/00 this invention meets the definition of "safety" but this subclass is very large and includes a lot of irrelevant art	7/7/2014	wm

CPC COMBINATION SETS - SEARCHED		
Symbol	Date	Examiner

US CLASSIFICATION SEARCHED			
Class	Subclass	Date	Examiner
137	488, 492, 492.5	7/7/2014	wm

SEARCH NOTES		
Search Notes	Date	Examiner
updated ccls and cpc searches	3/19/2015	wm

INTERFERENCE SEARCH			
US Class/ CPC Symbol	US Subclass / CPC Group	Date	Examiner

	/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	4062379		1977-12-13	Clinton	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

If you wish to add additional Foreign Patent Document citation information please click the Add button Add

NON-PATENT LITERATURE DOCUMENTS Remove

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Receipt date: 12/29/2014	Application Number	13480704 13480704 - GAU: 3753
INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99**)	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

	1	Chinese Office Action for Chinese Patent Applicaton Number 201180038303.7, dated October 23, 2014.	☐

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature	/William Mccalister/	Date Considered	03/19/2015

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 227

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	4062379		1977-12-13	Clinton	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

If you wish to add additional Foreign Patent Document citation information please click the Add button Add

NON-PATENT LITERATURE DOCUMENTS Remove

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

	1	Chinese Office Action for Chinese Patent Applicaton Number 201180038303.7, dated October 23, 2014.	☐

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☒ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/B. Todd Patterson/	Date (YYYY-MM-DD)	2014-12-29
Name/Print	B. Todd Patterson	Registration Number	37906

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 231

PTO/SB/22 (03-13)
Approved for use through 3/31/2013. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PETITION FOR EXTENSION OF TIME UNDER 37 CFR 1.136(a)	Docket Number (Optional) 1435.054959
Application Number 13/480,704-Conf. #9598	Filed May 25, 2012
For SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE	
Art Unit 3753	Examiner W. M. McCalister

This is a request under the provisions of 37 CFR 1.136(a) to extend the period for filing a reply in the above-identified application.

The requested extension and fee are as follows (check time period desired and enter the appropriate fee below):

	Fee	Small Entity Fee	Micro Entity Fee	
☐ One month (37 CFR 1.17(a)(1))	$200	$100	$50	$
☐ Two months (37 CFR 1.17(a)(2))	$600	$300	$150	$
☒ Three months (37 CFR 1.17(a)(3))	$1,400	$700	$350	$ 700.00
☐ Four months (37 CFR 1.17(a)(4))	$2,200	$1,100	$550	$
☐ Five months (37 CFR 1.17(a)(5))	$3,000	$1,500	$750	$

☐ Applicant asserts small entity status. See 37 CFR 1.27.

☐ Applicant certifies micro entity status. See 37 CFR 1.29.
Form PTO/SB/15A or B or equivalent must either be enclosed or have been submitted previously.

☐ A check in the amount of the fee is enclosed.

☐ Payment by credit card. Form PTO-2038 is attached.

☐ The Director has already been authorized to charge fees in this application to a Deposit Account.

☒ The Director is hereby authorized to charge any fees which may be required, or credit any overpayment, to Deposit Account Number 20-0782 .

☒ Payment made via EFS-Web.

WARNING: Information on this form may become public. Credit card information should not be included on this form. Provide credit card information and authorization on PTO-2038.

I am the

☐ applicant/inventor.

☐ assignee of record of the entire interest. See 37 CFR 3.71. 37 CFR 3.73(b) statement is enclosed (Form PTO/SB/96).

☒ attorney or agent of record. Registration number 37,906 .

☐ attorney or agent acting under 37 CFR 1.34. Registration number _____.

/B. Todd Patterson/	December 29, 2014
Signature	Date
B. Todd Patterson	713-623-4844
Typed or printed name	Telephone Number

NOTE: This form must be signed in accordance with 37 CFR 1.33. See 37 CFR 1.4 for signature requirements and certifications. Submit multiple forms if more than one signature is required, see below*.

☐ * Total of 1 forms are submitted.

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: David Lymberopoulos	§	
Serial No.: 13/480,704	§	Group Art Unit: 3753
Filed: May 25, 2012	§	Examiner: McCalister, William M.
Confirmation No.: 9598	§	
For: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE	§	

MAIL STOP AMENDMENT
Commissioner for Patents
P.O. Box 1450
Alexandria, VA 22313-1450

Dear Sir:

RESPONSE TO OFFICE ACTION DATED JULY 11, 2014

In response to the Office Action dated July 11, 2014, please enter this response and reconsider the claims pending in the application for reasons discussed below. Although Applicant believes that no additional fees are due in connection with this response, the Commissioner is hereby authorized to charge counsel's Deposit Account No. 20-0782/ SAFO/0012USP1/BTP for any fees required to make this response timely and acceptable to the Office.

Amendments to the Specification begin on page 2 of this paper.

Amendments to the Claims begin on page 3 of this paper.

Remarks begin on page 7 of this paper.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 233

AMENDMENTS TO THE SPECIFICATION:

Please amend paragraph [0043] as follows:

[0043] Figure 3 illustrates a surface safety valve 120 according to one embodiment. The surface safety valve 120 may include a valve actuator 122 for moving a gate 116 within a body 104 of a gate valve 124 between an open and closed position. Pressurized fluid from the fluid reservoir 250 of the ESD control system 200 or pressurized fluid from the ESD control system 700 may be supplied to a chamber 123 of the valve actuator 122 via tubing 201 to open the gate valve 124. A biasing member 127, such as a spring disposed within the valve actuator 122 may be used to close the gate valve 124 when the force of the biasing member exceeds the fluid pressure in the valve actuator chamber 123. The valve actuator 122 may also include a top shaft 126 that can be used to manually actuate the valve actuator 122 by rotation of a hand wheel 128 to open and close the gate valve 124. The top shaft 126 may also be used as a visual indication to determine whether the gate valve ~~120~~ 124 is in an open or closed position. For example, when the top shaft 126 is fully extended outward from the upper end of the valve actuator 122, the gate valve 124 may be in a closed position, and when the top shaft 126 is retracted into the upper end of the valve actuator 122, the gate valve 124 may be in an open position.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 234

AMENDMENTS TO THE CLAIMS:

1. (Currently Amended) A control system for controlling ~~a safety valve attached to~~ fluid flow through a flow line at a wellsite, the control system comprising:

a safety valve having a gate;

a valve actuator configured to move the gate;

[[a]] an electronic controller assembly configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property;

a valve assembly in communication with the controller assembly; and

a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the ~~safety valve to actuate the safety~~ valve actuator to move the gate to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the ~~safety~~ valve actuator to move the gate to a second position.

2. (Original) The system of claim 1, further comprising a housing for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

3. (Original) The system of claim 2, wherein the fluid is supplied from a reservoir disposed outside of the housing.

4. (Withdrawn) The system of claim 1, wherein the fluid drive assembly is a compressor and the fluid is a pneumatic fluid.

5. (Original) The system of claim 1, wherein the fluid drive assembly is a pump and the fluid is a hydraulic fluid.

6. (Original) The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly.

7. (Currently Amended) The system of claim 1, wherein the first position is a closed position and the second position is an open position.

8. (Original) The system of claim 1, further comprising a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly.

9. (Withdrawn) The system of claim 1, wherein the fluid is ambient air.

10. (Original) The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system.

11. (Original) The system of claim 1, wherein the controller assembly is a programmable logic controller, and wherein the valve assembly is operable to release or return fluid from the safety valve for actuating the safety valve to the second position.

12. (Currently Amended) A method for controlling ~~a safety valve attached to~~ fluid flow through a flow line at a wellsite, the method comprising:

providing a control system comprising a safety valve having a gate, a valve actuator configured to move the gate, a housing, [[a]] an electronic controller assembly, a fluid drive assembly, and a valve assembly;

supplying fluid to the ~~safety~~ valve actuator using the fluid drive assembly to actuate the ~~safety~~ valve actuator to move the gate into a first position;

monitoring a physical property in the flow line using the controller assembly; and

actuating the valve assembly using the controller assembly to actuate the ~~safety~~ valve actuator to move the gate into a second position based upon a comparison of the monitored physical property to a predetermined condition.

13. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid disposed external to the housing, and further comprising filtering the pneumatic fluid as it enters the housing by the fluid drive assembly.

14. (Original) The method of claim 12, wherein the fluid is a hydraulic fluid disposed in a reservoir within the housing that is in fluid communication with the fluid drive assembly.

15. (Original) The method of claim 12, further comprising measuring the physical property using a transducer configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. (Original) The method of claim 12, wherein the first position is a closed position and the second position is an open position.

17. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid, and wherein the fluid drive assembly is a compressor.

18. (Original) The method of claim 12, wherein the fluid is a hydraulic fluid, and wherein the fluid drive assembly is a pump.

19. (Original) The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 237

20. (Original) The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly.

21. (Currently Amended) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system ~~having~~ comprising a safety valve having a gate, a valve actuator configured to move the gate, and a sensor;

actuating the ~~safety~~ valve actuator to move the gate into a closed position by supplying actuator fluid to the valve actuator;

monitoring fluid pressure in the flow line using the sensor while maintaining the ~~safety valve~~ gate in the closed position; and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator and moving the ~~safety valve~~ gate into an open position to relieve fluid pressure in the flow line.

REMARKS

This is intended as a full and complete response to the Office Action dated July 11, 2014. Claims 1-21 remain pending in the application and are shown above. Claims 4, 9, 13, and 17 stand withdrawn by the Examiner. Claims 1-3, 5-8, 10-12, 14-16, and 18-21 stand rejected by the Examiner. Reconsideration of the rejected claims is requested for the reasons presented below.

Drawings

The drawings stand objected to because they include reference character 116, which is not mentioned in the specification. In response, Applicants have amended paragraph [0043] of the specification to include gate 116 and body 104 of the gate valve 124. No new matter has been added. Applicants respectfully request withdrawal of the objection.

The drawings stand objected to because they fail to disclose the features of claims 7, 16, and 21. Applicants submit that Figure 12, as described in paragraph [0066] of the specification, illustrates the gate valve 402 in a (spring biased) fail-safe open position. Applicants respectfully request withdrawal of the objection.

Claim Rejections Under 35 USC § 112

Claims 7, 16, and 21 stand rejected under 35 U.S.C. § 112. Applicants submit that paragraph [0066] of the specification describes, and Figure 12 illustrates, the gate valve 402 in a (spring biased) fail-safe open position. Applicants respectfully request withdrawal of the rejection.

Claim 8 stands rejected under 35 U.S.C. § 112. Applicants submit that claim 8 positively recites both a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly. Applicants respectfully request withdrawal of the rejection.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 239

Claim Rejections Under 35 USC § 102

Claims 1-3, 6, 8, 10, 12, 15, 16, 19 and 20 are rejected under pre-AIA 35 U.S.C. § 102(b) as being anticipated by *Kouketsu* (US 6,289,737).

Claim 1 recites a safety valve having a gate, and a valve actuator configured to move the gate, wherein an electronic controller assembly is operable to actuate the fluid drive assembly to supply fluid to the valve actuator to move the gate to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the valve actuator to move the gate to a second position. Claim 12 recites a safety valve having a gate, a valve actuator configured to move the gate, and an electronic controller assembly; and supplying fluid to the valve actuator using a fluid drive assembly to actuate the valve actuator to move the gate into a first position. *Kouketsu* fails to disclose these elements.

Kouketsu discloses a vacuum proportional valve 16 with a bellows-type poppet valve 42 configured to change the conductance of an exhaust system from a reaction chamber 10. See Col. 7, lines 59-65. *Kouketsu* does not disclose a safety valve having a gate, a valve actuator, or an electronic controller assembly as recited in claims 1 and 12. *Kouketsu* thus fails to disclose each and every element of claims 1 and 12, and claims dependent therefrom. Applicants respectfully request withdrawal of the rejection.

Claims 1 and 5 are rejected under pre-AIA 35 U.S.C. § 102(b) as being anticipated by *Etheridge* (US 4,774,980).

Claim 1 recites a safety valve having a gate, and a valve actuator configured to move the gate, wherein an electronic controller assembly is operable to actuate the fluid drive assembly to supply fluid to the valve actuator to move the gate to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the valve actuator to move the gate to a second position. *Etheridge* fails to disclose these elements.

Etheridge discloses a non-electronic choke control valve 10 with a tapered male control member 66 or 68 configured to engage a tapered seat 72 or 76 of a lining 56 to throttle fluid flow through a valve body 12. See Abstract and Col. 3, lines 57-63.

Etheridge does not disclose a safety valve having a gate, a valve actuator, or an electronic controller assembly as recited in claims 1 and 5. *Etheridge* thus fails to disclose each and every element of claims 1 and 5. Applicants respectfully request withdrawal of the rejection.

Claims 1, 7, and 21 stand rejected under pre-AIA 35 U.S.C. § 102(a) as being anticipated by *Kotapish* (US 2010/0154894).

Claim 1 recites a safety valve having a gate, and a valve actuator configured to move the gate, wherein an electronic controller assembly is operable to actuate the fluid drive assembly to supply fluid to the valve actuator to move the gate to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the valve actuator to move the gate to a second position. Claim 21 recites a safety valve having a gate, a valve actuator configured to move the gate, and a sensor; and actuating the valve actuator to move the gate into a closed position by supplying actuator fluid to the valve actuator. *Kotapish* fails to disclose these elements.

Kotapish discloses a non-electronic control system 25 configured to maintain a back pressure on a valve 12 having a head portion 50 that seats against a seating collar 51. See Paragraphs [0019] and [0020]. *Kotapish* does not disclose a safety valve having a gate, a valve actuator, or an electronic controller assembly as recited in claims 1 and 21. *Kotapish* thus fails to disclose each and every element of claims 1 and 21, and claims dependent therefrom. Applicants respectfully request withdrawal of the rejection.

Claim Rejections Under 35 USC § 103

Claims 11 stands rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Kouketsu* (US 6,289,737).

Claim 11 depends from claim 1 and is therefore allowable for at least the same reasons. *Kouketsu* fails to cure the deficiencies discussed above. Applicants respectfully request withdrawal of the rejection.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 241

Claims 12, 14 and 18 stand rejected under pre-AIA 35 U.S.C. § 103(a) as being unpatentable over *Etheridge* (US 4,774,980).

Claim 12 recites a safety valve having a gate, a valve actuator configured to move the gate, and an electronic controller assembly; and supplying fluid to the valve actuator using a fluid drive assembly to actuate the valve actuator to move the gate into a first position. *Etheridge* fails to disclose these elements.

Etheridge discloses a non-electronic choke control valve 10 with a tapered male control member 66 or 68 configured to engage a tapered seat 72 or 76 of a lining 56 to throttle fluid flow through a valve body 12. See Abstract and Col. 3, lines 57-63. *Etheridge* does not disclose a safety valve having a gate, a valve actuator, or an electronic controller assembly as recited in claim 12. *Etheridge* thus fails to disclose each and every element of claim 12 and claims dependent therefrom. Applicants respectfully request withdrawal of the rejection.

Conclusion

Having addressed all issues set out in the office action, Applicant respectfully submits that the claims are in condition for allowance and respectfully requests that the claims be allowed.

Respectfully submitted,

/B. Todd Patterson/

B. Todd Patterson
Registration No. 37,906
PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046
Telephone: (713) 623-4844
Facsimile: (713) 623-4846
Attorney for Applicant(s)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 242

Electronic Patent Application Fee Transmittal

Application Number:	13480704
Filing Date:	25-May-2012
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Filer:	Barden Todd Patterson/Rahim Pirani
Attorney Docket Number:	SAFO/0012USP1

Filed as Small Entity

Filing Fees for Utility under 35 USC 111(a)

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Basic Filing:				
Pages:				
Claims:				
Miscellaneous-Filing:				
Petition:				
Patent-Appeals-and-Interference:				
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Extension - 3 months with $0 paid	2253	1	700	700
Miscellaneous:				
Submission- Information Disclosure Stmt	2806	1	90	90
		Total in USD ($)		**790**

Electronic Acknowledgement Receipt	
EFS ID:	21074531
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Barden Todd Patterson/Rahim Pirani
Filer Authorized By:	Barden Todd Patterson
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	29-DEC-2014
Filing Date:	25-MAY-2012
Time Stamp:	14:13:06
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	Credit Card
Payment was successfully received in RAM	$790
RAM confirmation Number	381
Deposit Account	
Authorized User	
The Director of the USPTO is hereby authorized to charge indicated fees and credit any overpayment as follows:	

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	IDS.PDF	612222 8b7ab2d012a22f96d3fdfa0042d1456e68e313da	no	4
Warnings:					
Information:					
2	Other Reference-Patent/App/Search documents	Other-CN-OAA.pdf	2464099 77a0323febbf6ad962cd4844e31dd1e4627f5006	no	8
Warnings:					
Information:					
3	Extension of Time	ext.pdf	78305 e9c891a78c42e80e819e74dfb40aba7788b96843	no	1
Warnings:					
Information:					
4		ROA.pdf	90968 44ba63f4582f6841d49df51d6431242ff9931c2c	yes	10

Multipart Description/PDF files in .zip description

Document Description	Start	End
Amendment/Req. Reconsideration-After Non-Final Reject	1	1
Specification	2	2
Claims	3	6
Applicant Arguments/Remarks Made in an Amendment	7	10

Warnings:					
Information:					
5	Fee Worksheet (SB06)	fee-info.pdf	32607 ccafa3eeae8b4a0d6f2fdee5d67b51482226a6b7	no	2
Warnings:					
Information:					
			Total Files Size (in bytes):	3278201	

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

PTO/SB/06 (09-11)
Approved for use through 1/31/2014. OMB 0651-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PATENT APPLICATION FEE DETERMINATION RECORD Substitute for Form PTO-875	Application or Docket Number 13/480,704	Filing Date 05/25/2012	☐ To be Mailed

ENTITY: ☐ LARGE ☒ SMALL ☐ MICRO

APPLICATION AS FILED – PART I

FOR	(Column 1) NUMBER FILED	(Column 2) NUMBER EXTRA	RATE ($)	FEE ($)
☐ BASIC FEE (37 CFR 1.16(a), (b), or (c))	N/A	N/A	N/A	
☐ SEARCH FEE (37 CFR 1.16(k), (i), or (m))	N/A	N/A	N/A	
☐ EXAMINATION FEE (37 CFR 1.16(o), (p), or (q))	N/A	N/A	N/A	
TOTAL CLAIMS (37 CFR 1.16(i))	minus 20 =	*	X $ =	
INDEPENDENT CLAIMS (37 CFR 1.16(h))	minus 3 =	*	X $ =	
☐ APPLICATION SIZE FEE (37 CFR 1.16(s))	If the specification and drawings exceed 100 sheets of paper, the application size fee due is $310 ($155 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).			
☐ MULTIPLE DEPENDENT CLAIM PRESENT (37 CFR 1.16(j))				
* If the difference in column 1 is less than zero, enter "0" in column 2.			TOTAL	

APPLICATION AS AMENDED – PART II

AMENDMENT	12/29/2014	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
	Total (37 CFR 1.16(i))	* 21	Minus	** 21	= 0	X $40 =	0
	Independent (37 CFR 1.16(h))	* 3	Minus	***3	= 0	X $210 =	0
	☐ Application Size Fee (37 CFR 1.16(s))						
	☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
						TOTAL ADD'L FEE	**0**

AMENDMENT		(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
	Total (37 CFR 1.16(i))	*	Minus	**	=	X $ =	
	Independent (37 CFR 1.16(h))	*	Minus	***	=	X $ =	
	☐ Application Size Fee (37 CFR 1.16(s))						
	☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
						TOTAL ADD'L FEE	

* If the entry in column 1 is less than the entry in column 2, write "0" in column 3.

** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 20, enter "20".

*** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 3, enter "3".

The "Highest Number Previously Paid For" (Total or Independent) is the highest number found in the appropriate box in column 1.

LIE
/STEFANIE BRYCE/

This collection of information is required by 37 CFR 1.16. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

If you wish to add additional Foreign Patent Document citation information please click the Add button Add

NON-PATENT LITERATURE DOCUMENTS Remove

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

	1	Canadian Office Action for Canadian Patent Applicaton Number 2,806,849, dated August 29, 2014.	☐

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☒ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☐ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/Jessie Herrera/	Date (YYYY-MM-DD)	2014-10-14
Name/Print	Jessie Herrera	Registration Number	63799

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 252

Electronic Acknowledgement Receipt

EFS ID:	20404276
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Rahim Pirani
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	14-OCT-2014
Filing Date:	25-MAY-2012
Time Stamp:	10:51:34
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	IDS.PDF	612193 182d9b9e299388393d30ec108e0678234a383fe3	no	4

Warnings:	
Information:	

A U.S. Patent Number Citation or a U.S. Publication Number Citation is required in the Information Disclosure Statement (IDS) form for autoloading of data into USPTO systems. You may remove the form to add the required data in order to correct the Informational Message if you are citing U.S. References. If you chose not to include U.S. References, the image of the form will be processed and be made available within the Image File Wrapper (IFW) system. However, no data will be extracted from this form. Any additional data such as Foreign Patent Documents or Non Patent Literature will be manually reviewed and keyed into USPTO systems.

2	Other Reference-Patent/App/Search documents	CAOfficeAction.pdf	609482 7d068625f0cf9cd245c72f9a7e40c24c64831f1a	no	2

Warnings:

Information:

Total Files Size (in bytes):	1221675

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111

If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371

If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office

If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

26290 7590 07/11/2014

PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046

EXAMINER	
MCCALISTER, WILLIAM M	
ART UNIT	PAPER NUMBER
3753	

NOTIFICATION DATE	DELIVERY MODE
07/11/2014	ELECTRONIC

Please find below and/or attached an Office communication concerning this application or proceeding.

The time period for reply, if any, is set in the attached communication.

Notice of the Office communication was sent electronically on above-indicated "Notification Date" to the following e-mail address(es):

PSDocketing@pattersonsheridan.com
pair_eofficeaction@pattersonsheridan.com
jcardenas@pattersonsheridan.com

Office Action Summary	Application No. 13/480,704	Applicant(s) LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	AIA (First Inventor to File) Status No

-- The MAILING DATE of this communication appears on the cover sheet with the correspondence address --

Period for Reply

A SHORTENED STATUTORY PERIOD FOR REPLY IS SET TO EXPIRE *3* MONTHS FROM THE MAILING DATE OF THIS COMMUNICATION.

- Extensions of time may be available under the provisions of 37 CFR 1.136(a). In no event, however, may a reply be timely filed after SIX (6) MONTHS from the mailing date of this communication.
- If NO period for reply is specified above, the maximum statutory period will apply and will expire SIX (6) MONTHS from the mailing date of this communication.
- Failure to reply within the set or extended period for reply will, by statute, cause the application to become ABANDONED (35 U.S.C. § 133). Any reply received by the Office later than three months after the mailing date of this communication, even if timely filed, may reduce any earned patent term adjustment. See 37 CFR 1.704(b).

Status

1)☒ Responsive to communication(s) filed on *5/19/14*.

☐ A declaration(s)/affidavit(s) under **37 CFR 1.130(b)** was/were filed on _____.

2a)☐ This action is **FINAL**. 2b)☒ This action is non-final.

3)☐ An election was made by the applicant in response to a restriction requirement set forth during the interview on _____; the restriction requirement and election have been incorporated into this action.

4)☐ Since this application is in condition for allowance except for formal matters, prosecution as to the merits is closed in accordance with the practice under *Ex parte Quayle*, 1935 C.D. 11, 453 O.G. 213.

Disposition of Claims*

5)☒ Claim(s) *1-21* is/are pending in the application.

5a) Of the above claim(s) *4,9,13 and 17* is/are withdrawn from consideration.

6)☐ Claim(s) _____ is/are allowed.

7)☒ Claim(s) *1-3,5-8,10-12,14-16 and 18-21* is/are rejected.

8)☐ Claim(s) _____ is/are objected to.

9)☐ Claim(s) _____ are subject to restriction and/or election requirement.

* If any claims have been determined allowable, you may be eligible to benefit from the **Patent Prosecution Highway** program at a participating intellectual property office for the corresponding application. For more information, please see http://www.uspto.gov/patents/init_events/pph/index.jsp or send an inquiry to PPHfeedback@uspto.gov.

Application Papers

10)☐ The specification is objected to by the Examiner.

11)☒ The drawing(s) filed on *5/25/12* is/are: a)☐ accepted or b)☒ objected to by the Examiner.

Applicant may not request that any objection to the drawing(s) be held in abeyance. See 37 CFR 1.85(a).

Replacement drawing sheet(s) including the correction is required if the drawing(s) is objected to. See 37 CFR 1.121(d).

Priority under 35 U.S.C. § 119

12)☐ Acknowledgment is made of a claim for foreign priority under 35 U.S.C. § 119(a)-(d) or (f).

Certified copies:

a)☐ All b)☐ Some** c)☐ None of the:

1.☐ Certified copies of the priority documents have been received.

2.☐ Certified copies of the priority documents have been received in Application No. _____.

3.☐ Copies of the certified copies of the priority documents have been received in this National Stage application from the International Bureau (PCT Rule 17.2(a)).

** See the attached detailed Office action for a list of the certified copies not received.

Attachment(s)

1) ☒ Notice of References Cited (PTO-892)

2) ☒ Information Disclosure Statement(s) (PTO/SB/08a and/or PTO/SB/08b) Paper No(s)/Mail Date *9/7/12, 4/2/13, 6/19/13, 10/15/13, 6/16/14*.

3) ☐ Interview Summary (PTO-413) Paper No(s)/Mail Date. _____ .

4) ☐ Other: _____.

The present application is being examined under the pre-AIA first to invent provisions.

Election/Restrictions

Claims 4, 9, 13 and 17 are withdrawn from further consideration pursuant to 37 CFR 1.142(b) as being drawn to a nonelected species, there being no allowable generic or linking claim. Election was made **without** traverse in the reply filed on 5/19/14.

Claims 1-3, 5-8, 10-12, 14-16 and 18-21 are being treated on the merits.

Drawings

The drawings are objected to as failing to comply with 37 CFR 1.84(p)(5) because they include the following reference character(s) not mentioned in the description: 116.

The drawings are objected to under 37 CFR 1.83(a). The drawings must show every feature of the invention specified in the claims. Therefore, the limitations of claims 7, 16 and 21 (where the supplying fluid to the safety valve actuates the safety valve to a first, closed position) must be shown or the feature(s) canceled from the claim(s). No new matter should be entered.

Corrected drawing sheets in compliance with 37 CFR 1.121(d) are required in reply to the Office action to avoid abandonment of the application. Any amended replacement drawing sheet should include all of the figures appearing on the immediate

prior version of the sheet, even if only one figure is being amended. The figure or figure number of an amended drawing should not be labeled as “amended.” If a drawing figure is to be canceled, the appropriate figure must be removed from the replacement sheet, and where necessary, the remaining figures must be renumbered and appropriate changes made to the brief description of the several views of the drawings for consistency. Additional replacement sheets may be necessary to show the renumbering of the remaining figures. Each drawing sheet submitted after the filing date of an application must be labeled in the top margin as either “Replacement Sheet” or “New Sheet” pursuant to 37 CFR 1.121(d). If the changes are not accepted by the examiner, the applicant will be notified and informed of any required corrective action in the next Office action. The objection to the drawings will not be held in abeyance.

Corrected drawing sheets in compliance with 37 CFR 1.121(d), or amendment to the specification to add the reference character(s) in the description in compliance with 37 CFR 1.121(b) are required in reply to the Office action to avoid abandonment of the application. Any amended replacement drawing sheet should include all of the figures appearing on the immediate prior version of the sheet, even if only one figure is being amended. Each drawing sheet submitted after the filing date of an application must be labeled in the top margin as either “Replacement Sheet” or “New Sheet” pursuant to 37 CFR 1.121(d). If the changes are not accepted by the examiner, the applicant will be notified and informed of any required corrective action in the next Office action. The objection to the drawings will not be held in abeyance.

Claim Rejections - 35 USC § 112

The following is a quotation of the first paragraph of 35 U.S.C. 112(a):

> (a) IN GENERAL.—The specification shall contain a written description of the invention, and of the manner and process of making and using it, in such full, clear, concise, and exact terms as to enable any person skilled in the art to which it pertains, or with which it is most nearly connected, to make and use the same, and shall set forth the best mode contemplated by the inventor or joint inventor of carrying out the invention.

The following is a quotation of the first paragraph of pre-AIA 35 U.S.C. 112:

> The specification shall contain a written description of the invention, and of the manner and process of making and using it, in such full, clear, concise, and exact terms as to enable any person skilled in the art to which it pertains, or with which it is most nearly connected, to make and use the same, and shall set forth the best mode contemplated by the inventor of carrying out his invention.

Claims 7, 16 and 21 are rejected under 35 U.S.C. 112(a) or 35 U.S.C. 112 (pre-AIA), first paragraph, as failing to comply with the written description requirement. The claim(s) contains subject matter which was not described in the specification in such a way as to reasonably convey to one skilled in the relevant art that the inventor or a joint inventor, or for pre-AIA the inventor(s), at the time the application was filed, had possession of the claimed invention. These claims require the supply of actuator fluid to the valve actuator to cause the safety valve to close, whereas the specification sets forth that supply of actuator fluid to the valve actuator causes the safety valve to open (see paragraph 0052, PG Pub, referencing FIGS 4 and 6). In other words, Applicant's disclosed invention is spring-biased closed, not spring-biased open.

Claim Rejections - 35 USC § 112

The following is a quotation of 35 U.S.C. 112(b):
(b) CONCLUSION.—The specification shall conclude with one or more claims particularly pointing out and distinctly claiming the subject matter which the inventor or a joint inventor regards as the invention.

The following is a quotation of 35 U.S.C. 112 (pre-AIA), second paragraph:
The specification shall conclude with one or more claims particularly pointing out and distinctly claiming the subject matter which the applicant regards as his invention.

Claim 8 is rejected under 35 U.S.C. 112(b) or 35 U.S.C. 112 (pre-AIA), second paragraph, as being indefinite for failing to particularly point out and distinctly claim the subject matter which the inventor or a joint inventor, or for pre-AIA the applicant regards as the invention. It cannot be determined if claim 8 positively recites a filter, or merely requires a housing which is capable of supporting a filter.

Claim Rejections - 35 USC § 102

The following is a quotation of the appropriate paragraphs of pre-AIA 35 U.S.C. 102 that form the basis for the rejections under this section made in this Office action:

A person shall be entitled to a patent unless –

(b) the invention was patented or described in a printed publication in this or a foreign country or in public use or on sale in this country, more than one year prior to the date of application for patent in the United States.

Claims 1-3, 6, 8, 10, 12, 15, 16, 19 and 20 are rejected under pre-AIA 35 U.S.C. 102(b) as being anticipated by Kouketsu (US 6,289,737).

1. A control system for controlling a safety valve attached to a flow line at a wellsite (intended use of preamble given no patentable weight because not necessary to understand the body of claim), the control system comprising:

a controller assembly (20) configured to receive a signal from a transducer (60) connected to the flow line (from 10 to 13), wherein the signal corresponds to a measured physical property (60 is a pressure sensor);

a valve assembly (34, 35 and/or 33) in communication with the controller assembly; and

a fluid drive assembly (32, 33, and or 34) in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the safety valve (40) to actuate the safety valve to a first position (by supplying air to the actuating chamber of 40, valve 40 opens), and wherein the controller assembly is operable to actuate the valve assembly to actuate the safety valve to a second position (by venting air from the actuating chamber of 40, valve 40 closes).

2. The system of claim 1, further comprising a housing (surrounding the piston, as shown in FIG 4) *for* supporting the controller assembly, the valve assembly, and the fluid drive assembly (it is *capable* of providing such support).

3. The system of claim 2, wherein the fluid is supplied from a reservoir disposed outside of the housing (inherently, at the very least atmosphere is seen as an air reservoir).

6. The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly (inherently, all machines use energy provided by a source).

8. The system of claim 1, further comprising a housing (surrounding the piston, as shown in FIG 4) for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly (it is capable of supporting the fluid drive assembly and a filter).

10. The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system (via 21, the “desired vacuum pressure” and “vacuum pressure changing speed” are communicated).

12. A method for controlling a safety valve attached to a flow line at a wellsite, the method comprising:

providing a control system having a housing (surrounding the piston, as shown in FIG 4), a controller assembly (20, 60), a fluid drive assembly (32, 33, and or 34), and a valve assembly (34, 35 and/or 33);

supplying fluid to the safety valve using the fluid drive assembly to actuate the safety valve into a first position (open);

monitoring a physical property in the flow line using the controller assembly (at least part 60); and

actuating the valve assembly using the controller assembly to actuate the safety valve into a second position (closed) based upon a comparison of the monitored physical property to a predetermined condition (col. 9 lines 30-42).

15. The method of claim 12, further comprising measuring the physical property using a transducer (60) configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. The method of claim 12, wherein the first position is a closed position and the second position is an open position (the recitations of claim 12 “to actuate the safety valve into a first/second position” are seen as reciting the intended effects of positively recited method steps (“supplying fluid to the safety valve”, and “actuating the valve assembly”, respectively), which recitations, according to MPEP 2111.04, should not be given patentable weight because they "simply expresses the intended result of a process step positively recited.”)

19. The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve (via 21).

20. The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly (via the "remote" or "on-site" input signal).

Claims 1 and 5 are rejected under pre-AIA 35 U.S.C. 102(b) as being anticipated by Etheridge (US 4,774,980).

Etheridge discloses:

1. A control system for controlling a safety valve attached to a flow line at a wellsite (intended use of preamble given no patentable weight because not necessary to understand the body of claim), the control system comprising:

a controller assembly (228, 236) configured to receive a signal from a transducer (240) connected to the flow line (204), wherein the signal corresponds to a measured physical property (pressure);

a valve assembly (250) in communication with the controller assembly (via lines 206b and/or 248); and

a fluid drive assembly (208, 230) in communication with the controller assembly (via line 226d), wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the safety valve (along 206b) to actuate the safety valve to a first position (open), and wherein the controller assembly is operable to actuate the valve assembly (via 248) to actuate the safety valve to a second position (closed).

5. The system of claim 1, wherein the fluid drive assembly is a pump (208 is a pump) and the fluid is a hydraulic fluid (see Abstract).

Claims 1, 7 and 21 (7 and 21 as understood) are rejected under pre-AIA 35 U.S.C. 102(a) as being anticipated by Kotapish (US 2010/0154894).

Kotapish discloses:

1. A control system for controlling a safety valve attached to a flow line at a wellsite (intended use of preamble given no patentable weight because not necessary to understand the body of claim), the control system comprising:

a controller assembly (25) configured to receive a signal from a transducer (27) connected to the flow line (11), wherein the signal corresponds to a measured physical property (pressure);

a valve assembly (36) in communication with the controller assembly; and

a fluid drive assembly (42, 44) in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the safety valve (via 18) to actuate the safety valve to a first position (closed), and wherein the controller assembly is operable to actuate the valve assembly (36) to actuate the safety valve to a second position (open).

7. The system of claim 1, wherein the first position a closed position and the second position is an open position (as set forth above).

21. A system, during the normal and usual provision and operation of which the following method would necessarily be performed:

providing a control system having a safety valve (50, 52), a valve actuator (16), and a sensor (27);

actuating the safety valve into a closed position by supplying actuator fluid to the valve actuator (via line 18);

monitoring fluid pressure in the flow line using the sensor while maintaining the safety valve in the closed position (25 continuously monitors pressure along line 31); and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator and moving the safety valve into an open position to relieve fluid pressure in the flow line (e.g., para. 0021).

Claim Rejections - 35 USC § 103

The following is a quotation of pre-AIA 35 U.S.C. 103(a) which forms the basis for all obviousness rejections set forth in this Office action:

> (a) A patent may not be obtained though the invention is not identically disclosed or described as set forth in section 102 of this title, if the differences between the subject matter sought to be patented and the prior art are such that the subject matter as a whole would have been obvious at the time the invention was made to a person having ordinary skill in the art to which said subject matter pertains. Patentability shall not be negatived by the manner in which the invention was made.

The factual inquiries set forth in *Graham v. John Deere Co.*, 383 U.S. 1, 148 USPQ 459 (1966), that are applied for establishing a background for determining obviousness under pre-AIA 35 U.S.C. 103(a) are summarized as follows:

1. Determining the scope and contents of the prior art.

2. Ascertaining the differences between the prior art and the claims at issue.

3. Resolving the level of ordinary skill in the pertinent art.

4. Considering objective evidence present in the application indicating obviousness or nonobviousness.

This application currently names joint inventors. In considering patentability of the claims under pre-AIA 35 U.S.C. 103(a), the examiner presumes that the subject matter of the various claims was commonly owned at the time any inventions covered therein were made absent any evidence to the contrary. Applicant is advised of the obligation under 37 CFR 1.56 to point out the inventor and invention dates of each claim that was not commonly owned at the time a later invention was made in order for the examiner to consider the applicability of pre-AIA 35 U.S.C. 103(c) and potential pre-AIA 35 U.S.C. 102(e), (f) or (g) prior art under pre-AIA 35 U.S.C. 103(a).

Claims 11 is rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Kouketsu (US 6,289,737).

Kouketsu discloses the invention as claimed with exception to the controller assembly being a programmable logic controller. However, the use of programmable

logic controllers (aka "PLCs") was notoriously well-known in the art at the time of invention and it would have been obvious to embody Kouketsu's controller as a PLC to obtain the benefits of programmability/adjustability.

Claims 12, 14 and 18 are rejected under pre-AIA 35 U.S.C. 103(a) as being unpatentable over Etheridge (US 4,774,980).

Etheridge discloses the invention as claimed, as set forth above, further including where the fluid drive is a pump (208), where the fluid is a hydraulic fluid (see Abstract), and where the hydraulic fluid is supplied from a reservoir (212). Etheridge does not disclose a housing in which the reservoir is disposed. However, the use of a housing was notoriously well-known in the art at the time of invention as a means for protecting a hydraulic system, and it would have been obvious to use a housing in which Etheridge's reservoir is disposed in order to protecting Etheridge's hydraulic system.

Conclusion

The prior art made of record and not relied upon is considered pertinent to applicant's disclosure.

Any inquiry concerning this communication or earlier communications from the examiner should be directed to William McCalister, whose telephone number 571 270

1869. The examiner can normally be reached on Monday-Friday (7:30AM-4:00PM EST).

If attempts to reach the examiner by telephone are unsuccessful, the examiner's supervisors can be reached by phone. **Steve Hepperle** can be reached at 571-272-4913 or **John Fristoe** can be reached at 571-272-4926. The fax phone number for the organization where this application or proceeding is assigned is 571-273-8300.

Information regarding the status of an application may be obtained from the Patent Application Information Retrieval (PAIR) system. Status information for published applications may be obtained from either Private PAIR or Public PAIR. Status information for unpublished applications is available through Private PAIR only. For more information about the PAIR system, see http://pair-direct.uspto.gov. Should you have questions on access to the Private PAIR system, contact the Electronic Business Center (EBC) at 866-217-9197 (toll-free). If you would like assistance from a USPTO Customer Service Representative or access to the automated information system, call 800-786-9199 (IN USA OR CANADA) or 571-272-1000.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

7/7/14

Notice of References Cited	Application/Control No. 13/480,704	Applicant(s)/Patent Under Reexamination LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	Page 1 of 1

U.S. PATENT DOCUMENTS

*		Document Number Country Code-Number-Kind Code	Date MM-YYYY	Name	Classification
*	A	US-4,774,980 A	10-1988	Etheridge, Reggie H.	137/488
*	B	US-6,116,268 A	09-2000	Johnson, Clarence William	137/458
*	C	US-6,289,737 B1	09-2001	Kouketsu et al.	73/714
	D	US-			
	E	US-			
	F	US-			
	G	US-			
	H	US-			
	I	US-			
	J	US-			
	K	US-			
	L	US-			
	M	US-			

FOREIGN PATENT DOCUMENTS

*		Document Number Country Code-Number-Kind Code	Date MM-YYYY	Country	Name	Classification
	N					
	O					
	P					
	Q					
	R					
	S					
	T					

NON-PATENT DOCUMENTS

*		Include as applicable: Author, Title Date, Publisher, Edition or Volume, Pertinent Pages)
	U	
	V	
	W	
	X	

*A copy of this reference is not being furnished with this Office action. (See MPEP § 707.05(a).)
Dates in MM-YYYY format are publication dates. Classifications may be US or foreign.

EAST Search History

EAST Search History (Prior Art)

Ref #	Hits	Search Query	DBs	Default Operator	Plurals	Time Stamp
L3	20	(US-20060219299-$ or US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6056008-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.	US-PGPUB; USPAT	OR	OFF	2014/07/07 14:46
L4	16	L3 and hydraulic	US-PGPUB; USPAT	OR	OFF	2014/07/07 14:46
L5	9	L3 and hydraulic and pump	US-PGPUB; USPAT	OR	OFF	2014/07/07 15:12
L6	592	g05d16/2086.cpc.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/07 15:44
L7	2283	f16k17/00.cpc.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/07 15:55
S1	1	13/480704	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 12:52
S2	626	137/492.5.ccls.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:17
S3	170	S2 and (pump or compressor)	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:17

S5	138	S2 and pump	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:18
S6	44	("6349772" | "20100154894" | "20020108747" | "20020112632" | "20060159569" | "20110036415" | "20110240126" | "5275086" | "6772718" | "4082147" | "6199629" | "3741116" | "5335730" | "6435282" | "20100025045" | "20110094752" | "20020124889" | "4213480" | "5273113" | "5526883" | "6854704" | "7004445" | "20130008519" | "20130008519" | "20120031494" | "20050236594" | "4667570" | "5490564" | "6412510" | "RE39583" | "6296052" | "4215746" | "5684451" | "20050087712" | "3788341" | "4527429" | "5097857" | "5132904" | "6450477" | "7231971" | "20100154894" | "20090126798" | "4461449" | "20040135112" | "20110094752" | "6633236" | "7635029").PN.	US-PGPUB; USPAT	OR	OFF	2014/07/02 13:18
S7	15	S2 and (pump near3 (command$4 or control$4)) and (pressure near3 (sens$4 or transduc$4))	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 13:25
S8	626	137/492.5.ccls.	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 16:51
S9	72	S8 and pump and hydraulic	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/02 16:51
S10	12	("3788341" | "4335744" | "4337788" | "4461450" | "4503878").PN. OR ("4774980").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/02 17:00
S11	21	("1223326" | "3225785" | "4037619" | "4414882" | "4431159" | "4585205" | "4613111" | "4774980" | "4778351" | "5094267" | "5158108" | "5158230" | "5197328" | "5318272" | "5431182" | "5460196").PN. OR ("6202681").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/02 17:01
S12	3	("2010/0154894").URPN.	USPAT	OR	OFF	2014/07/03 13:51
S13	19	("2132132" | "2203243" | "3227171" | "3367355" | "3467129").PN. OR ("3788341").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/03 13:53

S14	11	("3788341" | "4186766" | "4240463" | "4319603" | "5293910" | "5396923").PN. OR ("7044156").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/03 13:54
S15	18	(US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.	US-PGPUB; USPAT	OR	OFF	2014/07/03 14:01
S16	6	S15 and control$4 near4 pump	US-PGPUB; USPAT	OR	OFF	2014/07/03 14:01
S17	18	(US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.	US-PGPUB; USPAT	OR	OFF	2014/07/07 07:40
S18	7	S17 and pump	USPAT	OR	OFF	2014/07/07 07:40
S19	10	S17 and pump	US-PGPUB; USPAT; USOCR; FPRS; EPO; JPO; DERWENT; IBM_TDB	OR	OFF	2014/07/07 07:40
S20	12	("3788341" | "4335744" | "4337788" | "4461450" | "4503878").PN. OR ("4774980").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 08:55
S21	8	("5341837" | "5526883").PN. OR ("6116268").URPN.	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:01
S22	313	137/492,492.5.ccls. and well	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:06
S23	61	137/492,492.5.ccls. and well and controller	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:06
S24	5	11/426109	US-PGPUB; USPAT; USOCR	OR	OFF	2014/07/07 09:10
S25	10	("2006/0219299").URPN.	USPAT	OR	OFF	2014/07/07 09:12
S26	10	"6450477"	USPAT	OR	OFF	2014/07/07 09:19
S27	20	(US-20060219299-$ or US-20100154894-$ or US-20110240126-$ or US-20120031494-$ or US-20120227983-$).did. or (US-3788341-$ or US-4186766-$ or US-4213480-$ or US-4240463-$ or US-4774980-$ or US-6056008-$ or US-	US-PGPUB; USPAT	OR	OFF	2014/07/07 12:21

		6116268-$ or US-6202681-$ or US-6289737-$ or US-6450477-$ or US-6854704-$ or US-7004445-$ or US-7044156-$ or US-7934562-$ or US-8763983-$).did.				
S28	9	S27 and pump with control$4	US-PGPUB; USPAT	OR	OFF	2014/07/07 12:21
S29	12	S27 and housing	US-PGPUB; USPAT	OR	OFF	2014/07/07 12:25

7/7/2014 3:59:04 PM
C:\Users\wmccalister\Documents\EAST\Workspaces\13480704.wsp

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198

Doc code: IDS
Doc description: Information Disclosure Statement (IDS) Filed

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT
(Not for submission under 37 CFR 1.99)

Application Number	13480704
Filing Date	2012-05-25
First Named Inventor	David Lymberopoulos
Art Unit	N/A
Examiner Name	Not Yet Assigned
Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	3788341		1974-01-29	Athy, Jr. et al.	
	2	4213480		1980-07-22	Orum et al.	
	3	4461449		1984-07-24	Turner	
	4	4527429		1985-07-09	Combest et al.	
	5	4667570		1987-05-26	Jensen, Jr. et al.	
	6	5097857		1992-03-24	Mayhew	
	7	5132904		1992-07-21	Lamp	
	8	5273113		1993-12-28	Schultz	

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

	9	5275086		1994-01-04	Stallings, Jr.	
	10	5335730		1994-08-09	Cotham, III	
	11	5526883		1996-06-18	Breaux	
	12	6349772		2002-02-26	Mullen et al.	
	13	6435282		2002-08-20	Robison et al.	
	14	6450477		2002-09-17	Young	
	15	6854704		2005-02-15	Young	
	16	7004445		2006-02-28	Lymberopoulos	
	17	7231971		2007-06-19	McCalvin	
	18	RE39583		2007-04-24	Upchurch	
	19	5490564		1996-02-13	Schultz et al.	

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

	20	6412510		2002-07-02	Johnson	
	21	3741116		1973-06-26	Green et al.	
	22	6772718		2004-08-10	Allen	

If you wish to add additional U.S. Patent citation information please click the Add button.

U.S.PATENT APPLICATION PUBLICATIONS

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20020124889	A1	2002-09-12	Sundararajan	
	2	20050087712	A1	2005-04-28	Lymberopoulos	
	3	20110036415	A1	2011-02-17	Lymberopoulos	
	4	20110240126	A1	2011-10-06	Lymberopoulos et al.	
	5	20060159569	A1	2006-07-20	Biester	
	6	20020112632		2002-08-22	Faibish	

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

	7	20050236594		2005-10-27	Lilly et al.	

If you wish to add additional U.S. Published Application citation information please click the Add button.

FOREIGN PATENT DOCUMENTS

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2]	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	07-042856	JP	A	1995-02-10	Nakai, Kazuo		☐
	2	02/25612	WO	A1	2002-03-28	Keyspan Energy		☐
	3	0 647 770	EP	A2	1995-04-12	Ford Motor Co et al.		☐

If you wish to add additional Foreign Patent Document citation information please click the Add button

NON-PATENT LITERATURE DOCUMENTS

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	Versa Series B Valves Bulletin B-2011; Versa Products Company, Inc.; 2011, 8 Pages.	☐
	2	Rotowink Indicators; Norgren 1996; 2 Pages.	☐

If you wish to add additional non-patent literature document citation information please click the Add button

EXAMINER SIGNATURE

Examiner Signature	/William Mccalister/	Date Considered	07/07/2014

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99**)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	Not Assigned
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS						Remove
Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					
If you wish to add additional U.S. Patent citation information please click the Add button.						Add

U.S.PATENT APPLICATION PUBLICATIONS						Remove
Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20100154894		2010-06-24	Kotapish et al.	
	2	20110094752		2011-04-28	Hudson et al.	
	3	20130008519		2013-01-10	Crawford	
If you wish to add additional U.S. Published Application citation information please click the Add button.						Add

FOREIGN PATENT DOCUMENTS							Remove	
Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Receipt date: 06/19/2013	Application Number	13480704 13480704 - GAU: 3753
INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	Not Assigned
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button			Add
NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1		☐
If you wish to add additional non-patent literature document citation information please click the Add button			Add

EXAMINER SIGNATURE			
Examiner Signature	/William Mccalister/	Date Considered	07/07/2014

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

BIB DATA SHEET

CONFIRMATION NO. 9598

SERIAL NUMBER	FILING or 371(c) DATE	CLASS	GROUP ART UNIT	ATTORNEY DOCKET NO.
13/480,704	05/25/2012 RULE	137	3753	SAFO/0012USP1

APPLICANTS

INVENTORS

David Lymberopoulos, Houston, TX;
Benjamin R. Matthews, Missouri City, TX;

**** CONTINUING DATA ***************************

This appln claims benefit of 61/551,319 10/25/2011
and is a CIP of 13/195,662 08/01/2011
which claims benefit of 61/370,721 08/04/2010
and claims benefit of 61/415,238 11/18/2010

**** FOREIGN APPLICATIONS ***************************

**** IF REQUIRED, FOREIGN FILING LICENSE GRANTED **** ** SMALL ENTITY **
06/04/2012

Foreign Priority claimed	35 USC 119(a-d) conditions met	Verified and Acknowledged		STATE OR COUNTRY	SHEETS DRAWINGS	TOTAL CLAIMS	INDEPENDENT CLAIMS
☐ Yes ☑ No	☐ Yes ☑ No	/WILLIAM M MCCALISTER/ Examiner's Signature	☐ Met after Allowance Initials	TX	15	21	3

ADDRESS

PATTERSON & SHERIDAN, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, TX 77046
UNITED STATES

TITLE

SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

FILING FEE RECEIVED	FEES: Authority has been given in Paper	
560	No._____ to charge/credit DEPOSIT ACCOUNT No._____ for following:	☐ All Fees ☐ 1.16 Fees (Filing) ☐ 1.17 Fees (Processing Ext. of time) ☐ 1.18 Fees (Issue) ☐ Other _____ ☐ Credit

BIB (Rev. 05/07).

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	4082147		1978-04-04	Wolff et al.	
	2	6199629		2001-03-13	Shirk et al.	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20020108747		2002-08-15	Dietz et al.	
	2	20120031494		2012-02-09	Lymberopoulos	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Receipt date: 10/15/2013	Application Number	13480704 13480704 - GAU: 3753
INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button Add

NON-PATENT LITERATURE DOCUMENTS Remove

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	PCT Search Report and Written Opinion for International Application No. PCT/US2013/042095 dated August 22, 2013	☐

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature	/William Mccalister/	Date Considered	07/07/2014

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

EFS Web 2.1.17 ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99**)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	Unassigned
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	6296052		2001-10-02	Sidwell	
	2	6633236		2003-10-14	Vinegar et al.	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20040135112		2004-07-15	Greeb et al.	
	2	20100025045		2010-02-04	Lake et al.	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	0165061	WO	A1	2001-09-07	Shell Oil Co		☐

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Receipt date: 04/02/2013	Application Number	13480704 13480704 - GAU: 3753
INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	Unassigned
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button Add

NON-PATENT LITERATURE DOCUMENTS Remove

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	PCT International Search Report and Written Opinion; International Application No. PCT/US2012/061313; Mailed March 14, 2013.	☐

If you wish to add additional non-patent literature document citation information please click the Add button Add

EXAMINER SIGNATURE

Examiner Signature	/William Mccalister/	Date Considered	07/07/2014

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

EFS Web 2.1.17 ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

Search Notes	Application/Control No.	Applicant(s)/Patent Under Reexamination
	13480704	LYMBEROPOULOS ET AL.
	Examiner	Art Unit
	WILLIAM MCCALISTER	3753

CPC- SEARCHED		
Symbol	Date	Examiner
G05D 16/2086 good for electrical controls for a fluid pilot valve that controls a main valve	7/7/2014	wm
F16K 17/00 this invention meets the definition of "safety" but this subclass is very large and includes a lot of irrelevant art	7/7/2014	wm

CPC COMBINATION SETS - SEARCHED		
Symbol	Date	Examiner

US CLASSIFICATION SEARCHED			
Class	Subclass	Date	Examiner
137	488, 492, 492.5	7/7/2014	wm

SEARCH NOTES		
Search Notes	Date	Examiner

INTERFERENCE SEARCH			
US Class/ CPC Symbol	US Subclass / CPC Group	Date	Examiner

	/WILLIAM MCCALISTER/ Primary Examiner.Art Unit 3753

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99**)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	7635029		2009-12-22	MacDougall et al.	
	2	5684451		1997-11-04	Seberger et al.	
	3	4215746		1980-08-05	Hallden et al.	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20090126798	A1	2009-05-21	Mather	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] i	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	2005097792	WO	A1	2005-10-20	Westlock Controls Corp		☐

EFS Web 2.1.17

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704 13480704 - GAU: 3753
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button			Add
NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	Austrailian Exam Report for Patent Application No. 2011285979, dated May 16, 2014.	☐
If you wish to add additional non-patent literature document citation information please click the Add button			Add

EXAMINER SIGNATURE			
Examiner Signature	/William Mccalister/	Date Considered	07/07/2014

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

ALL REFERENCES CONSIDERED EXCEPT WHERE LINED THROUGH. /W.M./

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	7635029		2009-12-22	MacDougall et al.	
	2	5684451		1997-11-04	Seberger et al.	
	3	4215746		1980-08-05	Hallden et al.	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20090126798	A1	2009-05-21	Mather	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	2005097792	WO	A1	2005-10-20	Westlock Controls Corp		☐

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button			Add
NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	Austrailian Exam Report for Patent Application No. 2011285979, dated May 16, 2014.	☐
If you wish to add additional non-patent literature document citation information please click the Add button			Add

EXAMINER SIGNATURE			
Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	W. M. McCalister
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/B. Todd Patterson/	Date (YYYY-MM-DD)	2014-06-16
Name/Print	B. Todd Patterson	Registration Number	37906

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 292

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
20 October 2005 (20.10.2005)

PCT

(10) International Publication Number
WO 2005/097792 A1

(51) International Patent Classification[7]: C07D 471/04, A61K 31/519

(21) International Application Number: PCT/US2005/011566

(22) International Filing Date: 5 April 2005 (05.04.2005)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
60/559,002 5 April 2004 (05.04.2004) US

(71) Applicant *(for all designated States except US)*: **WESTLOCK CONTROLS CORPORATION** [US/US]; (a corporation organized Under the Laws of Delawar, e), 280 Midland Avenue, Building Z2C2, Saddle Brook, NJ 07663 (US).

(72) Inventors; and
(75) Inventors/Applicants *(for US only)*: **MINERVINI, Leo** [US/US]; 26 Sherry Lane, Saddle Brook, NJ 07663 (US). **JORDAN, Eric** [US/US]; 45 Wayne Avenue, River Edge, NJ 07661 (US).

(74) Agents: **LAUB, David, W.** et al.; Morgan, Lewis & Bockius, LLP, 1111 Pennsylvania Avenue, NW, Washington, DC 20004 (US).

(81) Designated States *(unless otherwise indicated, for every kind of national protection available)*: AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BW, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KM, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NA, NI, NO, NZ, OM, PG, PH, PL, PT, RO, RU, SC, SD, SE, SG, SK, SL, SM, SY, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, YU, ZA, ZM, ZW.

(84) Designated States *(unless otherwise indicated, for every kind of regional protection available)*: ARIPO (BW, GH, GM, KE, LS, MW, MZ, NA, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HU, IE, IS, IT, LT, LU, MC, NL, PL, PT, RO, SE, SI, SK, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Published:
— *with international search report*

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

WO 2005/097792 A1

(54) Title: DEVICE AND METHOD FOR PNEUMATIC VALVE CONTROL

(57) Abstract: A valve control apparatus (10) includes an enclosure (12, 14) that defines first and second chambers (16), an indicator (24) that is proximate the first and second chambers (16), an operating media distribution system (20) that is disposed in the first chamber (12), an electronic control unit that is disposed in the second chamber, and a plurality of connection ports (34). The first and second chambers (16) are spaced from each other along a longitudinal axis. The indicator (24) has a visual symbol (388) that identifies an operational state of at least one process valve (3). The operating media distribution system (20) includes an operating media supply passage (28), an operating media exhaust passage (30), at least three operating media transmission passages (32), and a plurality of valves (64, 66, 68, 70) in fluid communication with the operating media supply passage (28), the operating media exhaust passage (30), and the at least three operating media transmission passages (32). The electronic control unit operates at least one of the plurality of valves (64, 66, 68, 70) to control operating media flow in the operating media distribution system (20). And the plurality of connection ports (34) communicate with the operating media supply passage (28), the operating media exhaust passage (30), and the at least three operating media transmission passages (32).

DEVICE AND METHOD FOR PNEUMATIC VALVE CONTROL

Cross-Reference to Related Applications

This application claims the benefit of the earlier filing date of U.S. Provisional Application No. 60/559,002, filed 5 April 2004, which is incorporated by reference herein in its entirety.

Field of the Invention

The present invention relates generally to a valve controller, further to an actuator within an integrated valve controller. The present invention also relates to systems that include the valve controller and operational methods for monitoring the operational characteristics of a valve through knowledge-based valve performance criteria.

Background of the Invention

Valve control systems are known in the related art. A valve control system may be used, for example, to continuously control the position of a valve based on pneumatic pressure. A valve control system may also have the capability to indicate valve position. A valve control system may further have the capability to monitor valve operation and signal an error message, if a failure condition occurs.

Summary of the Invention

The present invention relates to a low profile multi-purpose pneumatic valve controller with an operating media distribution system. The valve controller may be used to control one process valve with increased air flow dynamics, provide redundant control for one process valve, or control two independent valves. The valve controller may be configured with integral pressure sensors to allow for advanced diagnostics that can be tailored to a particular valve and/or actuator. The valve controller may also be configured to automatically acquire and process data to create advanced diagnostic methods and systems.

The valve controller may have an enclosure that includes various features that can be utilized to achieve other functions in addition to simply house the valve controller.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 294

For example, the valve controller may have separate enclosures for mechanical and electronic components, and the separate enclosures may define chambers for all components to avoid exposure to operative conditions. The valve controller enclosure may be configured to integrate with an actuator, such that the integrated valve controller may have separate chambers for mechanical and electronic components. The integrated actuator and valve controller with separate chambers may allow for a method of maintenance for the valve controller that only requires access to either mechanical or electrical chambers. The valve controller may have a height profile of no more than 3 inches. The valve controller with a height profile of no more than 3 inches may be capable of providing two pneumatic control signals from a single pneumatic control supply, and may be provided with an integrated actuator.

According to a preferred embodiment, a valve control apparatus includes an enclosure that defines first and second chambers, an indicator proximate the first and second chambers, an operating media distribution system disposed in the first chamber, an electronic control unit disposed in the second chamber, and a plurality of connection ports. The first and second chambers are spaced from each other along a longitudinal axis. The indicator has a visual symbol that identifies an operational state of at least one valve. The operating media distribution system includes an operating media supply passage, an operating media exhaust passage, at least three operating media transmission passages, and a plurality of valves in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least three operating media transmission passages. The electronic control unit operates at least one of the plurality of valves to control operating media flow in the operating media distribution system. And the plurality of connection ports communicate with the operating media supply passage, the operating media exhaust passage, and the at least three operating media transmission passages.

According to another preferred embodiment, a valve control apparatus includes an enclosure, an operating media distribution system that is disposed in the enclosure, an electronic control unit that is disposed in the enclosure, at least one sensor that is disposed in the enclosure, and a plurality of connection ports. The operating media distribution system includes an operating media supply passage, an operating media exhaust passage, at least two operating media transmission passages, and a valve that is

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 295

in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least two operating media transmission passages. The electronic control unit operates the valve to control operating media flow in the operating media distribution system. The sensor evaluates the operating media distribution system and provides information to the electronic control unit about at least one operating condition in at least one of the passages. And the plurality of connection ports are in fluid communication with the operating media supply passage the operating media exhaust passage, and the at least two operating media transmission passages.

The valve controller may have a beacon (position indicator) located between separate chambers for mechanical and electronic components. The size of the beacon (position indicator) may be selected to allow for viewing by an observer from a remote location. The beacon (position indicator) may operate via a non-contact position sensor. The valve controller with a beacon (position indicator) disposed adjacent operative components may be viewed from a site range both above and below the centerline of a position indicator. The position indicator may be a rotary or linear configuration. The valve controller and beacon (position indicator) may also be integrated with an actuator to provide an integrated actuator and valve controller, the valve controller having a beacon (position indicator) located between separate chambers for mechanical and electronic components. The integrated actuator and valve controller may be configured to provide the valve controller with a beacon (position indicator) disposed adjacent operative components so that it can be viewed by an observer from a site range both above and below the center line of a position indicator.

Design aspects of the valve controller package are unique. For example, the valve controller enclosure or package may have a housing with the enclosure being a bow-tie configuration, or may be contained within a limited size space.

According to a preferred embodiment, an apparatus that distributes operating media includes an enclosure, an indicator proximate the enclosure, an operating media distribution system disposed in the enclosure, and a plurality of connection ports that communicate with the operating media distribution system. The enclosure includes upper and lower surfaces that respectively define first and second parallel planes, and the enclosure is located entirely within a distance between the first and second planes. The indicator includes a visual symbol that identifies an operational state of the at least one

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 296

process valve. The visual symbol is visible from above the first plane and from below the second plane.

According to another preferred embodiment, a valve control apparatus for at least one process valve that has a maximum exterior package dimension. The apparatus includes an enclosure that is disposed entirely between first and second parallel planes. The first and second parallel planes are spaced apart a distance that is less than or equal to the exterior package dimension. The apparatus further includes an indicator that is proximate the enclosure, an operating media distribution system, an electronic control unit and at least one sensor that are disposed in the enclosure, and a plurality of connection ports that communicate with the operating media distribution system. The indicator includes a visual symbol that identifies an operational state of the at least one process valve. The visual symbol is visible from above the first plane and from below the second plane. And the at least one sensor evaluates the operating media distribution system and provides the electronic control unit information about at least one operating condition in the operating media distribution system.

The valve controller may have a manifold assembly having one, two three or four integral coils and one or two spools. The valve controller may use the same fasteners to secure the cover to the manifold and the manifold assembly to the base of a housing. The valve controller may include a pneumatic manifold assembly that uses a cover to define pneumatic operative paths. The valve controller may have a housing with a single pneumatic supply path, two separate pilot paths, a single exhaust path, and an individual pressure sensor for each path. Two of the sensors can be differential pressure sensors.

According to a preferred embodiment, a manifold apparatus that distributes operating media includes a first member that defines an operating media supply cavity, an operating media exhaust cavity, and at least four operating media transmission cavities in communication with the operating media supply cavity and the operating media exhaust cavity. The apparatus further includes a surface that communicates a flow of operating media flow between a minimum of two of the at least four operating media transmission cavities.

According to another preferred embodiment, an apparatus for distributing an operating media includes a manifold that has an operating media supply passage, an operating media exhaust passage, and first, second, third and fourth operating media

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 297

transmission passages. The apparatus further includes a means for directing the operating media from the operating media supply passage to the first and third operating media transmission passages, and a means for directing the operating media to the operating media exhaust passage from the second and fourth operating media transmission passages.

The valve controller may provide for different operative arrangements. The valve controller may have a single pneumatic supply port that allows for two operational control signals. The two operational control signals may provide a first command signal and a second command signal to a single valve. The first command signal may be a discrete command signal. The second command signal may be a modulating command signal. The valve controller may be integrated with an actuator, the valve controller having a single pneumatic supply port that allows for two operational control signals. The valve controller may be used to operate a valve with two different command signals from a single pneumatic supply port. The valve controller may be used in a method of operating an integrated actuator with two different command signals from a single pneumatic supply port. The valve controller may have a single pneumatic supply port that allows for two operational control signals. The two operational control signals may provide a discrete command signal to a first valve and a separate discrete command signal to a second valve. The valve controller may be integrated with an actuator, the valve controller having a single pneumatic supply port that allows for two separate and identical operational control signals. The valve controller may be configured to provide a method of controlling fail-safe operation of two valves with a single supply.

According to a preferred embodiment, a system, which controls two process valves, includes a manifold, a surface, and first and second process valves. The manifold defines a member that defines an operating media supply cavity, an operating media exhaust cavity, and at least four operating media transmission cavities in communication with the operating media supply cavity and the operating media exhaust cavity. The surface communicates a flow of operating media between a minimum of two of the at least four operating media transmission cavities. The first process valve actuator includes a first operating media port that is connected to the first operating media transmission cavity, and a second operating media port that is connected to the second operating media transmission cavity. And the second process valve actuator includes a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 298

third operating media port that is connected to the third operating media transmission cavity, and a fourth operating media port that is connected to the fourth operating media transmission cavity.

According to another preferred embodiment, a method of distributing operating media includes introducing an operating media supply to a manifold, allotting within the manifold the operating media supply to at least four operating media transmission passages, transporting to a first actuator operating media from a first minimum of two of the at least four operating media transmission passages, and collecting in an operating media exhaust passage exiting the manifold operating medium from a minimum of two of the at least four transmission passages.

According to another preferred embodiment, a method of distributing operating media include connecting an operating media supply to a manifold. The manifold defines an operating media supply passage, an operating media exhaust passage, a first operating media transmission passage, a second operating media transmission passage, a third operating media transmission passage, and a fourth operating media transmission passage. The method further includes directing operating media from the operating media supply to the first and third operating media outlet passages, and directing operating media from the second and fourth operating media outlet passages to the operating media exhaust passage.

The valve controller may have knowledge-based valve performance ("performance") attributes. The functionality of the microprocessor and methods for implementing performance attributes are developed by generic process flow charts that relate the evaluated pressures and the valve condition determined from the evaluated pressures. The valve controller with integral pressure sensors can be used to profile pressures of a single supply port and a single exhaust port so that diagnostics and fault monitoring can be accomplished with a microprocessor. Diagnostics for the performance attributes may include: (1) a "Factory Torque Profile", (2) a "Commissioned Torque Profile" and (3) a "Maintenance Torque Profile". Performance attribute fault monitoring may include: (1) "Insufficient Line Pressure to Guarantee Correct Operation", (2) "Supply Pressure Failure", (3) "Valve Shaft Bent", (4) "Valve Not Achieving Full Stroke", (5) "Backlash Detection", (6) "Torque Demand of Valve Approaching Actuator limit", (7) "Valve Seating/ Break-Out Torque Monitoring", (8)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 299

"Torque Limit Exceeded", (9) "Close on Torque", (10) "Shaft Broken", (11) "Valve Exercise", (12) "Valve Packing Torque", (13) "Line Filter and Silencers Conditions", and (14) "Solenoid Spool Sticking".

Methods of valve diagnostics and fault monitoring provided by a valve controller with integrated pressure sensors are described. Each of the diagnostic capabilities of the valve controller has a separate method. For example, the "Commissioned Torque Profile" or "Maintenance Torque Profile" may be used to compare with a factory torque profile to detect any fouling of the valve disc or deformation of the valve seat. In another example, the "Insufficient Line Pressure to Guarantee Correct Operation" fault monitoring can be used to indicate that the air supply pressure to a valve may not be sufficient to guarantee either opening or closing. In another example, the "Supply Pressure Failure" fault monitoring may be used to indicate that supply line pressure has fallen bellow a required amount. In yet another example, "Valve Shaft Bent" fault monitoring may be used with a phase shift of torque profile to determine if a valve shaft is bent.

Remote communication with the valve controller can be provided via wire or wireless technology. Each of the features for protection with respect to the valve operative arrangements and knowledge based valve performance can be used with a short-range wireless protocol, or a communication method via the Internet. The combination of knowledge based valve performance with remote communications via the Internet provides various opportunities to implement maintenance and monitoring of valves at a location remote from the location of maintenance staff. For example, the valve controller can be used with a method of maintaining the operative performance of two valves, including evaluating the operative conditions of two valves with a single valve controller, communicating the operative conditions of the two valves to a remote location via an internet communication link, and changing operative commands of the valve controller via an internet communication link.

Sub-components of the valve controller may have preferred embodiments. For instance, features of the pneumatic manifold assembly/manifold may have a preferred embodiment. In one example, the manifold assembly may include a manifold with coils and spools. In another example, the manifold assembly may have a single supply path, two pilot paths, and a single exhaust path. The manifold assembly may further be a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 300

monolithic member or a two-piece member. The two-piece member may include a base and a cover, the cover defining paths within the base. In another example, the manifold assembly may include a manifold with two coils, two spools, and sensors. In another example, the manifold assembly may a single supply path, two pilot paths, and single exhaust path that can be used as a stand alone valve controller island. In yet another example, the manifold assembly may be operatively associated with an electronic controller disposed in the enclosure, the manifold assembly having a single supply path, two pilot paths, and single exhaust path. In another embodiment, the manifold assembly may be operatively associated with existing smart valve controllers. Moreover, features of the mechanical enclosure may be preferred. For example, in one embodiment the mechanical enclosure may include a pneumatic manifold assembly and a manifold block. In another embodiment, the mechanical enclosure may be packaged together with a separate electronic enclosure. In another embodiment, the mechanical enclosure may be used as a stand-alone valve controller island. Additionally, features of the beacon (position indicator) housing and beacon (position indicator) may be preferred. For example in one embodiment, the beacon (position indicator) may have a housing that defines a viewing window for a position indicator and a mounting surface generally parallel to a longitudinal axis of the position sensor.

According to a preferred embodiment, a manifold apparatus, which distributes operating media, includes first and second members. The first member has a plurality of cavities, including an operating media supply cavity, that transport operating media, and the second member defines a surface that cooperates with the first member so as to contain and transport operating media between at least two cavities.

Systems that include the valve controller or utilize a feature on the valve controller are described. For example, the valve controller can be used in a system of piping including a first pipe, a second pipe proximate the first pipe, a valve disposed between the first pipe and the second pipe, a valve actuator that operates the valve, and a valve controller that operates the valve actuator, the valve controller including a housing having a single supply path that feeds two separate pilot paths, the two separate pilot paths having a common exhaust path. Further details of the system are described to specify various illustrative uses of the valve controller. For example, piping to the controller can be defined.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 301

According to a preferred embodiment, a piping system includes a first pipe, a first process valve that is connected to the first pipe, a first actuator that operates the first process valve, and a device that controls the first actuator. The device includes an enclosure that defines first and second chambers, an indicator proximate the first and second chambers, an operating media distribution system disposed in the first chamber, and an electronic control unit disposed in the second chamber. The first and second chambers are spaced from each other along a longitudinal axis. The indicator has a visual symbol that identifies an operational state of at least one valve. The operating media distribution system includes an operating media supply passage, an operating media exhaust passage, at least three operating media transmission passages, and a plurality of valves in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least three operating media transmission passages. And the electronic control unit operates at least one of the plurality of valves to control operating media flow in the operating media distribution system.

According to another preferred embodiment, a piping system includes a first pipe, a first process valve that is connected to the first pipe, a first actuator that operates the first process valve, and a device that controls the first actuator. The device includes an enclosure, an operating media distribution system disposed in the enclosure, an electronic control unit that is disposed in the enclosure, and at least one sensor that is disposed in the enclosure. The operating media distribution system includes an operating media supply passage, an operating media exhaust passage, at least two operating media transmission passages, and a valve that is in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least two operating media transmission passages. The electronic control unit operates the valve to control operating media flow in the operating media distribution system. And the sensor evaluates the operating media distribution system and provides information to the electronic control unit about at least one operating condition in at least one of the passages.

According to yet another preferred embodiment, a piping system includes a first pipe, a first process valve that is proximate the first pipe, a first actuator that operates the first process valve, and an operating media distribution system that controls the first actuator. The operating media distribution system includes a manifold. The manifold

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 302

defines an operating media supply passage that introduces operating media into the operating media distribution system from outside the housing, an operating media exhaust passage that discharges operating media from the operating media distribution system to outside the housing, and at least four operating media transmission passages that are in fluid communication with the operating media supply and exhaust passages. A minimum of two of the at least four operating media transmission passages are in fluid communication with the first actuator.

Brief Descriptions of the Drawings

The accompanying drawings, which are incorporated herein and constitute part of this specification, illustrate an embodiment of the invention, and, together with the general description given above and the detailed description given below, serve to explain the features of the invention.

Figure 1A is a perspective view of an exemplary embodiment of a system including a preferred embodiment of a pneumatic valve controller, the valve controller having separate chambers for mechanical and electrical components.

Figure 1B is a perspective view, with the cover removed, of the valve controller illustrated in Figure 1A.

Figure 2 is a view, taken along line 2-2 in Figure 1A, showing in cross-section an enclosure for the pneumatic valve controller illustrated in Figure 1B, and showing in elevation internal components of the pneumatic valve controller.

Figure 3A is a perspective view of a pneumatic manifold assembly for the valve controller illustrated in Figure 1B.

Figure 3B is a schematic diagram of selected features of the manifold assembly illustrated in Figure 3A.

Figures 4A is a top plan view, showing internal cavities in hidden lines, of a bottom portion of the manifold assembly illustrated in Figure 3A.

Figures 4B is a left-side plan view of a bottom portion of the manifold assembly illustrated in Figure 3A.

Figures 4C is a back plan view of a bottom portion of the manifold assembly illustrated in Figure 3A.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 303

Figures 4D is a bottom plan view, showing internal cavities in hidden lines, of a bottom portion of the manifold assembly illustrated in Figure 3A.

Figures 4E is a right-side plan view of a bottom portion of the manifold assembly illustrated in Figure 3A.

Figures 5A is a left-side plan view of a top portion of the manifold assembly illustrated in Figure 3A.

Figures 5B is a top plan view of a top portion of the manifold assembly illustrated in Figure 3A.

Figures 5C is a right-side plan view of a top portion of the manifold assembly illustrated in Figure 3A.

Figures 5D is a front plan view of a top portion of the manifold assembly illustrated in Figure 3A.

Figures 5E is a bottom plan view of a top portion of the manifold assembly illustrated in Figure 3A.

Figure 5F is a back plan view of a top portion of the manifold assembly illustrated in Figure 3A.

Figure 6 is a front plan view of the pneumatic manifold assembly illustrated in Figure 3A.

Figures 6A is a cross-section view taken along line 6A-6A in Figure 6.

Figures 6B is a cross-section view taken along line 6B-6B in Figure 6.

Figures 6C is a cross-section view taken along line 6C-6C in Figure 6.

Figures 6D is a cross-section view taken along line 6D-6D in Figure 6.

Figures 6E is a cross-section view taken along line 6E-6E in Figure 6.

Figures 6F is a cross-section view taken along line 6F-6F in Figure 6.

Figures 6G is a cross-section view taken along line 6G-6G in Figure 6.

Figures 6H is a cross-section view taken along line 6H-6H in Figure 6.

Figure 7A is a top plan view of a cap portion of the manifold assembly illustrated in Figure 3A.

Figure 7B is a front plan view of a cap portion of the manifold assembly illustrated in Figure 3A.

Figure 7C is a bottom plan view of a cap portion of the manifold assembly illustrated in Figure 3A.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 304

Figure 8 is a partial top plan view including tubing connecting pressure sensors to monitoring ports on the manifold assembly illustrated in Figure 3A.

Figure 9A is a view, taken along a portion of line 2-2 in Figure 1A, showing in cross-section an enclosure for the pneumatic valve controller illustrated in Figure 1B, and showing partially in cross-section and partially in elevation a valve position indicator of the pneumatic valve controller. Figure 9A accurately depicts the scale and relative proportion of the features shown therein.

Figure 9B is a perspective view of the valve position indicator illustrated Figure 9A. Figure 1B accurately depicts the scale and relative proportion of the features shown therein.

Figure 10A is a plan view of electrical components of the valve controller illustrated in Figure 1B.

Figure 10B is a front view of electrical components illustrated in Figure 10A.

Figures 11A, 11B and 11C are schematic diagrams illustrating an electrical circuit of the valve controller illustrated in Figure 1B.

Figure 12A is a schematic diagram illustrating a first preferred embodiment of a piping system with a valve controller, as shown in Figure 1B, in an exemplary configuration for independently controlling two process valves. Valve actuators for both process valves are show in a zeroed position.

Figure 12B is a schematic diagram similar to Figure 12A except showing in a spanned position the valve actuators for both process valves.

Figure 13A is a schematic diagram illustrating a second preferred embodiment of a piping system with a valve controller, as shown in Figure 1B, in an exemplary configuration for controlling one process valve. The valve actuator for the process valve is shown in a zeroed position.

Figure 13B is a schematic diagram similar to Figure 13A except showing in a spanned position the valve actuator for the process valve.

Figure 13C is a schematic diagram similar to Figures 13A and 13B except showing in a partially stroke position the valve actuator for the process valve.

Figure 14A is a schematic diagram illustrating a third preferred embodiment of a piping system with a valve controller, as shown in Figure 1B, in an exemplary

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 305

configuration for controlling one process valve. The valve actuator for the process valve is shown in a zeroed position.

Figure 14B is a schematic diagram similar to Figure 14A except showing in a spanned position the valve actuator for the process valve.

Figure 15 is a chart showing exemplary data describing the relationship between valve controller air supply pressure and valve position.

Figures 1A, 1B, 2, 3A, 4A-4E, 5A-5F, 6, 6A-6H, 7A-7C, 8, 9A and 9B accurately depict the scale and relative proportion of the features shown therein.

Detailed Description of the Preferred Embodiments

Figure 1A illustrates an exemplary embodiment of a piping system 1 including a process valve 3, an actuator 5 for the process valve 3, and a valve controller 10 with enclosures 12,14 for mechanical and electronic components. Referring additionally to Figure 1B, the enclosures define chambers 16 for all components to avoid exposure to operative conditions. Referring back to Figure 1A, releaseably securable enclosure covers 18a,18b, which may be independently removed, separately cover enclosures 12,14, respectively. The enclosure covers 18a,18b allow for maintenance of the valve controller 10 such that access to either the mechanical or electrical chamber only is required for service. Alternatively, a single cover could be used in place of separate enclosure covers 18a,18b.

As shown in Figure 1B, the valve controller 10 may have separate enclosures 12, 14 for mechanical and electronic components, one enclosure 12 may provide housing for mechanical components such as a pneumatic manifold assembly 20 and another enclosure 14 may provide space in the chamber 16 for electronic components such as circuit boards including a microprocessor and/or other circuits, as will be described further with respect to Figure 10A. The enclosures may have any shape and configuration as long as they define at least one chamber for all components to avoid exposure to operative conditions. For instance, the separate enclosures 12,14 may abut or be situated adjacent to one another, and form a particular shape. For example, the valve controller 10 may have a polygonal shape with each enclosure 12,14 forming a portion of the polygonal shape. According to a preferred embodiment, the valve controller 10 may have a bow-tie shape.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 306

The enclosures 12,14 for mechanical and electrical components may be separated by a third enclosure 22 for housing a valve position indicator 24. The third enclosure 22 may include an independently and releasably securable cover 22a. The third enclosure cover 22a may also have a bow tie configuration, the tapered sides of the third cover 22a allowing the valve position indicator 24 to be directly visible from a site range above the centerline of the position indicator 24. The third enclosure cover 22a, however, may have any shape or configuration provided it allows the valve position indicator to be viewed from a position above the valve controller. Further, the three enclosures 12,14,22, may have any configuration that provides direct visibility of the position indicator 24. For example, the valve controller 10 may have a suitable shape such as, for example, square, rectangular, oval-like or circular configuration such that the shape allows the valve position indicator 24 to be directly visible to an observer from a site range both above and below the center line of the position indicator 24. Similarly, any number of members may be used to cover the enclosures provided the members cooperate with the enclosures to define at least one chamber for all components to avoid exposure to operative conditions. Thus, in one example, the cover may be a unitary member. In another example, the cover may have two members.

The valve controller enclosures 12,14,22 and covers 18a,18b,22a may be formed from any suitable metal, alloy, composite, or plastic material. For example, one or more of the independently removable enclosure covers 18a,18b,22a may be formed from a transparent plastic material. Similarly, as shown in Figure 1A, one or more of the enclosures 12,14 and enclosure covers 18a,18b may be fashioned from opaque plastic materials. The valve controller enclosures 12,14,22 and covers 18a,18b,22a may further be made from corrosion resistant materials such as polypropylene. The enclosure and covers may also be adapted for approved use in hazardous atmospheres.

As shown in Figure 2, the valve controller 10 of Figure 1B has a height profile h that is measured from between parallel planes 17a,17b. According to a preferred embodiment, the top and bottom surfaces of the enclosure of valve controller 10 coincide with parallel planes 17a,17b. Essentially, the process valve 3, including the actuator 5, has a maximum exterior package dimension, i.e., the distance between the distal most points of the combination process valve 3 and actuator 5, that is greater than the height profile h. Preferably, height profile h of the enclosure of valve controller 10 is about

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 307

three inches. In the preferred embodiment illustrated in Figure 2, height profile h is about 2.725 inches.

Referring back to Figures 1A and 1B, the valve position indicator 24 may also have a beacon or position indicator 26 or visual signal for identifying the position or operating state of one or more process valves that are being controlled by the controller. For example, the beacon 26 may provide a distinct visual signal for a process valve operating under normal conditions in an open position, closed position, or an intermediate position between the open and span position. As described further below with respect to Figure 9B, the valve position indicator 24 may also have a distinct visual beacon signal 26 for identifying the state of at least one, and preferably two, independent process valves that are being controlled by the controller. The valve position indicator 24 may be a rotary or linear, and may be located between separate chambers 12,14 for mechanical and electronic components. The size of the beacon 26 may be selected to allow for viewing from a remote location. The valve position indicator 24 may be disposed adjacent operative components so that beacon 26 can be viewed from a site range both above and below the centerline of the position indicator. The beacon 26 may operate, for example, via a non-contact position sensor (not shown) such that the valve controller 10 need not be integrally connected to a process valve actuator. Alternatively, the valve position indicator 24 may have a shaft (not shown) that is operatively coupled directly to the actuator for the process valve 3, so that movement of the actuator directly rotates the beacon 26 to indicate the position of the process valve 3.

Referring to Figure 3A, valve controller 10 has one manifold inlet operating media supply port 28, one manifold outlet operating media exhaust port 30, and four operating media transmission ports 32 for process valve actuator operation. The ports 28,30,32 are adapted to connect to one-half inch NPT or M20 conduit (not shown) with suitable conduit attachment members 34 on a port manifold 36 of the valve controller 10. The port manifold 36 is located at the base of manifold assembly 20. Manifold assembly 20 includes port manifold 36 (lower manifold portion), manifold 38 (upper manifold portion), spool valve assembly 40, manifold cap 42, and coil bank assembly 44. As shown in Figure 1B, manifold assembly 20 may also include one or more pressure sensors (two exemplary pressure sensors 346 and 356 are indicated in Figure 1B).

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 308

Referring to Figures 3A and 3B, manifold assembly 20 has one inlet air supply that is directed to two spool valves 48,50, via separate supply cavities 52,54. The inlet air supply is also directed to four separate poppet cavities 56,58,60,62, which set the configuration of the spool valves 48,50. The supply of inlet air to the poppet cavities 56,58,60,62 is regulated by four actuators, for example, electromagnetic solenoid valves or micro-poppets 64,66,68,70. For example, valves 64,66,68,70 can be part number A00SC231P solenoid valves manufactured by Parker Hannifin Corporation® (Richland, Michigan). The single exhaust outlet 30 is diverted into eight exhaust cavities 72,74,76,78,80,82,84,86. Exhaust cavities 80,82,84,86 are not depicted in Figure 3B, but are shown in Figures 5A-5F as described further below. Exhaust cavities 72,74,76,78 of manifold 38 join four cavities 88,90,92,94 of port manifold 36.

Referring additionally to Figures 4A-4E, port manifold 36 accepts an external operating media, e.g., air, supply to inlet air supply port 28, which transports the inlet air supply to the manifold 38 via a pair of supply cavities 52,54. Inlet air supply cavity 28 also has a secondary external port 96 for possible emergency pressure relief. Port manifold 36 collects manifold 38 exhaust for discharge to the ambient atmosphere at exhaust port 30. Port manifold 36 separately collects and transports spool valve 48,50 exhaust from four cavities 72,74,76,78 in the manifold 38 to external ports 88,90,92,94, which can be used to operate up to two pneumatic valve actuators. Port manifold 36 can also serve as a structural base for seating the manifold 38, spool valve assemblies 48,50 and/or the mechanical enclosure 12. Port manifold 36 has a groove 36a for receiving a gasket 98, four fastener holes 100 for securing the port manifold 36 to the manifold 38, and four fastener holes 102 for securing the manifold assembly 36,38 to the medial portion of the enclosure 12.

Referring to Figures 5A-5F, manifold 38 contains and transports compressed air between the port manifold 36, spool valves 48,50 and coil bank assembly 44 in conjunction with the manifold cap 42. Manifold 38 preferably includes a monolithic member 104. As it is used herein, the term "monolithic" refers to a single, uniform whole member, preferably formed of a homogeneous material. The monolithic member 104 has at least one outer surface 106. As shown in Figures 5A-5E, the manifold 38 preferably includes six outer surfaces or sides 108,110,112,114,116,118 (e.g., "left-side", "top", " right-side", "front", "bottom", and "rear" surfaces). The six outer surfaces

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 309

108,110,112,114,116,118 form a rectangular block having a length, width and height, such that a distance measured between the front and rear surfaces 114,118 defines the length of the block, a distance measured between the top and bottom surfaces 110,116, defines the height of the block, and a distance measured between the right-side and left-side surfaces 108,112 defines the width of the block. Preferably, the length of the manifold 38 is greater than the width, and the width is greater than the height. As described further below the outer surfaces 108,110,112,114,116,118 of the manifold 38 have openings that are in fluid communication with a plurality of internal cavities. The manifold has openings on five sides 108,110,112,114,116, such that the rear side 118 of the block does not have a cavity opening. The manifold 38 can be made of any suitable material, such as for example, metal, alloy, composite, and plastic materials. At ambient temperatures, the block material and internal cavity configuration should be capable of containing and transporting operating media, for example, non-lubricated air filtered to about 20 microns (or some other fluid), at temperatures between about –4 degrees Fahrenheit to 180 degrees Fahrenheit and at pressures of between about 45 to 120 pounds per square inch gauge.

As shown in Figure 5A, left side surface 108 includes three fastener holes 150, one inlet air supply cavity 52 and one inlet air supply transfer cavity 132f, two poppet cavity transfer cavities 124,138, two spool valve exhaust cavities 72,74, and two poppet cavity exhaust cavities 80,82.

As shown in Figure 5B, top surface 110 includes four fastener holes 120, four spool valve exhaust pressure monitoring port cavities 72,74,76,78, four poppet cavity exhaust cavities 80,82,84,86, one manifold exhaust cavity 122, four poppet cavity transfer cavities 124,126,128,130, and two inlet air supply transfer cavities 132,134.

As shown in Figure 5C, right side surface 112 includes three fastener holes 150, one inlet air supply cavity 54 and one inlet air supply transfer cavity 132e, two poppet cavity transfer cavities 140,128, two spool valve exhaust cavities 76,78, and two poppet cavity exhaust cavities 84,86.

As shown in Figure 5D, front surface 114 includes four fastener holes 136, four inlet air supply transfer cavities 132a,132b,132c,132d, four poppet cavity transfer cavities 138,126,130,140, and four solenoid (or micro-poppet) exhaust cavities

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 310

142,144,146,148. The four solenoid exhaust cavities discharge to poppet cavity exhaust cavities 82,86.

As shown in Figure 5E, bottom surface 116 includes four fastener holes 120, two manifold inlet air supply cavities 52,54, four spool valve exhaust cavities 72,74,76,78, one manifold exhaust cavity 122, and one gasket seat cavity 152.

As shown in Figure 5F, the rear surface 118 does not include any openings.

Figures 6A-6H illustrate the internal pathways, connections and spatial relationships between the internal cavities identified in Figures 4A-4E and 5A-5F. These pathways, connections and spatial relationships between the internal cavities provide means for directing operating media flow between the operating media supply passage 28, the operating media exhaust passage 30, and the media transmission passages 32.

Referring to Figure 6H, spool valve 48 and spool valve 50 direct airflow though the manifold 38 to operate one or more pneumatic valve actuators. Each spool valve 48,50 includes a spool valve assembly 40. Each spool valve 48,50, which may be constructed according to known techniques, includes a valve body 154 and a spool assembly 156, and two valve caps 158. For example, spool valves 48,50 can be part number 92273U-1 spool assemblies manufactured by Numatics® (Highland, Michigan).

As shown in Figure 6H, valve body 154 encloses spool assembly 156 and includes and two poppet cavities 160, 162 that operate to contain operating media from poppet transport cavities (e.g., 128,140) in manifold 38, and to direct manifold inlet air supply to an appropriate exhaust cavity (e.g., 78,76). Valve body 154 includes outer surfaces (e.g., six according to the preferred embodiment), some or all of which may have openings in fluid communication with a plurality of internal cavities.

According to a preferred embodiment, the manifold assembly 20 includes a first operating media distribution valve, e.g., spool valve 48, in fluid communication with the operating media supply cavity 28, first and second ones of the operating media transmission cavities 32, and the operating media exhaust cavity 30. The first operating media distribution valve 48 includes a first configuration that A) connects the operating media supply cavity 28 with the first one of operating media transmission cavities 32, and B) connects the second one of the operating media transmission cavities 32 with the operating media exhaust cavity 30. The first operating media distribution valve 48 also includes a second configuration that C) connects the operating media supply cavity 28

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 311

with the second one of the operating media transmission cavities 32, and D) connects the first one of the operating media transmission cavities 32 with the operating media exhaust cavity 30. The manifold assembly 20 also includes a second operating media distribution valve, e.g., spool valve 50, in fluid communication with the operating media supply cavity 28, first and second ones of the operating media transmission cavities 32, and the operating media exhaust cavity 30. The second operating media distribution valve 50 includes a third configuration that A) connects the operating media supply cavity 28 with the third one of operating media transmission cavities 32, and B) connects the fourth one of the operating media transmission cavities 32 with the operating media exhaust cavity 30. The second operating media distribution valve 50 also includes a fourth configuration that C) connects the operating media supply cavity with the fourth one of the operating media transmission cavities 40, and D) connects the third one of the operating media transmission cavities 32 with the operating media exhaust cavity 30. The first, second, third and fourth configurations provide means for directing operating media flow between the operating media supply passage 28, the operating media exhaust passage 30, and the media transmission passages 32.

The valve body 154 can be made of any suitable material, such as for example, metal, alloy, composite, and plastic materials. At ambient temperatures, the valve material and internal cavity configuration should be capable of containing and transporting operating media, for example, non lubricated air filtered to about 20 microns (or some other fluid), at a temperature between about –4 degrees Fahrenheit to 180 degrees Fahrenheit and at pressures of between about 45 to 120 pounds per square inch gauge. The valve material and internal cavity configuration should also be capable of containing and transporting operating media, preferably air, at a flow rate of about 5 standard cubic feet per minute at about 40 pounds per square inch to about 100 standard cubic feet per minute at about 120 pounds per square inch.

Referring additionally to Figure 3A, the valve body 154 includes at least one fastener 164 (e.g., three are shown per valve body 154) securing the valve body 154 to the manifold 38. Each of the valve caps 158 is secured to the valve body 154 by at least one fastener 166 (e.g., two are shown per valve cap 158). Individual valve caps 158 are configured and dimensioned to be releasably secured to opposite surfaces of valve body

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 312

154 so as to retain spool assembly 156 within valve body 154 and to contain operating media in spool valve poppet cavities 160,162.

Spool assembly 156 selectively directs spool valve inlet air supply from cavity 180 to one of two spool valve exhaust cavities 182,184. The spool assembly 156, in a known manner, has a length measured from end to end that is less than the length of a bore of the valve body 154. Spool assembly 156 includes at least one internal bore (not shown) and a plurality of apertures 214 extending from the outer surface of spool assembly 156 to the bore. Apertures 214 are preferably of equal size and are preferably spaced in a uniform pattern uniformly about at least one designated portion of spool assembly 156. According to a preferred embodiment, a pattern including five rings of radially aligned apertures 214 is alternately disposed with six radial grooves 215 spaced equidistant along spool assembly 156. Each radial groove 215 is configured and dimensioned to receive a gasket material such as an o-ring (not shown). The inner surface of the bore of valve body 154 is generally smooth and has a diameter that is sized and configured to telescopically receive spool assembly 156.

Referring to Figures 7A-7C, as well as to Figures 6A-6G, manifold cap 42 is releasably securable to manifold 38 to contain and transport operating media, such as compressed air, between four poppet cavity exhaust cavities 80,82,84,86 and the manifold exhaust cavity 122, two pairs of poppet cavity transfer cavities 124,126,128,130, and one pair of inlet air supply transfer cavities 132,134.

Manifold cap 42 includes a generally planar member having top and bottom surfaces 288,290 and four bores or fastener holes 292 extending from the top surface 288 to the bottom surface 290. The bores 292 are generally located around the periphery of the top surface 288. The bottom surface 290 is generally flat and smooth. The bottom surface 290 has four recesses 294 extending from the bottom surface toward the top surface. One recess 294a is generally U-shaped and three recesses 294b-294d are generally linear in shape. Each recess 294 has a bottom surface generally parallel in orientation to the bottom surface 290 of the manifold cap 42, and one or more sidewalls extending from the bottom surface of each recess 294 to the bottom surface 290 of manifold cap 42. The sidewalls are generally perpendicular to the bottom surfaces of both recess 294 and manifold cap 42. The bottom surface of one or more of the recesses 294 may be located above a portion of the top surface 286 of the manifold cap 42, such

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 313

that one or more of the recesses 294 may form a structure in relief relative to a base area of top surface 288 of manifold cap 42. Each recess 294 defines an isolated portion in the manifold cap 42. When the manifold cap 42 is secured to the manifold 38, each of the recesses 294a-d form a separate chamber, and each chamber communicates with two or more cavity openings on top surface 110 of manifold 38. The recesses, however, may have any shape provided each recess defines a separate chamber and each chamber communicates with the proper cavity openings as described below. A manifold cap gasket may be placed between the manifold cap 42 and the manifold 38 to maintain chamber isolation.

Figures 6A-6G show four "air ports" 396a-d formed by recesses 294 in the manifold cap 42 when the manifold cap 42 is secured to the manifold 38. U-shaped "air port" 396a communicates with four poppet cavity exhaust cavities 80,82,84,86, and one manifold exhaust cavity 122. A first linear "air port" 396b communicates with one pair of poppet cavity transfer cavities 124,126. A second linear "air port" 396c communicates with a second pair of poppet cavity transfer cavities 128,130. And, a third linear "air port" 396d communicates with a pair of inlet air supply transfer cavities 132,134. As shown in Figure 3A, the manifold cap 42 can also include external sample ports 302 that are in fluid communication with underlying cavities. The sample ports 302 can also have attachment sites for plastic tubing, as shown in Figures 1B and 2.

Fastener holes 292 in the manifold cap 42 allow at least one fastener 102 (*see* Figure 6F) to secure the manifold cover 42 to manifold 38, and to secure the manifold 38 to the base of the port manifold 36. The manifold cap 42, manifold 38, and port manifold 36, therefore, may be fastened together using a set of common fasteners. For instance, the fasteners may be screws. Any number of fasteners or type of mechanical fastening system may be used to sure the manifold cap 42, manifold 38, and port manifold 36 together provided the assembly is securely fastened and capable of operation.

Referring to Figure 3A, coil bank assembly 44 selectively diverts inlet air and exhaust from the poppet cavities 56,58,60,62 of the two spool valves 48 and 50 to control the position of the respective process valve shafts. The four micro-poppet solenoids 64,66,68,70 are individually and independently associated with a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 314

corresponding poppet cavity in spool valves 48 and 50. Solenoid valves 64,66,68,70 are operatively associated with poppet cavities 144,142,146,148, respectively.

Coil bank assembly 44 includes four micro-poppet solenoid valves 64,66,68,70, a coil bank gasket 310, a coil plate 312, and coil bank gasket 314. The front of the each micro-poppet solenoid valve 64,66,68,70 has a receptacle 318 for receiving an electrical signal, and two holes 320 for receiving fastening elements. The back surface of each micro-poppet solenoid valve 64,66,68,70 has three openings 324 for receiving or conveying airflow with the manifold 38.

Coil bank gasket 310 includes a thin flexible sheet gasket with openings 312 for transmitting airflow and fastening elements. One side of the coil bank gasket 310 abuts the rear side of the coil bank assembly 44, and a second side of the coil bank gasket 310 abuts coil plate 312. Coil plate 312 includes a planar member having first and second sides and a side surface between the first and second sides. The first side abuts the coil bank gasket 310 and the second side abuts coil bank gasket 314. Coil plate 312 has sixteen bores extending from the first side to the second side. Twelve of the bores are for transmitting airflow, and four are for receiving fastening elements. The four fastener bores are countersunk on the first side. Coil plate 312 also has eight bores extending into the coil plate 312 from the first side. Coil bank gasket 314 includes a planar member or thin flexible sheet with openings for transmitting airflow and fastening elements. One side of coil bank gasket 314 abuts the rear side of coil plate 312. A second side of coil bank gasket 314 abuts manifold 38.

Referring to Figure 8, pressure sensors can be used to measure manifold inlet air pressure, manifold exhaust air pressure, and the differential pressure across the exhaust cavities of each spool valve. Inlet air pressure and manifold exhaust air pressure sensors 344,346 are pressure transducers with one port for receiving airflow. Each pressure transducer 344,346 has six leads 350 for receiving electrical current and transmitting electrical signals to the electronic controller. The inlet air pressure sensor and manifold air pressure sensor are mounted to a bracket 352 adjacent the coil bank assembly 44 within the enclosure. Differential pressure sensors 354,356 are pressure transducers with two ports 358,360 for receiving airflow. The pressure transducers 354,356 have six leads 362 for receiving electrical current and transmitting electrical signals to the electronic controller. The differential pressure sensors 354,356 are each individually

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 315

mounted adjacent their respective spool valve 48,50. Plastic tubing 366 is used to connect each pressure transducer to the designated sample ports.

Referring also to Figure 8, one-half of a so-called "bow-tie" shape is illustrated with respect to enclosure 12. As it is used herein, the term "bow-tie" refers to a shape of an elongated body that extends along a longitudinal axis between end portions, and has a middle portion that is relatively constricted with respect the end portions. According to a preferred embodiment, enclosure 12, for example, includes a wall that extends around the manifold assembly 20. The wall includes a first segment 12a and a second segment 12b that, at least in part, mutually define a portion of the chamber 16 in which the manifold assembly 20 is disposed. As shown in Figure 8, the first and second segments 12a,12b extend transversely with respect to a longitudinal axis L, and have respective lengths L1,L2 One-half of the "bow tie" shape is achieved when the first segment 12a, which is closer to enclosure 14 than second segment 12b, is also shorter than segment 12b (i.e., L1 is less than L2).

Although segments 12a,12b are shown extending transversely with respect to longitudinal axis L, they may alternatively extend obliquely and/or may not extend along a line, e.g., they may be curved. In any event, one –half of the bow-tie shape is still formed as long as a projection along the longitudinal axis of the segment 12b has a transverse length L2 with respect to the longitudinal axis L that is greater than the transverse length L1 of a similar projection along the longitudinal axis of the segment 12a, which is closer than segment 12b to the middle of valve controller 10.

Referring to Figures 1A, 9A and 9B, the valve position indicator 24 includes a cage 374 and a beacon (position indicator) 376. The cage 374 is preferably formed integrally with either or both of the enclosures 12,14, but may be separately formed and subsequently secured to the enclosure for the mechanical components 12 and/or the enclosure for the electronic components 14. Cage 374 defines a volume 378 in which the beacon 376 is received and includes a projection 386 for slidably receiving beacon (position indicator) 376. As shown in Figure 9B, an exemplary beacon (position indicator) 376 has markings 388 that show the position of two valves. The cage 374 and exemplary beacon (position indicator) 376 can be mounted on to a rotary actuator or remotely wired to a position sensor on the actuator. For instance, the position sensor can be a non-contact Hall effect sensor as described in Avid position monitors technical

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 316

publications "tech-251/DW011930", "tech-260/D.W.O.11030", and "tech-300/D.W.O.13882", the contents of each of these publication are herein incorporated by reference herein their entirety, and were attached as Appendix A to U.S. Provisional Application No. 60/559,002, filed 5 April 2004, which is also incorporated by reference herein in its entirety.

Referring to Figures 1A, 9A and 9B, the valve controller 10 may also have a separate enclosure 14 and enclosure cover 18b for electronic components so that an electronic controller may be disposed on or within the electronic enclosure 14 in manner which may provide for access to the electronic components independently from the mechanical assembly. As is the case for the enclosure cover 18a for mechanical components in the enclosure 12, the electronic enclosure cover 18b may be attached or releasably securable to the enclosure 14 by any suitable means. For instance, the covers 18a,18b may be fastened to the enclosures 12,14 with one or more fasteners, such as a screw.

Referring to Figures 10A and 10B, electronic components 390 may be arranged or disposed in any suitable fashion within the enclosure 14. For example, circuit boards 392 and other electronic components in the enclosure may be stacked vertically and connected by cable. As shown in Figure 10B, an exemplary configuration of electronic components has four circuit boards 392 stacked over top each other and spaced apart by varying distances as may be appropriate for the components of each circuit board. Some or all of the components on lower boards 392 located vertically below one or more other boards may still be visible from a plan view. For example, solenoid valve output connections may be located on the third circuit board as enumerated from the top board, yet may still be visible and accessible from the top of the electronic enclosure. Such an arrangement may facilitate installation, maintenance, testing or ascertaining faulty electronic components or circuits.

Referring to Figures 11A-11C, the electronic components of the valve controller may include a universal mother board having: a 2 Line by 16 Character liquid-crystal display (LCD) 400; Programming buttons (e.g., Select, Next↑, Next↓) 402; Analog Inputs (e.g., one position sensor for measuring valve position from 0.0 to 100.0% (e.g., a Hall Effect Position Sensor), and five Pressure Sensors for measuring air pressure of the supply and manifold) 404; Analog Outputs (e.g., one primary 0-5 milliamps output for

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 317

driving a transducer, and one secondary 0-5 milliamps output for driving a transducer) 406; Discrete Outputs (e.g., four open collectors for driving solenoids, and one open collector for driving an light emitting diode) 408; Discrete Inputs (e.g., two dry contact sensing inputs for "Open & Close Limit Switches", one dry contact sensing input for "Partial Stroke Switch", and one voltage input for "Sensing SIS Power") 410.

The valve controller electronics may further include: a communications port (e.g., one RS232 for local diagnostics), 412; and a microprocessor 414 with associated peripherals such as, for example, various memory, controllers and converters. For instance, microprocessor CPU 414 can be a Motorola® MC68CK331CPV16 32 bit Microprocessor; Program Memory 416 can include AMD® Am29LV400BT-55REI, 256K x 16bit Flash memory; Data Memory 418 can include a CYPRESS® CY62146VLL-70ZI, 256K x 16 bit Static RAM; and Non-Volatile Memory 420 can include an ATMEL® AT25256W-10SI-2.7, 32K x 8 bit EEPROM. The valve controller electronics may also include: an Analog to Digital Converter 422 (e.g., Maxim® MAX1295BEEI, 6 Channel 12 bit); a Digital to Analog Converter 424 (e.g., Analog Devices® AD5342BRU, 2 Channel 12 bit); and Analog Instrument Amplifiers 426 (e.g., Texas Instruments® TLC27L4BID, Op-Amps). The valve controller electronics may further include: Discrete Output drivers 428 (e.g., Fairchild® NDS9945, 60V FET's); and Inter-processor communication circuitry 430 (e.g., TI® CD74HC40105M96, 16 Word FIFO). The valve controller electronics has a power supply 432, and may further have a plug-in network card 434 (e.g., ASi®, DeviceNet®, Profibus®, Foundation Fieldbus®, Modbus®, and/or HART®) for additional communication and other capabilities.

The valve controller may include short-range radio links 436 for local interface with the electronic components to provide for a peer-to peer wireless area network. The wireless network may be used, for example, to configure, calibrate, or perform diagnostics on the valve controller electronic systems. As described in more detail below, the wireless network may also be used to monitor and implement knowledge based performance systems. One known technology that uses short-range radio links for local interface is Bluetooth® technology. The valve controller electronics may include a "Bluetooth" radio module so that the controller is Bluetooth-capable. When Bluetooth-capable devices 438 (e.g., Personal Digital Assistants (PDAs), laptop computers, hand

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 318

phones) come within range of one another, an electronic conversation takes place to determine whether one needs to control the other. The user does not have to press a button or give a command -- the electronic conversation happens automatically. Once the conversation has occurred, the devices form a personal-area network or "piconet." Once the piconet is established, the members randomly hop frequencies in unison so they stay in touch with one another. The wireless system may further include one or more security measures which restricts access to the piconet.

In use, the electronic controller monitors electrical signals from the pressure sensors and valve position indicator to control the flow of an appropriate operating medium such as, for example, air through the manifold assembly. Specifically, each solenoid valve or micro poppet 64,66,68,70 opens and closes pathways to one spool valve poppet cavity 144,142,146,148, respectively. In one configuration, the solenoid valve or micro-poppet allows inlet air supply to the spool valve poppet cavity. In a second configuration, the solenoid valve or micro-poppet blocks inlet air supply to the spool valve poppet cavity, and opens an exhaust path to the atmosphere via the manifold. In this fashion, spool valve poppet cavities are energized or de-energized. Each spool valve 48,50 has a pair of opposing poppet cavities. For example, poppet cavity 142 and 144 can constitute the poppet cavities of spool valve 48, and poppet cavities 146 and 148 can constitute the poppet cavities of spool valve 50. When one spool valve cavity is energized, (i.e., 142) the opposing poppet cavity (i.e., 144) is de-energized. Energizing one poppet cavity while de-energizing another poppet cavity causes a pressure differential across the spool valve assembly, that pushes the spool shaft toward the de-energized cavity and allows segments on the shaft to selectively direct inlet air supply to the spool cavity of one of two exhaust cavities. Reversing the state of the poppet cavities moves the position of the shaft, and allows segments on the shaft to direct the inlet air supply to the second exhaust cavity. Exhaust from the spool valve drives the process valve actuator.

Figures 12A and 12B illustrate an exemplary manifold design for an operative arrangement that provides control for two independent valves. In particular, the schematic of Figures 12A and 12B describe two independent valve controls with one inlet air supply and one exhaust outlet. The single inlet air supply (I/A) is diverted into

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 319

six separate supply cavities. The single exhaust outlet (E) is diverted into eight exhaust cavities. The inlet air supply cavities are as follows:

- Cavity I/A 1 is to spool cavity SA, 52 -- This feeds I/A to a primary pneumatic actuator, which energizes and de-energizes a critical valve and / or damper.
- Cavity I/A 2 is to spool cavity SB, 54 -- This feeds I/A to a secondary pneumatic actuator, which energizes and de-energizes a non-critical valve and / or damper.
- Cavity I/A 3 is to poppet cavity A1, 56 -- This feeds I/A to the poppet coil E1, 64 that energizes primary spool A, 48.
- Cavity I/A 4 is to poppet cavity A2, 53 -- This feeds I/A to the poppet coil A2, 66 which de-energizes primary spool A, 48. This cavity may not be required if the application uses a spring return primary spool.
- Cavity I/A 5 is to poppet cavity B1, 60 -- This feeds I/A to the poppet coil B1, 68 that energizes secondary spool B, 50.
- Cavity I/A 6 is to poppet cavity B2, 62 -- This feeds I/A to the poppet coil B2, 70 which de-energizes secondary spool B, 50. This cavity may not be required if the application uses a spring return secondary spool.

The EX exhaust cavities are as follows:

- Cavity EX 1 is to exhaust cavity EA1, 72 -- This allows exhaust to atmosphere of the energizing primary pneumatic actuator port on a de-energizing command of the primary valve.
- Cavity EX 2 is to exhaust cavity EA2, 74 -- This allows exhaust to atmosphere of the de-energizing primary pneumatic actuator port on an energizing command of the primary valve.
- Cavity EX 3 is to exhaust cavity EB1, 76 -- This allows exhaust to atmosphere of the energizing secondary pneumatic actuator port on a de-energizing command of the secondary valve.
- Cavity EX 4 is to exhaust cavity EB2, 78 -- This allows exhaust to atmosphere of the de-energizing secondary pneumatic actuator port on an energizing command of the secondary valve.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 320

- Cavity EX 5 is to exhaust cavity PEA1, 80 -- This allows exhaust to atmosphere of the energizing primary poppet coil port on a de-energizing command of the primary valve.
- Cavity EX 6 is to exhaust cavity PEA2, 82 -- This allows exhaust to atmosphere of the de-energizing primary poppet coil port on an energizing command of the primary valve.
- Cavity EX 7 is to exhaust cavity PEB1, 84 -- This allows exhaust to atmosphere of the energizing secondary poppet coil port on a de-energizing command of the secondary valve.
- Cavity EX 8 is to exhaust cavity PEB2, 86 -- This allows exhaust to atmosphere of the de-energizing secondary poppet coil port on an energizing command of the secondary valve.

Figures 13A-C illustrate an exemplary manifold design for an operative arrangement that provides control for a single process valve. In particular, the schematics of Figures 13A-C describe a single valve control by two dependent spool valves with one inlet air supply and one exhaust outlet. The single inlet air supply (I/A) is diverted into five (5) separate supply cavities. The single exhaust outlet (EX) is diverted into eight exhaust cavities. The I/A supply cavities are as follows:

- Cavity I/A 1 is to spool cavity SB, 54 -- This feeds I/A to the secondary spool B, 50, which when energized will supply I/A to the primary spool A, 48, authorizing control of the pneumatic actuator. This is intended for use in Emergency Shut Down and Partial Stroke Testing of a critical valve and / or damper.
- Cavity I/A 2 is to poppet cavity A1, 56 -- This feeds I/A to the poppet coil A1, 64 that energizes primary spool A, 48.
- Cavity I/A 3 is to poppet cavity A2, 58 -- This feeds I/A to the poppet coil A2, 66, which de-energizes primary spool A, 48. (This cavity may not be required if the application uses a spring return primary spool.)
- Cavity I/A 4 is to poppet cavity B1, 60 -- This feeds I/A to the poppet coil B1, 68 that energizes secondary spool B, 50.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 321

- Cavity I/A 5 is to poppet cavity B2, 62 -- This feeds I/A to the poppet coil B2, 70 which de-energizes secondary spool B, 50. (This cavity may not be required if the application uses a spring return secondary spool.)

The EX exhaust cavities are as follows:

- Cavity EX 1 is to exhaust cavity EA1, 72 -- This allows exhaust to atmosphere of the energizing pneumatic actuator port on a de-energizing command of the valve and / or damper under normal operating conditions.
- Cavity EX 2 is to exhaust cavity EA2, 74 -- This allows exhaust to atmosphere of the de-energizing pneumatic actuator port on an energizing command of the valve and / or damper under normal operating conditions.
- Cavity EX 3 is to exhaust cavity EB1, 76 -- This allows exhaust to atmosphere of the energizing port of the authorization spool B on a de-energizing command for Emergency Shut Down and / or Partial Stroke Test requirements.
- Cavity EX 4 is to exhaust cavity EB2, 78 -- This allows exhaust to atmosphere of the de-energizing of the authorization spool B on an energizing command for normal operating conditions.
- Cavity EX 5 is to exhaust cavity PEA1, 80 -- This allows exhaust to atmosphere of the energizing primary poppet coil port on a de-energizing command of the valve and / or damper under normal operating conditions.
- Cavity EX 6 is to exhaust cavity PEA2, 82 -- This allows exhaust to atmosphere of the de-energizing primary poppet coil port on an energizing command of the valve and/or damper under normal operating conditions.
- Cavity EX 7 is to exhaust cavity PEB1, 84 -- This allows exhaust to atmosphere of the energizing authorization poppet coil port on a de-energizing command for Emergency Shut Down and / or Partial Stroke Test requirements. A data sheet for "Foundation Fieldbus Partial Stroke ESD Valve Monitor, Model 7345-ESD," by Westlock Controls Corp., Saddle Brook, New Jersey, describes a known Emergency Shut Down valve monitor and discusses of partial stroke testing. The contents of this publication is herein incorporated by reference herein its entirety, and was attached as Appendix B to U.S. Provisional Application No. 60/559,002,

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 322

filed 5 April 2004, which is also incorporated by reference herein in its entirety.

- Cavity EX 8 is to exhaust cavity PEB2, 86 -- This allows exhaust to atmosphere of the de-energizing authorization poppet coil port on an energizing command for normal operating conditions.

According to the preferred embodiment shown in Figures 13A-13C, a valve controller 10 with a single operating media supply port 28 allows for two operational control signals via . The two operation control signals can provide a first command signal and a second command signal to a single process valve 3. The first command signal could be a discrete command signal, e.g., to produce full and generally immediate operation by the process valve actuator 5, such as OPEN/CLOSE. The second command signal could be a modulating command signal, e.g., to produce a progressive and measured operation by the process valve actuator 5, such as to move between different partially open positions, e.g., 15%, 42%, 75%, etc.

Figures 14A and 14B illustrate another exemplary manifold design for an operative arrangement that provides control of a single process valve by two spool valves. In particular, the schematics of Figures 14A and 14B describe two dependent spool valves controlling one primary pneumatic actuator with one inlet air supply and one exhaust outlet. These operative arrangements may allow for increased airflow dynamics for the pneumatic actuator while utilizing a single inlet supply and single outlet exhaust. The single inlet air supply (I/A) is diverted into six (6) separate supply cavities. The single exhaust outlet (EX) is diverted into eight exhaust cavities. The I/A supply cavities are as follows:

- Cavity I/A 1 is to spool cavity SA, 52 -- This feeds I/A to a primary pneumatic actuator, which energizes and de-energizes a valve or damper.
- Cavity I/A 2 is to spool cavity SB, 54 -- This feeds I/A to a primary pneumatic actuator, which energizes and de-energizes a valve or damper.
- Cavity I/A 3 is to poppet cavity A1, 56 -- This feeds I/A to the poppet coil A1, 64 that energizes spool A, 48.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 323

- Cavity I/A 4 is to poppet cavity A2, 58 -- This feeds I/A to the poppet coil A2, 66 that de-energizes spool A, 48. This cavity may not be required if the application uses a spring return spool.
- Cavity I/A 5 is to poppet cavity B1, 60 -- This feeds I/A to the poppet coil B1, 68 that energizes spool B, 50.
- Cavity I/A 6 is to poppet cavity B2, 62 -- This feeds I/A to the poppet coil B2, 70 that de-energizes spool B, 50. This cavity may not be required if the application uses a spring return spool.

The EX exhaust cavities are as follows:

- Cavity EX 1 is to exhaust cavity EA1, 72 -- This allows exhaust to atmosphere of the energizing pneumatic actuator port on a de-energizing command of the valve.
- Cavity EX 2 is to exhaust cavity EA2, 74 -- This allows exhaust to atmosphere of the de-energizing pneumatic actuator port on an energizing command of the valve.
- Cavity EX 3 is to exhaust cavity EB1, 76 at the same time as the EA1, 72 -- This allows exhaust to atmosphere of the energizing pneumatic actuator port on a de-energizing command of the valve.
- Cavity EX 4 is to exhaust cavity EB2, 78 at the same time as the EA2, 74 -- This allows exhaust to atmosphere of the de-energizing pneumatic actuator port on an energizing command of the valve.
- Cavity EX 5 is to exhaust cavity PEA1, 80 this allows exhaust to atmosphere of the energizing poppet coil port on a de-energizing command of the valve.
- Cavity EX 6 is to exhaust cavity PEA2, 82 this allows exhaust to atmosphere of the de-energizing poppet coil port on an energizing command of the valve.
- Cavity EX 7 is to exhaust cavity PEB1, 84 at the same time as the PEA1, 80 this allows exhaust to atmosphere of the energizing poppet coil port on a de-energizing command of the valve.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 324

- Cavity EX 8 is to exhaust cavity PEB2, 86 at the same time as the PEA2, 82 this allows exhaust to atmosphere of the de-energizing poppet coil port on an energizing command of the valve.

The electronic and mechanical components of the valve controller according to the preferred embodiments may further provide for intelligent diagnostics for integrated actuator/valve packages. For instance, operational data from the valve controller may be collected and analyzed to signal maintenance information and/or prevent potentially dangerous process conditions. Environmental learning and diagnostics and fault monitoring may be referred to collectively as developing and implementing a knowledge based valve performance program. For example, a valve controller with integral pressure sensors may be used to profile pressures of a single supply port and a single exhaust port so that diagnostics and fault monitoring can be accomplished with a microprocessor. The diagnostics may comprise developing the following non-limiting and exemplary profiles:

- a "Factory Torque Profile" – this function may record the un-installed valve/actuator torque demand versus position; and
- a "Commissioned and/or Maintenance Torque Profile" – this function may record the installed valve actuator torque demand. It may be used, for example, for comparison to the Factory Torque Profile to determine whether any fouling of the disc or deformation of the seat to has occurred. In addition, during shutdown a "Maintenance Profile" may be obtained for comparison to an initial installed Torque profile and/or the factory torque profile. Moreover, a commission torque profile may also be developed during start-up operations (a start-up profile) that may be used as the reference profile for use by the continuous diagnostics. Initially, such comparisons would require the skill and knowledge of the commissioning and maintenance engineers. However, such comparisons may also be analyzed by an integrated actuator controller according to the preferred embodiments.

The fault monitoring may comprise the following non-limiting exemplary functions:

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 325

- "Insufficient Line Pressure to Guarantee Correct Operation" – the purpose of this function may be to warn that air supply pressure may not be sufficient to guarantee either opening or closing of the valve;
- "Supply Pressure Failure" – the purpose of this function may be to raise an alarm if line pressure falls below the maximum average differential requirements or is zero;
- "Valve Shaft Bent" – the purpose of this function may be to detect if the shaft is bent (for example, this may be achieved by detecting a phase shift of the torque profile);
- "Valve Not Achieving Full Stroke" – the purpose of this function may be to evaluate the span of movement of the valve and issue a warning if pre-defined limits are exceeded;
- "Backlash Detection" – the purpose of this function may be to detect and identify dynamic loading on the valve and provide an opportunity to prevent premature valve/actuator failure (the torque/speed profile and the transients produced by conditions of dynamic loading may be used to detect the presence of backlash, which may be caused by a worn actuator, slack mountings, ill fitting of shaft to valve or other correctable features of the valve actuator system;
- "Torque Demand of Valve Approaching Actuator limit" – the purpose of this function may be to raise a warning or alarm if differential pressure reaches 90% of the line pressure at any time during cycle (a bypass time, however, may be included to inhibit or suppress the warning or alarm, immediately after control signal is received;
- "Valve Seating/ Break-Out Torque Monitoring" – the purpose of this function is to identify the torque required to seat and unseat the valve and then give an indication of seat wear, liner failure and/or other mechanical conditions that may require maintenance or immediate attention (values may be compared to acceptable limits for particular valve types and warnings issued under triggering conditions);
- "Torque Limit Exceeded" – the purpose of this function may be to prevent the torque on the valve stem from exceeding a pre-set limit

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 326

that may be programmable and which may be set as a function of a published limit (an alarm may be set if appropriate);

- "Close on Torque" -- the purpose of this function may be to ensure that actuators would have sufficient torque to unseat the valve, remove any dependence on spring rate vs. air supply pressure to achieve a closing torque, and may relate to the use of a dual coil spring center of spool to limit torque output;
- "Shaft Broken" – the purpose of this function may be to determine whether the valve shaft is broken or the valve actuator is not attached to the valve, each of these conditions may have a torque profile with a torque level lower than the historical demand;
- "Valve Exercise" – the purpose of this function may be to exercise and monitor valves that remain in one position, such as the closed or open position, for extended periods;
- "Valve Packing Torque" – the purpose of this function may be to extract valve packing hysteresis between the open and closed cycle for applications such as BFV applications with sufficient dynamic torques;
- "Line Filter and Silencers Conditions" – the purpose of this function may be to identify and signal whether air supply or air exhaust is restricted by measuring and evaluating time constants of charging and discharging of actuator cylinder pressures;
- "Solenoid Spool Sticking" – this function may be used to identify and signal whether the solenoid valve is sticking by measuring and evaluating the time from solenoid control signal to pressure response.

Safety integration levels may be used to define the goals and identify unacceptable levels of operational risk. The techniques and methods for identifying and quantifying safety integrity levels, calculating average probability of failure on demand, and failure and test strategies to reduce the overall failure rate are known from the related art. Thus, the electronic components of the valve controller according to the preferred embodiments may combine real time monitoring data with risk assessment models and safety algorithms identified in a logic solver either remotely or through the use of an on-

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 327

board microprocessor to reduce the average probability of potentially dangerous failures of process valves and ancillary equipment and systems.

To implement such a diagnostic program, a data-sampling rate can be used to develop an accurate representation of all the valve failure trends of interest. For example, Figure 15 shows a graph with 200 samples representing a valve movement, which may detect many if not all valve failure trends. The hardware and software of the valve controller according to the preferred embodiments may be configured to handle 4000 samples to further ensure that valve failure trends of interest are captured by the diagnostic program.

Hardware requirements may be determined as follows. If 100 samples per second were collected and each sample consists of reading the analog value of the valve position, and 5 analog pressure readings and each analog value requires 2 bytes then approximately 100 Samples/Second X 6 Analog Values X 2 bytes/Analog Value or 1200 bytes/Second would be required. In addition, if 4000 bytes for one Sequence of Samples were collected, this may provide about 3.3 seconds worth of data for one Sequence of Samples. A slower moving valve may require more time than this to complete it's movement, so a sampling rate of 50 Samples/Second, 25 Samples/Second, or 12.5 Samples/Second may be used to give times of 6.3 seconds, 12.6 seconds or 25.2 seconds. Moreover, there may be a need to store the Initial Sequence of Samples (captured at installation) for the valve opening and for the valve closing. A number of recent Sequence of Samples for valve opening and for valve closing may also need to be stored. Thus, the Initial and most recent Sequence of Samples may be stored in Non-Volatile memory, which may require about 4 times 4000 or 16000 bytes of Non-Volatile memory. To achieve such a non-volatile memory storage, the EEPROM for non-volatile storage may be increased to a 32K x 8 EEPROM.

In addition, some Network Cards may have less than 1K of RAM so transferring all this data over to the Network Card may have to be done in fragmented messages (small pieces such as 6-8 bytes at a time), where each piece may be individually identified, for example, by a 2 byte fragment address. A similar technique may further be used to transfer this data over the network, as each network protocol also has a limit to the amount of data that can be sent in one message. Thus, for example, in the DeviceNet network card a typical message consists of a CAN Header of 19 bit, followed

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 328

by, a Data Field of up to 64 bits (8 byte), followed by a CAN Trailer of 25 bits. There is a minimum Interframe Space time of 3 bits. This would be 19 + 64 + 25 + 3 or 111 bits for one fragment (six bytes) of the Sequence of Samples. At a rate of 125 kbps this would take 888 uSec. To send the entire 4000 byte Sequence of Samples would require 667 DeviceNet messages. If this were the only device on the network and it could continually broadcast these messages this could take 667 X 888 uSec or 0.592 seconds for the 4000 bytes. Because there are also messages to the device, not just from the device, and because the device would likely need to send status information, not just Sample data, this time may increase significantly and could be doubled. If there are 64 devices on a network and each were sending data this time could be 64 X 2 X 0.592 or 75.8 seconds. As this amount of time may be unacceptable in some applications, other steps may be added to the process to further reduce this time. For example, one may lower the number of samples taken in each Sequence of Samples, compress the data, and/or process some of the data locally, on the motherboard. For these reasons, the valve controller according to the preferred embodiments may be configured with hardware and software robust enough to allow for all three cases.

Wireless technology may be used in combination with a valve controller having the specific valve operative arrangements and knowledge based valve performance discussed above. For example, each of the features for protection with respect to the valve operative arrangements and knowledge based valve performance may be individually protected for use with a short-range wireless protocol, and a communication method via the Internet. Combining the knowledge based valve performance methods with remote communications via the Internet may provide various opportunities to protect new methods of maintenance of valves at a location remote from the location of a maintenance staff. For example, a method of maintaining the operative performance of two valves may be performed. The method includes, for example, evaluating the operative conditions of two valves with a single valve controller; communicating the operative conditions of the two valves to a remote location via an Internet communication link; and changing operative commands of the valve controller via an Internet communication link.

Systems that utilize features on the valve controller may be protected. For example, a system of piping including a first pipe, a second pipe proximate the first pipe,

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 329

a valve disposed between the first pipe and the second pipe, a valve actuator that operates the valve, and a valve controller that operates the valve actuator, the valve controller including a housing having a single supply path that feeds two separate pilot paths, the two separate pilot paths having a common exhaust path may be protected by the valve controller. The operative performance of the system may likewise be protected. Further details of the system may be added to specify the various uses of the valve controller. For example, piping to the controller could be defined and protection of written materials specifying the valve controller and its use may also be protected on a system wide basis.

Based on the foregoing, valve controller 10 may include a manifold assembly 20 including a manifold with integral coils and spools. The manifold assembly may further include a manifold having a single supply path, two pilot paths, and single exhaust path. The manifold may be a monolithic member or a two-piece member. For example, a two-piece manifold may include a base and a cover. The cover can define paths within the base. Thus, the manifold assembly may use a cover to define pneumatic operative paths of the valve controller. Moreover, the valve controller may have a manifold assembly that uses the same fasteners to secure the cover to the base of a housing. The manifold may also include one or more sensors. The sensors may monitor airflow through the manifold and signal other mechanical or electronic components. The valve controller may have a housing with a single pneumatic supply path, two separate pilot paths, a single exhaust path, and an individual pressure sensor for each path. In one embodiment, two of the sensors may be differential pressure sensors. The valve controller may also have valve position indicator or beacon (position indicator) located between separate chambers for mechanical and electronic components. The size of the beacon (position indicator) being selected to allow for viewing from a remote location. The beacon (position indicator) can operate via a non-contact position sensor. Moreover, the valve controller may provide for different operative arrangements. The valve controller may have a single pneumatic supply port that allows for two operational control signals. The two operational control signals may provide a first command signal and a second command signal to a single valve. The first command signal may be a discrete command signal. The second command signal may be a modulating command signal. The valve controller may be integrated with an actuator, the valve controller having a single pneumatic supply port that allows for two operational control signals. The valve

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 330

controller may be used to operate a valve with two different command signals from a single pneumatic supply port. The valve controller may be used in a method of operating an integrated actuator with two different command signals from a single pneumatic supply port. The valve controller may have a single pneumatic supply port that allows for two operational control signals. The two operation control signals may provide a discrete command signal to a first valve and a separate discrete command signal to a second valve. The valve controller may be integrated with an actuator, the valve controller having a single pneumatic supply port that allows for two separate and identical operational control signals. The valve controller may be configured to provide a method of controlling fail-safe operation of two valves with a single pneumatic supply port

While the present invention has been disclosed with reference to certain preferred embodiments, numerous modifications, alterations, and changes to the described embodiments are possible without departing from the sphere and scope of the present invention, as defined in the appended claims. Accordingly, it is intended that the present invention not be limited to the described embodiments, but that it have the full scope defined by the language of the following claims, and equivalents thereof.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 331

What is claimed is:

1. A valve control apparatus comprising:

an enclosure defining a first chamber and a second chamber, the first and second chambers being spaced from each other along a longitudinal axis;

an indicator proximate the first and second chambers, the indicator having a visual symbol that identifies an operational state of at least one valve;

an operating media distribution system disposed in the first chamber, the operating media distribution system including:

an operating media supply passage;

an operating media exhaust passage;

at least three operating media transmission passages; and

a plurality of valves in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least three operating media transmission passages;

an electronic control unit disposed in the second chamber, the electronic control unit operates at least one of the plurality of valves to control operating media flow in the operating media distribution system; and

a plurality of connection ports that communicate with the operating media supply passage, the operating media exhaust passage, and the at least three operating media transmission passages.

2. The apparatus of claim 1, further comprising:

at least one sensor disposed in the enclosure, the sensor evaluates the operating media distribution system and provides information to the electronic control unit about at least one operating condition in at least one of the passages.

3. A piping system comprising:

a first pipe;

a first process valve connected to the first pipe;

a first actuator operating the first process valve; and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 332

a device controlling the first actuator, the device including:

an enclosure defining a first chamber and a second chamber, the first and second chambers being spaced from each other along a longitudinal axis;

an indicator proximate the first and second chambers, the indicator having a visual symbol that identifies an operational state of at least one valve;

an operating media distribution system disposed in the first chamber, the operating media distribution system including:

an operating media supply passage;

an operating media exhaust passage;

at least three operating media transmission passages; and

a plurality of valves in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least three operating media transmission passages; and

an electronic control unit disposed in the second chamber, the electronic control unit operates at least one of the plurality of valves to control operating media flow in the operating media distribution system.

4. A valve control apparatus comprising:

an enclosure;

an operating media distribution system disposed in the enclosure, the operating media distribution system including:

an operating media supply passage;

an operating media exhaust passage;

at least two operating media transmission passages; and

a valve in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least two operating media transmission passages;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 333

an electronic control unit disposed in the enclosure, the electronic control unit operates the valve to control operating media flow in the operating media distribution system;

at least one sensor disposed in the enclosure, the sensor evaluates the operating media distribution system and provides information to the electronic control unit about at least one operating condition in at least one of the passages; and

a plurality of connection ports that communicate with the operating media supply passage, the operating media exhaust passage, and the at least two operating media transmission passages.

5. The apparatus of claim 4, wherein the enclosure comprises first and second chambers, and the first chamber is spaced along a longitudinal axis from the second chamber.

6. The apparatus of claim 5, further comprising:

an indicator proximate the first and second chambers, the indicator having a visual symbol that identifies an operational state of at least one valve.

7. A piping system comprising:

a first pipe;

a first process valve connected to the first pipe;

a first actuator operating the first process valve; and

a device controlling the first actuator, the device including:

an enclosure;

an operating media distribution system disposed in the enclosure, the operating media distribution system including:

an operating media supply passage;

an operating media exhaust passage;

at least two operating media transmission passages; and

a valve in fluid communication with the operating media supply passage, the operating media exhaust

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 334

passage, and the at least two operating media transmission passages;

an electronic control unit disposed in the enclosure, the electronic control unit operates the valve to control operating media flow in the operating media distribution system; and

at least one sensor disposed in the enclosure, the sensor evaluates the operating media distribution system and provides information to the electronic control unit about at least one operating condition in at least one of the passages.

8. A valve control apparatus for at least one process valve having a maximum exterior package dimension, the apparatus comprising:

an enclosure disposed entirely between first and second parallel planes, the first and second parallel planes being spaced apart a distance less than or equal to the exterior package dimension;

an indicator proximate the enclosure, the indicator includes a visual symbol that identifies an operational state of the at least one process valve, and the visual symbol is visible from above the first plane and from below the second plane;

an operating media distribution system disposed in the enclosure;

an electronic control unit disposed in the enclosure;

at least one sensor disposed in the enclosure, the at least one sensor evaluates the operating media distribution system and provides the electronic control unit information about at least one operating condition in the operating media distribution system; and

a plurality of connection ports that communicate with the operating media distribution system.

9. The apparatus of claim 8, wherein the distance between the first and second parallel planes is less than or equal to three inches.

10. The apparatus of claim 8, wherein the enclosure comprises first and second chambers, and the first chamber is spaced along a longitudinal axis from the second chamber.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 335

11. The apparatus of claim 8, wherein the operating media distribution system comprises:

an operating media supply passage;

an operating media exhaust passage;

at least two operating media transmission passages; and

a valve in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least two operating media transmission passages.

12. The apparatus of claim 8, wherein the electronic control unit controls media flow in the operating media distribution system to operate the at least one process valve.

13. An apparatus for distributing an operating media, the apparatus comprising:

a manifold defining:

an operating media supply passage;

an operating media exhaust passage;

a first operating media transmission passage;

a second operating media transmission passage;

a third operating media transmission passage; and

a fourth operating media transmission passage;

means for directing the operating media from the operating media supply passage to the first and third operating media transmission passages, and

means for directing the operating media to the operating media exhaust passage from the second and fourth operating media transmission passages.

14. The apparatus of claim 13, further comprising:

means for directing the operating media from the operating media supply to the second and fourth operating media transmission passages; and

means for directing the operating media to the operating media exhaust passage from the first and third operating media transmission passages.

15. The apparatus of claim 14, further comprising:

an electronic control unit;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 336

means for evaluating operating media pressure in each of the passages and for providing information to the electronic control unit about the operating media pressure in each of the passages.

16. The apparatus of claim 14, further comprising:

means for evaluating valve position and for providing valve position data to the control unit.

17. The apparatus of claim 16, further comprising:

means for monitoring valve performance and for developing at least one diagnostic performance attribute profile.

18. The apparatus of claim 17, wherein the at least one diagnostic performance attribute profile is selected from the group consisting essentially of a Commissioned Torque Profile and a Maintenance Torque Profile.

19. The apparatus of claim 17, further comprising:

means for fault monitoring valve performance by comparing the at least one diagnostic performance attribute profile with stored valve data.

20. The apparatus of claim 19, further comprising,

means for calculating an average probability of valve failure; and

means for predicting valve failure by comparing the average probability of valve failure with stored valve data.

21. A piping system comprising:

a first pipe;

a first process valve proximate the first pipe;

a first actuator operating the first process valve; and

an operating media distribution system controlling the first actuator, the operating media distribution system includes a manifold defining:

an operating media supply passage introducing operating media into the operating media distribution system from outside the housing;

an operating media exhaust passage discharging operating media from the operating media distribution system to outside the housing, and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 337

at least four operating media transmission passages in fluid communication with the operating media supply and exhaust passages, and a minimum of two of the at least four operating media transmission passages are in fluid communication with the first actuator.

22. The system of claim 21, wherein a minimum of two of the four operating media transmission passages are in fluid communication with a second actuator.

23. The system of claim 22, further comprising:
a second process valve being operated by the second actuator.

24. The system of claim 23, further comprising:
a second pipe proximate the second process valve.

25. The system of claim 21, wherein the operating media distribution system includes a plurality of valves in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least four operating media transmission passages.

26. The system of claim 25, further comprising:
an electronic control unit operating the plurality of valves to control operating media flow in the operating media distribution system;
at least one sensor evaluating the operating media distribution system and providing information to the electronic control unit about at least one operating condition in at least one of the passages; and
a plurality of connection ports that communicate with the operating media supply passage, the operating media exhaust passage, and the at least four operating media transmission passages.

27. The system of claim 21, wherein the manifold is disposed entirely between first and second parallel planes, the first and second parallel planes being spaced apart a distance less than or equal to three inches.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 338

28. An apparatus for distributing an operating media, the apparatus comprising:

an enclosure that includes upper and lower surfaces respectively defining first and second parallel planes, the enclosure is located entirely within a distance between the first and second planes;

an indicator proximate the enclosure, the indicator includes a visual symbol that identifies an operational state of the at least one process valve, and the visual symbol is visible from above the first plane and from below the second plane;

an operating media distribution system disposed in the enclosure; and

a plurality of connection ports that communicate with the operating media distribution system.

29. The apparatus of claim 28, wherein the distance between the first and second planes is less than or equal to three inches.

30. The apparatus of claim 28, wherein the enclosure comprises first and second chambers, and the first chamber is spaced along a longitudinal axis from the second chamber.

31. The apparatus of claim 28, wherein the operating media distribution system comprises:

an operating media supply passage;

an operating media exhaust passage;

at least two operating media transmission passages; and

a valve in fluid communication with the operating media supply passage, the operating media exhaust passage, and the at least two operating media transmission passages.

32. The apparatus of claim 31, further comprising:

an electronic control unit operating the valve to control operating media flow in the operating media distribution system;

at least one sensor evaluating the operating media distribution system and providing information to the electronic control unit about at least one operating condition in at least one of the passages.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 339

33. A method of distributing operating media, the method comprising:

introducing an operating media supply to a manifold;

allotting within the manifold the operating media supply to at least four operating media transmission passages;

transporting to a first actuator operating media from a first minimum of two of the at least four operating media transmission passages; and

collecting in an operating media exhaust passage exiting the manifold operating medium from a minimum of two of the at least four transmission passages.

34. The method of claim 33, further comprising:

transporting to a second actuator operating media from a second minimum of two of the at least four operating media transmission passages.

35. The method of claim 33, wherein the introducing comprises connecting the operating media supply to an operating media supply passage of the manifold.

36. The method of claim 35, wherein the allotting comprises connecting the operating media supply passage to at least one of a first operating media transmission passage, a second operating media transmission passage, a third operating media transmission passage, and a fourth operating media transmission passage.

37. The method of claim 36, wherein the wherein the allotting comprises connecting the operating media supply passage to the first and third operating media transmission passages.

38. The method of claim 33, wherein the operating media comprises air.

39. The method of claim 33, wherein the manifold is disposed entirely between first and second parallel planes, the first and second parallel planes being spaced apart a distance less than or equal to three inches.

40. A method of distributing operating media comprising:

connecting an operating media supply to a manifold, the manifold defining an operating media supply passage, an operating media exhaust passage, a first operating media transmission passage, a second operating media transmission passage, a third

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 340

operating media transmission passage, and a fourth operating media transmission passage;

directing operating media from the operating media supply to the first and third operating media outlet passages; and

directing operating media from the second and fourth operating media outlet passages to the operating media exhaust passage.

41. The method of claim 40, wherein the operating media comprises air.

42. A manifold apparatus for distributing operating media, the apparatus comprising:

a first member defining:

an operating media supply cavity;

an operating media exhaust cavity;

at least four operating media transmission cavities in communication with the operating media supply cavity and the operating media exhaust cavity; and

a surface communicating a flow of operating media flow between a minimum of two of the at least four operating media transmission cavities.

43. The apparatus of claim 42, further comprising:

a second member defining at least one surface that cooperates with the first member to contain and transport operating media between a minimum of two of the at least four operating media transmission cavities.

44. A manifold apparatus for distributing operating media, that apparatus comprising:

a first member having a plurality of cavities for transporting operating media, the plurality of cavities including an operating media supply cavity, and

a second member defining a surface that cooperates with the first member to contain and transport operating media between at least two cavities.

45. The apparatus of any of claims 43 and 44, wherein the at least one surface comprises an interior surface that defines a recess, the recess cooperates with the first member to form a chamber in fluid communication with at least two cavities.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 341

46. The apparatus of claim 45, wherein the at least one surface defines a plurality of recesses that cooperate with the first member to form a plurality of chambers.

47. The apparatus of any of claims 42 and 46, wherein the second member comprises a manifold cover.

48. The apparatus of any of claims 42 and 44, further comprising a plurality of external ports that connect to the operating media supply cavity, the operating media exhaust cavity, and the first, second, third and fourth operating media transmission cavities.

49. The apparatus of claims 48, further comprising:

a first operating media distribution valve in fluid communication with the operating media supply cavity, the first and second operating media transmission cavities, and the operating media exhaust cavity, the first operating media distribution valve including:

a first configuration connecting the operating media supply cavity with the first operating media transmission cavity and connecting the second operating media transmission cavity with the operating media exhaust cavity; and

a second configuration connecting the operating media supply cavity with the second operating media transmission cavity and connecting the first operating media transmission cavity with the operating media exhaust cavity; and

a second operating media distribution valve in fluid communication with the operating media supply cavity, the third and fourth operating media transmission cavities, and the operating media exhaust cavity, the second operating media distribution valve including:

a third configuration connecting the operating media supply cavity with the third operating media transmission cavity and connecting the fourth operating media transmission cavity with the operating media exhaust cavity; and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 342

a fourth configuration connecting the operating media supply cavity with the fourth operating media transmission cavity and connecting the third operating media transmission cavity with the operating media exhaust cavity

50. The apparatus of claim 49, further comprising:

a first operational mode including the first configuration of the first operating media distribution valve and the third configuration of the second operating media distribution valve.

51. The apparatus of claim 49, further comprising:

a second operational mode including the second configuration of the first operating media distribution valve and the fourth configuration of the second operating media distribution valve.

52. The apparatus of claim 49, further comprising:

a third operational mode that includes occluding one of the plurality of connection ports corresponding to one of the first, second, third and fourth operating media transmission passages.

53. The apparatus of claim 49, further comprising:

an enclosure defining a first chamber, the first and second members being disposed in the first chamber, the enclosure is disposed entirely between first and second parallel planes, and the first and second parallel planes being spaced apart a distance less than or equal to three inches.

54. The apparatus of claim 48, wherein the plurality of external ports are disposed in a third member proximate the first member.

55. A system controlling two process valves, the system comprising:

a manifold defining a member that defines an operating media supply cavity, an operating media exhaust cavity, and at least four operating media transmission cavities in communication with the operating media supply cavity and the operating media exhaust cavity;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 343

a surface communicating a flow of operating media between a minimum of two of the at least four operating media transmission cavities;

a first process valve actuator including:

a first operating media port connected to the first operating media transmission cavity, and

a second operating media port connected to the second operating media transmission cavity; and

a second process valve actuator including:

a third operating media port connected to the third operating media transmission cavity, and

a fourth operating media port connected to the fourth operating media transmission cavity.

56. A system controlling two process valves, the system comprising:

a manifold defining first and second members, the first member having a plurality of cavities for transporting operating media, the plurality of cavities including an operating media supply cavity, and the second member defining a surface that cooperates with the first member to contain and transport operating media between at least two cavities;

a first operating media distribution valve in fluid communication with the operating media supply cavity, the first and second operating media transmission cavities, and the operating media exhaust cavity, the first operating media distribution valve including:

a first configuration connecting the operating media supply cavity with the first operating media transmission cavity and connecting the second operating media transmission cavity with the operating media exhaust cavity; and

a second configuration connecting the operating media supply cavity with the second operating media transmission cavity and connecting the first operating media transmission cavity with the operating media exhaust cavity;

a second operating media distribution valve in fluid communication with the operating media supply cavity, the third and fourth operating media transmission

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 344

cavities, and the operating media exhaust cavity, the second operating media distribution valve including:

a third configuration connecting the operating media supply cavity with the third operating media transmission cavity and connecting the fourth operating media transmission cavity with the operating media exhaust cavity; and

a fourth configuration connecting the operating media supply cavity with the fourth operating media transmission cavity and connecting the third operating media transmission cavity with the operating media exhaust cavity;

a first process valve actuator including:

a first operating media port connected to the first operating media transmission cavity, and

a second operating media port connected to the second operating media transmission cavity; and

a second process valve actuator including:

a third operating media port connected to the third operating media transmission cavity, and

a fourth operating media port connected to the fourth operating media transmission cavity.

57. The system of any of claims 55 and 56, further comprising:

an electronic control unit controlling the first process valve actuator by operating the first operating media distribution valve and controlling the second process valve actuator by operating the second operating media distribution valve.

58. The system of claim 57, wherein the electronic control unit operates the first and second operating media distribution valves to select the first operational mode.

59. The system of claim 57, wherein the electronic control unit operates the first and second operating media distribution valves to select the second operational mode.

60. A piping system comprising:

a first pipe;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 345

a first process valve connected to the first pipe;

a first actuator operating the first process valve; and

a device controlling the first actuator, the device including:

a manifold defining a member that defines an operating media supply cavity, an operating media exhaust cavity, and at least four operating media transmission cavities in communication with the operating media supply cavity and the operating media exhaust cavity;

a surface communicating a flow of operating media flow between a minimum of two of the at least four operating media transmission cavities;

a first process valve actuator including:

a first operating media port connected to the first operating media transmission cavity, and

a second operating media port connected to the second operating media transmission cavity; and

a second process valve actuator including:

a third operating media port connected to the third operating media transmission cavity, and

a fourth operating media port connected to the fourth operating media transmission cavity.

61. A piping system comprising:

a first pipe;

a first process valve connected to the first pipe;

a first actuator operating the first process valve; and

a device for controlling the first actuator, the device including:

a manifold defining first and second members, the first member having a plurality of cavities for transporting operating media, the plurality of cavities including an operating media supply cavity, and the second member defining a surface that cooperates with the first member to contain and transport operating media between at least two cavities;

a first operating media distribution valve in fluid communication with the operating media supply cavity, the first and second operating

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 346

media transmission cavities, and the operating media exhaust cavity, the first operating media distribution valve including:

a first configuration connecting the operating media supply cavity with the first operating media transmission cavity and connecting the second operating media transmission cavity with the operating media exhaust cavity; and

a second configuration connecting the operating media supply cavity with the second operating media transmission cavity and connecting the first operating media transmission cavity with the operating media exhaust cavity;

a second operating media distribution valve in fluid communication with the operating media supply cavity, the third and fourth operating media transmission cavities, and the operating media exhaust cavity, the second operating media distribution valve including:

a third configuration connecting the operating media supply cavity with the third operating media transmission cavity and connecting the fourth operating media transmission cavity with the operating media exhaust cavity; and

a fourth configuration connecting the operating media supply cavity with the fourth operating media transmission cavity and connecting the third operating media transmission cavity with the operating media exhaust cavity;

a first process valve actuator including:

a first operating media port connected to the first operating media transmission cavity, and

a second operating media port connected to the second operating media transmission cavity; and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 347

a second process valve actuator including:

a third operating media port connected to the third operating media transmission cavity, and

a fourth operating media port connected to the fourth operating media transmission cavity.

62. A method of method of maintaining operative performance of first and second valves, the method comprising:

evaluating with a single valve controller operative conditions of the first and second valves;

communicating the operative conditions of the first and second valves to a remote location via an internet communication link; and

changing operative commands of the single valve controller via the internet communication link.

63. The method of claim 62, further comprising:

operating the first and second valves with the single valve controller, the single valve controller including an operating media distribution system including a third valve in communication with an operating media supply passage, an operating media exhaust passage, and at least four operating media transmission passages.

64. The valve controller of claim 63, wherein the operating comprises an electronic control unit proximate the operating media distribution system and operating the third valve to control operating media flow in the operating media distribution system.

65. The valve controller of claim 64, further comprising:

evaluating the air distribution system with a plurality of sensors and providing the electronic control unit information about at least one operating condition in each of the passages.

66. The apparatus of any of claims 4, 8 and 28, wherein the enclosure comprises at least one cover that provides access to the operating media distribution system.

67. The apparatus of claim 66, wherein the at least one cover is secured to the enclosure by at least one fastening element.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 348

68. The apparatus of claim 67, wherein the enclosure has at least one fastening element attachment site, and the at least one fastening element cooperates with the at least one fastening element attachment site to secure the at least one cover to the enclosure.

69. The apparatus of any of claims 1, 5, 10 and 30, wherein the enclosure comprises at least one cover providing access to the first and second chambers.

70. The apparatus of claim 69, wherein the at least one cover is secured to the enclosure by at least one fastening element.

71. The apparatus of claim 70, wherein the enclosure has at least one fastening element attachment site, and the at least one fastening element cooperates with the at least one fastening element attachment site to secure the at least one cover to the enclosure.

72. The apparatus of claim 69, wherein the at least one cover comprises first and second covers, the first cover provides access to only the first chamber and the second cover provides access to only the second chamber.

73. The apparatus of any of claims 1 and 6, wherein the enclosure is disposed entirely between first and second parallel planes, the first and second parallel planes being spaced apart a distance less than or equal to three inches.

74. The apparatus of claim 73, wherein the visual symbol is visible from above the first plane and is visible from below the second plane.

75. The apparatus of any of claims 1, 5, 10 and 30, wherein the enclosure comprises:

a first wall including first and second segments that define portions of the first chamber, a projection along the longitudinal axis of the first segment has a first length transverse to the longitudinal axis, and a projection along the longitudinal axis of the second segment has a second length transverse to the longitudinal axis, the second length being greater than the first length; and

a second wall including third and fourth segments that define portions of the second chamber, a projection along the longitudinal axis of the third segment has a third

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 349

length transverse to the longitudinal axis, and a projection along the longitudinal axis of the fourth segment has a fourth length transverse to the longitudinal axis, the fourth length being greater than the third length.

76. The apparatus of claim 75, wherein the first segment is proximate to the second wall, the second segment is distal to the second wall, the third segment is proximate to the first wall, the fourth segment is distal to the first wall, and the second segment of the first wall and the fourth segment of the second wall are parallel.

77. The apparatus of any of claims 1, 6, 8 and 28, wherein the indicator comprises:

a first member defining an interior space; and

a second member disposed within the interior space, the second member including the visual symbol that identifies the operational state of the at least one valve.

78. The apparatus of claim 77, wherein the second member oscillates with respect to the first member.

79. The apparatus of any of claims 1, 4, 11, 26, 31 and 44, wherein the operating media transmission passages comprise first, second, third and fourth operating media transmission passages and the operating media distribution system includes a manifold assembly comprising:

a first operating media distribution valve in fluid communication with the operating media supply passage, the first and second operating media transmission passages, and the operating media exhaust passage, the first operating media distribution valve including:

a first configuration connecting the operating media supply passage with the first operating media transmission passage and connecting the second operating media transmission passage with the operating media exhaust passage; and

a second configuration connecting the operating media supply passage with the second operating media transmission passage and connecting the first operating media transmission passage with the operating media exhaust passage; and

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 350

a second operating media distribution valve in fluid communication with the operating media supply passage, the third and fourth operating media transmission passages, and the operating media exhaust passage, the second operating media distribution valve including:

a third configuration connecting the operating media supply passage with the third operating media transmission passage and connecting the fourth operating media transmission passage with the operating media exhaust passage; and

a fourth configuration connecting the operating media supply passage with the fourth operating media transmission passage and connecting the third operating media transmission passage with the operating media exhaust passage.

80. The apparatus of claim 79, wherein the manifold assembly consists of a single operating media exhaust passage.

81. The apparatus of claim 79, wherein the manifold assembly comprises a monolithic manifold defining:

a first outer surface portion including first, second, third and fourth openings, the first opening being in fluid communication with the operating media supply passage, the second opening being in fluid communication with the operating media exhaust passage, the third opening being in fluid communication with the first operating media transmission passage, and the fourth opening being in fluid communication with the second operating media transmission passage; and

a second outer surface portion including fifth, sixth, seventh and eighth openings, the fifth opening being in fluid communication with the operating media supply passage, the sixth opening being in fluid communication with the operating media exhaust passage, the seventh opening being in fluid communication with the third operating media transmission passage, and the eighth opening being in fluid communication with the fourth operating media transmission passage.

82. The apparatus of claim 79, wherein the manifold assembly comprises first and second manifold parts.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 351

83. The apparatus of claim 82, wherein the manifold assembly comprises at least one fastener commonly securing together the first manifold part, the second manifold part, and the enclosure.

84. The apparatus of claim 79, wherein the manifold assembly comprises a cover defining at least one operating media path.

85. The apparatus of claim 79, further comprising:

a first operational mode including the first configuration of the first operating media distribution valve and the third configuration of the second operating media distribution valve.

86. The apparatus of claim 85, wherein the electronic control unit operates the first and second operating media distribution valves to select the first operational mode.

87. The apparatus of claim 85, further comprising:

a second operational mode including the second configuration of the first operating media distribution valve and the fourth configuration of the second operating media distribution valve.

88. The apparatus of claim 87, wherein the electronic control unit operates the first and second operating media distribution valves to select the second operational mode.

89. The apparatus of claim 87, further comprising:

a third operational mode that includes occluding one of the plurality of connection ports corresponding to one of the first, second, third and fourth operating media transmission passages.

90. The apparatus of claim 79, wherein the first and second operating media distribution valves comprise spool valves.

91. The method of any of claims 37 and 40, further comprising:

directing operating media from the operating media supply passage to the second and fourth operating media transmission passages: and

directing operating media from the first and third operating media transmission passages to the operating media exhaust passage.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 352

92. The apparatus of any of claims 2, 4, 11, 26 and 32, wherein the at least one sensor comprises a plurality of sensors that evaluate at least one operating condition in at least one of the passages.

93. The apparatus of claim 92, wherein the plurality of sensors evaluate the operating media distribution system and provide information to the electronic control unit about at least one operating condition in each of the passages.

94. The apparatus of claim 92, wherein the plurality of sensors evaluate operating media pressure.

95. The apparatus of claim 92, wherein at least one of the plurality of sensors comprises a differential pressure sensor.

96. The apparatus of claim 92, wherein the indicator comprises a position sensor that evaluates valve position and provides valve position data to the electronic control unit.

97. The apparatus of claim 92, wherein the electronic control unit monitors valve performance and develops at least one diagnostic profile.

98. The apparatus of claim 97, wherein the at least one diagnostic profile is selected from the group consisting of Insufficient Line Pressure to Guarantee Correct Operation, Supply Pressure Failure, and Valve Shaft Bent.

99. The apparatus of claim 97, wherein the at least one diagnostic profile is selected from the group consisting of Valve Not Achieving Full Stroke, Backlash Detection, and Torque Demand of Valve Approaching Actuator Limit.

100. The apparatus of claim 97, wherein the at least one diagnostic profile is selected from the group consisting of Valve Seating/Break-out Torque Monitoring, Torque Limit Exceeded, and Close-on Torque.

101. The apparatus of claim 97, wherein the at least one diagnostic profile is selected from the group consisting of Shaft Broken, Valve Exercise, Valve Packing Torque, Line Filter and Silencer Conditions, and Solenoid Spool Sticking.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 353

102. The method of any of claims 36 and 40, further comprising:
sensing operating media pressure in each of the passages; and
evaluating in a control unit information about the operating media pressure in each of the passages.

103. The method of claim 102, further comprising:
sensing a valve operative position; and
evaluating in the electronic control unit information about the valve operative position.

104. The method of claim 103, further comprising:
developing a valve diagnostic performance attribute profile.

105. The method of claim 104, further comprising:
developing a Commissioned Torque Profile.

106. The method of claim 104, further comprising:
developing a Maintenance Torque Profile.

107. The method of claim 104, further comprising:
monitoring valve performance fault by comparing the valve diagnostic performance attribute profile with stored valve data.

108. The method of claim 107, further comprising:
indicating operating media pressure is insufficient to guarantee opening of the valve.

109. The method of claim 107, further comprising:
indicating Insufficient Line Pressure to Guarantee Correct Operation.

110. The method of claim 107, further comprising:
indicating Supply Pressure Failure.

111. The method of claim 107, further comprising:
indicating Valve Not Achieving Full Stroke.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 354

112. The method of claim 107, further comprising:
indicating Backlash Detection.

113. The method of claim 107, further comprising:
indicating Torque Demand of Valve Approaching Actuator Limit.

114. The method of claim 107, further comprising:
monitoring Valve Seating/Break-out Torque.

115. The method of claim 107, further comprising:
indicating Torque Limit Exceeded.

116. The method of claim 107, further comprising:
indicating Close-on Torque.

117. The method of claim 107, further comprising:
indicating Shaft Broken.

118. The method of claim 107, further comprising:
indicating Line Filter and Silencer Conditions.

119. The method of claim 107, further comprising:
indicating Solenoid Spool Sticking.

120. The method of claim 107, further comprising:
indicating Valve Exercise.

121. The method of claim 107, further comprising:
indicating Valve Packing Torque.

122. The method of claim 107, further comprising:
calculating average probability of failure on demand; and
predicting valve failure by comparing the calculated average probability of failure with stored valve data.

123. The apparatus of any of claims 1, 4, 8, 26 and 28, wherein the electronic control unit comprises at least one printed circuit board.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 355

124. The apparatus of claim 123, wherein the electronic control unit comprises a microprocessor.

125. The apparatus of any of claims 123 to 124, wherein the electronic control unit comprises a liquid crystal display.

126. The apparatus of any of claims 123 to 125, wherein the electronic control unit comprises an analog input.

127. The apparatus of any of claims 123 to 126, wherein the electronic control unit comprises an analog output.

128. The apparatus of any of claims 123 to 127, wherein the electronic control unit comprises a discrete output.

129. The apparatus of any of claims 123 to 128, wherein the electronic control unit comprises a discrete input.

130. The apparatus of any of claims 123 to 129, wherein the electronic control unit comprises a communications port.

131. The apparatus of any of claims 123 to 130, wherein the electronic control unit comprises a Flash memory.

132. The apparatus of any of claims 123 to 131, wherein the electronic control unit comprises a Data memory.

133. The apparatus of any of claims 123 to 132, wherein the electronic control unit comprises a Non-volatile memory.

134. The apparatus of any of claims 123 to 133, wherein the electronic control unit comprises a Discrete Output driver.

135. The apparatus of any of claims 123 to 134, wherein the electronic control unit comprises an Inter-processor communication circuitry.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 356

136. The apparatus of any of claims 123 to 135, wherein the electronic control unit comprises a power supply.

137. The apparatus of any of claims 123 to 136, wherein the electronic control unit comprises a plug in network card.

138. The apparatus of any of claims 123 to 137, wherein the electronic control unit comprises a radio module interfacing with a peer-to-peer wireless area network.

139. The apparatus of any of claims 1, 4, 8, 21 and 28, wherein the operating media distribution system distributes an operating media comprising air.

140. The apparatus of claim 139, wherein the operating media in the operating media supply passage comprises the air having a pressure of about 40 to 120 pounds per square inch.

141. The apparatus of claim 139, wherein the operating media in the operating media supply passage comprises the air having a pressure of about 15 to 45 pounds per square inch.

142. The apparatus of claim 139, wherein the operating media in the operating media supply passage comprises the air having a pressure of less than about 120 pounds per square inch.

143. The apparatus of claim 142, wherein the pressure of the air in the operating media supply passage is less than about 40 pounds per square inch.

144. The apparatus of claim 139, wherein the operating media in the operating media supply passage comprises the air having a temperature of about –40 to 180 degrees Fahrenheit.

145. The apparatus of claim 139, wherein the operating media in the operating media supply passage comprises the air having a flow rate of about 5 standard cubic feet per minute at about 40 pounds per square inch to about 100 standard cubic feet per minute at about 120 pounds per square inch.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 357

146. The system of any of claims 3, 7, 60 and 61, further comprising:
a second process valve; and
a second actuator operating the second process valve;
wherein the device controls the first and second actuators.

147. The system of claim 146, further comprising:
a second pipe connected to the first process valve.

148. An operating media distributor comprising:
a first operating media distribution valve in fluid communication with an operating media supply passage, first and second operating media transmission passages, and an operating media exhaust passage, the first operating media distribution valve including:
a first configuration connecting the operating media supply passage with the first operating media transmission passage and connecting the second operating media transmission passage with the operating media exhaust passage; and
a second configuration connecting the operating media supply passage with the second operating media transmission passage and connecting the first operating media transmission passage with the operating media exhaust passage; and
a second operating media distribution valve in fluid communication with the operating media supply passage, third and fourth operating media transmission passages, and the operating media exhaust passage, the second operating media distribution valve including:
a third configuration connecting the operating media supply passage with the third operating media transmission passage and connecting the fourth operating media transmission passage with the operating media exhaust passage; and
a fourth configuration connecting the operating media supply passage with the fourth operating media transmission passage and connecting the third operating media transmission passage with the operating media exhaust passage.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 358

149. The distributor of claim 148, further comprising:

a first operational mode including the first configuration of the first operating media distribution valve and the third configuration of the second operating media distribution valve.

150. The distributor of claim 149, further comprising:

a second operational mode including the second configuration of the first operating media distribution valve and the fourth configuration of the second operating media distribution valve.


151. The distributor of claim 150, further comprising:

a third operational mode that includes occluding one of the plurality of connection ports corresponding to one of the first, second, third and fourth operating media transmission passages.

152. The subject of any of the preceding claims, wherein the operating media comprises compressed air.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 359

FIG. 1A





32
36
32
34
34
356
346
38
16
20
388
24
376
12
22
22a
POS = 100%
CUR=20.0 mA
10
14
16

FIG. 1B





FIG. 2

FIG. 3A


20
28
50
30
164
42
302
48
34
36
32
158
166
314
312
310
320
70
68
66
64
318
44



34
32
32
34
50
94
92
68
MTR
60
62
MTR
78
54
76
EXH
34
SUPPLY
28
EXH
EXHAUST
30
34
74
52
72
64
MTR
56
58
MTR
66
48
96
88
34
32
32
34

FIG. 3B

FIG. 4B




FIG. 4C




FIG. 4A




FIG. 4E





FIG. 4D






FIG. 5C

FIG. 5B

FIG. 5D

FIG. 5A




FIG. 5E




FIG. 5F

FIG. 6




FIG. 6A



102
102
294a
72
128
84
54
132e
140
86
78
92
96
94

FIG. 6B



102
294a
122
128
84
54
86
140
92
96
94

FIG. 6C



294c
130
294a
128
146
122
132c
86
92
94

FIG. 6D



294b
102
294a
134
122
132

FIG. 6E



52
126
294a
294b
142
124
132b
122
80
82
88
74
72
90

FIG. 6F




294a
102
80
38
42
124
144
132a
52
82
36
88
90

FIG. 6G





158
160
154
156
214
162
50
158
310
312
70
68
66
64
324
158
158
162
156
154
215
160
48

FIG. 6H

FIG. 7A




FIG. 7B




FIG. 7C




FIG. 8




L
42
48
72
12b
50
L2
12
76
366
366
74
366
366
78
312
358
362
360
354
356
64
66
68
70
344
346
352
350
L1
12a
24
22a
14

FIG. 9A






FIG. 9B

FIG. 10A





FIG. 10B






FROM/TO FIG. 11B
CTRL LINES
FLASH MEMORY 416
I/O PORT 2 BDM PORT
CTRL LINES
436
412
BLUETOOTH RADIO MODULE
I/O PORT 1
CTRL LINES
CTRL LINES
FROM/TO FIG. 11C
SERIAL LINES
CTRL LINES
420
EEPROM
MICROPROCESSOR 414
CRYSTAL
438
HANDHELD
RESET
408
RESET SWITCH
LED

FIG. 11A

FIG. 11B


NETWORK I/O PORT
434
NETWORK INTERFACE CARD
NETWORK PHYSICAL MEDIA INTERFACE
430
NETWORK COMMUNICATION INTERFACE CIRCUITRY
7.2V POWER SUPPLY 432
+3V POWER SUPPLY 432
402
DOWN PUSH BUTTON
402
UP PUSH BUTTON
402
SELECT PUSH BUTTON
+7.2V
ANOLOG CIRCUITRY POWER
+3V
DIGITAL CIRCUITRY POWER
LED DISPLAY 2 LINE X 16 CHAR 400
STATIC RAM 418
FROM / TO FIG. 11A




410
CLOSE LS INPUT
OPEN LS INPUT
AUX 1 INPUT
408
SOL 1 OUTPUT
SOL 2 OUTPUT
SOL 1 OUTPUT
SOL 2 OUTPUT
FROM / TO FIG. 11A
CTRL LINES
DIGITAL INPUT / OUTPUT LATCHES
428
426
VOLTAGE AMPLIFIER
POSITION SENSOR INPUT
SUPPLY PRESSURE INPUT
EXHAUST PRESSURE INPUT
ACTUATOR "A" DIFF PRESSURE
ACTUATOR "B" DIFF PRESSURE
AUX INPUT
12 BIT A / D CONVERTER
422
CTRL LINES
12 BIT D / A CONVERTER
424
406
TRANSDUCER OUTPUT
404

FIG. 11C



PROCESS VALVES IN ZERO POSITION
VALVE A DE-ENERGIZED, VALVE B DE-ENERGIZED

FIG. 12A




PROCESS VALVE 2
DB2
DB1
B1
VALVE B
B2
EB2
SB
EB1
S (SUPPLY AIR)
E (EXHAUST)
EA2
SA
EA1
A1
VALVE A
A2
DA2
DA1
PROCESS VALVE 1
PROCESS VALVES IN SPAN POSITION
VALVE A ENERGIZED, VALVE B ENERGIZED

FIG. 12B



PROCESS VALVE IN ZERO POSITION
VALVE A DE-ENERGIZED, VALVE B ENERGIZED

FIG. 13A




S (SUPPLY AIR)
E (EXHAUST)
DB2
DB1
B1
VALVE B
B2
EB2
SB
EB1
EA2
SA
EA1
A1
VALVE A
A2
DA2
DA1
PROCESS VALVE
PROCESS VALVE IN SPAN POSITION
VALVE A ENERGIZED, VALVE B ENERGIZED

FIG. 13B



ESD / PARTIAL STROKE STATE
VALVE A ENERGIZED, VALVE B DE-ENERGIZED

FIG. 13C




S (SUPPLY AIR)
E (EXHAUST)
VALVE B
VALVE A
A1
A2
DB2
DB1
EB2
SB
EB1
EA2
SA
EA1
DA2
DA1
PROCESS VALVE 1
PROCESS VALVES IN ZERO POSITION
VALVE A DE-ENERGIZED, VALVE B DE-ENERGIZED

FIG. 14A



PROCESS VALVES IN SPAN POSITION
VALVE A ENERGIZED, VALVE B ENERGIZED

FIG. 14B



VALVE OPENING
% OPEN AND PSI
110
100
90
80
70
60
50
40
30
20
10
0
-10
1
11
21
31
41
51
61
71
81
91
101
111
121
131
141
151
161
171
181
191
SAMPLE NUMBER
POSITION (% OPEN)
PRESSURE (PSI)

FIG. 15

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US04/11566

A. CLASSIFICATION OF SUBJECT MATTER
IPC(7). : C07D 471/04; A61K 31/519
US CL : 544/279; 514/264.11
According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
U.S. : 544/279; 514/264.11

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched
Fused Pyrimidines, Part Four

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)
CAS ONLINE

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	VICTORY, P. et al, New synthesis of pyrido[2,3-d]pyrimidines. V. Dehydrogenation of dihydropyridonic acid ring in 5- or 6-alkyl-substituted systems Afinidad, 1989, Vol. 46, No. 420, pages 107-13.	1-13
A	SCHOFFSTALL, A.M., Synthesis of 5,6-Dihydropyrido[2,3-d]pyrimidine derivatives directly from acyclic precursors	1-13

☐ Further documents are listed in the continuation of Box C. ☐ See patent family annex.

* Special categories of cited documents:

"A" document defining the general state of the art which is not considered to be of particular relevance

"B" earlier application or patent published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&" document member of the same patent family

Date of the actual completion of the international search
16 March 2005 (16.03.2005)

Date of mailing of the international search report
06 JUN 2005

Name and mailing address of the ISA/US
Mail Stop PCT, Attn: ISA/US
Commissioner for Patents
P.O. Box 1450
Alexandria, Virginia 22313-1450
Facsimile No. (703) 305-3230

Authorized officer
Thomas C. McKenzie, Ph.D.
Telephone No. (703) 308-1235

Form PCT/ISA/210 (second sheet) (January 2004)

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US04/115(

Box No. II Observations where certain claims were found unsearchable (Continuation of item 2 of first sheet)

This international search report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:

2. ☐ Claims Nos.:
because they relate to parts of the international application that do not comply with the prescribed requirements to such an extent that no meaningful international search can be carried out, specifically:

3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box No. III Observations where unity of invention is lacking (Continuation of item 3 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:
Please See Continuation Sheet

1. ☐ As all required additional search fees were timely paid by the applicant, this international search report covers all searchable claims.
2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.
3. ☐ As only some of the required additional search fees were timely paid by the applicant, this international search report covers only those claims for which fees were paid, specifically claims Nos.:

4. ☒ No required additional search fees were timely paid by the applicant. Consequently, this international search report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.: parts of claims 1-13

Remark on Protest
☐ The additional search fees were accompanied by the applicant's protest.
☐ No protest accompanied the payment of additional search fees.

Form PCT/ISA/210 (continuation of first sheet(2)) (January 2004)

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US04/11566

BOX III. OBSERVATIONS WHERE UNITY OF INVENTION IS LACKING

This application contains the following inventions or groups of inventions, which are not so linked as to form a single general inventive concept under PCT Rule 13.1. In order for all inventions to be examined, the appropriate additional examination fees must be paid.

Group I, claim(s) parts of 1-13, drawn to 2-amino-pyrido[2,3-d]pyrimidine-4,7(3H,8H)-dione compounds and compositions.

Group II, claim(s) parts of 1-13, drawn to 5-amino-thiazolo[4,5-d]pyrimidine-2,7(3H,6H)-dione compounds and compositions.

Group III, claim(s) parts of 1-13, drawn to 2-amino-3H-pyrrolo[2,3-d]pyrimidin-4(7H)-one compounds and compositions.

Group IV, claim(s) parts of 1-13, drawn to 2-amino-3H-pyrrolo[3,2-d]pyrimidin-4(5H)-one compounds and compositions.

Group V, claim(s) 14-32, drawn to nucleic acid compounds, compositions, and method of use.

Group VI, claim(s) 33-51, drawn to a second use of the nucleic acid compounds.

Group VII, claim(s) 52-63, drawn to treatment of viral infections with any IMPDH inhibitor.

Group VIII, claim(s) 64-82, drawn to treatment of cancer with any IMPDH inhibitor.

Group IX, claim(s) 83-100, drawn to treatment of autoimmune diseases with any IMPDH inhibitor.

Group X, claim(s) 101-111, drawn to treatment of tropical diseases with any IMPDH inhibitor.

Group XI, claim(s) 112 and 113, drawn to a second treatment of cancer.

Group XII, claim(s) 114 and 115, drawn to a second treatment of viral infection.

Group XIII, claim(s) 116 and 117, drawn to a second treatment of Autoimmune Diseases.

Group XIV, claim(s) 118, drawn to a treatment of Crohn's disease.

The inventions listed as Groups I-V do not relate to a single general inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features for the following reasons: the technical features of claim 1 are the four heterocyclic cores represented by the four different formulas. The technical feature of claim 14 is a nucleic acid, not present in claim 1.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 392

The inventions listed as Groups V and VI do not relate to a single general inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features for the following reasons: Applicants may have a single use of the compounds of claim 14 searched, not the two distinct uses they claim.

.

The inventions listed as Groups VII-XIV do not relate to a single general inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features for the following reasons: these claims do not require the compounds of claim 1 are drawn to separate uses of the IMPDH inhibitors.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 393

Electronic Acknowledgement Receipt

EFS ID:	19320345
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Barden Todd Patterson/Rahim Pirani
Filer Authorized By:	Barden Todd Patterson
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	16-JUN-2014
Filing Date:	25-MAY-2012
Time Stamp:	18:59:55
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	IDS-FillableForm.PDF	612421 2d52e969e541ff6a88e8971147fe00facb50532d	no	4

Warnings:	
Information:	

2	Foreign Reference	WO2005097792A1.pdf	4608268 90d686ce212965c48ddb100c2f06348fa7bc5d83	no	101
Warnings:					
Information:					
3	Other Reference-Patent/App/Search documents	PatentExaminationReport-5_16_2014.PDF	100459 92849e70450850d83f715ceabf11c76f2fc8c897	no	7
Warnings:					
Information:					
			Total Files Size (in bytes):	5321148	

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: David Lymberopoulos et al.	§	
Serial No.: 13/480,704	§	Group Art Unit: 3753
Confirmation No.: 9598	§	
	§	Examiner: WILLIAM M. MCCALISTER
Filed: May 25, 2012	§	
For: SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE	§	

MAIL STOP AMENDMENT
Commissioner for Patents
P.O. Box 1450
Alexandria, VA 22313-1450

Dear Sir:

RESPONSE TO RESTRICTION REQUIREMENT DATED MARCH 18, 2014

In response to the Restriction Requirement dated March 18, 2014, having a shortened statutory period for response on May 18, 2014, please enter the following response and reconsider the claims pending in the application for the reasons discussed below. Although Applicant believes that no additional fee is due in conjunction with this response, the Commissioner is hereby authorized to charge counsel's Deposit Account No. 20-0782/SAFO-0012USP1/JDH for any fees required to make this response timely and acceptable to the Office.

Amendments to the Claims begin on page 2 of this paper.

Remarks begin on page 5 of this paper.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 396

IN THE CLAIMS:

Please amend the claims as follows:

1. (Original) A control system for controlling a safety valve attached to a flow line at a wellsite, the control system comprising:

a controller assembly configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property;

a valve assembly in communication with the controller assembly; and

a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the safety valve to actuate the safety valve to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the safety valve to a second position.

2. (Original) The system of claim 1, further comprising a housing for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

3. (Original) The system of claim 2, wherein the fluid is supplied from a reservoir disposed outside of the housing.

4. (Withdrawn) The system of claim 1, wherein the fluid drive assembly is a compressor and the fluid is a pneumatic fluid.

5. (Original) The system of claim 1, wherein the fluid drive assembly is a pump and the fluid is a hydraulic fluid.

6. (Original) The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 397

7. (Original) The system of claim 1, wherein the first position a closed position and the second position is an open position.

8. (Original) The system of claim 1, further comprising a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly.

9. (Withdrawn) The system of claim 1, wherein the fluid is ambient air.

10. (Original) The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system.

11. (Original) The system of claim 1, wherein the controller assembly is a programmable logic controller, and wherein the valve assembly is operable to release or return fluid from the safety valve for actuating the safety valve to the second position.

12. (Original) A method for controlling a safety valve attached to a flow line at a wellsite, the method comprising:

providing a control system having a housing, a controller assembly, a fluid drive assembly, and a valve assembly;

supplying fluid to the safety valve using the fluid drive assembly to actuate the safety valve into a first position;

monitoring a physical property in the flow line using the controller assembly; and

actuating the valve assembly using the controller assembly to actuate the safety valve into a second position based upon a comparison of the monitored physical property to a predetermined condition.

13. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid disposed external to the housing, and further comprising filtering the pneumatic fluid as it enters the housing by the fluid drive assembly.

14. (Original) The method of claim 12, wherein the fluid is a hydraulic fluid disposed in a reservoir within the housing that is in fluid communication with the fluid drive assembly.

15. (Original) The method of claim 12, further comprising measuring the physical property using a transducer configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. (Original) The method of claim 12, wherein the first position is a closed position and the second position is an open position.

17. (Withdrawn) The method of claim 12, wherein the fluid is a pneumatic fluid, and wherein the fluid drive assembly is a compressor.

18. (Original) The method of claim 12, wherein the fluid is a hydraulic fluid, and wherein the fluid drive assembly is a pump.

19. (Original) The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve.

20. (Original) The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly.

21. (Original) A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system having a safety valve, a valve actuator, and a sensor;

actuating the safety valve into a closed position by supplying actuator fluid to the valve actuator;

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 399

monitoring fluid pressure in the flow line using the sensor while maintaining the safety valve in the closed position; and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator and moving the safety valve into an open position to relieve fluid pressure in the flow line.

REMARKS

This is intended as a full and complete response to the Restriction Requirement dated March 18, 2014. Please reconsider the claims pending in the application for reasons discussed below.

Election/Restriction

Claims 1-21 are pending in the application and are subject to restriction and/or election requirement. The claims have been restricted under 35 U.S.C. 121 as follows:

Species I. Claims 4, 13, 17 drawn to pneumatic fluid species.
Species II. Claims 5, 14, 18 drawn to hydraulic fluid species.
Species III. Claim 9 drawn to ambient air species.

Applicant hereby elects Species II, which includes 5, 14, and 18, without traverse. Claims 4, 9, 13, and 17 have been withdrawn. Claims 1-3, 6-8, 10-12, 15-16, and 19-21 are indicated to be generic claims. Withdrawal of the restriction requirement and examination of claims 1-3, 5-8, 10-12, 14-16, and 18-21 is respectfully requested.

Conclusion

Having addressed all issues set out in the Restriction Requirement, Applicant respectfully requests early examination of the claims that read on the elected invention.

Respectfully submitted,

/Jessie D. Herrera/

Jessie D. Herrera
Registration No. 63,799
Patterson & Sheridan, L.L.P.
24 Greenway Plaza, Suite 1600
Houston, Texas 77046
Telephone: (713) 623-4844
Facsimile: (713) 623-4846
Attorney for Applicant(s)

Electronic Acknowledgement Receipt

EFS ID:	19065684
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Sharlyn Guthrie
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	19-MAY-2014
Filing Date:	25-MAY-2012
Time Stamp:	15:11:41
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1		SAFO0012USP1RRA031814.pdf	80654 996dc6420f1b37f4b5b4e745dfc43aefbb2d3b6f	yes	6

	Multipart Description/PDF files in .zip description		
	Document Description	**Start**	**End**
	Response to Election / Restriction Filed	1	1
	Claims	2	5
	Applicant Arguments/Remarks Made in an Amendment	6	6
Warnings:			
Information:			
	Total Files Size (in bytes):	80654	

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

PTO/SB/06 (09-11)
Approved for use through 1/31/2014. OMB 0651-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PATENT APPLICATION FEE DETERMINATION RECORD Substitute for Form PTO-875	Application or Docket Number 13/480,704	Filing Date 05/25/2012	☐ To be Mailed

ENTITY: ☐ LARGE ☒ SMALL ☐ MICRO

APPLICATION AS FILED – PART I

FOR	(Column 1) NUMBER FILED	(Column 2) NUMBER EXTRA	RATE ($)	FEE ($)
☐ BASIC FEE (37 CFR 1.16(a), (b), or (c))	N/A	N/A	N/A	
☐ SEARCH FEE (37 CFR 1.16(k), (i), or (m))	N/A	N/A	N/A	
☐ EXAMINATION FEE (37 CFR 1.16(o), (p), or (q))	N/A	N/A	N/A	
TOTAL CLAIMS (37 CFR 1.16(i))	minus 20 =	*	X $ =	
INDEPENDENT CLAIMS (37 CFR 1.16(h))	minus 3 =	*	X $ =	
☐ APPLICATION SIZE FEE (37 CFR 1.16(s))	If the specification and drawings exceed 100 sheets of paper, the application size fee due is $310 ($155 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).			
☐ MULTIPLE DEPENDENT CLAIM PRESENT (37 CFR 1.16(j))				
* If the difference in column 1 is less than zero, enter "0" in column 2.			TOTAL	

APPLICATION AS AMENDED – PART II

AMENDMENT **05/19/2014**

	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
Total (37 CFR 1.16(i))	* 21	Minus	** 21	= 0	X $40 =	0
Independent (37 CFR 1.16(h))	* 3	Minus	***3	= 0	X $210 =	0
☐ Application Size Fee (37 CFR 1.16(s))						
☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
					TOTAL ADD'L FEE	0

AMENDMENT

	(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE ($)	ADDITIONAL FEE ($)
Total (37 CFR 1.16(i))	*	Minus	**	=	X $ =	
Independent (37 CFR 1.16(h))	*	Minus	***	=	X $ =	
☐ Application Size Fee (37 CFR 1.16(s))						
☐ FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))						
					TOTAL ADD'L FEE	

* If the entry in column 1 is less than the entry in column 2, write "0" in column 3.

** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 20, enter "20".

*** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 3, enter "3".

The "Highest Number Previously Paid For" (Total or Independent) is the highest number found in the appropriate box in column 1.

LIE
/JAMES ELLIOTT/

This collection of information is required by 37 CFR 1.16. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NO.	FILING DATE	FIRST NAMED INVENTOR	ATTORNEY DOCKET NO.	CONFIRMATION NO.
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1	9598

26290 7590 03/18/2014

PATTERSON & SHERIDAN, L.L.P.
3040 Post Oak Blvd.
Suite 1500
Houston, TX 77056

EXAMINER	
MCCALISTER, WILLIAM M	
ART UNIT	PAPER NUMBER
3753	

NOTIFICATION DATE	DELIVERY MODE
03/18/2014	ELECTRONIC

Please find below and/or attached an Office communication concerning this application or proceeding.

The time period for reply, if any, is set in the attached communication.

Notice of the Office communication was sent electronically on above-indicated "Notification Date" to the following e-mail address(es):

PSDocketing@pattersonsheridan.com
pair_eofficeaction@pattersonsheridan.com
jcardenas@pattersonsheridan.com

Office Action Summary	Application No. 13/480,704	Applicant(s) LYMBEROPOULOS ET AL.	
	Examiner WILLIAM MCCALISTER	Art Unit 3753	AIA (First Inventor to File) Status No

-- The MAILING DATE of this communication appears on the cover sheet with the correspondence address --

Period for Reply

A SHORTENED STATUTORY PERIOD FOR REPLY IS SET TO EXPIRE 2 MONTHS FROM THE MAILING DATE OF THIS COMMUNICATION.

- Extensions of time may be available under the provisions of 37 CFR 1.136(a). In no event, however, may a reply be timely filed after SIX (6) MONTHS from the mailing date of this communication.
- If NO period for reply is specified above, the maximum statutory period will apply and will expire SIX (6) MONTHS from the mailing date of this communication.
- Failure to reply within the set or extended period for reply will, by statute, cause the application to become ABANDONED (35 U.S.C. § 133). Any reply received by the Office later than three months after the mailing date of this communication, even if timely filed, may reduce any earned patent term adjustment. See 37 CFR 1.704(b).

Status

1)☒ Responsive to communication(s) filed on *5/25/12*.

☐ A declaration(s)/affidavit(s) under **37 CFR 1.130(b)** was/were filed on _____.

2a)☐ This action is **FINAL**. 2b)☐ This action is non-final.

3)☐ An election was made by the applicant in response to a restriction requirement set forth during the interview on _____; the restriction requirement and election have been incorporated into this action.

4)☐ Since this application is in condition for allowance except for formal matters, prosecution as to the merits is closed in accordance with the practice under *Ex parte Quayle*, 1935 C.D. 11, 453 O.G. 213.

Disposition of Claims*

5)☒ Claim(s) *1-21* is/are pending in the application.

5a) Of the above claim(s) _____ is/are withdrawn from consideration.

6)☐ Claim(s) _____ is/are allowed.

7)☐ Claim(s) _____ is/are rejected.

8)☐ Claim(s) _____ is/are objected to.

9)☒ Claim(s) *1-21* are subject to restriction and/or election requirement.

* If any claims have been determined allowable, you may be eligible to benefit from the **Patent Prosecution Highway** program at a participating intellectual property office for the corresponding application. For more information, please see http://www.uspto.gov/patents/init_events/pph/index.jsp or send an inquiry to PPHfeedback@uspto.gov.

Application Papers

10)☐ The specification is objected to by the Examiner.

11)☐ The drawing(s) filed on _____ is/are: a)☐ accepted or b)☐ objected to by the Examiner.

Applicant may not request that any objection to the drawing(s) be held in abeyance. See 37 CFR 1.85(a).

Replacement drawing sheet(s) including the correction is required if the drawing(s) is objected to. See 37 CFR 1.121(d).

Priority under 35 U.S.C. § 119

12)☐ Acknowledgment is made of a claim for foreign priority under 35 U.S.C. § 119(a)-(d) or (f).

Certified copies:

a)☐ All b)☐ Some** c)☐ None of the:

1.☐ Certified copies of the priority documents have been received.

2.☐ Certified copies of the priority documents have been received in Application No. _____.

3.☐ Copies of the certified copies of the priority documents have been received in this National Stage application from the International Bureau (PCT Rule 17.2(a)).

** See the attached detailed Office action for a list of the certified copies not received.

Attachment(s)

1) ☐ Notice of References Cited (PTO-892)

2) ☐ Information Disclosure Statement(s) (PTO/SB/08a and/or PTO/SB/08b) Paper No(s)/Mail Date _____.

3) ☐ Interview Summary (PTO-413) Paper No(s)/Mail Date. _____ .

4) ☐ Other: _____.

The present application is being examined under the pre-AIA first to invent provisions.

DETAILED ACTION

Election/Restrictions

This application contains claims directed to the following patentably distinct species: pneumatic fluid species (claims 4, 13, 17), hydraulic fluid species (claims 5, 14, and 18), and ambient air species (claim 9) . The species are independent or distinct because the claims recite the mutually exclusive characteristics of the several species. In addition, these species are not obvious variants of each other based on the current record.

Applicant is required under 35 U.S.C. 121 to elect a single disclosed species, or a single grouping of patentably indistinct species, for prosecution on the merits to which the claims shall be restricted if no generic claim is finally held to be allowable. Currently, all non-identified claims appear to be generic.

There is a search and/or examination burden for the patentably distinct species as set forth above because at least the following reason(s) apply: the species have acquired different status in the art and would require divergent searches (e.g., using distinct key words).

Applicant is advised that the reply to this requirement to be complete must include (i) an election of a species to be examined even though the requirement

may be traversed (37 CFR 1.143) **and (ii) identification of the claims encompassing the elected species or grouping of patentably indistinct species**, including any claims subsequently added. An argument that a claim is allowable or that all claims are generic is considered nonresponsive unless accompanied by an election.

The election may be made with or without traverse. To preserve a right to petition, the election must be made with traverse. If the reply does not distinctly and specifically point out supposed errors in the election of species requirement, the election shall be treated as an election without traverse. Traversal must be presented at the time of election in order to be considered timely. Failure to timely traverse the requirement will result in the loss of right to petition under 37 CFR 1.144. If claims are added after the election, applicant must indicate which of these claims are readable on the elected species or grouping of patentably indistinct species.

Should applicant traverse on the ground that the species, or groupings of patentably indistinct species from which election is required, are not patentably distinct, applicant should submit evidence or identify such evidence now of record showing them to be obvious variants or clearly admit on the record that this is the case. In either instance, if the examiner finds one of the species unpatentable over the prior art, the evidence or admission may be used in a rejection under 35 U.S.C. 103 or pre-AIA 35 U.S.C. 103(a) of the other species.

Upon the allowance of a generic claim, applicant will be entitled to consideration of claims to additional species which depend from or otherwise require all the limitations of an allowable generic claim as provided by 37 CFR 1.141.

A telephone call was made to Todd Patterson on 3/12/14 to request an oral election to the above restriction requirement, but did not result in an election being made. Mr. Patterson was expected to be out of the office until 3/17/14.

Applicant is reminded that upon the cancellation of claims to a non-elected invention, the inventorship must be corrected in compliance with 37 CFR 1.48(a) if one or more of the currently named inventors is no longer an inventor of at least one claim remaining in the application. A request to correct inventorship under 37 CFR 1.48(a) must be accompanied by an application data sheet in accordance with 37 CFR 1.76 that identifies each inventor by his or her legal name and by the processing fee required under 37 CFR 1.17(i).

Any inquiry concerning this communication or earlier communications from the examiner should be directed to William McCalister, whose telephone number 571 270 1869. The examiner can normally be reached on Monday-Friday (7:30AM-4:00PM EST).

If attempts to reach the examiner by telephone are unsuccessful, the examiner's supervisors can be reached by phone. **Steve Hepperle** can be reached at 571-272-4913 or **John Fristoe** can be reached at 571-272-4926. The fax phone number for the organization where this application or proceeding is assigned is 571-273-8300.

Information regarding the status of an application may be obtained from the Patent Application Information Retrieval (PAIR) system. Status information for published applications may be obtained from either Private PAIR or Public PAIR. Status information for unpublished applications is available through Private PAIR

only. For more information about the PAIR system, see http://pair-direct.uspto.gov. Should you have questions on access to the Private PAIR system, contact the Electronic Business Center (EBC) at 866-217-9197 (toll-free). If you would like assistance from a USPTO Customer Service Representative or access to the automated information system, call 800-786-9199 (IN USA OR CANADA) or 571-272-1000.

/WILLIAM MCCALISTER/
Primary Examiner, Art Unit 3753

3/12/14

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	4082147		1978-04-04	Wolff et al.	
	2	6199629		2001-03-13	Shirk et al.	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20020108747		2002-08-15	Dietz et al.	
	2	20120031494		2012-02-09	Lymberopoulos	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button			Add
NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	PCT Search Report and Written Opinion for International Application No. PCT/US2013/042095 dated August 22, 2013	☐
If you wish to add additional non-patent literature document citation information please click the Add button			Add

EXAMINER SIGNATURE			
Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	William M. McCalister
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/Jessie D. Herrera/	Date (YYYY-MM-DD)	2013-10-15
Name/Print	Jessie D. Herrera	Registration Number	63799

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 413

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 414

Due Date: 10/22/13

PCT/US2013/042095

PATENT COOPERATION TREATY

From the INTERNATIONAL SEARCHING AUTHORITY

To:
PATTERSON B. TODD.

PATTERSON & SHERIDAN, L.L.P. 3040 POST OAK BLVD., SUITE 1500 HOUSTON TX 77056-6582 USA

1435.061824
SAFO0012PC04
FORWARDED TO BTP/JH MS.
RECEIVED
DOCKETED CJ 9/6/13

PCT

NOTIFICATION OF TRANSMITTAL OF THE INTERNATIONAL SEARCH REPORT AND THE WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY, OR THE DECLARATION

(PCT Rule 44.1)

Date of mailing *(day/month/year)* 22 August 2013 (22.08.2013)	
Applicant's or agent's file reference SAFO0012PC04	**FOR FURTHER ACTION** See paragraphs 1 and 4 below
International application No. **PCT/US2013/042095**	International filing date *(day/month/year)* **21 May 2013 (21.05.2013)**
Applicant **SAFOCO, INC. et al**	

1. ☒ The applicant is hereby notified that the international search report and the written opinion of the International Searching Authority have been established and are transmitted herewith.

Filing of amendments and statement under Article 19:

The applicant is entitled, if he so wishes, to amend the claims of the international application (see Rule 46):

When? The time limit for filing such amendments is normally two months from the date of transmittal of the international search report.

Where? Directly to the International Bureau of WIPO, 34 chemin des Colombettes 1211 Geneva 20, Switzerland, Facsimile No.: +41 22 338 82 70

For more detailed instructions, see *PCT Applicant's Guide*, International Phase, paragraphs 9.004 . 9.011.

2. ☐ The applicant is hereby notified that no international search report will be established and that the declaration under Article 17(2)(a) to that effect and the written opinion of the International Searching Authority are transmitted herewith.

3. ☐ **With regard to any protest** against payment of (an) additional fee(s) under Rule 40.2, the applicant is notified that:

☐ the protest together with the decision thereon has been transmitted to the International Bureau together with any request to forward the texts of both the protest and the decision thereon to the designated Offices.

☐ no decision has been made yet on the protest; the applicant will be notified as soon as a decision is made.

4. **Reminders**

The applicant may submit comments on an informal basis on the written opinion of the International Searching Authority to the International Bureau. The International Bureau will send a copy of such comments to all designated Offices unless an international preliminary examination report has been or is to be established. Following the expiration of 30 months from the priority date, these comments will also be made available to the public.

Shortly after the expiration of **18 months** from the priority date, the international application will be published by the International Bureau. If the applicant wishes to avoid or postpone publication, a notice of withdrawal of the international application, or of the priority claim, must reach the International Bureau before the completion of the technical preparations for international publication (Rules 90bis.1 and 90bis.3).

Within **19 months** from the priority date, but only in respect of some designated Offices, a demand for international preliminary examination must be filed if the applicant wishes to postpone the entry into the national phase **until 30 months** from the priority date (in some Offices even later); otherwise, the applicant must, **within 20 months** from the priority date, perform the prescribed acts for entry into the national phase before those designated Offices.

In respect of other designated Offices, the time limit of **30 months** (or later) will apply even if no demand is filed within 19months.

For details about the applicable time limits, Office by Office, see www.wipo.int/pct/en/texts/time_limits.html and the PCT Applicant's Guide, National Chapters.

SEP 5 2013
PATTERSON & SHERIDAN, LLP
HOUSTON OFFICE

Name and mailing address of the ISA/KR Korean Intellectual Property Office 189 Cheongsa-ro, Seo-gu, Daejeon Metropolitan City, 302-701, Republic of Korea Facsimile No. 82-42-472-7140	Authorized officer COMMISSIONER Telephone No. 82-42-481-8754

Form PCT/ISA/220 (July 2010)

* Attention

Copies of the documents cited in the international search report can be searched in the following Korean Intellectual Property Office English website for three months from the date of mailing of the international search report.

http://www.kipo.go.kr/en/ => PCT Services => PCT Services

ID : PCT international application number
PW : **5GL377JD**

Inquiries related to PCT International Search Report or Written Opinion prepared by KIPO as an International Searching Authority can be answered not only by KIPO but also through IPKC (Intellectual Property Korea Center), located in Vienna, VA, which functions as a PCT Help Desk for PCT applicants.

Homepage: http://www.ipkcenter.com

Email: ipkc@ipkcenter.com

Notes to Form PCT/ISA/220 (July 2010)

PATENT COOPERATION TREATY

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference SAFO0012PC04	**FOR FURTHER ACTION**	see Form PCT/ISA/220 as well as, where applicable, item 5 below.
International application No. **PCT/US2013/042095**	International filing date *(day/month/year)* **21 May 2013 (21.05.2013)**	(Earliest) Priority Date *(day/month/year)* 25 May 2012 (25.05.2012)

Applicant

SAFOCO, INC. et al

This International search report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This international search report consists of a total of **3** sheets.

☐ It is also accompanied by a copy of each prior art document cited in this report.

1. **Basis of the report**
   a. With regard to the **language**, the international search was carried out on the basis of:
      ☒ the international application in the language in which it was filed
      ☐ a translation of the international application into _____, which is the language of a translation furnished for the purposes of international search (Rules 12.3(a) and 23.1(b))
   b. ☐ This international search report has been established taking into account the **rectification of an obvious mistake** authorized by or notified to this Authority under Rule 91 (Rule 43.6*bis*(a)).
   c. ☐ With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, see Box No. I.
2. ☐ **Certain claims were found unsearchable** (See Box No. II)
3. ☐ **Unity of invention is lacking** (See Box No. III)
4. With regard to the **title,**
   ☒ the text is approved as submitted by the applicant.
   ☐ the text has been established by this Authority to read as follows:
5. With regard to the **abstract,**
   ☒ the text is approved as submitted by the applicant.
   ☐ the text has been established, according to Rule 38.2, by this Authority as it appears in Box No. IV. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.
6. With regard to the drawings,
   a. the figure of the **drawings** to be published with the abstract is Figure No. **14**
      ☒ as suggested by the applicant.
      ☐ as selected by this Authority, because the applicant failed to suggest a figure.
      ☐ as selected by this Authority, because this figure better characterizes the invention.
   b. ☐ none of the figure is to be published with the abstract.

Form PCT/ISA/210 (first sheet) (July 2009)

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US2013/042095

A. CLASSIFICATION OF SUBJECT MATTER

E21B 34/16(2006.01)i, E21B 43/12(2006.01)i, E21B 34/14(2006.01)i

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
E21B 34/16; E21B 33/03; E21B 34/06; F16K 31/02; E21B 43/00; F16K 31/145; F16K 51/00; E21B 34/10; E21B 36/00; E21B 43/12; E21B 34/14

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched
Korean utility models and applications for utility models
Japanese utility models and applications for utility models

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)
eKOMPASS(KIPO internal) & Keywords: safety valve, controller assembly, transducer, valve assembly, fluid drive assembly, housing, power source, and filter

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 2012-0031494 A1 (LYMBEROPOULOS, DAVID) 09 February 2012 See paragraphs [0009]-[0010], [0025], [0027], [0029], [0034]-[0036], [0038]-[0039] and figures 1-3.	1-7,9-12,14-21
Y		8,13
Y	US 4082147 A (WOLFF, DANNY K. et al.) 04 April 1978 See column 14, lines 9-26 and figure 5.	8,13
A	US 6450477 B1 (YOUNG, TERRY G.) 17 September 2002 See column 5, line 66 - column 6, line 33 and figure 5.	1-21
A	US 2002-0108747 A1 (DIETZ, WESLEY P. et al.) 15 August 2002 See paragraphs [0014]-[0017], [0020] and figures 1-3.	1-21
A	US 6199629 B1 (SHIRK, STEVE et al.) 13 March 2001 See column 5, line 19 - column 6, line 22 and figures 3-4.	1-21

☐ Further documents are listed in the continuation of Box C. ☒ See patent family annex.

* Special categories of cited documents:
"A" document defining the general state of the art which is not considered to be of particular relevance
"E" earlier application or patent but published on or after the international filing date
"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of citation or other special reason (as specified)
"O" document referring to an oral disclosure, use, exhibition or other means
"P" document published prior to the international filing date but later than the priority date claimed
"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents,such combination being obvious to a person skilled in the art
"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
21 August 2013 (21.08.2013)	**22 August 2013 (22.08.2013)**
Name and mailing address of the ISA/KR Korean Intellectual Property Office 189 Cheongsa-ro, Seo-gu, Daejeon Metropolitan City, 302-701, Republic of Korea Facsimile No. +82-42-472-7140	Authorized officer LEE Jong Kyung Telephone No. +82-42-481-3360

Form PCT/ISA/210 (second sheet) (July 2009)

INTERNATIONAL SEARCH REPORT
Information on patent family members

International application No.
PCT/US2013/042095

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
US 2012-0031494 A1	09/02/2012	AU 2011-285979 A1	21/02/2013
		CA 2806849 A1	09/02/2012
		CN 103097787 A	08/05/2013
		GB 201303629 D0	17/04/2013
		GB 2495897 A	24/04/2013
		MX 2013001025 A	27/02/2013
		SG 187676 A1	28/03/2013
		WO 2012-018730 A2	09/02/2012
		WO 2012-018730 A3	12/04/2012
US 4082147 A	04/04/1978	None	
US 6450477 B1	17/09/2002	US 2005-0017209 A1	27/01/2005
		US 2005-0067592 A1	31/03/2005
		US 2006-0091339 A1	04/05/2006
		US 6089531 A	18/07/2000
		US 6250605 B1	26/06/2001
		US 6854704 B1	15/02/2005
		US 7028986 B2	18/04/2006
		WO 95-23937 A1	08/09/1995
US 2002-0108747 A1	15/08/2002	EP 1236862 A2	04/09/2002
		EP 1236862 A3	11/02/2004
		US 6619388 B2	16/09/2003
US 6199629 B1	13/03/2001	AU 761221 B2	29/05/2003
		CA 2247834 A1	24/03/1999
		CA 2247834 C	26/06/2007
		GB 2330598 A	28/04/1999
		GB 2330598 B	17/07/2002
		GB 9820702 D0	18/11/1998
		NO 318597 B1	18/04/2005
		NO 984459 A	25/03/1999
		NO 984459 D0	24/09/1998

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 419

PATENT COOPERATION TREATY

From the
INTERNATIONAL SEARCHING AUTHORITY

To:
PATTERSON B. TODD.

PATTERSON & SHERIDAN, L.L.P. 3040 POST OAK BLVD., SUITE 1500 HOUSTON TX 77056-6582 USA

PCT

WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY

(PCT Rule 43bis.1)

Date of mailing *(day/month/year)*	**22 August 2013 (22.08.2013)**
Applicant's or agent's file reference: SAFO0012PC04	**FOR FURTHER ACTION** See paragraph 2 below

International application No.	International filing date *(day/month/year)*	Priority date *(day/month/year)*
PCT/US2013/042095	**21 May 2013 (21.05.2013)**	25 May 2012 (25.05.2012)

International Patent Classification (IPC) or both national classification and IPC

E21B 34/16(2006.01)i, E21B 43/12(2006.01)i, E21B 34/14(2006.01)i

Applicant
SAFOCO, INC. et al

1. This opinion contains indications relating to the following items:

- [x] Box No. I Basis of the opinion
- [ ] Box No. II Priority
- [ ] Box No. III Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- [ ] Box No. IV Lack of unity of invention
- [x] Box No. V Reasoned statement under Rule 43bis.1(a)(i) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- [ ] Box No. VI Certain documents cited
- [ ] Box No. VII Certain defects in the international application
- [ ] Box No. VIII Certain observations on the international application

2. **FURTHER ACTION**

If a demand for international preliminary examination is made, this opinion will be considered to be a written opinion of the International Preliminary Examining Authority ("IPEA") except that this does not apply where the applicant chooses an Authority other than this one to be the IPEA and the chosen IPEA has notified the International Bureau under Rule 66.1bis(b) that written opinions of this International Searching Authority will not be so considered.

If this opinion is, as provided above, considered to be a written opinion of the IPEA, the applicant is invited to submit to the IPEA a written reply together, where appropriate, with amendments, before the expiration of 3 months from the date of mailing of Form PCT/ISA/220 or before the expiration of 22 months from the priority date, whichever expires later.
For further options, see Form PCT/ISA/220.

Name and mailing address of the ISA/KR	Date of completion of this opinion	Authorized officer
Korean Intellectual Property Office 189 Cheongsa-ro, Seo-gu, Daejeon Metropolitan City, 302-701, Republic of Korea Facsimile No. +82-42-472-7140	21 August 2013 (21.08.2013)	LEE Jong Kyung Telephone No. +82-42-481-3360

Form PCT/ISA/237 (cover sheet) (July 2011)

WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY

International application No.
PCT/US2013/042095

Box No. I Basis of this opinion

1. With regard to the **language**, this opinion has been established on the basis of :

   ☒ the international application in the language in which it was filed

   ☐ a translation of the international application into _____, which is the language of a translation furnished for the purposes of international search (Rules 12.3(a) and 23.1(b))

2. ☐ This opinion has been established taking into account the **rectification of an obvious mistake** authorized by or notified to this Authority under Rule 91 (Rule 43*bis*.1(a))

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, this opinion has been established on the basis of:

   a. a sequence listing filed or furnished
      ☐ on paper
      ☐ in electronic form

   b. time of filing or furnishing
      ☐ contained in the international application as filed.
      ☐ filed together with the international application in electronic form.
      ☐ furnished subsequently to this Authority for the purposes of search.

4. ☐ In addition, in the case that more than one version or copy of a sequence listing has been filed or furnished, the required statements that the information in the subsequent or additioanl copies is identical to that in the application as filed or does not go beyond the application as filed, as appropriate, were furnished.

5. Additional comments:

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 421

WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY

International application No.
PCT/US2013/042095

Box No. V Reasoned statement under Rule 43bis.1(a)(i) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Claims	4,7-8,13,16-17,21	YES
	Claims	1-3,5-6,9-12,14-15,18-20	NO
Inventive step (IS)	Claims	NONE	YES
	Claims	1-21	NO
Industrial applicability (IA)	Claims	1-21	YES
	Claims	NONE	NO

2. Citations and explanations :

Reference is made to the following documents:

D1: US 2012-0031494 A1 (LYMBEROPOULOS, DAVID) 09 February 2012
D2: US 4082147 A (WOLFF, DANNY K. et al.) 04 April 1978

1. Novelty and Inventive Step

1.1 Independent Claim 1

D1, which is considered to represent the most relevant state of the art, discloses an ESD control system (200) comprising a controller assembly (220) configured to receive a signal from a pressure transducer (280) connected to a flow line (135), a valve assembly (260) in communication with the controller assembly (220), and a pump assembly (240) in communication with the controller assembly (220), wherein the control assembly (220) is operable to actuate the pump assembly (240) to supply fluid from a fluid reservoir (250) to the safety valve (120) to actuate the safety valve (120) into an open position, and is operable to actuate the valve assembly (260) to actuate the safety valve (120) into a closed position (see paragraphs [0009], [0029] and figures 1-2).
As all of the features of claim 1 are disclosed in D1, this claim is anticipated by D1. Therefore, claim 1 lacks novelty under PCT Article 33(2).

Continued on Supplemental Box

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 422

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of : Box No. V

1.2 Dependent Claims 2-11

1.2.1 Concerning claim 2

The additional feature of claim 2 is identical to a housing (210) for supporting the controller assembly (220) in D1 (see paragraph [0025] and figure 2). Accordingly, claim 2 is anticipated by D1. Therefore, claim 2 lacks novelty under PCT Article 33(2).

1.2.2 Concerning claim 3

The additional feature of claim 3 is identical to the fluid reservoir (250) of D1 (see paragraph [0025] and figure 2). Accordingly, claim 3 is anticipated by D1. Therefore, claim 3 lacks novelty under PCT Article 33(2).

1.2.3 Concerning claim 4

The additional feature of claim 4, characterized in that a fluid drive assembly is a compressor and the fluid is a pneumatic fluid, is not explicitly disclosed in D1. However, this feature would be easily conceived from D1 considering that the pump assembly (240) pumps a pneumatic fluid from the fluid reservoir (250) to actuate the safety valve (120) (see paragraph [0034] and figure 2). Accordingly, claim 4 would have been obvious over D1. Therefore, claim 4 lacks an inventive step under PCT Article 33(3).

1.2.4 Concerning claim 5

The additional feature of claim 5 is identical to the feature of D1, wherein the pump assembly (240) pumps a hydraulic fluid from the fluid reservoir (250) to actuate the safety valve (120) (see paragraph [0034] and figure 2). Accordingly, claim 5 is anticipated by D1. Therefore, claim 5 lacks novelty under PCT Article 33(2).

Continued on The Next Page

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 423

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of : Previous Page

1.2.5 Concerning claim 6

The additional feature of claim 6 is identical to a power source (230) for supplying power to the controller assembly (220), the valve assembly (260), and the pump assembly (240) in D1 (see paragraph [0025] and figure 2). Accordingly, claim 6 is anticipated by D1. Therefore, claim 6 lacks novelty under PCT Article 33(2).

1.2.6 Concerning claim 7

The additional feature of claim 7, characterized in that a first position is a closed position and the second position is an open position, is not explicitly disclosed in D1. However, this feature would be easily conceived from D1 considering that the safety valve (120) is shiftable between the open position and the closed position (see paragraphs [0009], [0029]). Accordingly, claim 7 would have been obvious over D1. Therefore, claim 7 lacks an inventive step under PCT Article 33(3).

1.2.7 Concerning claim 8

The additional feature of claim 8, concerning a housing for supporting the fluid drive assembly and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly, is not disclosed in D1. However, D2 discloses that a surface control system for subsurface safety valves comprises a line filter (174) to filter air supplied to a pneumatic operated hydraulic pump (180) disposed in a housing (see column 14, lines 9-26 and figure 5). It would be obvious to a person skilled in the art to apply the feature of D2 to the ESD control system (200) of D1 to arrive at claim 8. Thus, claim 8 does not involve an inventive step under PCT Article 33(3).

1.2.8 Concerning claim 9

The additional feature of claim 9 is identical to the feature of D1, wherein the fluid includes air (see paragraph [0035]). Accordingly, claim 9 is anticipated by D1. Therefore, claim 9 lacks novelty under PCT Article 33(2).

Continued on The Next Page

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 424

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of : Previous Page

1.2.9 Concerning claim 10

The additional feature of claim 10 is identical to the feature of D1, wherein the controller assembly (220) is operable to send and receive signals corresponding to the sensed physical property with a computer system (150) at a remote location from a wellhead control system (100) (see paragraphs [0010], [0027] and figures 1-2). Accordingly, claim 10 is anticipated by D1. Therefore, claim 10 lacks novelty under PCT Article 33(2).

1.2.10 Concerning claim 11

The additional feature of claim 11 is identical to the feature of D1, wherein the controller assembly (220) is a programmable logic controller and the valve assembly (260) is operable to return fluid from the safety valve (120) for actuating the safety valve (120) into a closed position (see paragraphs [0009], [0027], [0029]). Accordingly, claim 11 is anticipated by D1. Therefore, claim 11 lacks novelty under PCT Article 33(2).

1.3 Independent Claim 12

D1, which is considered to represent the most relevant state of the art, discloses a method comprising the steps of: providing an ESD control system (200) having a housing (210), a controller assembly (220), a pump assembly (240), and a valve assembly (260); supplying fluid to the safety valve (120) using the pump assembly (240) to actuate the safety valve (120) into an open position; sensing a physical property in a flow line (135) using the controller assembly (220); and actuating the valve assembly (260) using the controller assembly (220) to actuate the safety valve (120) into a closed position based on a comparison of the sensed physical property to a pre-set condition (see paragraphs [0009]-[0010], [0025], [0029] and figures 1-2).
As all of the features of claim 12 are disclosed in D1, this claim is anticipated by D1. Therefore, claim 12 lacks novelty under PCT Article 33(2).

Continued on The Next Page

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 425

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of: Previous Page

1.4 Dependent Claims 13-20

1.4.1 Concerning claim 13

The additional feature of claim 13, concerning a step of filtering a pneumatic fluid as it enters a housing by a fluid drive assembly, is not disclosed in D1. However, D2 discloses a step of filtering air supplied to a pneumatic operated hydraulic pump (180) disposed in a housing (see column 14, lines 9-26 and figure 5). It would be obvious to a person skilled in the art to apply the feature of D2 to the method of D1 to arrive at claim 13. Thus, claim 13 does not involve an inventive step under PCT Article 33(3).

1.4.2 Concerning claim 14

The additional feature of claim 14 is identical to the feature of D1, wherein the pump assembly (240) pumps a hydraulic fluid from a fluid reservoir (250) to actuate the safety valve (120) (see paragraph [0034] and figure 2). Accordingly, claim 14 is anticipated by D1. Therefore, claim 14 lacks novelty under PCT Article 33(2).

1.4.3 Concerning claim 15

The additional feature of claim 15 is identical to a step of sensing a physical property using a pressure transducer (280) configured to communicate signals corresponding to the sensed physical property to the controller assembly (220) (see paragraphs [0009]-[0010], [0025], [0027], [0029]). Accordingly, claim 15 is anticipated by D1. Therefore, claim 15 lacks novelty under PCT Article 33(2).

1.4.4 Concerning claim 16

The additional feature of claim 16, characterized in that a first position is a closed position and the second position is an open position, is not explicitly disclosed in D1. However, this feature would be easily conceived from D1 considering that the safety valve (120) is shiftable between the open position and the closed position (see paragraphs [0009], [0029]). Accordingly, claim 16 would have been obvious over D1. Therefore, claim 16 lacks an inventive step under PCT Article 33(3).

Continued on The Next Page

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 426

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of : Previous Page

1.4.5 Concerning claim 17

The additional feature of claim 17, characterized in that the fluid is the pneumatic fluid and a fluid drive assembly is a compressor, is not explicitly disclosed in D1. However, this feature would be easily conceived from D1 considering that the pump assembly (240) pumps a pneumatic fluid from the fluid reservoir (250) to actuate the safety valve (120) (see paragraph [0034] and figure 2). Accordingly, claim 17 would have been obvious over D1. Therefore, claim 17 lacks an inventive step under PCT Article 33(3).

1.4.6 Concerning claim 18

The additional feature of claim 18 is identical to the feature of D1, wherein the pump assembly (240) pumps a hydraulic fluid from the fluid reservoir (250) to actuate the safety valve (120) (see paragraph [0034] and figure 2). Accordingly, claim 18 is anticipated by D1. Therefore, claim 18 lacks novelty under PCT Article 33(2).

1.4.7 Concerning claim 19

The additional feature of claim 19 is identical to a step of communicating signals from the controller assembly (220) to a computer system (150) at a remote location from a wellhead control system (100), wherein the signals correspond to an operational characteristic of the safety valve (120) (see paragraphs [0010], [0027], [0039] and figures 1-2). Accordingly, claim 19 is anticipated by D1. Therefore, claim 19 lacks novelty under PCT Article 33(2).

1.4.8 Concerning claim 20

The additional feature of claim 20 is identical to a step of actuating the safety valve (120) communicating a signal from the computer system (150) at a remote location from the wellhead control system (100) to the controller assembly (220) (see paragraphs [0009]-[0010], [0025], [0027], [0029] and figures 1-2). Accordingly, claim 20 is anticipated by D1. Therefore, claim 20 lacks novelty under PCT Article 33(2).

Continued on The Next Page

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 427

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of: Previous Page

1.5 Independent Claim 21

D1, which is considered to be the closest prior art to the subject matter of independent claim 21, discloses a method comprising the steps of: providing an ESD control system (200) having a surface safety valve (120), a valve actuator (122), and a pressure gauge (264); actuating the safety valve (120) into an open position by supplying actuator fluid to the valve actuator (122), monitoring a physical property in a flow line (213) using the pressure gauge (264), actuating the pressure gauge (264), thereby releasing the actuator fluid from the valve actuator (122) and moving the safety valve (120) into a closed position (see paragraphs [0009]-[0010], [0036], [0038]-[0039] and figures 1-3). Claim 21 differs from D1 in that the safety valve of claim 21 is moved into a closed position by supplying actuator fluid to a valve actuator and is moved into an open position by releasing the actuator fluid from the valve actuator, whereas the surface safety valve (120) of D1 is moved into the open position by supplying the actuator fluid to the valve actuator (122) and is moved into the closed position by releasing the actuator fluid from the valve actuator (122). However, such a slight change in the actuating method of the safety valve comes within the scope of the customary practice followed by persons skilled in the art. Accordingly, claim 21 would have been obvious over D1. Therefore, claim 21 lacks an inventive step under PCT Article 33(3).

2. Industrial Applicability

Claims 1-21 are industrially applicable under PCT Article 33(4).

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 428

Electronic Acknowledgement Receipt

EFS ID:	17130827
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Jessie D. Herrera/Sharlyn Guthrie
Filer Authorized By:	Jessie D. Herrera
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	15-OCT-2013
Filing Date:	25-MAY-2012
Time Stamp:	15:33:27
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	SAFO0012USP1SIDS.pdf	611925 af860c5e27363f7f8ad91c7c6da778163350 7861	no	4

Warnings:	
Information:	

2	Non Patent Literature	PCTSEARCH082213.pdf	559972 5fd6816e9e86692fb2a85d8c16dfd4d56a202c9b	no	14

Warnings:	
Information:	
Total Files Size (in bytes):	1171897

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	Not Assigned
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1					

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20100154894		2010-06-24	Kotapish et al.	
	2	20110094752		2011-04-28	Hudson et al.	
	3	20130008519		2013-01-10	Crawford	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1							☐

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	Not Assigned
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button			Add
NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1		☐
If you wish to add additional non-patent literature document citation information please click the Add button			Add

EXAMINER SIGNATURE			
Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	3753
	Examiner Name	Not Assigned
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/B. Todd Patterson/	Date (YYYY-MM-DD)	2013-06-19
Name/Print	B. Todd Patterson	Registration Number	37906

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 434

Electronic Acknowledgement Receipt

EFS ID:	16088394
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Barden Todd Patterson/Sharlyn Guthrie
Filer Authorized By:	Barden Todd Patterson
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	19-JUN-2013
Filing Date:	25-MAY-2012
Time Stamp:	17:32:32
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	SAFO0012USP1SIDS.pdf	611775 2f7610ee833be23a423744e343fe4e7dc537bb4b	no	4

Warnings:	
Information:	

Total Files Size (in bytes):	611775

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	Unassigned
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS Remove

Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	6296052		2001-10-02	Sidwell	
	2	6633236		2003-10-14	Vinegar et al.	

If you wish to add additional U.S. Patent citation information please click the Add button. Add

U.S.PATENT APPLICATION PUBLICATIONS Remove

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20040135112		2004-07-15	Greeb et al.	
	2	20100025045		2010-02-04	Lake et al.	

If you wish to add additional U.S. Published Application citation information please click the Add button. Add

FOREIGN PATENT DOCUMENTS Remove

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2] ¡	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	0165061	WO	A1	2001-09-07	Shell Oil Co		☐

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99)**		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	Unassigned
	Attorney Docket Number	SAFO/0012USP1

If you wish to add additional Foreign Patent Document citation information please click the Add button			Add
NON-PATENT LITERATURE DOCUMENTS			Remove
Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	PCT International Search Report and Written Opinion; International Application No. PCT/US2012/061313; Mailed March 14, 2013.	☐
If you wish to add additional non-patent literature document citation information please click the Add button			Add

EXAMINER SIGNATURE			
Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David LYMBEROPOULOS
	Art Unit	3753
	Examiner Name	Unassigned
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	/B. Todd Patterson/	Date (YYYY-MM-DD)	2013-04-02
Name/Print	B. Todd Patterson	Registration Number	37906

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these record s.

2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.

3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.

4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).

5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.

6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).

7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.

8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.

9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 440

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
7 September 2001 (07.09.2001)

PCT

(10) International Publication Number
WO 01/65061 A1

(51) International Patent Classification[7]: E21B 34/06, 17/00, 47/12, F16K 31/06

(21) International Application Number: PCT/US01/06949

(22) International Filing Date: 2 March 2001 (02.03.2001)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
60/186,531 2 March 2000 (02.03.2000) US

(71) Applicant *(for all designated States except US)*: **SHELL OIL COMPANY** [US/US]; One Shell Plaza, P.O. Box 2463, Houston, TX 77252-2463 (US).


(72) Inventors; and
(75) Inventors/Applicants *(for US only)*: **VINEGAR, Harold, J.** [US/US]; 5219 Yarwell, Houston, TX 77096 (US). **BURNETT, Robert, Rex** [US/US]; 20711 Flagmore Court, Katy, TX 77450 (US). **SAVAGE, William, Mountjoy** [US/US]; 8446 Ariel, Houston, TX 77074 (US). **CARL, Frederick, Gordon, Jr.** [US/US]; 8406 Edgemoor, Houston, TX 77036 (US).

(74) Agent: **CHRISTENSEN,, Del, S.**; Shell Oil Company, One Shell Plaza, P.O. Box 2463, Houston, TX 77252-2463 (US).

(81) Designated States *(national)*: AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CR, CU, CZ, DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

[Continued on next page]

(54) Title: ELECTRO-HYDRAULICALLY PRESSURIZED DOWNHOLE VALVE ACTUATOR



(57) Abstract: A petroleum well having a communication system and a hydraulic system is provided. The petroleum well includes a borehole and a piping structure positioned within the borehole. The communication system supplies a time varying electric current downhole along the piping structure. The hydraulic system (70), which is positioned downhole proximate the piping structure (26), receives the time varying current to operate an electric motor (78). The motor drives a pump (76) which pressurizes hydraulic fluid to selectively drive an actuator (84). The actuator (84) is operably connected to a downhole device, such as a shutoff valve, and operates the downhole device as the actuator (84) is driven by the pressurized hydraulic fluid.

WO 01/65061 A1

(84) Designated States *(regional)*: ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

Published:
— *with international search report*

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

5

Electro-hydraulically pressurized downhole valve actuator

CROSS-REFERENCES TO RELATED APPLICATIONS

10 This application claims the benefit of the following U.S. Provisional Applications, all of which are hereby incorporated by reference:

COMMONLY OWNED AND PREVIOUSLY FILED U.S. PROVISIONAL PATENT APPLICATIONS			
T&K #	**Serial Number**	**Title**	**Filing Date**
TH 1599	60/177,999	Toroidal Choke Inductor for Wireless Communication and Control	Jan. 24, 2000
TH 1600	60/178,000	Ferromagnetic Choke in Wellhead	Jan. 24, 2000
TH 1602	60/178,001	Controllable Gas-Lift Well and Valve	Jan. 24, 2000
TH 1603	60/177,883	Permanent, Downhole, Wireless, Two-Way Telemetry Backbone Using Redundant Repeater, Spread Spectrum Arrays	Jan. 24, 2000
TH 1668	60/177,998	Petroleum Well Having Downhole Sensors, Communication, and Power	Jan. 24, 2000
TH 1669	60/177,997	System and Method for Fluid Flow Optimization	Jan. 24, 2000
TS 6185	60/181,322	A Method and Apparatus for the Optimal Predistortion of an Electromagnetic Signal in a Downhole Communications System	Feb. 9, 2000
TH 1599x	60/186,376	Toroidal Choke Inductor for Wireless Communication and Control	Mar. 2, 2000
TH 1600x	60/186,380	Ferromagnetic Choke in Wellhead	Mar. 2, 2000
TH 1601	60/186,505	Reservoir Production Control from Intelligent Well Data	Mar. 2, 2000
TH 1671	60/186,504	Tracer Injection in a Production Well	Mar. 2, 2000
TH 1672	60/186,379	Oilwell Casing Electrical Power Pick-Off Points	Mar. 2, 2000
TH 1673	60/186,394	Controllable Production Well Packer	Mar. 2, 2000
TH 1674	60/186,382	Use of Downhole High Pressure Gas in a Gas Lift Well	Mar. 2, 2000
TH 1675	60/186,503	Wireless Smart Well Casing	Mar. 2, 2000

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 443

TH 1677	60/186,527	Method for Downhole Power Management Using Energization from Distributed Batteries or Capacitors with Reconfigurable Discharge	Mar. 2, 2000
TH 1679	60/186,393	Wireless Downhole Well Interval Inflow and Injection Control	Mar. 2, 2000
TH 1681	60/186,394	Focused Through-Casing Resistivity Measurement	Mar. 2, 2000
TH 1704	60/186,531	Downhole Rotary Hydraulic Pressure for Valve Actuation	Mar. 2, 2000
TH 1705	60/186,377	Wireless Downhole Measurement and Control For Optimizing Gas Lift Well and Field Performance	Mar. 2, 2000
TH 1722	60/186, 381	Controlled Downhole Chemical Injection	Mar. 2, 2000
TH 1723	60/186,378	Wireless Power and Communications Cross-Bar Switch	Mar. 2, 2000

5

The current application shares some specification and figures with the following commonly owned and concurrently filed applications, all of which are hereby incorporated by reference:

COMMONLY OWNED AND CONCURRENTLY FILED U.S PATENT APPLICATIONS			
T&K #	**Serial Number**	**Title**	**Filing Date**
TH 1601US	09/_____	Reservoir Production Control from Intelligent Well Data	
TH 1671US	09/_____	Tracer Injection in a Production Well	
TH 1672US	09/_____	Oil Well Casing Electrical Power Pick-Off Points	
TH 1673US	09/_____	Controllable Production Well Packer	
TH 1674US	09/	Use of Downhole High Pressure Gas in a Gas-Lift Well	
TH 1675US	09/_____	Wireless Smart Well Casing	
TH 1677US	09/_____	Method for Downhole Power Management Using Energization from Distributed Batteries or Capacitors with Reconfigurable Discharge	
TH 1679US	09/_____	Wireless Downhole Well Interval Inflow and Injection Control	
TH 1681US	09/_____	Focused Through-Casing Resistivity Measurement	
TH 1705US	09/_____	Wireless Downhole Measurement and Control For Optimizing Gas Lift Well and Field Performance	
TH 1722US	09/_____	Controlled Downhole Chemical Injection	
TH 1723US	09/_____	Wireless Power and Communications Cross-Bar Switch	

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 444

The current application shares some specification and figures with the following commonly owned and previously filed applications, all of which are hereby incorporated by reference:

COMMONLY OWNED AND PREVIOUSLY FILED U.S PATENT APPLICATIONS			
T&K #	**Serial Number**	**Title**	**Filing Date**
TH 1599US	09/_____	Choke Inductor for Wireless Communication and Control	
TH 1600US	09/_____	Induction Choke for Power Distribution in Piping Structure	
TH 1602US	09/_____	Controllable Gas-Lift Well and Valve	
TH 1603US	09/_____	Permanent Downhole, Wireless, Two-Way Telemetry Backbone Using Redundant Repeater	
TH 1668US	09/_____	Petroleum Well Having Downhole Sensors, Communication, and Power	
TH 1669US	09/_____	System and Method for Fluid Flow Optimization	
TH 1783US	09/_____	Downhole Motorized Flow Control Valve	
TS 6185US	09/_____	A Method and Apparatus for the Optimal Predistortion of an Electro Magnetic Signal in a Downhole Communications System	

The benefit of 35 U.S.C. § 120 is claimed for all of the above referenced commonly owne applications. The applications referenced in the tables above are referred to herein as the "Related Applications."

BACKGROUND OF THE INVENTION

Field of the Invention

The present invention relates generally to petroleum wells and in particular to petroleum wells having a communication system for delivering power and communications to a downhole hydraulic system, the hydraulic system being operably connected to a downhole device for operating the downhole device.

Description of Related Art

Several methods have been devised to place electronics, sensors, or controllable valve downhole along an oil production tubing string, but all such known devices typically use a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 445

internal or external cable along the tubing string to provide power and communications downhol It is, of course, highly undesirable and in practice difficult to use a cable along the tubing strin either integral to the tubing string or spaced in the annulus between the tubing string and th casing. The use of a cable presents difficulties for well operators while assembling and insertin the tubing string into a borehole. Additionally, the cable is subjected to corrosion and heavy wea due to movement of the tubing string within the borehole. An example of a downhol communication system using a cable is shown in PCT/EP97/01621.

U. S. Patent No. 4,839,644 describes a method and system for wireless two-wa communications in a cased borehole having a tubing string. However, this system describes communication scheme for coupling electromagnetic energy in a TEM mode using the annul between the casing and the tubing. This inductive coupling requires a substantially nonconductiv fluid such as crude oil in the annulus between the casing and the tubing. Therefore, the inventio described in U. S. Patent No. 4,839,644 has not been widely adopted as a practical scheme fo downhole two-way communication. Another system for downhole communication using mu pulse telemetry is described in U. S. Patent Nos. 4,648,471 and 5,887,657. Although mud puls telemetry can be successful at low data rates, it is of limited usefulness where high data rates ar required or where it is undesirable to have complex, mud pulse telemetry equipment downhol Other methods of communicating within a borehole are described in U.S. Patent Nos. 4,468,66 4,578,675; 4,739,325; 5,130,706; 5,467,083; 5,493,288; 5,576,703; 5,574,374; and 5,883,51 Similarly, several permanent downhole sensors and control systems have been described in U.S Pat. Nos. 4,972,704; 5,001,675; 5,134,285; 5,278,758; 5,662,165; 5,730,219; 5,934,371; an 5,941,307.

The Related Applications describe methods for providing electrical power and communications to various downhole devices in petroleum wells. These methods use either the production tubing as a supply and the casing as a return for the power and communications transmission circuit, or alternatively, the casing as the supply with a formation ground as the return. In either configuration, electrical losses in the transmission circuit are highly variable, depending on the specific conditions for a particular well. Power supplied along the casing with a formation ground as the return is especially susceptible to current losses. Electric current leakage generally occurs through the completion cement into the earthen formation. The more conductive the cement and earthen formation, the greater the current loss as the current travels along the casing.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 446

A need therefore exists to accommodate power losses which will be experienced when using a downhole wireless communication system. Since these losses place limits on the availabl amount of instantaneous electrical power, a need also exists for a system and method of storing energy for later use with downhole devices, especially high energy devices such as emergency shutoff valves, or other safety equipment. Although one solution to downhole energy storage problems could be provided by electrical storage such as capacitors, or chemical storage such as batteries, the limited lifetimes of such devices makes the use of the devices less than ideal in an operating petroleum well.

All references cited herein are incorporated by reference to the maximum extent allowabl by law. To the extent a reference may not be fully incorporated herein, it is incorporated b reference for background purposes and indicative of the knowledge of one of ordinary skill in th art.

BRIEF SUMMARY OF THE INVENTION

The problems presented in accommodating energy losses along a transmission path and in providing a usable source of instantaneous downhole energy are solved by the systems and methods of the present invention. In accordance with one embodiment of the present invention, a method for operating a downhole device in a borehole of a petroleum well is provided. The petroleum well includes a piping structure positioned within the borehole of the well. The metho includes delivering a time-varying current along the piping structure, the current being used to operate a motor. The motor drives a pump, which performs the step of pressuring a hydraulic fluid. Finally, the step of operating the downhole device is accomplished using the pressurized hydraulic fluid.

In another embodiment of the present invention, a petroleum well having a borehole and a piping structure positioned within the borehole is provided. The petroleum well includes a communications system and a hydraulic system. The communications system is operably associated with the piping structure of the well and transmits a time varying current along the piping structure. The hydraulic system is electrically connected to the piping structure and is configured to operate a downhole device.

In another embodiment of the present invention, a hydraulic actuation system includes a motor that is configured to receive a time varying current along a pipe member. A pump is operably connected to and is driven by the motor such that the pump pressurizes a hydraulic fluid.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 447

An actuator is hydraulically connected to the pump and is selectively driven by the pressurized hydraulic fluid supplied by the pump. The actuator is configured for operable attachment to a target device, the actuator operating the target device as the actuator is driven by the pressurized hydraulic fluid.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 is a schematic of a petroleum well having a wireless communication system and a hydraulic pressure system according to the present invention.

FIG. 2 is a schematic of an offshore petroleum well having a wireless communication system and a hydraulic pressure system according to the present invention.

FIG. 3 is an enlarged schematic of a piping structure of a petroleum well, the piping structure having an enlarged pod that houses a hydraulic pressure system according to the present invention.

FIG. 4 is an electrical and plumbing schematic of the hydraulic pressure system of FIG. 3.

FIG. 5 is an enlarged schematic of a piping structure of a petroleum well, the piping structure having an enlarged pod that houses a hydraulic adjustment system according to an alternate embodiment of the present invention.

FIG. 6 is an electrical and plumbing schematic of the hydraulic adjustment system of FIG. 5.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT

As used in the present application, a "piping structure" can be one single pipe, a tubing string, a well casing, a pumping rod, a series of interconnected pipes, rods, rails, trusses, lattices, supports, a branch or lateral extension of a well, a network of interconnected pipes, or other structures known to one of ordinary skill in the art. The preferred embodiment makes use of the invention in the context of an oil well where the piping structure comprises tubular, metallic, electrically-conductive pipe or tubing strings, but the invention is not so limited. For the present invention, at least a portion of the piping structure needs to be electrically conductive, such electrically conductive portion may be the entire piping structure (e.g., steel pipes, copper pipes) or a longitudinal extending electrically conductive portion combined with a longitudinally extending non-conductive portion. In other words, an electrically conductive piping structure is one that provides an electrical conducting path from one location where a power source is

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 448

electrically connected to another location where a device and/or electrical return is electrically connected. The piping structure will typically be conventional round metal tubing, but the cross-sectional geometry of the piping structure, or any portion thereof, can vary in shape (e.g., round, rectangular, square, oval) and size (e.g., length, diameter, wall thickness) along any portion of the piping structure.

A "valve" is any device that functions to regulate the flow of a fluid. Examples of valves include, but are not limited to, bellows-type gas-lift valves and controllable gas-lift valves, each c which may be used to regulate the flow of lift gas into a tubing string of a well. The internal workings of valves can vary greatly, and in the present application, it is not intended to limit the valves described to any particular configuration, so long as the valve functions to regulate flow. Some of the various types of flow regulating mechanisms include, but are not limited to, ball valv configurations, needle valve configurations, gate valve configurations, and cage valve configurations. Valves generally fall into one or the other of two classes: regulating valves intended to regulate flow continuously over a dynamic range from fully closed to fully open, and valves intended to be operated only fully open or fully closed, with intermediate positions considered transient. The latter class of valves may be operated to protect personnel or equipmen during scheduled maintenance or modification, or may form part of the emergency shut-in syster of a well, in which case they must be capable of operating rapidly and without lengthy preparatio Sub-surface safety valves are an example of this type of valve. Valves can be mounted downhole in a well in many different ways, some of which include tubing conveyed mounting configurations, side-pocket mandrel configurations, or permanent mounting configurations such a mounting the valve in an enlarged tubing pod.

The term "modem" is used generically herein to refer to any communications device for transmitting and/or receiving electrical communication signals via an electrical conductor (e.g., metal). Hence, the term is not limited to the acronym for a modulator (device that converts a voic or data signal into a form that can be transmitted)/demodulator (a device that recovers an original signal after it has modulated a high frequency carrier). Also, the term "modem" as used herein is not limited to conventional computer modems that convert digital signals to analog signals and vice versa (e.g., to send digital data signals over the analog Public Switched Telephone Network). For example, if a sensor outputs measurements in an analog format, then such measurements may only need to be modulated (e.g., spread spectrum modulation) and transmitted—hence no analog-

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 449

to-digital conversion is needed. As another example, a relay/slave modem or communication device may only need to identify, filter, amplify, and/or retransmit a signal received.

The term "processor" is used in the present application to denote any device that is capable of performing arithmetic and/or logic operations. The processor may optionally include a control unit, a memory unit, and an arithmetic and logic unit.

The term "sensor" as used in the present application refers to any device that detects, determines, monitors, records, or otherwise senses the absolute value of or a change in a physical quantity. Sensors as described in the present application can be used to measure temperature, pressure (both absolute and differential), flow rate, seismic data, acoustic data, pH level, salinity levels, valve positions, or almost any other physical data.

As used in the present application, "wireless" means the absence of a conventional, insulated wire conductor e.g. extending from a downhole device to the surface. Using the tubing and/or casing as a conductor is considered "wireless."

The term "electronics module" in the present application refers to a control device. Electronics modules can exist in many configurations and can be mounted downhole in many different ways. In one mounting configuration, the electronics module is actually located within a valve and provides control for the operation of a motor within the valve. Electronics modules can also be mounted external to any particular valve. Some electronics modules will be mounted within side pocket mandrels or enlarged tubing pockets, while others may be permanently attached to the tubing string. Electronics modules often are electrically connected to sensors and assist in relaying sensor information to the surface of the well. It is conceivable that the sensors associated with a particular electronics module may even be packaged within the electronics module. Finally, the electronics module is often closely associated with, and may actually contain, a modem for receiving, sending, and relaying communications from and to the surface of the well. Signals that are received from the surface by the electronics module are often used to effect changes within downhole controllable devices, such as valves. Signals sent or relayed to the surface by the electronics module generally contain information about downhole physical conditions supplied by the sensors.

In accordance with conventional terminology of oilfield practice, the descriptors "upper," "lower," "uphole," and "downhole" as used herein are relative and refer to distance along hole depth from the surface, which in deviated or horizontal wells may or may not accord with vertical elevation measured with respect to a survey datum.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 450

Referring to FIG. 1 in the drawings, a petroleum well 10 according to the present inventio is illustrated. Petroleum well 10 includes a borehole 11 extending from a surface 12 into a production zone 14 located downhole. A production platform 20 is located at surface 12 and includes a hanger 22 for supporting a casing 24 and a tubing string 26. Casing 24 is of the type conventionally employed in the oil and gas industry. The casing 24 is typically installed in sections and is cemented in borehole 11 during well completion. Tubing string 26, also referred t as production tubing, is generally conventional comprising a plurality of elongated tubular pipe sections joined by threaded couplings at each end of the pipe sections. Production platform 20 also includes a gas input throttle 30 to permit the input of compressed gas into an annular space 3 between casing 24 and tubing string 26. Conversely, output valve 32 permits the expulsion of oil and gas bubbles from an interior of tubing string 26 during oil production.

Petroleum well 10 includes a communication system 34 for providing power and two-way communications downhole in well 10. Communication system 34 includes a lower induction choke 42 that is installed on tubing string 26 to act as a series impedance to electric current flow. The size and material of lower induction choke 42 can be altered to vary the series impedance value; however, the lower induction choke 42 is made of a ferromagnetic material. Induction choke 42 is mounted concentric and external to tubing string 26, and is typically hardened with epoxy to withstand rough handling.

An insulating tubing joint 40 (also referred to as an electrically insulating joint) is positioned on tubing string 26 near the surface of the well. Insulating tubing joint 40, along with lower induction choke 42, provide electrical isolation for a section of tubing string 26 located between insulating tubing joint 40 and induction choke 42. The section of tubing string 26 between insulating tubing joint 40 and lower choke 42 may be viewed as a power and communications path. In alternative to or in addition to the insulating tubing joint 40, an upper induction choke (not shown) can be placed about the tubing string 26 or an insulating tubing hanger (not shown) could be employed.

A computer and power source 44 including a power supply 46 and a spread spectrum communications device 48 (e.g. modem) is disposed outside of borehole 11 at surface 12. The computer and power source 44 is electrically connected to tubing string 26 below insulating tubin joint 40 for supplying time varying current to the tubing string 26. A return feed for the current is attached to casing 24. In operation the use of tubing string 26 as a conductor is fairly lossy because of the often great lengths of tubing string along which current is supplied. However, the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 451

spread spectrum communications technique is tolerant of noise and low signal levels, and can operate effectively even with losses as high as -100db.

The method of electrically isolating a section of the tubing string as illustrated in FIG.1 is not the sole method of providing power and communications signals downhole. In the preferred embodiment of FIG. 1, power and communication signals are supplied on tubing string 26, with the electrical return being provided by casing 24. Instead, the electrical return could be provided by an earthen ground. An electrical connection to earthen ground could be provided by passing a wire through casing 24 or by connecting the wire to the tubing string below lower choke 42 (if the lower portion of the tubing string was grounded).

An alternative power and communications path could be provided by casing 24. In a configuration similar to that used with tubing string 26, a portion of casing 24 could be electrically isolated to provide a telemetry backbone for transmitting power and communication signals downhole. If induction chokes were used to isolate a portion of casing 24, the chokes would be disposed concentrically around the outside of the casing. Instead of using chokes with the casing 24, electrically isolating connectors could be used similar to insulating tubing joint 40. In embodiments using casing 24 to supply power and communications signals downhole, an electrical return could be provided either via the tubing string 26 or via an earthen ground.

A packer 49 is placed within casing 24 below lower induction choke 42. Packer 49 is located above production zone 14 and serves to isolate production zone 14 and to electrically connect metal tubing string 26 to metal casing 24. Typically, the electrical connections between tubing string 26 and casing 24 would not allow electrical signals to be transmitted or received up and down borehole 11 using tubing string 26 as one conductor and casing 24 as another conductor. However, the disposition of insulating tubing joint 40 and lower induction choke 42 create an electrically isolated section of the tubing string 26, which provides a system and method to provide power and communication signals up and down borehole 11 of petroleum well 10.

Referring to FIG. 2 in the drawings, an offshore petroleum well 60 is illustrated. Petroleum well 60 includes a main production platform 62 at an aqueous surface 63 anchored to a earthen floor 64 with support members 66. Petroleum well 60 has many similarities to petroleum well 10 of FIG. 1. The borehole 11 of petroleum well 60 begins at earthen floor 64. Casing 24 is positioned within borehole 11, and tubing hanger 22 provides downhole support for tubing string 26. One of the primary differences between petroleum well 10 and petroleum well 60 is that tubing string 26 in petroleum well 60 extends through water 67 before reaching borehole 11.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 452

Induction choke 42 is positioned on tubing string 26 just above a wellhead 68 at earthen floor 64. An insulating tubing joint (similar to insulating tubing joint 40, but not shown) is provided at a portion of the tubing string 26 on production platform 62. Time varying current is imparted to a section of tubing string 26 between the insulating tubing joint and induction choke 42 to supply power and communications at wellhead 68.

A person skilled in the art will recognize that under normal circumstances a short circuit would occur for current passed along tubing string 26 since the tubing string is surrounded by electrically conductive sea water. However, corrosion inhibiting coatings on tubing string 26 are generally non-conductive and can provide an electrically insulating "sheath" around the tubing string, thereby allowing current transfer even when tubing string 26 is immersed in water. In an alternative arrangement, power could be supplied to wellhead 68 by an insulated cable (not shown) and then supplied downhole in the same manner provided in petroleum well 10. In such an arrangement, the insulating tubing joint and induction choke 42 would be positioned within the borehole 11 of petroleum well 60.

Referring still to FIG. 2, but also to FIGS. 1 and 3 in the drawings, a hydraulic system 70 provided for operating a downhole device, or a target device (not shown). Hydraulic system 70 is disposed within an enlarged pod 72 on tubing string 26. In FIG. 3 the downhole device is a shut-off valve 74; however, a number of different downhole devices could be operated by hydraulic system 70. Shut-off valve 74 is driven incrementally by hydraulic fluid pressurized by a pump 76 An electric motor 78 is powered by time varying current passed along tubing string 26. Motor 78 is operably connected to pump 76 for driving the pump 76. The electric motor 78 driving hydraulic pump 76 consumes small amounts of power such that it may operate with the limited power available at depth in the well. By appropriate design of hydraulic pump 76 and other components of hydraulic system 70, especially in the design of seals that minimize hydraulic fluid leakage in these components, the low amount of available power does not restrict the hydraulic pressure that can be generated, but rather restricts the flow rate of the hydraulic fluid.

Referring now to FIG. 4 in the drawings, the plumbing and electrical connections for hydraulic system 70 are illustrated in more detail. In addition to pump 76 and motor 78, hydraulic system 70 includes a fluid reservoir 80, a pilot valve 82, a valve actuator 84, and the necessary tubing and hardware to route hydraulic fluid between these components. Reservoir 80 is hydraulically connected to pump 76 for supplying hydraulic fluid to the pump 76. Pilot valve 82 is hydraulically connected to pump 76, actuator 84, and reservoir 80. Pilot valve 82 selectively

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 453

routes pressurized hydraulic fluid to actuator 84 for operating the actuator 84. Actuator 84 includes a piston 86 having a first side 87 and a second side 88. Piston 86 is operably connected to valve 74 for opening and closing the valve 74. By selectively routing pressurized hydraulic fluid to different sides of piston 86, valve 74 can be selectively opened or closed. For example, in one configuration, hydraulic fluid might be routed to a chamber just above first side 87 of piston 86. The pressurized fluid would exert a force on piston 86, causing the piston 86 to move downward, thereby closing valve 74. Fluid in a chamber adjacent the second side 88 of piston 86 would be displaced into reservoir 80. In this configuration, valve 74 could be opened by adjusting pilot valve 82 such that pressurized hydraulic fluid is supplied to the chamber adjacent the second side 88 of piston 86. The pressurized fluid would exert an upward force on piston 86, thereby moving piston 86 upward and opening valve 74. Displaced hydraulic fluid in the chamber adjacent front side 87 would be routed to reservoir 80.

As previously mentioned, electric current is supplied to motor 78 along tubing string 26. A modem 89 is positioned within enlarged pod 72 for receiving signals from modem 48 at surface 12. Modem 89 is electrically connected to a controller 90 for controlling the operation of motor 78. Controller 90 is also electrically connected to pilot valve 82 for controlling operation of the pilot valve, thereby insuring that the valve properly routes hydraulic fluid from the pump 76 to the actuator 84 and the reservoir 80.

In operation, electric current is supplied downhole along tubing string 26 and is received by modem 89. Controller 90 receives instructions from modem 89 and routes power to motor 78. Controller 90 also establishes the setting for pilot valve 82 so that hydraulic fluid is properly routed throughout the hydraulic system 70. As motor 78 is powered, it drives pump 76 which draws hydraulic fluid from reservoir 80. Pump 76 pressurizes the hydraulic fluid, pushing the fluid into pilot valve 82. From pilot valve 82, the pressurized hydraulic fluid is selectively routed to one side of piston 86 to drive the actuator 84. Depending on the side of piston 86 to which fluid was delivered, valve 74 will be opened or closed. As the piston 86 moves, displaced hydraulic fluid is routed from actuator 84 to reservoir 80.

Hydraulic system 70 may also include a bottom hole pressure compensator 92 (see FIG. 3) to balance the static pressure of the hydraulic fluid circuit against the static pressure of downhole fluids in the well. Use of a pressure compensator minimizes differential pressure across any rotary or sliding seals between the hydraulic circuit and the well fluids if these seals are present in the design, and thus minimizes stress on such seals.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 454

Enlarged pod 72 is filled with oil, the pressure of which is balanced with the pressure of any fluid present in annulus 31. By porting one side of the pressure compensator 92 to the exteric of pod 72, the pressure of oil within the enlarged pod 72 can be matched to the pressure of fluid within the annulus 31. The adjustment of internal pod pressure allows many of the components o the hydraulic system 70 to operate more efficiently.

Referring now to FIGS. 5 and 6 in the drawings, an alternate embodiment for hydraulic system 70 is illustrated. The components for this hydraulic system are substantially similar to those illustrated in FIGS. 3 and 4. In this particular embodiment, however, an accumulator 96 is hydraulically connected between pump 76 and pilot valve 82 for collecting pressurized hydraulic fluid supplied by the pump 76. The control of hydraulic system 70 is identical to that previously described, except that accumulator 96 is now used to supply the pressurized hydraulic fluid to actuator 84. Accumulator 96 allows instantaneous hydraulic operations to be intermittently performed (e.g. quick opening or closing of a valve). This is in contrast to the previous embodiment, which used a pump to supply hydraulic fluid to the actuator 84 more gradually.

Accumulator 96 includes a piston 98 slidingly and sealingly disposed within a housing, th piston being biased in one direction by a spring 100. A compensator port 102 is disposed in the housing and allows pressurized oil within enlarged pod 72 to exert an additional force on piston 9 which is complementary to the force exerted by spring 100. Motor 78 and pump 76 charge accumulator 96 to a high pressure by pushing hydraulic fluid into a main chamber 104 against the biased piston 98. When the force exerted by hydraulic fluid within main chamber 104 equals the forces on the opposite side of piston 98, pump 76 ceases operation, and the hydraulic fluid is stored within accumulator 96 until needed.

The stored, pressurized hydraulic fluid is released under control of pilot valve 82 to drive actuator 84 and thus actuate the main valve 74. Because of the energy stored in the accumulator 96, valve 74 can be opened or closed immediately upon receipt of an open or close command. Accumulator 96 is sized to enable at least one complete operation (open or close) of valve 74. Thus the methods of the present invention provide for the successful operation of valves which require transient high transient power, such as sub-surface safety valves.

It will be clear that a variety of hydraulic devices may be substituted for shutoff valve 74, which has been described for illustrative purposes only. It should also be clear that communication system 34 and hydraulic system 70 provided by the present invention, while

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 455

located on tubing string 26 in the preceding description, could be disposed on casing 24 of the well, or any other piping structure associated with the well.

Even though many of the examples discussed herein are applications of the present invention in petroleum wells, the present invention also can be applied to other types of wells, including but not limited to water wells and natural gas wells.

One skilled in the art will see that the present invention can be applied in many areas where there is a need to provide a communication system and a hydraulic system within a borehole, well, or any other area that is difficult to access. Also, one skilled in the art will see tha the present invention can be applied in many areas where there is an already existing conductive piping structure and a need to route power and communications to a hydraulic system located proximate the piping structure. A water sprinkler system or network in a building for extinguishing fires is an example of a piping structure that may be already existing and may have same or similar path as that desired for routing power and communications to a hydraulic system. In such case another piping structure or another portion of the same piping structure may be used as the electrical return. The steel structure of a building may also be used as a piping structure and/or electrical return for transmitting power and communications to a hydraulic system in accordance with the present invention. The steel rebar in a concrete dam or a street may be used as a piping structure and/or electrical return for transmitting power and communications to a hydraulic system in accordance with the present invention. The transmission lines and network o piping between wells or across large stretches of land may be used as a piping structure and/or electrical return for transmitting power and communications to a hydraulic system in accordance with the present invention. Surface refinery production pipe networks may be used as a piping structure and/or electrical return for transmitting power and communications in accordance with the present invention. Thus, there are numerous applications of the present invention in many different areas or fields of use.

It should be apparent from the foregoing that an invention having significant advantages has been provided. While the invention is shown in only a few of its forms, it is not just limited but is susceptible to various changes and modifications without departing from the spirit thereof.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 456

CLAIMS

We claim:

1. A method of operating a downhole device in a petroleum well having a borehole and a piping structure positioned within the borehole, comprising the steps of:
delivering a time varying current along the piping structure to a downhole location;
pressurizing a hydraulic fluid using the time varying current at the downhole location; and
operating the downhole device using the pressurized hydraulic fluid.

2. The method according to claim 1, including the steps of:
operating a motor at the downhole location; and
driving a pump with said motor to pressurize the hydraulic fluid.

3. The method according to claim 1 wherein the delivering step further comprising:
impeding the time-varying current on the piping structure to define a conductive section; and
routing the time varying current along the conductive section of the piping structure.

4. The method according to claim 2 wherein the step of operating the downhole device further comprises the steps of:
providing an actuator operably connected to the downhole device and hydraulically connected to the pump; and
selectively driving the actuator with the pressurized hydraulic fluid such that the downhole device is actuated.

5. The method according to claim 4 wherein the step of selectively driving further comprises
providing a pilot valve hydraulically connected between the pump and the actuator; and
adjusting the pilot valve to selectively drive the actuator.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 457

6. The method according to claim 1 further comprising the step of:
storing hydraulic fluid in a reservoir; and
drawing hydraulic fluid from the reservoir.

7. The method according to claim 1 further comprising the steps of:
collecting pressurized hydraulic fluid in an accumulator; and
selectively releasing pressurized hydraulic fluid from the accumulator to operate the downhole device.

8. The method according to claim 1 further comprising:
collecting pressurized hydraulic fluid in an accumulator;
providing an actuator operably connected to the downhole device and hydraulically connected to the accumulator; and
selectively releasing pressurized hydraulic fluid from the accumulator to drive the actuator, thereby operating the downhole device.

9. The method according to claim 8 wherein the step of selectively releasing further comprises:
providing a pilot valve hydraulically connected between the accumulator and the actuator; and
adjusting the pilot valve to selectively drive the actuator.

10. The method according to claim 1 further comprising the steps of:
impeding the time varying current on the piping structure;
routing the time varying current along the piping structure to the downhole location;
providing an actuator operably connected to the downhole device and hydraulically connected to a pump; and
selectively operating a pilot valve hydraulically connected between the pump and the actuator to drive the actuator, thereby operating the downhole device.

11. The method according to claim 10 wherein the downhole device is a main valve and the actuator opens and closes the main valve.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 458

12. The method according to claim 1 further comprising the steps of:
impeding the time varying current on the piping structure;
routing the time varying current along the piping structure;
collecting pressurized hydraulic fluid in an accumulator;
providing an actuator operably connected to the downhole device and hydraulically connected to the accumulator; and
selectively operating a pilot valve hydraulically connected between the accumulator and the actuator to drive the actuator, thereby operating the downhole device.

13. The method according to claim 12 wherein the downhole device is a main valve and the actuator opens and closes the main valve.

14. A petroleum well having a borehole and a piping structure positioned within the borehole comprising:
a communications system operably associated with the piping structure for transmitting a time varying signal along the piping structure; and
a hydraulic system electrically connected to the piping structure and configured for connection to a downhole device, wherein the hydraulic system is configured to receive power from said time varying signal and to operate the downhole device

15. The petroleum well of claim 14 wherein the time varying signal includes a communications signal to selectively operate the downhole device.

16. The petroleum well of claim 14 wherein the communication system further comprises:
an impedance device positioned around the piping structure to define a conducting portion; and
wherein the time varying current is passed along the conducting portion of the piping structure.

17. The petroleum well of claim 14 wherein the downhole device is a downhole emergency shutoff valve.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 459

18. The petroleum well of claim 14 wherein the hydraulic system further comprises:
a motor for receiving the time varying current from the piping structure;
a pump for selectively pressurizing a hydraulic fluid, the pump being operably connected to and driven by the motor;
an actuator hydraulically connected to the pump and operably connected to the downhole device; and
wherein the pressurized hydraulic fluid is used to drive the actuator, thereby operating the downhole device.

19. The petroleum well of claim 14 wherein the hydraulic system further comprises:
a motor for receiving the time varying current from the piping structure;
a pump for selectively pressurizing a hydraulic fluid, the pump being operably connected to and driven by the motor;
a pilot valve hydraulically connected to the pump;
an actuator hydraulically connected to the pilot valve and operably connected to the downhole device; and
wherein the pilot valve selectively routes pressurized hydraulic fluid to the actuator, thereby driving the actuator and operating the downhole device.

20. The petroleum well of claim 19, wherein the downhole device is a valve.

21. The petroleum well of claim 14 wherein the hydraulic system further comprises:
a motor for receiving the time varying current from the piping structure;
a pump for selectively pressurizing a hydraulic fluid, the pump being operably connected to and driven by the motor;
an accumulator hydraulically connected to the pump for collecting pressurized hydraulic fluid;
an actuator hydraulically connected to the accumulator and operably connected to the downhole device; and
wherein the pressurized hydraulic fluid supplied by the accumulator drives the actuator thereby operating the downhole device.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 460

22. The petroleum well of claim 14 wherein the hydraulic system further comprises:
a motor for receiving the time varying current from the piping structure;
a pump for selectively pressurizing a hydraulic fluid, the pump being operably connected to and driven by the motor;
an accumulator hydraulically connected to the pump for collecting pressurized hydraulic fluid;
a pilot valve hydraulically connected to the accumulator;
an actuator hydraulically connected to the pilot valve and operably connected to the downhole device; and
wherein the pilot valve selectively routes pressurized hydraulic fluid to the actuator, thereby driving the actuator and operating the downhole device.

23. A hydraulic actuation system comprising:
a motor configured to receive a time varying signal delivered along a piping structure;
a pump for pressurizing a hydraulic fluid, the pump being operably connected to and being driven by the motor; and
an actuator hydraulically connected to the pump and configured for operable attachmen to a target device, wherein the actuator is selectively driven by the pressurized hydraulic fluid, thereby operating the target device.

24. The hydraulic actuation system according to claim 23, including:
an impedance device positioned around the piping structure to define a conducting portion; and
wherein the time varying current is passed along the conducting portion of the piping structure.

25. The hydraulic actuation system according to claim 23, wherein the time varying signal includes a communications signal to selectively operate said target device

26. The hydraulic actuation system according to claim 23 further comprising:
a pilot valve hydraulically connected between the pump and the actuator; and
wherein the pilot valve selectively routes pressurized hydraulic fluid to the actuator.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 461


27. The hydraulic actuation system according to claim 23 further comprising an accumulator hydraulically connected to the pump for collecting pressurized hydraulic fluid.

28. The hydraulic actuation system according to claim 23 further comprising:
an accumulator hydraulically connected to the pump for collecting pressurized hydraulic fluid; and
a pilot valve hydraulically connected between the accumulator and the actuator, wherei the pilot valve selectively routes pressurized hydraulic fluid to the actuator

29. The hydraulic actuation system according to claim 23 further comprising:
an accumulator hydraulically connected to the pump for collecting pressurized hydraulic fluid;
a pilot valve hydraulically connected between the accumulator and the actuator, wherei the pilot valve selectively routes pressurized hydraulic fluid to the actuator;
wherein an electrically insulating joint is positioned on the pipe member;
wherein an induction choke is positioned around the pipe member; and
wherein the time varying current is routed along the pipe member between the electrically insulating joint and the induction choke.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 462

FIG. 1


COMPUTER SYSTEM
44
46
MODEM
48
47
20
32
10
30
22
12
40
11
24
31
31
26
34
70
42
14
49





FIG. 2

FIG. 3







FIG. 4

FIG. 5






FIG. 6

INTERNATIONAL SEARCH REPORT

Internal Application No
PCT/US 01/06949

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 E21B34/06 E21B17/00 E21B47/12 F16K31/06

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 E21B F16K

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)
EPO-Internal, TULSA

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 5 257 663 A (MORRIS ARTHUR J ET AL) 2 November 1993 (1993-11-02) column 8, line 34-59; figure 3B	1,2,4, 6-8,23, 25,27
Y	column 10, line 5-15; figure 4C	3,5, 9-22,24, 26,28,29

Y	US 5 971 072 A (HUBER KLAUS B ET AL) 26 October 1999 (1999-10-26) column 9, line 7 -column 10, line 10; figures 11-13	5,9,12, 13,19, 20,22, 26,28,29

Y	EP 0 721 053 A (SHELL INT RESEARCH) 10 July 1996 (1996-07-10) column 4, line 31-44; figure 2	3,10-22, 24

	-/--	

[X] Further documents are listed in the continuation of box C.

[X] Patent family members are listed in annex.

° Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
21 May 2001	30/05/2001

Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL – 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3016	van Berlo, A

Form PCT/ISA/210 (second sheet) (July 1992)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 469

INTERNATIONAL SEARCH REPORT

Internal Application No
PCT/US 01/06949

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication,where appropriate, of the relevant passages	Relevant to claim No.
Y	US 3 837 618 A (JUHEL B) 24 September 1974 (1974-09-24) figures 1-4	29
A	US 5 358 035 A (GRUDZINSKI RICHARD) 25 October 1994 (1994-10-25) column 3, line 13-23 column 4, line 4-29	1,14,23
A	EP 0 919 696 A (HALLIBURTON ENERGY SERV INC) 2 June 1999 (1999-06-02) abstract; figures 1-3,5,7	1
A	EP 0 972 909 A (HALLIBURTON ENERGY SERV INC) 19 January 2000 (2000-01-19) column 1, line 40-51	1
A	US 5 941 307 A (TUBEL PAULO) 24 August 1999 (1999-08-24) column 21, line 57 -column 22, line 56	1
A	US 3 732 728 A (FITZPATRICK J) 15 May 1973 (1973-05-15) column 1, line 66 -column 2, line 2 column 10, line 26 -column 11, line 13	14

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 470

INTERNATIONAL SEARCH REPORT

ation on patent family members

Internat Application No
PCT/US 01/06949

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
US 5257663 A	02-11-1993	US 5236047 A	17-08-1993
		GB 2260352 A,B	14-04-1993
		GB 2264134 A,B	18-08-1993
		GB 2264135 A,B	18-08-1993
		GB 2264136 A,B	18-08-1993
		GB 2264137 A	18-08-1993
		GB 2264138 A,B	18-08-1993
		NO 304475 B	21-12-1998
		US 5226491 A	13-07-1993
		US 5230383 A	27-07-1993
		US 5207272 A	04-05-1993
US 5971072 A	26-10-1999	NONE	
EP 0721053 A	10-07-1996	BR 9606966 A	04-11-1997
		CA 2208661 A	11-07-1996
		DE 69600520 D	17-09-1998
		DE 69600520 T	28-01-1999
		DK 800614 T	28-06-1999
		WO 9621085 A	11-07-1996
		EP 0800614 A	15-10-1997
		NO 973088 A	02-07-1997
		US 5745047 A	28-04-1998
US 3837618 A	24-09-1974	NONE	
US 5358035 A	25-10-1994	FR 2695450 A	11-03-1994
		CA 2105526 A	08-03-1994
		GB 2270707 A,B	23-03-1994
EP 0919696 A	02-06-1999	US 6144316 A	07-11-2000
		NO 985279 A	02-06-1999
EP 0972909 A	19-01-2000	US 6160492 A	12-12-2000
		NO 993514 A	18-01-2000
US 5941307 A	24-08-1999	US 5732776 A	31-03-1998
		US 6192988 B	27-02-2001
		AU 708330 B	05-08-1999
		AU 4980696 A	27-08-1996
		AU 5022396 A	27-08-1996
		CA 2187422 A	15-08-1996
		CA 2187423 A	15-08-1996
		GB 2302114 A,B	08-01-1997
		GB 2302432 A	15-01-1997
		NO 960518 A	12-08-1996
		NO 960527 A	12-08-1996
		US 6192980 B	27-02-2001
		WO 9624751 A	15-08-1996
		WO 9624747 A	15-08-1996
		US 6176312 B	23-01-2001
		US 5975204 A	02-11-1999
US 3732728 A	15-05-1973	NONE	

Form PCT/ISA/210 (patent family annex) (July 1992)

PATENT COOPERATION TREATY

From the INTERNATIONAL SEARCHING AUTHORITY

To:

PATTERSON B. TODD

PATTERSON & SHERIDAN, LLP 3040 POST OAK BLVD. SUITE 1500 HOUSTON TX 77056-6582 USA

PCT

NOTIFICATION OF TRANSMITTAL OF THE INTERNATIONAL SEARCH REPORT AND THE WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY, OR THE DECLARATION

(PCT Rule 44.1)

	Date of mailing *(day/month/year)* 14 MARCH 2013 (14.03.2013)
Applicant's or agent's file reference SAFO0012PC03	**FOR FURTHER ACTION** See paragraphs 1 and 4 below
International application No. **PCT/US2012/061313**	International filing date *(day/month/year)* **22 OCTOBER 2012 (22.10.2012)**
Applicant **SAFOCO, INC. et al**	

1. ☒ The applicant is hereby notified that the international search report and the written opinion of the International Searching Authority have been established and are transmitted herewith.

Filing of amendments and statement under Article 19:

The applicant is entitled, if he so wishes, to amend the claims of the international application (see Rule 46):

When? The time limit for filing such amendments is normally two months from the date of transmittal of the international search report.

Where? Directly to the International Bureau of WIPO, 34 chemin des Colombettes 1211 Geneva 20, Switzerland, Facsimile No.: +41 22 338 82 70

For more detailed instructions, see *PCT Applicant's Guide*, International Phase, paragraphs 9.004 . 9.011.

2. ☐ The applicant is hereby notified that no international search report will be established and that the declaration under Article 17(2)(a) to that effect and the written opinion of the International Searching Authority are transmitted herewith.

3. ☐ **With regard to any protest** against payment of (an) additional fee(s) under Rule 40.2, the applicant is notified that:

☐ the protest together with the decision thereon has been transmitted to the International Bureau together with any request to forward the texts of both the protest and the decision thereon to the designated Offices.

☐ no decision has been made yet on the protest; the applicant will be notified as soon as a decision is made.

4. **Reminders**

The applicant may submit comments on an informal basis on the written opinion of the International Searching Authority to the International Bureau. The International Bureau will send a copy of such comments to all designated Offices unless an international preliminary examination report has been or is to be established. Following the expiration of 30 months from the priority date, these comments will also be made available to the public.

Shortly after the expiration of **18 months** from the priority date, the international application will be published by the International Bureau. If the applicant wishes to avoid or postpone publication, a notice of withdrawal of the international application, or of the priority claim, must reach the International Bureau before the completion of the technical preparations for international publication (Rules 90bis.1 and 90bis.3).

Within **19 months** from the priority date, but only in respect of some designated Offices, a demand for international preliminary examination must be filed if the applicant wishes to postpone the entry into the national phase **until 30 months** from the priority date (in some Offices even later); otherwise, the applicant must, **within 20 months** from the priority date, perform the prescribed acts for entry into the national phase before those designated Offices.

In respect of other designated Offices, the time limit of **30 months** (or later) will apply even if no demand is filed within 19months.

For details about the applicable time limits, Office by Office, see www.wipo.int/pct/en/texts/time_limits.html and the PCT Applicant's Guide, National Chapters.

Name and mailing address of the ISA/KR Korean Intellectual Property Office 189 Cheongsa-ro, Seo-gu, Daejeon Metropolitan City, 302-701, Republic of Korea Facsimile No. 82-42-472-7140	Authorized officer COMMISSIONER MAR 20 2013 Telephone No. 82-42-481-8753

Form PCT/ISA/220 (July 2010)

* Attention

Copies of the documents cited in the international search report can be searched in the following Korean Intellectual Property Office English website for three months from the date of mailing of the international search report.

http://www.kipo.go.kr/en/ => PCT Services => PCT Services

ID : PCT international application number
PW : **35YC59VE**

Inquiries related to PCT International Search Report or Written Opinion prepared by KIPO as an International Searching Authority can be answered not only by KIPO but also through IPKC (Intellectual Property Korea Center), located in Vienna, VA, which functions as a PCT Help Desk for PCT applicants.

Homepage: http://www.ipkcenter.com
Email: ipkc@ipkcenter.com
Phone: +1 703 388 1066
Fax: +1 703 388 1084

Notes to Form PCT/ISA/220 (July 2010)

PATENT COOPERATION TREATY

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference	FOR FURTHER ACTION	see Form PCT/ISA/220 as well as, where applicable, item 5 below.
SAFO0012PC03		
International application No.	International filing date *(day/month/year)*	(Earliest) Priority Date *(day/month/year)*
PCT/US2012/061313	**22 OCTOBER 2012 (22.10.2012)**	25 OCTOBER 2011 (25.10.2011)

Applicant

SAFOCO, INC. et al

This International search report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This international search report consists of a total of 4 sheets.

☒ It is also accompanied by a copy of each prior art document cited in this report.

1. **Basis of the report**
   a. With regard to the **language**, the international search was carried out on the basis of :
      ☒ the international application in the language in which it was filed
      ☐ a translation of the international application into _____, which is the language of a translation furnished for the purposes of international search (Rules 12.3(a) and 23.1(b))
   b. ☐ This international search report has been established taking into account the **rectification of an obvious mistake** authorized by or notified to this Authority under Rule 91 (Rule 43.6*bis*(a)).
   c. ☐ With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, see Box No. I.
2. ☐ **Certain claims were found unsearchable** (See Box No. II)
3. ☐ **Unity of invention is lacking** (See Box No. III)
4. With regard to the **title,**
   ☒ the text is approved as submitted by the applicant.
   ☐ the text has been established by this Authority to read as follows:
5. With regard to the **abstract,**
   ☒ the text is approved as submitted by the applicant.
   ☐ the text has been established, according to Rule 38.2, by this Authority as it appears in Box No. IV. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.
6. With regard to the drawings,
   a. the figure of the **drawings** to be published with the abstract is Figure No. 13
      ☒ as suggested by the applicant.
      ☐ as selected by this Authority, because the applicant failed to suggest a figure.
      ☐ as selected by this Authority, because this figure better characterizes the invention.
   b. ☐ none of the figure is to be published with the abstract.

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US2012/061313

A. CLASSIFICATION OF SUBJECT MATTER

E21B 34/16(2006.01)i, E21B 34/06(2006.01)i

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

E21B 34/16; E21B 43/12; E21B 34/06; E21B 43/16; F16K 31/44; B01V 3/00; E21B 17/00

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Korean utility models and applications for utility models

Japanese utility models and applications for utility models

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

eKOMPASS(KIPO internal) & keywords: controller assembly, valve assembly, compressor assembly, and power source

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	WO 01-65061 A1 (SHELL OIL COMPANY et al.) 07 September 2001 See abstract, page 9, lines 31-34, page 11, line 19 - page 12, line 31, and figures 1,3,4.	1-10
Y	US 6296052 B1 (SIDWELL, HERBERT R.) 02 October 2001 See abstract, column 3, lines 32-65, and figure 5.	1-10
Y	US 2004-0135112 A1 (GREEB et al.) 15 July 2004 See abstract, paragraph [0034], and figure 1.	10
A	US 6633236 B2 (VINEGAR et al.) 14 October 2003 See abstract, column 10, lines 4-14, and figure 1.	1-10
A	US 2010-0025045 A1 (LAKE et al.) 04 February 2010 See abstract, claim 1, and figure 2.	1-10

☐ Further documents are listed in the continuation of Box C. ☒ See patent family annex.

* Special categories of cited documents:
"A" document defining the general state of the art which is not considered to be of particular relevance
"E" earlier application or patent but published on or after the international filing date
"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of citation or other special reason (as specified)
"O" document referring to an oral disclosure, use, exhibition or other means
"P" document published prior to the international filing date but later than the priority date claimed
"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents,such combination being obvious to a person skilled in the art
"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
13 MARCH 2013 (13.03.2013)	**14 MARCH 2013 (14.03.2013)**
Name and mailing address of the ISA/KR Facsimile No. 82-42-472-7140	Authorized officer SONG, Ho Keun Telephone No. 82-42-481-5580

Form PCT/ISA/210 (second sheet) (July 2009)

INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No.
PCT/US2012/061313

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
WO 01-65061 A1	07.09.2001	AU 2001-243412 B2	14.10.2004
		AU 4341201 A	12.09.2001
		BR 0108895 A	29.06.2004
		BR 0108895 B1	25.01.2011
		CA 2401707 A1	07.09.2001
		CA 2401707 C	03.11.2009
		EP 1259705 A1	27.11.2002
		MX PA02008578 A	14.04.2003
		NO 20024138 A	01.11.2002
		NO 20024138 D0	30.08.2002
		NO 324777 B1	10.12.2007
		OA 12390 A	18.04.2006
		RU 2002126206 A	20.02.2004
		RU 2260676 C2	20.09.2005
		US 2003-0051881 A1	20.03.2003
		US 6851481 B2	08.02.2005
		WO 01-65061 A1	07.09.2001
US 6296052 B1	02.10.2001	WO 03-012256 A1	13.02.2003
US 2004-0135112 A1	15.07.2004	AT 480693 T	15.09.2010
		AU 2004-204467 A1	29.07.2004
		AU 2004-204467 B2	10.04.2008
		CA 2512615 A1	29.07.2004
		CA 2512615 C	03.01.2012
		CN 1748072 A	15.03.2006
		CN 1748072 C0	15.03.2006
		DE 602004029007 D1	21.10.2010
		EP 1585885 A2	19.10.2005
		EP 1585885 A4	02.08.2006
		EP 1585885 B1	08.09.2010
		EP 2258921 A1	08.12.2010
		EP 2258921 A8	30.03.2011
		ES 2351123 T3	31.01.2011
		JP 04526531 B2	11.06.2010
		JP 2006-519323 A	24.08.2006
		MX PA05007432 A	07.04.2006
		US 2004-0134665 A1	15.07.2004
		US 6953084 B2	11.10.2005
		US 7059418 B2	13.06.2006
		WO 2004-063607 A2	29.07.2004
		WO 2004-063607 A3	12.05.2005
US 6633236 B2	14.10.2003	US 2002-0126021 A1	12.09.2002
		US 2004-0263350 A1	30.12.2004
		US 6958704 B2	25.10.2005
US 2010-0025045 A1	04.02.2010	AU 2009-276908 A1	04.02.2010
		GB 201101638 D0	16.03.2011

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 476

INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No.
PCT/US2012/061313

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
		GB 2474189 A	06.04.2011
		NO 20110224 A	09.02.2011
		US 7967074 B2	28.06.2011
		WO 2010-014398 A2	04.02.2010
		WO 2010-014398 A3	29.04.2010

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 477

PATENT COOPERATION TREATY

From the
INTERNATIONAL SEARCHING AUTHORITY

To:
PATTERSON B. TODD

PATTERSON & SHERIDAN, LLP 3040 POST OAK BLVD., SUITE 1500 HOUSTON TX 77056-6582 USA

PCT

WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY

(PCT Rule 43bis.1)

	Date of mailing *(day/month/year)* **14 MARCH 2013 (14.03.2013)**
Applicant's or agent's file reference SAFO0012PC03	**FOR FURTHER ACTION** See paragraph 2 below

International application No.	International filing date *(day/month/year)*	Priority date *(day/month/year)*
PCT/US2012/061313	**22 OCTOBER 2012 (22.10.2012)**	25 OCTOBER 2011 (25.10.2011)

International Patent Classification (IPC) or both national classification and IPC

E21B 34/16(2006.01)i, E21B 34/06(2006.01)i

Applicant

SAFOCO, INC. et al

1. This opinion contains indications relating to the following items:

- [X] Box No. I Basis of the opinion
- [ ] Box No. II Priority
- [ ] Box No. III Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- [ ] Box No. IV Lack of unity of invention
- [X] Box No. V Reasoned statement under Rule 43bis.1(a)(i) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- [ ] Box No. VI Certain documents cited
- [ ] Box No. VII Certain defects in the international application
- [X] Box No. VIII Certain observations on the international application

2. **FURTHER ACTION**

If a demand for international preliminary examination is made, this opinion will be considered to be a written opinion of the International Preliminary Examining Authority ("IPEA") except that this does not apply where the applicant chooses an Authority other than this one to be the IPEA and the chosen IPEA has notified the International Bureau under Rule 66.1bis(b) that written opinions of this International Searching Authority will not be so considered.

If this opinion is, as provided above, considered to be a written opinion of the IPEA, the applicant is invited to submit to the IPEA a written reply together, where appropriate, with amendments, before the expiration of 3 months from the date of mailing of Form PCT/ISA/220 or before the expiration of 22 months from the priority date, whichever expires later.
For further options, see Form PCT/ISA/220.

Name and mailing address of the ISA/KR	Date of completion of this opinion	Authorized officer
Facsimile No. 82-42-472-7140	13 MARCH 2013 (13.03.2013)	SONG, Ho Keun Telephone No.82-42-481-5580

Form PCT/ISA/237 (cover sheet) (July 2011)

WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY

International application No.
PCT/US2012/061313

Box No. I Basis of this opinion

1. With regard to the **language**, this opinion has been established on the basis of:

   ☒ the international application in the language in which it was filed

   ☐ a translation of the international application into _____, which is the language of a translation furnished for the purposes of international search (Rules 12.3(a) and 23.1(b))

2. ☐ This opinion has been established taking into account the **rectification of an obvious mistake** authorized by or notified to this Authority under Rule 91 (Rule 43*bis*.1(a))

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, this opinion has been established on the basis of:

   a. a sequence listing filed or furnished
      ☐ on paper
      ☐ in electronic form

   b. time of filing or furnishing
      ☐ contained in the international application as filed.
      ☐ filed together with the international application in electronic form.
      ☐ furnished subsequently to this Authority for the purposes of search.

4. ☐ In addition, in the case that more than one version or copy of a sequence listing has been filed or furnished, the required statements that the information in the subsequent or additioanl copies is identical to that in the application as filed or does not go beyond the application as filed, as appropriate, were furnished.

5. Additional comments:

WRITTEN OPINION OF THE INTERNATIONAL SEARCHING AUTHORITY

International application No.
PCT/US2012/061313

Box No. V Reasoned statement under Rule 43bis.1(a)(i) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Claims	1-10	YES
	Claims	NONE	NO
Inventive step (IS)	Claims	NONE	YES
	Claims	1-10	NO
Industrial applicability (IA)	Claims	1-10	YES
	Claims	NONE	NO

2. Citations and explanations :

Reference is made to the following documents:

D1: WO 01-65061 A1 (SHELL OIL COMPANY et al.) 07 September 2001
D2: US 6296052 B1 (SIDWELL, HERBERT R.) 02 October 2001
D3: US 2004-0135112 A1 (GREEB et al.) 15 July 2004
D4: US 6633236 B2 (VINEGAR et al.) 14 October 2003
D5: US 2010-0025045 A1 (LAKE et al.) 04 February 2010

1. Novelty and Inventive Step

1.1 Independent Claim 1
D1, which is considered to be the closest prior art to the subject matter of claim 1, discloses a hydraulic actuation system comprising: an enlarged pod (72), a controller (90), pilot valves (82), and a modem (89) (see page 12, lines 1-31). Claim 1 differs from D1 in that a compressor assembly supplies a pneumatic fluid to a safety valve, whereas the pump (76) of D1 supplies a hydraulic fluid to a shut-off valve (74) (see page 11, lines 19-25). However, D2 discloses a compressor (66) which supplies a gas to pneumatic valves (62,74). Accordingly, claim 1 would have been obvious over D1 in view of D2. Therefore, claim 1 lacks an inventive step under PCT Article 33(3).

(Continued on Supplemental Box)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 480

WRITTEN OPINION OF THE
INTERNATIONAL SEARCHING AUTHORITY

International application No.
PCT/US2012/061313

Box No. VIII Certain observations on the international application

The following observations on the clarity of the claims, description, and drawings or on the question whether the claims are fully supported by the description, are made:

Claim 4 relates to a control system for controlling a safety valve, but claim 5 dependent on claim 4 relates to the system. As claim 5 does not clearly define the matter for which protection is sought, this claim does not meet the requirements of PCT Article 6.

Claim 7 relates to a method for controlling a safety valve, but claim 9 dependent on claim 7 relates to the control system. As claim 9 does not clearly define the matter for which protection is sought, this claim does not meet the requirements of PCT Article 6.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 481

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of :

Box No. V

1.2 Dependent Claims 2-5

1.2.1 Concerning Claim 2
The additional feature of claim 2 relates to a filter for filtering a pneumatic fluid, which is well known in this technical field. Therefore, claim 2 lacks an inventive step under PCT Article 33(3).

1.2.2 Concerning Claim 3
The additional feature of claim 3 is identical to a gas disclosed in D2 (see column 3, lines 32-65). Accordingly, claim 3 would have been obvious over D1 in view of D2. Therefore, claim 3 lacks an inventive step under PCT Article 33(3).

1.2.3 Concerning Claim 4
The additional feature of claim 4 is identical to a propane starter tank supply disclosed in D2 (see column 3, lines 32-65). Accordingly, claim 4 would have been obvious over D1 in view of D2. Therefore, claim 4 lacks an inventive step under PCT Article 33(3).

1.2.4 Concerning Claim 5
The additional feature of claim 5 is identical to the feature of D1 in that a computer and a spread spectrum communication device (48) are disposed at surface (12) (see page 9, lines 31-34). Accordingly, claim 5 would have been obvious over D1 in view of D2. Therefore, claim 5 lacks an inventive step under PCT Article 33(3).

(Continued on Supplemental Box)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 482

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of:

Box No. V

1.3 Independent Claim 6
D1, which is considered to be the closest prior art to the subject matter of claim 6, discloses a hydraulic actuation method comprising the steps of: positioning a hydraulic system (70) including a controller (90), a pump (76), and a modem (89); receiving an instruction from the modem (89); and closing a valve (74) (see page 12, lines 1-31). Claim 6 differs from D1 in that it comprises the step of supplying a pneumatic fluid to a safety valve using a compressor assembly, whereas D1 comprises the step of supplying a hydraulic fluid to a shut-off valve (74) using a pump (76) (see page 11, lines 19-25). However, D2 discloses the step of supplying a gas to pneumatic valves (62,74) using a compressor (66). Accordingly, claim 6 would have been obvious over D1 in view of D2. Therefore, claim 6 lacks an inventive step under PCT Article 33(3).

1.4 Dependent Claims 7-10

1.4.1 Concerning Claim 7
The additional feature of claim 7 relates to filtering a pneumatic fluid, which is well known in this technical field. Therefore, claim 7 lacks an inventive step under PCT Article 33(3).

1.4.2 Concerning Claim 8
The additional feature of claim 8 is identical to a gas disclosed in D2 (see column 3, lines 32-65). Accordingly, claim 8 would have been obvious over D1 in view of D2. Therefore, claim 8 lacks an inventive step under PCT Article 33(3).

(Continued on Supplemental Box)

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 483

Supplemental Box

In case **the space in any of the preceding boxes is not sufficient.**
Continuation of :

Box No. V

1.4.3 Concerning Claim 9
The additional feature of claim 9 is identical to a propane starter tank supply disclosed in D2 (see column 3, lines 32-65). Accordingly, claim 9 would have been obvious over D1 in view of D2. Therefore, claim 9 lacks an inventive step under PCT Article 33(3).

1.4.4 Concerning Claim 10
The additional feature of claim 10 is identical to a solar panel (24) disclosed in D3 (see paragraph [0034]). Accordingly, claim 10 would have been obvious over D1 in view of D2 and D3. Therefore, claim 10 lacks an inventive step under PCT article 33(3).

2. Industrial Applicability
Claims 1 - 10 are industrially applicable under PCT Article 33(4).

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 484

Electronic Acknowledgement Receipt

EFS ID:	15407105
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Barden Todd Patterson/katey hines
Filer Authorized By:	Barden Todd Patterson
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	02-APR-2013
Filing Date:	25-MAY-2012
Time Stamp:	10:56:30
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	SAFO0012USP1_IDS.pdf	611969 d6747408022fd11ec95a3cb7ed0c8448719 17120	no	4

Warnings:	
Information:	

2	Foreign Reference	WO0165061.pdf	1504234 f513d0a956b48d47d4e8ec6c6a345e76805bb855	no	31
Warnings:					
Information:					
3	Non Patent Literature	ISR_and_WO_14MAR2013.pdf	442727 d0f1b38ff098b075bd3182f2e89943c5cd0a617e	no	13
Warnings:					
Information:					
			Total Files Size (in bytes):	2558930	

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111
If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371
If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office
If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NUMBER	FILING OR 371(C) DATE	FIRST NAMED APPLICANT	ATTY. DOCKET NO./TITLE
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1

CONFIRMATION NO. 9598

26290
PATTERSON & SHERIDAN, L.L.P.
3040 Post Oak Blvd.
Suite 1500
Houston, TX 77056

PUBLICATION NOTICE

OC000000056505605

Title:SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

Publication No.US-2012-0227983-A1
Publication Date:09/13/2012

NOTICE OF PUBLICATION OF APPLICATION

The above-identified application will be electronically published as a patent application publication pursuant to 37 CFR 1.211, et seq. The patent application publication number and publication date are set forth above.

The publication may be accessed through the USPTO's publically available Searchable Databases via the Internet at www.uspto.gov. The direct link to access the publication is currently http://www.uspto.gov/patft/.

The publication process established by the Office does not provide for mailing a copy of the publication to applicant. A copy of the publication may be obtained from the Office upon payment of the appropriate fee set forth in 37 CFR 1.19(a)(1). Orders for copies of patent application publications are handled by the USPTO's Office of Public Records. The Office of Public Records can be reached by telephone at (703) 308-9726 or (800) 972-6382, by facsimile at (703) 305-8759, by mail addressed to the United States Patent and Trademark Office, Office of Public Records, Alexandria, VA 22313-1450 or via the Internet.

In addition, information on the status of the application, including the mailing date of Office actions and the dates of receipt of correspondence filed in the Office, may also be accessed via the Internet through the Patent Electronic Business Center at www.uspto.gov using the public side of the Patent Application Information and Retrieval (PAIR) system. The direct link to access this status information is currently http://pair.uspto.gov/. Prior to publication, such status information is confidential and may only be obtained by applicant using the private side of PAIR.

Further assistance in electronically accessing the publication, or about PAIR, is available by calling the Patent Electronic Business Center at 1-866-217-9197.

Office of Data Managment, Application Assistance Unit (571) 272-4000, or (571) 272-4200, or 1-888-786-0101

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 487

PTO/SB/08a (01-10)
Approved for use through 07/31/2012. OMB 0651-0031
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (**Not for submission under 37 CFR 1.99**)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

U.S.PATENTS						
Examiner Initial*	Cite No	Patent Number	Kind Code[1]	Issue Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	3788341		1974-01-29	Athy, Jr. et al.	
	2	4213480		1980-07-22	Orum et al.	
	3	4461449		1984-07-24	Turner	
	4	4527429		1985-07-09	Combest et al.	
	5	4667570		1987-05-26	Jensen, Jr. et al.	
	6	5097857		1992-03-24	Mayhew	
	7	5132904		1992-07-21	Lamp	
	8	5273113		1993-12-28	Schultz	

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

	9	5275086		1994-01-04	Stallings, Jr.	
	10	5335730		1994-08-09	Cotham, III	
	11	5526883		1996-06-18	Breaux	
	12	6349772		2002-02-26	Mullen et al.	
	13	6435282		2002-08-20	Robison et al.	
	14	6450477		2002-09-17	Young	
	15	6854704		2005-02-15	Young	
	16	7004445		2006-02-28	Lymberopoulos	
	17	7231971		2007-06-19	McCalvin	
	18	RE39583		2007-04-24	Upchurch	
	19	5490564		1996-02-13	Schultz et al.	

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

	20	6412510		2002-07-02	Johnson	
	21	3741116		1973-06-26	Green et al.	
	22	6772718		2004-08-10	Allen	

If you wish to add additional U.S. Patent citation information please click the Add button.

U.S.PATENT APPLICATION PUBLICATIONS

Examiner Initial*	Cite No	Publication Number	Kind Code[1]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear
	1	20020124889	A1	2002-09-12	Sundararajan	
	2	20050087712	A1	2005-04-28	Lymberopoulos	
	3	20110036415	A1	2011-02-17	Lymberopoulos	
	4	20110240126	A1	2011-10-06	Lymberopoulos et al.	
	5	20060159569	A1	2006-07-20	Biester	
	6	20020112632		2002-08-22	Faibish	

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

	7	20050236594		2005-10-27	Lilly et al.	

If you wish to add additional U.S. Published Application citation information please click the Add button.

FOREIGN PATENT DOCUMENTS

Examiner Initial*	Cite No	Foreign Document Number[3]	Country Code[2]	Kind Code[4]	Publication Date	Name of Patentee or Applicant of cited Document	Pages,Columns,Lines where Relevant Passages or Relevant Figures Appear	T[5]
	1	07-042856	JP	A	1995-02-10	Nakai, Kazuo		☐
	2	02/25612	WO	A1	2002-03-28	Keyspan Energy		☐
	3	0 647 770	EP	A2	1995-04-12	Ford Motor Co et al.		☐

If you wish to add additional Foreign Patent Document citation information please click the Add button

NON-PATENT LITERATURE DOCUMENTS

Examiner Initials*	Cite No	Include name of the author (in CAPITAL LETTERS), title of the article (when appropriate), title of the item (book, magazine, journal, serial, symposium, catalog, etc), date, pages(s), volume-issue number(s), publisher, city and/or country where published.	T[5]
	1	Versa Series B Valves Bulletin B-2011; Versa Products Company, Inc.; 2011, 8 Pages.	☐
	2	Rotowink Indicators; Norgren 1996; 2 Pages.	☐

If you wish to add additional non-patent literature document citation information please click the Add button

EXAMINER SIGNATURE

Examiner Signature		Date Considered	

*EXAMINER: Initial if reference considered, whether or not citation is in conformance with MPEP 609. Draw line through a citation if not in conformance and not considered. Include copy of this form with next communication to applicant.

EFS Web 2.1.17

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

[1] See Kind Codes of USPTO Patent Documents at www.USPTO.GOV or MPEP 901.04. [2] Enter office that issued the document, by the two-letter code (WIPO Standard ST.3). [3] For Japanese patent documents, the indication of the year of the reign of the Emperor must precede the serial number of the patent document. [4] Kind of document by the appropriate symbols as indicated on the document under WIPO Standard ST.16 if possible. [5] Applicant is to place a check mark here if English language translation is attached.

INFORMATION DISCLOSURE STATEMENT BY APPLICANT (Not for submission under 37 CFR 1.99)		
	Application Number	13480704
	Filing Date	2012-05-25
	First Named Inventor	David Lymberopoulos
	Art Unit	N/A
	Examiner Name	Not Yet Assigned
	Attorney Docket Number	SAFO/0012USP1

CERTIFICATION STATEMENT

Please see 37 CFR 1.97 and 1.98 to make the appropriate selection(s):

☐ That each item of information contained in the information disclosure statement was first cited in any communication from a foreign patent office in a counterpart foreign application not more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(1).

OR

☐ That no item of information contained in the information disclosure statement was cited in a communication from a foreign patent office in a counterpart foreign application, and, to the knowledge of the person signing the certification after making reasonable inquiry, no item of information contained in the information disclosure statement was known to any individual designated in 37 CFR 1.56(c) more than three months prior to the filing of the information disclosure statement. See 37 CFR 1.97(e)(2).

☐ See attached certification statement.

☐ The fee set forth in 37 CFR 1.17 (p) has been submitted herewith.

☒ A certification statement is not submitted herewith.

SIGNATURE

A signature of the applicant or representative is required in accordance with CFR 1.33, 10.18. Please see CFR 1.4(d) for the form of the signature.

Signature	B. Todd Patterson	Date (YYYY-MM-DD)	09/07/2012
Name/Print	B. Todd Patterson	Registration Number	37906

This collection of information is required by 37 CFR 1.97 and 1.98. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 1 hour to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

(19)日本国特許庁（ＪＰ）　(12) **公開特許公報（Ａ）**　(11)特許出願公開番号

特開平7－42856

(43)公開日　平成７年(1995)２月10日

(51)Int.Cl.[6]	識別記号	庁内整理番号	ＦＩ	技術表示箇所
Ｆ１６Ｋ　17/06	Ａ	7504－3Ｈ		
Ｇ０１Ｌ　7/00	Ｄ			

審査請求　未請求　請求項の数１　ＯＬ　（全　６　頁）

(21)出願番号　特願平5－190568

(22)出願日　平成５年(1993)７月30日

(71)出願人　591238866
中井　一夫
兵庫県揖保郡揖保川町正条139－16

(72)発明者　中井　一夫
兵庫県揖保郡揖保川町正条139－16

(74)代理人　弁理士　福井　豊明


(54)【発明の名称】　安全弁の開弁圧測定装置

(57)【要約】

【目的】　安全弁の開弁圧測定装置に関し、短時間内に正確な測定ができるようにした安全弁の開弁圧測定装置を提供することを目的とする。

【構成】　安全弁１のステム２に連結されるナット３と、安全弁１の圧力調整ネジ１４に受け止められ、上記ナット３を介してステム２を開弁方向に駆動するシリンダ４と、シリンダ４とナット３、又は、圧力調整ネジ１４との間に設けられ、シリンダ４の出力を検出する圧力検出素子５と、この圧力検出素子５が検出したシリンダの圧力を表示する表示装置６とを備える構成とする。

本発明の一実施例の構成図



KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 494

【特許請求の範囲】
【請求項１】　安全弁(1) のステム(2) に連結されるナット(3) と、安全弁(1) の圧力調整ネジ(14)に受け止められ、上記ナット(3) を介してステム(2) を開弁方向に駆動するシリンダ(4) と、シリンダ(4) とナット(3) 、又は、安全弁(1) の圧力調整ネジ(14)との間に設けた圧力検出素子(5) と、圧力検出素子(5)が検出したシリンダ(4) の圧力を表示する表示装置(7) とを備えることを特徴とする安全弁の開弁圧測定装置。
【発明の詳細な説明】
【０００１】
【産業上の利用分野】本発明は、安全弁の開弁圧測定装置に関する。
【０００２】
【従来の技術】ボイラなどの圧力配管には内圧が一定以上に上昇することを防止するため、安全弁が設けられる。安全弁が開弁する設定圧の誤差の範囲は、５ｋｇ未満で±０．１４ｋｇ以内、５ｋｇ～２３ｋｇでは±３％以内、２３～７０ｋｇｆでは±０．７ｋｇ以内、７０以上では±１．０％以内であることが求められている。
【０００３】安全弁の設定圧を設定するために圧力配管の内圧を実際に設定圧の近傍まで上昇させることは危険が伴い、また、エネルギーや労力の浪費、弁の損傷、騒音の発生等の問題が伴う。そこで、図３の原理説明図に示すように、圧力配管Ｔの内圧を例えば吹出し圧力の７５％以上、吹止まり圧力以下の任意の圧力にして、外部から安全弁１０１のステム１０２を油圧シリンダ１０３で牽引し、開弁する時の油圧を油圧計１１０で測定するという方法が採用されている。
【０００４】この安全弁の開弁圧の測定に用いられる装置としては、例えば図４に示すように、ヨーク１０４を安全弁１０１の圧力設定ネジ１０５に受け止めさせ、圧力設定ネジ１０５と反対側でヨーク１０４に支持させた油圧シリンダ１０３のピストンロッド１０６と安全弁１０１のステム１０２とをターンバックル１０７で連結するように構成している。
【０００５】油圧シリンダ１０３には、所定長さの高圧用ホース１０８を介して手動操作式の油圧ポンプ１０９が接続され、油圧ポンプ１０９の吐出口にアダプタを介して圧力計１１０が接続される。
【０００６】また、例えば図５に示すように、安全弁１０１の圧力設定ネジ１０５に受け止められるマウンティングプレート１１１にボルト１１２及びナット１１３で油圧シリンダ１１４を連結し、マウンティングプレート１１１を貫通して油圧シリンダ１１４側に突出させた安全弁１０１のステム１０２と油圧シリンダ１１４のピストンロッド１１５とを接続金具１１６で連結するように構成している。この接続金具１１６は互いにボルト１１７によって連結される１対の半割部材１１８を備え、両半割部材１１８の互いに対向する面にステム１０２に螺合される半割ネジ１１９とピストンロッド１１５に対応する半割ネジ１２０が形成される。
【０００７】この場合にも、油圧シリンダ１１４には、所定長さの高圧用ホース１０８を介して手動操作式の油圧ポンプ１０９が接続され、油圧ポンプ１０９の吐出口にアダプタを介して圧力計１１０が接続される。
【０００８】上記構成により、安全弁１０１の開弁方向に作用する力は、圧力配管Ｔの内圧と、油圧シリンダ１０３、１１４の出力との合計で与えられ、この出力が設定圧以上になると安全弁１０１が開弁し、安全弁１０１から圧力配管Ｔ内の圧力流体が吹き出す状態を模擬的に形成することができる。
【０００９】圧力配管Ｔの内圧は分かっているので、この吹出し音を確認した時の油圧シリンダ１０３、１１４の出力に基づいて安全弁１０１の開弁圧を測定することができる。ここで、油圧シリンダ１０３、１１４の出力は油圧シリンダ１０３、１１４のピストンの有効受圧面積と油圧シリンダ１０３、１１４の内圧の積で求められ、ピストンの有効受圧面積は一定であるので、油圧シリンダ１０３、１１４の内圧を測定すれば、安全弁１０１の開弁圧を測定できることになる。
【００１０】
【発明が解決しようとする課題】図３ないし図５に示した従来の安全弁の開弁圧測定装置においては、測定作業を一人で行えるようにするため、油圧シリンダ１０３、１１４の内圧を測定するための圧力計１１０が油圧ポンプ１０９の吐出口にアダプタを介して接続されている。
【００１１】従って、圧力計１１０と油圧シリンダ１０３、１１４との間には所定の長さののホース１０８が介在することになり、ホース１０８内で生じる圧力損失によって圧力計１１０の測定値よりも実際の油圧シリンダ１０３、１１４の内圧が低くなることがある。この圧力損失は、ホース１０８の引き回し方によって変化するが、ホース１０８に圧油を送り込むと、例えばホース１０８の曲がっている部分の曲率半径が圧油によって大きくなるので、圧力損失が変化する。また、弁の摩擦損失も測定の度に変化し、測定の安定性が得られないことがある。
【００１２】このため、従来の安全弁の開弁圧測定装置を用いて安全弁の開弁圧を測定する場合には、ホース１０８の経路が安定してホース１０８内で生じる圧力損失が安定するまで、あるいは、弁の摩擦損失が安定するまで、何度か測定を繰り返さないと正しい測定値を得ることができず、測定のために長い時間と労力とが必要とされる。更に、測定ゲージは機械的に構成され、ピークホールドし難い性質となっているので、精度よくゲージを読み取ることが容易でない。
【００１３】本発明は、上記の事情を鑑みてなされたものであり、短時間内に正確な測定ができるようにした安全弁の開弁圧測定装置を提供することを目的とする。


【００１４】
【課題を解決するための手段】上記の目的を達成するため、本発明は、例えば図１に示すように、安全弁１のステム２に連結されるナット３と、安全弁１の圧力調整ネジ１４に受け止められ、上記ナット３を介してステム２を開弁方向に駆動するシリンダ４と、シリンダ４とナット３、又は、圧力調整ネジ１４との間に設けられ、シリンダ４の出力を検出する圧力検出素子５と、この圧力検出素子５が検出したシリンダの圧力を表示する表示装置６とを備えることを特徴とする。
【００１５】
【作　用】本発明によれば、安全弁１にかかる圧力が直接に圧力検出素子５によって検出されるので、シリンダ４に作動流体を供給するホースの圧力損失と無関係に、１回の測定で正確にシリンダ４の出力を測定できる。
【００１６】本発明において、シリンダ４の構成は特に限定されないが、安全弁の圧力調整ネジに受け止められる筒体、この筒体内に進退可能に挿入され、外周面が異径に形成された中空ピストン、及び筒体と中空ピストンとによって区画された加圧室を有する中空シリンダ４を用いることができる。
【００１７】このような中空シリンダ４を用いる場合には、シリンダの中空部内で安全弁のステム２とナット３とを連結させることにより、小型化及びコンパクト化を図ることができる。
【００１８】
【実施例】以下、本発明の一実施例を図面に基づいて具体的に説明する。図１は本発明の構成図であり、この安全弁の開弁圧測定装置は、安全弁１のステム２に連結されるナット３と、このナット３を介してステム２を開弁方向に駆動するシリンダ４と、シリンダ４とナットとの間に設けた圧力検出素子５を内蔵した圧力検出ブロック６と、圧力検出素子５が検出したシリンダ４の圧力を表示する表示装置７とを備える。
【００１９】上記シリンダ４には、手動式の油圧ポンプ８が所定の長さ程度の高圧用ホース９を介して接続される。安全弁１の入口１０は例えばボイラの圧力配管１１に連通され、この圧力配管１１の内圧を例えば吹出し圧力の７５％以上、吹止まり圧力以下の任意の圧力にした後、上記油圧ポンプ８を操作してシリンダ４を伸長させることにより安全弁１の圧力設定バネ１２を圧縮し、安全弁１を開弁させる。安全弁１の開弁は圧力配管１１内の作動流体が安全弁１の出口１３から吹出す音によって認識され、この吹出し音が発生したときのシリンダ４の圧力を測定することにより安全弁１の開弁圧が測定される。
【００２０】上記シリンダ４は、複数本用いることも可能であるが、この実施例では構成を簡単にするために１本のシリンダ４を用い、又、装置の小型化及びコンパクト化を図るため、中空シリンダを用いている。
【００２１】すなわち、図２の断面図に示すように、このシリンダ４は、段付き異径内周面を有し、安全弁１の圧力調整ネジ１４に受け止められる筒体１５とこの筒体１５内に進退可能に挿入され、段付き異径外周面を有する中空ピストン１６とを備え、これら筒体１５と中空ピストン１６とによって加圧室１７が区画される。
【００２２】筒体１５の外周部には、加圧室１７に連通させたネジ孔１８が形成され、このネジ孔１８に上記ホース９の先端に設けた継手が螺合される。上記中空ピストン１６の大径部と小径部とにはそれぞれ、中空ピストン１６と筒体１５との間の隙間を油密状に封止するＯリング１９・２０が外嵌され、これにより、加圧室１７からシリンダ４の両端からの作動油の漏れが防止される。
【００２３】なお、この加圧室１７はエア抜き孔２１を介して外部に連通され、このエア抜き孔２１は、油圧ポンプ８からホース９を介して加圧室１７に圧油を供給し、加圧室１７から空気が完全に排出された後、図示しないプラグで閉塞される。
【００２４】シリンダ４の筒体１５は、直接に圧力調整ネジ１４に受け止めさせてもよいが、この実施例では、シリンダ４を装着したまま圧力調整ネジ１４を回転調整できるようにするため、筒体１５と圧力調整ネジ１４との間にスリップ板２２を介在させている。
【００２５】上記圧力検出ブロック６は、適当な剛性と弾性とを有する素材、例えば一般構造用圧延鋼、機械構造用炭素鋼などで形成され、その周縁部がシリンダ４の筒体１５に固定される。
【００２６】上記圧力検出素子５は、１個以上設けてあればよいが、この実施例では、複数個の圧力検出素子５を周方向に等間隔を置いて配置し、これらの検出値の平均値を求めて表示装置７に表示させるようにしている。
【００２７】圧力検出素子５は、圧力を加えた時にその圧力の大きさに対応する信号値を有する電気信号を出力するように構成してあればよく、例えば金属抵抗ひずみゲージ、半導体ひずみゲージなどのひずみゲージやピエゾ抵抗方式、ＰＮ接合方式の感圧素子を用いることができる。
【００２８】上記表示装置７は、従来の圧力計１１０の表示部に代わるものであり、圧力検出素子５が検出したシリンダ４の圧力を表示するように構成してあればよく、その表示方式はデジタル表示であっても、指針などによるアナログ表示であってもよい。また、表示装置７はピークホールド機能を持たせることによって読み取りがより正確になる。
【００２９】上記ナット３は、圧力検出ブロック６の中空部及び中空ピストン１６の中空部に挿入されるスリーブ２３を備え、シリンダ４をスリップ板２２を介して圧力調整ネジ１４の上に載せ、更に、圧力検出ブロック６を載せてからスリーブ２３を圧力検出ブロック６の中空部及び中空ピストン１６の中空部に挿入し、安全弁１の

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 496

ステム２に形成されたネジ２４に螺合される。
【００３０】ナット３の締結力は、ステム２とナット３との間のがたつきがなくなる程度であればよく、例えば、手回しで締め込み始めて回せなく成った後、該ナット３を１／３～３／４回転程度手で戻す程度でよい。
【００３１】この後、シリンダ４にホース９を介して油圧ポンプ８を接続し、エア抜きをした後、油圧ポンプ８により圧抜きをして、シリンダ４の内圧を大気圧に調整するとともに、表示装置７の表示の０点合わせをする。
【００３２】予め、あるいはこの後、圧力配管１１の内圧を例えば吹出し圧力の７５％以上、吹止まり圧力以下の任意の圧力に設定し、上記油圧ポンプ８を操作してシリンダ４に圧油を送る。
【００３３】圧油の供給により加圧室１７の内圧が上昇すると、中空ピストン１６が開弁方向（図上、上方向）に移動し、やがて、圧力検出ブロック６の外周部に中空ピストン１６が受け止められる。この後、加圧室１７の内圧を更に上昇させると、中空ピストン１６が更に強く圧力検出ブロック６の外周部を押出そうとする。
【００３４】しかし、シリンダ４の圧力が圧力設定バネ１２の圧力以下である場合には、圧力検出ブロック６の内周部が圧力設定バネ１２に牽制されるので、ステム２やナット３は開弁方向に移動しない。
【００３５】シリンダ４の圧力が圧力設定バネ１２の圧力を上回ると、ステム２及びナット３が圧力検出ブロック６の内周部とともに中空ピストン１６に駆動されて開弁方向に移動し、安全弁１が開弁され、作動流体（ここでは、飽和蒸気）が安全弁１から吹出す時に発する吹出し音が耳に入ることになる。
【００３６】中空ピストン１６がステム２、ナット及び圧力検出ブロック６の内周部に加える圧力、すなわち、シリンダ４の圧力は圧力検出素子５によって検出され、表示装置７に表示されているので、測定者は吹出し音が耳に入った時の表示装置７の表示を確認し、予め与えられた換算表によって安全弁１の開弁圧を読出すことができる。
【００３７】したがって、表示装置７を油圧ポンプ８の近傍に配置して、測定者が容易に観察できるようにすれば、安全弁１に掛かる圧力が直接に圧力検出素子５で計測されるので、ホース９の膨脹、収縮、流路抵抗などの影響を全く受けることなく、シリンダ４の圧力を測定することができ、しかも、１回の測定のみで正確にシリンダ４の圧力を測定することができる。
【００３８】測定者としては、実際の開弁圧が予め定められている開弁圧に対して所定の誤差内であるか否かが分かればよいので、予め定められている開弁圧に対応するシリンダ４の圧力を換算テーブルから読み取り、シリンダ４の圧力が読み取った圧力になるまで油圧ポンプ８を操作してシリンダ４の圧力を上げ、シリンダ４の圧力が所定の範囲内で吹出し音が発生するか否かを確認することにより、安全弁１の合否を決定することができる。
【００３９】不合格の場合には、この後、シリンダ４の圧力を降下させた状態で、吹出し音が出ていない場合には吹出し音が出るまで圧力調整ネジ１４を緩めて開弁圧を低くし、所定の範囲よりも下回る圧力で吹出し音が出た場合には所定の範囲内まで吹出し音が出なくなるように圧力調整ネジ１４を締めて開弁圧を高くする。すなわち、シリンダ４、圧力検出ブロック６及びナット３を付けたまま安全弁１の開弁圧調整ができる。
【００４０】なお、上記の一実施例においては、圧力検出ブロック６を設け、この圧力検出ブロック６に圧力検出素子５を設けているが、圧力検出素子５をシリンダ４の出力端（上記の一実施例では中空ピストン１６）に圧力検出素子５を支持させ、このシリンダ４の出力端からナット３に作用する圧力を検出するように構成することも可能であり、シリンダ４の筒体１５に圧力検出素子５を支持させ、圧力調整ネジ１４に受け止められる筒体１５の圧力を検出するように構成することも可能である。
【００４１】
【発明の効果】以上に説明したように、本発明は、安全弁のステムに連結されるナットと、このナットを介してステムを開弁方向に駆動するシリンダと、シリンダとナットとの間に設けた圧力検出素子と、圧力検出素子が検出したシリンダの圧力を表示する表示装置とを備えるので、簡単な構成で、安全弁に掛かる圧力を直接に測定することができ、１回の測定で正確にシリンダの圧力を測定できる。その結果、安全弁の開弁圧を短時間内に正確に測定できる。
【００４２】本発明において、特にシリンダとして中空シリンダを用いる場合には、装置全体を小型で、コンパクトにすることができる。
【図面の簡単な説明】
【図１】本発明の一実施例の構成図である。
【図２】本発明の一実施例の要部の断面図である。
【図３】従来例の原理説明図である。
【図４】従来例の要部の断面図である。
【図５】他の従来例の要部の断面図である。
【符合の説明】
１　安全弁
２　ステム
３　ナット
４　シリンダ
５　圧力検出素子
７　表示装置
１４　圧力調整ネジ


【図１】

本発明の一実施例の構成図




【図２】

本発明の一実施例の要部の断面図




【図３】

従来例の原理説明図




【図４】

従来例の要部の断面図



【図５】

他の従来例の要部の断面図



(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
28 March 2002 (28.03.2002)

PCT

(10) International Publication Number
WO 02/25612 A1

(51) International Patent Classification[7]: G08B 5/22

(21) International Application Number: PCT/US01/29764

(22) International Filing Date:
24 September 2001 (24.09.2001)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
09/667,351 22 September 2000 (22.09.2000) US

(71) Applicant: **KEYSPAN ENERGY** [US/US]; 175 East Old Country Road, Hicksville, NY 11801 (US).

(72) Inventor: **GELBEIN, Lawrence, J.**; 41 Alice Road, West Islip, NY 11795 (US).

(74) Agents: **FARRELL, Paul, J.** et al.; Dilworth & Barrese, LLP, 333 Earle Ovington Boulevard, Uniondale, NY 11553 (US).


(81) Designated States *(national)*: AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, UZ, VN, YU, ZA, ZW.

(84) Designated States *(regional)*: ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Published:
— *with international search report*
— *before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments*

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: PAGER-BASED GAS VALVE CONTROLLER



(57) Abstract: A pager-based controller including at least one pager configured to receive a signal from a remote location, the at least one pager being further configured to provide an output to control an on-off state of a valve actuator; a valve opening circuit to provide an output to locally control an on-off state of a valve actuator; a DC power source for supplying a required DC voltage to electrical components within the pager-based controller; a relay electrically connected to the at least one pager and the valve opening circuit; an isolation circuit electrically connected to the at least one pager and the relay, the isolation circuit configured to receive the output from the at least one pager and the valve opening circuit and supply a corresponding signal to the relay; the relay configured to receive the corresponding singal and control the valve actuator accordingly in response.

WO 02/25612 A1

PAGER-BASED GAS VALVE CONTROLLER

CROSS REFERENCE TO RELATED APPLICATION

This application is a continuation-in-part and claims the benefit of U.S. Utility Application No. 09/010,278, filed January 21, 1998, and incorporated by reference herein.

BACKGROUND OF THE INVENTION

1. Field of the Invention

The present disclosure relates generally to remote control systems for remotely controlling electrical equipment. More particularly, this disclosure relates to a controller which receives pager signals from a pager network to control electrical/electronic equipment, including electronic gas valve actuators.

2. Description of the Related Art

Remote control systems which are capable of generating and transmitting control signals to remotely control electronic equipment are known in the prior art. Electric utility companies, for example, typically utilize a private remote control system with a private radio network to remotely control on/off switching of capacitor banks in accordance with daily electric power requirements. Such systems, however, are costly

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 501

in that they require implementation and maintenance of the private radio network. In addition, their utility is generally limited to a narrow geographical region.

Hence, a need exists for a generally inexpensive remote control system which uses the public system telephone network (PSTN) to transmit control signals over a wide geographical region to remotely control equipment.

SUMMARY OF THE INVENTION

The present invention relates to a remote control system in which RF pager signals transmitted by means of a wide area pager network, are received by a pager-based controller to control electrical or electronic equipment. A human operator or automated computer at a telecommunication station connected to the PSTN, initiates the transmission of RF pager signals via the pager network to the pager-based controller at the remote equipment site. In a preferred embodiment, the pager-based controller includes at least one conventional pocket pager which has been modified by having its vibrator or other indicator removed. Each time the pocket pager receives a page, it outputs a control voltage normally used to drive the vibrator. This control voltage is used to change the switching state of a relay within the controller to thereby control the on-off state of external electronics connected to the relay such as gas valve actuators.

In an exemplary embodiment, at least one pager is employed within the controller having a pager (telecommunication) number. The pager is paged to set the valve actuator to a CLOSED state, while a separate valve opening circuit is activated

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 502

locally to set the valve activator to an open state. The relay switches power to the valve actuator. As such, the valve actuator can be switched closed merely by the remote operator or automated computer dialing the telecommunication number of the respective pager as allocated by the PSTN and pager network. The valve actuator is then closed locally.

A pager-based controller is provided which includes at least one pager configured to receive a signal from a remote location, the at least one pager being further configured to provide an output to close a valve; a valve opening circuit to provide an output to open the valve; a DC power source supplying DC voltage to electrical components within the pager-based controller; a relay electrically connected to the at least one pager and the valve opening circuit.

A method of remotely controlling an electronic device is also provided which includes the steps of transmitting a first pager signal from a pager network to a pager-based controller having at least one pager therein; outputting a first control voltage from the at least one pager controller to change a switching state of a relay within the pager-based controller to thereby control a valve actuator which is electrically connected to the relay; and locally initiating a second control voltage to change the switching state of the relay within the controller to control a valve actuator to a state which is opposite that which was caused by the first control voltage.

Advantageously, the use of conventional pocket pagers within the controller requires minimal set-up and maintenance costs and provides a reliable

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 503

method of controlling the capacitor bank via the use of the pager network. Set-up costs are minimal since a customized private radio network for the transmission of control signals is not necessary.

BRIEF DESCRIPTION OF THE DRAWINGS

For a better understanding of the invention, reference is made to the following description of exemplary embodiments thereof, and to the accompanying drawings, wherein:

FIG. 1 is a block diagram of a pager-based controller in accordance with the present invention;

FIG. 1A is a schematic diagram illustrating a valve opening circuit in accordance with a preferred embodiment of the present invention;

FIG. 2 is a block diagram of a conventional pocket pager configured to be utilized within the pager-based capacitor bank controller of the present invention; and

FIG. 3 is a block diagram of an illustrative remote control system including a pager network and multiple pager-based controllers of the present invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

FIG. 1 shows a simplified block diagram of the internal components of a pager-based controller 10 in accordance with the present invention. Controller 10

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 504

includes a pocket pager 14a which receives paging signals from a pager network. Pager 14a is registered with the pager network and is allocated a pager (telephone) number. Each time a remote operator or automated computer dials the respective pager number through the PSTN, the pager 14a receives the page signal via the PSTN and pager network. Whenever the page signal is received, the pager 14a outputs a control signal to an opto-isolator drive circuit 16a, which in turn changes a switching state of a power relay 20. A valve opening circuit 14b operates to switch the power relay 20 to an OFF state via opto-isolator drive circuit 16b, as described further with reference to FIG. 1A.

In a preferred embodiment, the switching of power relay 20 is used to switch an external gas valve actuator on or off. However, it is to be understood that pager-based controller 10 may alternatively be employed to control other types of electrical or electronic equipment, such as valve actuators for controlling the supply of water or oil. In addition, while it is preferable to employ a single pager 14, multiple pagers could be alternatively utilized within each controller 10.

Controller 10 is preferably embodied as a small portable unit deployable in the field, with a housing 12 to environmentally protect the circuitry therein. Alternatively, the circuitry may be entirely encased in a protective material. Pocket pager 14a may be a modified conventional pager (e.g., Motorola Bravo, Bravo Plus or Advisor pagers) and can be maintained within its original housing 24 to simplify mounting within the controller 10. Also, electromagnetic shielding may be used along

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 505

the inner surface of the pager housing 24 to reduce electromagnetic interference (EMI) susceptibility. The pocket pager typically operates in a one-way pager system, although two-way pagers can also be used. Pager 14a is modified from its commercial design simply by having its batteries and vibrator removed. Conventional pagers include a vibrator which vibrates whenever a page is received to convey vibrational movement to the person wearing the pager. Vibrating action is typically selected by the user via a mode switch on the pager. When vibrating action is selected, the audio output of the pager is deactivated such that the user can effectively receive pages without an accompanying (disturbing) audible tone.

DC power is preferably supplied to controller 10 via a DC source 28, such as batteries or solar power. Here, DC is preferable since it meets the requirement for "intrinsically safe" control of gas equipment. This DC voltage is used to power the electronics within controller 10, including pagers 14a (which has its batteries removed) and valve opening circuit 14b. The DC power supply may supply multiple voltages as needed, or multiple DC power supplies may be used. As an alternative, an alternative energy source known to one having ordinary skill in the art, such as an AC line voltage and converter, could be used to power the various components.

When a page signal is transmitted to controller 10, pager 14a receives the page and responds by outputting the control voltage normally used to drive the respective vibrator. The control voltage is supplied to an opto-isolator drive circuit 16a on line 27a. The valve opening circuit 24 provides a local control output to opto-

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 506

isolator drive circuit 16b on line 27b. Drive circuit 16 includes two portions, 16a and 16b, each including respective opto-isolator electronics 17a or 17b. Drive circuit 16 responds to the control voltage on line 27a or 27b by outputting a respective output voltage VRa or VRb at an appropriate level to power relay 20. When one of these voltages is applied to relay 20, the switching state of the relay changes.

The power relay 20 includes a relay switch 22 that activates one of two positions A or B corresponding to an energized or de-energized state of the gas valve actuator, until electrically reset by a new application of the voltage VRa or VRb from drive circuit 16. The switch 22 input is connected to the DC power source on line 33. The switch output connects to either line 34a or 34b which sends a "close" or "open" command, respectively, to valve actuator 9. Valve actuator 9 is preferably a magnetically latching type valve actuator and remains in a latched state. As such, when power relay 20 changes switching state, the operational state of the valve actuator is correspondingly changed. Alternatively, the relay may be a latching type relay to provide a maintained closure to the valve actuator.

The opto-isolators within drive circuit 16 operate to isolate the pager 14a and valve opening circuit 14b from the relatively high voltage/current levels at the power relay 20. The drive circuit 16 thus prevents voltage spikes from reaching the pager 14a during operation of the external electrical device. A fuse may also be provided on lines 33 and/or 34a, 34b to avoid damage to the relay 20 if current is excessively high.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 507

DC power source 28 supplies DC voltage to pager 14a, valve opening circuit 14b and drive circuit 16. Typically, the energy requirement of each pager is 80 mA at 1.5 VDC.

Each controller 10 may include a heater and fan (not shown) within the enclosure to maintain the pagers and other electronics within a proper operating temperature range.

The present invention is particularly advantageous for use by utility companies supplying natural gas to homes. In such a case, the utility company may actuate the gas valve, as described above, remotely via the pager 14a. Controlling the gas valve via pager 14a effectively shuts off the gas supply to a home or business. The present invention therefore provides a means to shut off the gas supply remotely from a utility office, for example. This represents a labor savings to the utility, and represents an advantageous safety feature in that potential safety hazards can be eliminated without risk to personnel.

Continuing the exemplary application described above, it is further advantageous to provide a means for the utility to reset the valve locally. While remote shut off of gas service is preferable, turning the gas service back on remotely presents obvious safety concerns. Therefore, it is more advantageous to turn the gas service back on locally, on-premises, preferably using a safe and reliable means.

Referring to FIG. 1A, a simplified schematic diagram of a preferred embodiment of the valve opening circuit 14b is shown. The valve opening circuit 14b

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 508

preferably includes an infra-red (IR) transistor 6, a magnetic reed switch 7, and a current limiting resistor 8. In operation, a pulse of current from the DC power supply source causes relay 20 to change state, thereby gas valve actuator 9 to open the valve. The current source is limited by current limiting resistor 8 and isolated by opto-isolator 16b. Both the IR transistor 6 and the magnetic reed switch must be in a conductive state for at least a temporary period to provide a pulse to power relay 20. Preferably, two different technologies are used to increase reliability and safety by preventing false trigers of the relay. Here, a technician, or any trained user, must apply both an IR source and a magnetic source to the circuit simultaneously to complete the circuit, thereby triggering power relay 20. Both IR and magnetic sources are preferable to limit any possibility of sparking. A magnetic reed switch is also preferable, since it is encapsulated in a glass tube, limiting the possibility of sparking. Limiting the possibility of sparking is preferable due to the potential for igniting the near-by gas supply.

Accordingly, the valve opening circuit of FIG. 1A provides a safe and reliable means to control the gas valve actuator 9 to turn the gas supply on locally. While an IR transistor 6 and reed switch are employed in the preferred embodiment, it is understood that many variations of the valve opening circuit may be made by one having ordinary skill in the art. For example, only an IR transistor 6 or magnetic reed switch 7 may be employed, or only an IR transistor 6 with a decoder, such that a predetermined sequence of IR pulses are required to activate power relay 20.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 509

With reference now to FIG. 2, a simplified block diagram of the conventional pocket pager 14a modified for use within the pager-based controller 10 is illustrated. Pocket pager 14a has the battery and vibrator removed and the battery contact points T1, T2 coupled to the DC power source 28 to receive the proper operating voltage for the electronics within the pager. A motor drive circuit 35 is coupled to the opto-isolator drive circuit 16 via connection at terminal points T3, T4 normally connected to the vibrator. A mode switch 35 is set to the vibrator position such that when a page is received by receiver/control circuit 32 via antenna 15, it responds by sending a command to motor drive circuit 34 rather than to the audio driver 36. Motor drive circuit 34 responds by outputting a voltage V1 of approximately 1.5 volts for a short duration. Pager 14a also includes LED driver 38, LED display 39 and audio transducer 37. These components are preferably not removed, since they can be used to verify reception of pages for testing purposes. It is noted that in alternative embodiments of the controller 10, it is possible to tap into the LED driver 38 and/or audio driver 36 (rather than or in addition to the motor drive circuit 34) to derive control signals for controlling the power relay switching state.

Furthermore, conventional pocket pagers are normally programmed by the pager company prior to delivery. A standard program used by the pager company requires the pager to give a reminder beep or vibration if the page is not acknowledged by pressing a button. The vibration is caused by a small motor with an unbalanced

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 510

shaft which vibrates the pager. Since the pagers will be unattended, the typical pager programming needs to be modified to disable the reminder function.

Referring now to FIG. 3, a remote control system 100 is illustrated which includes the pager-based controller 10 of the present invention. The system 100 controls the operational states of external electrical devices 50. System 100 includes a remote telecommunication terminal 70 which is connected to the PSTN 110 by a conventional telephone line 108. Terminal 70 can be as simple as a single telephone 80 operated by a human operator, or as complex as a fully automated computer 90 which maintains, *inter alia*, a memory of the operational state of each external electrical device. In the latter case, computer 90 automatically dials the pager numbers of pagers 14 within associated controllers 10 to dynamically switch specific external electrical devices 50 into and out of operation based on the desired result. For example, an electric generating station or capacitor bank may be switched in and out of service based on electric power requirements within a certain geographical area. When a page is initiated at terminal 70, the call is relayed through the PSTN 110 to a paging messaging center 60 via a wireline or wireless communication link 105. Messaging center 60 is coupled to each of a number of paging base stations 40 by means of wireline or wireless communication links 120. Typically, with one-way pager networks, each pager registered in the system can receive pages only within specific geographical regions associated with a particular one or more pager base stations 40. As such, when a call to a specific pager number is routed by the PSTN to messaging

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 511

center 60, the messaging center relays the call to the particular base station 40 associated with that pager. Each associated base station 40 then transmits the page signal. In the exemplary system described herein, since the external electrical devices controlled by each controller 10 are typically at fixed locations, only a single base station 40 need transmit the specific page signal to change the switching state of the corresponding external electrical device 50. The pager within controller 10 receives the specific page signal and switches the relay state accordingly. (It is noted that in some pager networks, each pager base station may transmit all pages to every pager registered with the system. The exemplary system of this invention can operate with this type of pager network as well).

A security measure may be incorporated to prevent persons other than the responsible operator or computer system at terminal 70 from dialing the pager numbers and thus changing the states of capacitor banks. For example, a security/access code can be allocated by the pager network service provider to each pager 14a. Therefore, in order to communicate with the pager 14a in the pager system 100, the security/access code must be transmitted followed by the corresponding telephone number (or vice versa) for that particular pager 14a.

Thus disclosed is a pager-based remote control system and controller particularly useful for controlling switching states of electronic equipment. Advantageously, since conventional pocket pagers are used to receive RF paging signals through a paging network, there are minimal costs in setting up and maintaining

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 512

the remote control system of the present disclosure. Further, customized transceiver circuitry and a radio network are not necessary to operate the pager-based controller 10 of the present disclosure.

It is to be understood that the embodiments described herein are merely exemplary and that one skilled in the art can make many modifications and variations to the disclosed embodiments without departing from the spirit or scope of the invention. For example, the present invention is not to be understood to be limited to employment in a pager system, but rather may be employed into numerous wireless communication systems, such as a Personal Communication Network (PCN) or into communication systems utilizing Personal and/or Terminal Mobility managers. According, all such modifications and variations are intended to be included within the scope and spirit of the present invention.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 513

IN THE CLAIMS:

1. A system for controlling an on-off state of a remote electrical valve actuator, said system comprising:

a pager-based controller; and

a terminal for transmitting a signal to the pager-based controller;

wherein the pager-based controller comprises a housing; at least one pager positioned within the housing and configured to receive a signal from a remote location, said at least one pager being further configured to provide an output to control the on-off state of the valve actuator; and a valve opening circuit operative to provide local control of the on-off state of the valve actuator.

2. The system recited in claim 1, wherein the valve opening circuit comprises an infra-red (IR) transistor and a magnetic reed switch connected in series and configured to change the on-off state of the valve actuator when an IR source and a magnetic source are brought into close proximity of the valve opening circuit.

3. The system recited in claim 1, wherein the pager-based controller further comprises a relay, the relay electrically connected and configured to receive the output from the at least one pager and supply a corresponding signal to the valve actuator.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 514

4. The system recited in claim 1, wherein the terminal is one of a telephone or a computer.

5. A pager-based controller which comprises:

a housing;

at least one pager positioned within the housing and configured to receive a signal from a remote location, said at least one pager being further configured to provide an output to change an on-off state of a valve actuator; and

a valve opening circuit positioned within the housing and operative to locally control the on-off state of the valve actuator.

6. The paper-based controller as recited in claim 5, further comprising:

a DC power source supplying DC power to the at least one pager, the valve opening circuit and the valve actuator.

7. The pager-based controller as recited in claim 5, further comprising a relay, the relay electrically connected and configured to receive the output from the at least one pager and supply a corresponding signal to the valve actuator.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 515

8. The pager-based controller as recited in claim 5, wherein the valve opening circuit comprises an infra-red (IR) transistor and a magnetic reed switch connected in series and configured to change the on-off state of the valve actuator when an IR source and a magnetic source are brought into close proximity of the valve opening circuit.

9. The pager-based controller as recited in claim 5, further comprising an isolation circuit configured to electrically isolate the at least one pager and the valve opening circuit from at least one of a high voltage and a high current.

10. The pager-based controller as recited in claim 9, wherein the isolation circuit is an opto-isolator drive circuit.

11. The pager-based controller as recited in claim 5, wherein the output of the at least one pager is a voltage from a motor drive circuit within the at least one pager.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 516

12. A method of remotely controlling a valve actuator comprising the steps of:

transmitting a first pager signal from a pager network to a pager-based controller located at a remote site, the pager-based controller having at least one pager therein; and

outputting a first control signal from the at least one pager to change a switching state of a relay within the pager-based controller to thereby control an on-off state of the valve actuator which is electrically connected to the relay.

13. The method recited in claim 12, further comprising the step of:

locally initiating a second control signal to change the switching state of the relay within the controller to switch the on-off state of the valve actuator to a state which is opposite that which was caused by the first control signal.

14. The method recited in claim 12, wherein the step of transmitting a first pager signal is automatically initiated by a computer.

15. The method recited in claim 13, wherein the step of locally initiating the second control signal includes bringing an IR source and a magnetic source within close proximity of the pager based controller.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 517

16. A gas system for controlling an on-off state of a remote electrical gas valve actuator, said gas system comprising:

a pager-based controller; and

a terminal for transmitting a signal to the pager-based controller;

wherein the pager-based controller comprises a housing; at least one pager positioned within the housing and configured to receive a signal from a remote location, said at least one pager being further configured to provide an output to control the on-off state of the gas valve actuator; and a valve opening circuit operative to provide local control of the on-off state of the gas valve actuator.

17. The system recited in claim 16, wherein the valve opening circuit comprises an infra-red (IR) transistor and a magnetic reed switch connected in series and configured to change the on-off state of the valve actuator when an IR source and a magnetic source are brought into close proximity of the valve opening circuit.

18. The system recited in claim 16, wherein the pager-based controller further comprises a relay, the relay electrically connected and configured to receive the output from the at least one pager and supply a corresponding signal to the valve actuator.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 518

19. The system recited in claim 16, wherein the terminal is one of a telephone or a computer.

20. The pager-based controller as recited in claim 16, further comprising an isolation circuit configured to electrically isolate the at least one pager and the valve opening circuit from at least one of a high voltage and a high current.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 519




FIG. 1

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 520




FIG. 1A

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 521




FIG. 2

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 522




FIG. 3

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 523

INTERNATIONAL SEARCH REPORT

Interna[illegible]l Application No
PCT/US 01/29764

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 G08B5/22

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 G08B B60R

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)
EPO-Internal

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	WO 94 29148 A (RONDISH CO LTD ;WILLIAMS STEVEN ALFRED (GB)) 22 December 1994 (1994-12-22) the whole document	1,3-7, 9-14,16, 18-20
X	WO 98 33153 A (GELBIEN LAWRENCE) 30 July 1998 (1998-07-30) claims 1-19	1,3-7, 9-14,16, 18-20
A	US 5 654 689 A (DEMOUY OLIVIER ET AL) 5 August 1997 (1997-08-05) abstract	2,8,15, 17
A	EP 0 716 553 A (MOTOROLA INC) 12 June 1996 (1996-06-12) abstract	1

☐ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

° Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
1 February 2002	08/02/2002

Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentlaan 2 NL – 2280 HV Rijswijk Tel. (+31–70) 340–2040, Tx. 31 651 epo nl, Fax: (+31–70) 340–3016	Sgura, S

2

Form PCT/ISA/210 (second sheet) (July 1992)

INTERNATIONAL SEARCH REPORT

Information on patent family members

Interna I Application No
PCT/US 01/29764

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
WO 9429148 A	22-12-1994	AU 6851794 A	03-01-1995
		WO 9429148 A1	22-12-1994
		ZA 9403858 A	01-02-1995
WO 9833153 A	30-07-1998	AT 208072 T	15-11-2001
		DE 69802258 D1	06-12-2001
		EP 0954834 A1	10-11-1999
		WO 9833153 A1	30-07-1998
US 5654689 A	05-08-1997	FR 2731965 A1	27-09-1996
		EP 0733521 A1	25-09-1996
		DE 69613877 D1	23-08-2001
		ES 2160781 T3	16-11-2001
EP 0716553 A	12-06-1996	US 5608655 A	04-03-1997
		EP 0716553 A2	12-06-1996
		JP 8237715 A	13-09-1996

Form PCT/ISA/210 (patent family annex) (July 1992)

(19) Europäisches Patentamt
European Patent Office
Office européen des brevets

(11) Publication number: **0 647 770 A2**

(12) EUROPEAN PATENT APPLICATION

(21) Application number: **94120028.9**

(51) Int. Cl.[6]: **F01L 9/02**, F02D 13/02

(22) Date of filing: **04.06.92**

This application was filed on 17 - 12 - 1994 as a divisional application to the application mentioned under INID code 60.

(30) Priority: **24.06.91 US 720115**

(43) Date of publication of application:
12.04.95 Bulletin 95/15

(60) Publication number of the earlier application in accordance with Art.76 EPC: **0 520 633**

(84) Designated Contracting States:
DE FR GB

(71) Applicant: **FORD MOTOR COMPANY LIMITED**
Eagle Way
Brentwood
Essex CM13 3BW (GB)
(84) **GB**

(71) Applicant: **FORD WERKE A.G.**
Werk Köln Niehl,
Henry Ford Strasse,
Postfach 60 40 02
D-50735 Köln (DE)
(84) **DE**

(71) Applicant: **FORD FRANCE S. A.**
B.P. 307
F-92506 Rueil-Malmaison Cédex (FR)
(84) **FR**

(72) Inventor: **Schechter, Michael Moses**
27686 Sutherlan
Southfield,
Michigan 48076 (US)

(74) Representative: **Messulam, Alec Moses**
A. Messulam & Co.
24 Broadway
Leigh on Sea
Essex SS9 1BN (GB)

(54) Hydraulically operated valve control system for an internal combustion engine.

(57) An engine valve control system of an internal combustion engine in which the valve stroke is controlled by varying timing and duration of electric signals sent to individually dedicated engine valve controlling means, comprises :

a controller programmed to send variable electric control signals (512) to the said engine valve controlling means (64),said control signals duration comprising the algebraic sum of a basic signal duration (508) and a correction signal duration (510)

means (504) for generating a basic signal duration determined by the controller as a function of engine operating conditions and being equal for all engine intake valves and equal for all engine exhaust valves; and

means (500,502) for generating a correction signal predetermined for each of the engine valve controlling means as a measure of the extent the performance of each engine valve controlling means varies from a predetermined standard, said correction signal generating means being operative in timed sequence to supply to the controller said predetermined correction signal just prior to a respective engine valve controlling means being activated.




Fig-19

EP 0 647 770 A2

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 526

This invention relates to systems for variably controlling internal combustion engine intake and exhaust valves. More specifically, it relates to engine valve systems of the type in which hydraulic pressure of a pressurised fluid is used through action of solenoid valves to control the engine valves motion.

The enhancement of engine performance to be attained by being able to vary the acceleration, velocity and travel time of the intake and exhaust valves in an engine is well known and appreciated in the art. However, the technology for providing a straight-forward, relatively inexpensive and highly reliable system has not been forthcoming. Increased use and reliance on micro electronic control systems for automotive vehicles and increased confidence in hydraulic as opposed to mechanical systems is now making substantial progress possible. In the area of intake and exhaust engine valves, prior development has been largely dependent upon sophisticated mechanical systems such as mechanically varying phase shift and other aspects of valve timing. increased use of multiple valve engines has also been promoted.

The use or adoption of hydraulically controlled engine valves has been quite slow. Examples of known systems include those as shown in U.S. Patent Nos. 2,915,052; 3,240,191; 3,361,121; 3,534,718; 3,926,159; 3,963,006; and 4,200,067. In some instances, such as shown in U.S. Patent No. 3,361,121 the poppet valve is maintained in a closed position by a mechanical coil spring, yet utilises a hydraulic actuator to bias the valves in the open position. Several of the aforementioned patents also disclose the use of a rotary distributor valve to alternately couple the hydraulic actuator ports to a source of pressurised fluid, such as shown in U.S. Patent Nos. 2,915,052 and 4,200,067. In certain of the aforementioned patents, it is also shown that the hydraulic fluid system is used to both open and close the engine valve, such feature being shown in U.S. Patent Nos. 2,915,052 and 3,963,006.

However, none of the aforementioned systems provide a variable engine valve control system offering the simplicity, reliability, flexibility and efficiency believed necessary for use in the high production, high performance automotive engines being produced today and those that will be required in the near future.

According to the present invention, there is provided an engine valve control system of an internal combustion engine in which the valve stroke is controlled by varying timing and duration of electric signals sent to individually dedicated engine valve controlling means, the system comprising a controller programmed to send variable electric control signals to the said engine valve controlling means, said control signals duration comprising the algebraic sum of a basic signal duration and a correction signal duration; means for generating a basic signal duration determined by the controller as a function of engine operating conditions and being equal for all engine intake valves and equal for all engine exhaust valves; and means for generating a correction signal predetermined for each of the engine valve controlling means as a measure of the extent the performance of each engine valve controlling means varies from a predetermined standard, said correction signal generating means being operative in timed sequence to supply to the controller said predetermined correction signal just prior to a respective engine valve controlling means being activated.

The engine valve controlling means may suitably be an hydraulic system as described below and as claimed in co-pending European Patent Application No. 92305111.4. In this system, sources of high and low pressure are connected by solenoid operated valves to a double acting piston acting to open and close each engine valve. Selective actuation and deactuation of the controlling means causes an inflow of pressurised fluid into a space at one end of said piston and an outflow of fluid from the space at the other end of the piston, such action leading to a change in the balance of forces acting on the piston and causing controlled motion of the valve from one fixed position to another.

The invention will now be described further, by way of example, with reference to the accompanying drawings, in which :

Figure 1 is a schematic diagram showing a single hydraulically controlled engine valve and the entire hydraulic system for supplying fluid to the valve controlling means according to the invention;

Figures 2a, 2b and 2c are elevation views showing a single engine valve and associated valve controlling means, with the valve being shown in three different stages of its being fully opened;

Figures 3a, 3b and 3c are elevation views showing a single engine valve and associated valve controlling means, with the valve being shown in three different stages of its being fully closed;

Figure 4 is a schematic diagram showing an alternative embodiment of the present invention wherein a single pair of control valves is used to control the operation of two valves associated with the same engine cylinder, thereby allowing the single engine valve to be functional or both valves to be functional through selective activation of the two control valves of the system;

Figure 5 is an alternate embodiment of the present invention and showing an elevation view of a engine valve and its control means utilising

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 527

a single spring bias pressure relief valve and a double acting high pressure rail solenoid valve;

Figures 6 and 7 show as an elevation view and front view, respectively, a rotary hydraulic distributor in accordance with the present invention for distributing both high pressure and low pressure fluid to a plurality of engine valves;

Figures 8a, 8b and 8c are basically schematic representations of an engine valve being hydraulically opened using a modified hydraulic control system including the rotary distributor of Figures 6 and 7, all in accordance with the present invention;

Figures 9a, 9b and 9c show schematic representations of an engine valve being hydraulically closed using a modified hydraulic control system including the rotary distributor of Figures 6 and 7, all in accordance with the present invention;

Figure 10 is a schematic diagram of an alternative embodiment of the present invention wherein the control means including the rotary hydraulic distributor is used to control a plurality of engine valves, one each for each of the engine cylinders and all the other intake valves or exhaust valves;

Figures 11-13 are similar to Figure 10 but showing the engine valves at another point in the engine's cycle;

Figures 10a through 13a are schematic diagrams of yet another embodiment of the present invention wherein a pair of control valves including a hydraulic rotary distributor is used for controlling the valve operation of a pair of engine cylinders and wherein each distributor alternately controls the functions of both intake valves and exhaust valves, one each in each of the cylinders;

Figure 14 is a schematic representation of the engine valves and control valve system therefor of a pair of engine cylinders as shown in Figures 10a-13a.

Figure 15 is a schematic valve lift diagram showing the valve lift pattern for the system shown in Figure 14;

Figure 16 is a schematic diagram of a conventional lost motion type, cam-operated, hydraulic engine valve control system;

Figure 17 is a composite graph showing the operating characteristics of a single solenoid valve as a function of time versus solenoid valve travel, current and voltage;

Figure 18 is a schematic diagram of yet another embodiment of the present invention wherein each solenoid valve used in the above-mentioned systems can be calibrated to allow adjusting the current input to the solenoid valve to produce an identical valve stroke for all of the variably hydraulically controlled valves in a system in accordance with the present invention as equipped with different solenoids; and

Figure 19 is a schematic diagram of a control system utilising a plurality of calibrated solenoid valves and adjusting the valve opening characteristics in each of the cylinders of the internal combustion engine in accordance with the present invention.

A system that provides variable control of engine valve timing, lift and velocity is illustrated in Figure 1. The system exploits elastic properties of compressed hydraulic fluid which, acting as a liquid spring, accelerates and decelerates the valve during its opening and closing motions. During acceleration, some of the potential energy of the fluid is converted into kinetic energy of the valve. During deceleration, the energy of the valve motion is returned to the fluid. With the exception of leakage, most of the energy of the fluid is conserved.

In Figure 1, an engine valve 10 is located within a cylinder head 12 which includes a port 14 for inlet air or exhaust, as the case may be. Valve 10 includes a valve head 16 and a stem portion 18. Valve stem portion 18 includes a series of concentric cylindrical sections 20, 22, 24 and 26 of varying outer diameter. The sections 20 and 24 guide the valve for reciprocation within guide bore 28. Section 26 constitutes a valve piston slidable within the limits of piston chamber 30 which is concentric with guide bore 28 and also constitutes a part of the cylinder head.

Fluid is selectively supplied to the piston 26 from a high pressure rail 40 and a low pressure rail 42 hydraulically connected through lines 44 and 46, respectively, to high pressure port 48 and low pressure port 50, respectively.

Hydraulic systems maintaining necessary fluid pressures in the high and low pressure rails can be arranged in a variety of ways. A variable displacement pump 52 is included between a reservoir 54 and the high pressure rail. Since the fluid in the high pressure rail is subject only to expansion and contraction, the pumping work of the pump is largely limited to that necessary to compensate for internal leakage through clearances. The variable displacement pump 52 may be under automatic control whereby a pressure sensor 56 will produce a pressure feedback signal to a pump controller 58 in the event pressure in the high pressure rail drops below the set minimum required at any particular vehicle speed or other operating condition. This then varies the pump displacement to maintain the required pressure in the high pressure rail. Fluid in the low pressure rail 42 is maintained at a fixed low pressure by means of pressure pump 60 supplying fluid from reservoir 54 and pressure regulator 62.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 528

The volume above the piston 26 can be connected to the high pressure rail through a solenoid valve 64 or a check valve 66, or to the low pressure rail through solenoid valve 68 or a check valve 70. The volume below the piston 26 is always connected to the high pressure rail. Fluid return line 72 completes the system and provides the means for returning to the reservoir 54 any fluid which leaks past the piston 26 at either end to the chamber formed between guide bore 28 and the reduced diameter section 22 of the valve.

The process of a single valve 10 opening and closing is illustrated in Figures 2a-c and 3a-c. The arrows indicate the direction of fluid flow and valve motion as the case may be.

During the engine valve opening, the solenoid valve 64 opens and the net pressure force acting on the piston 26 accelerates the engine valve downward (Figure 2a). When the solenoid valve 64 closes, pressure above the piston 26 drops, and the piston decelerates pushing the fluid from the volume below it back into the high pressure rail (Figure 2b). Low pressure fluid flowing through the check valve 70 prevents void formation in the volume above the piston 26 during deceleration. When the downward motion of the valve stops, the low pressure check valve 70 closes and the engine valve remains locked in its open position (Figure 2c).

The process of engine valve closing is similar, in principle, to that of the valve opening. The solenoid valve 68 opens, pressure above the piston 26 drops and the net pressure force accelerates the engine valve upward (Figure 3a). Then the solenoid valve 68 closes and the rising pressure above the piston 26 opens the high pressure check valve 66 (Figure 3b). The direction of the net pressure force is reversed, and the engine valve decelerates pushing the fluid from the volume above the piston 26 back into the high pressure rail. When the engine valve exhausts its kinetic energy, the high pressure check valve 66 closes and the engine valve remains locked in its closed position (Figure 3c). A brief reopening of the solenoid valve 68 assures that the engine valve is firmly pressed against its seat.

Varying the timing of activation of the two solenoid valves varies the timing of the engine valve opening and closing. Valve lift can be controlled by varying the duration of the solenoid voltage pulse. Changing fluid pressure in the high pressure rail permits control of valve acceleration, velocity and travel time. All this permits considerably greater flexibility in engine valve operation control than is possible in conventional cam driven valve trains; flexibility which, in effect, is equivalent to ability to vary the size and the shape of the cam while the engine is running.

In engines with more than two valves per cylinder, a single pair of solenoid valves can activate several intake (or exhaust) valves simultaneously. This is shown in Figure 4 where the high pressure and low pressure solenoid valves 64 and 68, respectively, activate two engine valves 10 and 110 when the control valves 74 and 76 are open. if the control valves 74 and 76 are closed, only the engine valve 10 is activated. The manner of operation of each engine valve 10,110 is otherwise as described above with reference to Figures 1-3. Like reference numerals are used to illustrate this structural identity except with the second engine valve 110, components identical to the first valve 10 are prefixed in the "100" series.

In Figure 5, there is shown another embodiment wherein the high pressure line 44 to the piston 26 includes only a single solenoid valve 70. The high pressure check valve 66 from Figures 1-4 is eliminated. Otherwise, structurally, the system is the same as shown in the embodiments of Figures 1-4.

In operation, solenoid valve 64 is actuated twice during each valve cycle, rather than once as previously described, since its actuation must duplicate the functioning of the eliminated check valve 68. Specifically, during the closing stroke, to effect deceleration of engine valve 10 (Figure 3b of the previous embodiment), the solenoid valve 64 is opened to allow fluid to be pushed back into the high pressure rail. At a point in time when the kinetic energy of the engine valve is calculated to be expended, the solenoid valve 64 is closed and the engine valve remains locked in position.

In the arrangements shown in Figures 6-15, there is provided a system whereby the two solenoid valves 64 and 68 control the operation of a group of two or more engine valves. One of the solenoid valves 64 controls the opening motion of the engine valves while the other one 68 is dedicated to control of the closing motion, as previously described. During each cycle of a solenoid valve opening and closing one of the engine valves is brought into motion, in much the same manner previously described in regard to Figures 1-4.

One of the key components of the system is a pair of rotary hydraulic distributors each coupled with a respective solenoid valve 64,68. An example of the rotary hydraulic distributor, generally designated 200, is illustrated in Figures 6 and 7. A normally closed solenoid valve 64 separates the inside of a rotatable distributor sleeve 210 from the source of pressurised fluid, namely for purposes of this discussion, the high pressure rail 40. The distributor sleeve 210 can rotate within an outside stationary sleeve 212, which has several equally radially spaced ports 214 about its circumference, each connected to a separate outlet line 48a-d. The

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 529

distributor sleeve 210 has a single radial passage 218 which, during each revolution, connects the inside of the distributor sleeve with each of the outlet ports 214 in succession. During engine operation, the distributor sleeve rotates with half the crankshaft speed, and the solenoid valve is opened each time the radial passage 218 is in register with one of the ports 214. The timing and duration of solenoid valve opening may vary within the window of the passage 218 and each port 214 registration.

During the valve opening, the high pressure solenoid valve 64 is connected to the engine valve through its rotary distributor. The solenoid valve 64 opens and the net pressure force acting on the piston 26 accelerates the engine valve 10 downward (Figure 8a). When the solenoid valve 64 closes, pressure above the piston 26 drops, and the piston decelerates pushing the fluid from the volume below it back into the high pressure rail (Figure 8b). Low pressure fluid flowing through the check valve 70 prevents void formation in the volume above the piston 26 during deceleration. When the downward motion of the valve stops, the check valve 70 closes and the engine valve remains locked in its open position (Figure 8c). During the opening period, the action at the solenoid valve 68 has no effect on this engine valve, since there is no connection between them through the rotary hydraulic distributor 200 of the solenoid valve 68.

The process of valve closing is similar, in principle, to that of the valve opening. This time, it is the low pressure solenoid valve 68 which is connected to the engine valve through its rotary distributor, while the high pressure solenoid valve 66 is disconnected. The low pressure solenoid valve 68 opens, pressure above the piston 26 drops and the net pressure force accelerates the engine valve upward (Figure 9a). Then the solenoid valve 68 closes and the rising pressure above the piston 26 opens the check valve 66 (Figure 9b). The direction of the net pressure force is reversed, and the engine valve decelerates pushing the fluid from the volume above the piston 26 through line 44 and back into the high pressure rail 40. When the engine valve exhausts its kinetic energy, the check valve 66 closes and the engine valve remains locked in its closed position (Figure 9c). Proper selection of solenoid valve 68 opening duration is, of course, to be determined to assure proper engine valve closing.

As with the previously described embodiment, varying the (i) timing of activation of the two solenoid valves varies the timing of the engine valve opening and closing, (ii) duration of the solenoid voltage pulse controls valve lift, and (iii) fluid pressure in the high pressure rail permits control of valve acceleration, velocity and travel time. Again, the advantage incurred is greater flexibility in engine valve operation control than is possible in conventional cam driven valve trains.

The previous description, which was illustrated in Figures 8a-c and 9a-c was limited to a case of a single valve operation. Figures 10-13 illustrate a case in which a pair of solenoid valves with rotary hydraulic distributors successively operate four valves in four engine cylinders, namely either four intake valves or four exhaust valves. Taken together, Figures 10-13 depict a series of events taking place during a single 720° engine cycle and separate from each other by 90° of rotary distributor angle (180° crankshaft angle). The engine firing order is cylinder Nos. 1-3-2-4.

In Figure 10, the high pressure solenoid valve 64 is open and the engine valve No. 1 is accelerated toward opening. The low pressure solenoid valve 68 is open also and engine valve No. 4 accelerates while moving toward its closed position. only lines in which fluid motion takes place are shown in the drawing.

In Figure 11, the solenoid valves 64 and 68 are open again, but, due to new positions of their rotary distributors 200, this time it is valve No. 3 which moves toward opening, while valve No. 1 is closing.

In Figure 12, the position of rotary distributors 200 is such that valve No. 2 is opening while valve No. 3 is closing, and in Figure 13 valve No. 4 is opening while valve No. 2 is closing. After that, the entire sequence is repeated again during each engine cycle.

As mentioned, the engine valves shown in Figures 10-13 could be four intake valves or four exhaust valves in four engine cylinders. However, they could also be one intake and one exhaust valve in one cylinder and another pair of intake and exhaust valves in another cylinder which is 360° crankshaft out of phase with the first one (for example, cylinders No. 1 and 2). In that case, the operational order would be: No. 1 exhaust, No. 1 intake, No. 2 exhaust, No. 2 intake. This is illustrated in Figures 10a-13a. As it was the case in Figures 10-13, the solenoid valves 64 and 68 are open in every case but, in each case, the rotary distributors 200 connect the solenoid valves to a different pair of engine valves. In Figure 10a, the No. 1 exhaust valve accelerates toward the opening and the No. 2 intake valve accelerates toward closing. In Figures 11a, the No. 1 intake valve accelerates toward opening, and the No. 1 exhaust valve accelerates toward closing. In Figure 12a, the No. 2 exhaust valve accelerates toward opening, and the No. 1 intake valve accelerates toward closing. In Figure 13a, the No. 2 intake valve accelerates toward opening, and the No. 2 exhaust valve accelerates toward closing. In a similar manner, the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 530

valves in cylinders No. 3 and 4 can be controlled. The operational order would be: No. 4 intake, No. 3 exhaust, No. 3 intake, No. 4 exhaust.

Figure 14 is a schematic diagram of hydraulic connections between the solenoid valves with their rotary hydraulic distributors and the engine valves they control as discussed above and illustrated in Figures 10a-13a. Solenoid valves 64 and 68 control the intake and exhaust engine valves in cylinders No. 1 and No. 2, and another pair of solenoid valves, 64' and 68', identical to valves 64 and 68, control the intake and exhaust engine valves in cylinders No. 3 and No. 4. Figure 15 shows an example of valve lift profiles in the four cylinder engine valve control system depicted in Figure 14.

The system of solenoid valves coupled with rotary hydraulic distributors was described above as applied to a specific concept of variable valve control. It is clear, however, that application of such a system is not limited to any specific concept and can be applied to many other variable valve control systems in which solenoid valves are used to control the engine valves motion.

Valve motion control by means of solenoid type control valves is also used in variable valve systems known as "lost motion" systems. An example of a lost motion valve control system is diagrammatically shown in Figure 16. It is a well known system and as such forms no part of this invention.

A cam 300 drives a cam plunger 302. The motion of the plunger 302 is transmitted through fluid filling a passage 304 to a valve plunger 306 driving the valve 308. Fluid leaking out of the system is replenished from a supply gallery 310 through a check valve 312. As long as the solenoid valve 314 remains closed, the motion of the valve 308 is determined by the profile of the cam 300. Opening the solenoid valve 314 permits some of the fluid to escape from the passage 304 into the supply gallery 310. As a result, motion of the valve 308 becomes different from that dictated by the profile of the cam 300. By varying the solenoid voltage pulse timing and duration, various shapes of the valve lift versus time curve can be obtained.

One of the most important advantages of the variable valve control is the ability to control the amount of air inducted into the engine cylinders by controlling the valve operation rather than by means of throttling the air flow. This permits elimination of a substantial portion of engine throttling losses and improvement in the fuel efficiency. In addition to improved fuel efficiency, skillful application of variable valve control can lead to improvements in combustion stability, maximum power and exhaust emissions. It is important, however, to prevent cylinder-to-cylinder intake air maldistribution. In engines with carburettors or with single point central fuel injection, uneven intake air distribution would lead to unequal power developed by individual cylinders. in engines with multi-point port fuel injection or with direct in-cylinder injection, intake air maldistribution would result in cylinder-to-cylinder variations in air-to-fuel ratios. Such deficiencies can cancel out the benefits of variable valve control.

The amount of air inducted into an engine cylinder is dependent on the engine intake valve lift and opening duration. Therefore, to assure equal air distribution, it is imperative that the valve lift and duration of opening in all cylinders are the same. Since the motion of the valves is controlled by solenoid valves, this amounts to a requirement that all solenoid valves in the system, given the same signal, produce identical results in terms of valve motion.

The accuracy of the cylinder-to-cylinder air distribution is also affected by the accuracy of exhaust valve motion control. Therefore, in variable valve control systems controlling both intake and exhaust valves, similar requirements should be applied to both kinds of valves.

Referring to Figure 17, the normally closed solenoid valve parameter which determines the engine valve motion is the solenoid valve opening duration $\underline{t}$. In systems using normally open solenoid valves it would be the closing duration. It is a function of the solenoid voltage pulse duration $\underline{t}_s$, but it differs from the latter by solenoid valve activation and deactivation delays, $\underline{t}_a$ and $\underline{t}_d$, respectively. This is illustrated in Figure 17 showing a graph of the solenoid voltage pulse versus time and corresponding graphs of the solenoid current and valve motion versus time. The activation and deactivation delays can vary from solenoid to solenoid due to differences associated with inevitable manufacturing tolerances. As a result, different solenoid valves receiving the same control voltage signal may exhibit different solenoid valve opening durations and, consequently, have different effects on the engine valve motion.

To ensure that the engine valve motion of all common valves (intake or exhaust) in all cylinders is identical, the solenoid valve opening duration in each solenoid must be the same. This is accomplished by modifying the duration of the voltage pulse sent to each individual solenoid, so as to compensate for variations in the activation and deactivation delays. The required correction in control pulse duration can be determined experimentally during solenoid testing and encoded on a tag attached to the solenoid valve. Subsequently, the information on the tag can be read and used by the engine electronic control system.

A conventional calibration device (not part of this invention) may be used to determine the cor-

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 531

rection required for individual solenoid valves. The device is intended for calibration of high pressure solenoid valves for a system such as illustrated in Figures 1-13. The calibration device would be connected to high and low fluid pressure sources. The device would need to include two solenoid valves. One of the two solenoid valves would be a permanent part of the device and have a verified standard characteristic. The other solenoid valve, e.g. the solenoid valve 64 shown in Figure 1, would be the one subject to testing.

During the test, both the solenoid valves in the calibration device are activated by voltage signals of a predetermined duration with some frequency, and the stroke of an engine valve forming a part of the calibration device and preferably identical to the engine valve 10 would be measured by a sensor. If the measured stroke differs from the expected standard one, the duration of the pulse applied to the solenoid valve 64 being calibrated is modified until the stroke of the engine valve corresponds to the required one. The final incremental value of the pulse duration added to or subtracted from the initial predetermined duration can be called the correction number of the solenoid valve. Different solenoid valves may have different correction numbers, but what is important is that if any of them is activated by a voltage pulse consisting of standard pulse duration, to which its individual correction number is added or subtracted, they will all produce the same valve lift. Since the correction number compensates for solenoid-to-solenoid variations in activation and deactivation delays, which do not vary with change in pulse duration and frequency, the correction determined under one set of conditions remains valid for any pulse duration and frequency.

Figure 18 shows a diagram of a solenoid valve calibration system which includes the above described calibration device and individually calibrates at least each high pressure solenoid valve 64 to be used in the variable engine valve control system of this invention. The calibration device 400 is operated and controlled by an electronic controller 402 programmed to send out an initial standard solenoid control pulse, to receive and interpret the valve stroke signal, and to modify the duration of the control signal until the required valve stroke is achieved. when this is accomplished, the controller activates a printer 404 which prints and issues a tag 406 with the solenoid valve correction number expressed in the form of a binary bar code. The tag 406 can be glued or otherwise attached to the solenoid valve. When each solenoid valve 64 is installed on the engine, its tag is detached from it and glued or otherwise attached to a rotatable member as described below which rotates with half the crankshaft speed during engine operation (in case of a two-stroke engine, this would be equal to crankshaft speed). The location of each tag on the rotating member depends on which cylinder its solenoid valve is installed.

As shown diagrammatically in Figure 19, a sensor is installed in proximity of a rotating member 502 and reads the bar code on each tag 406 as it passes by the sensor and sends this information to the engine electronic control system 504. The relative location of all the tags 406 on the rotating member is such that the engine control system successively receives information encoded in each tag just before its solenoid is to be actuated. The duration of the basic control signal computed for all solenoid valves controlling all engine intake (or exhaust) valves is determined by the control system as a function of engine operating parameters designated generally as input line 506, such as speed, load, etc. and is common to all intake (or exhaust) valves. The basic signal 508 is modified by addition or subtraction of the most recently received value of correction signal 510 and the corrected signal 512 is then relayed to the appropriate control solenoid valve 64, for example at cylinder No. 1 of engine 514 as shown, for that particular engine valve operation. Thus, tag 406-1 corrects the solenoid valve 64 at cylinder No. 1, as does tag 406-2 at cylinder 2, and so on. Therefore, each solenoid valve receives its own individualised corrected control signal which compensates for solenoid-to-solenoid differences and assures that at a given value of the basic control signal all engine intake (or exhaust) valves will perform in an identical manner.

The above described method of determining correction required for individual solenoid valves is not limited to the system illustrated in Figures 10-13. It is fully applicable to a variety of other systems. In each case the tested solenoid valve is installed in a calibration device representing a variably controlled single engine valve and run with a predetermined pulse which is subsequently modified until the required standard pattern of valve motion is achieved. The method is applicable to the lost motion system and numerous other systems.

Claims

1. An engine valve control system of an internal combustion engine in which the valve stroke is controlled by varying timing and duration of electric signals sent to individually dedicated engine valve controlling means, the system comprising:

   a controller programmed to send variable electric control signals (512) to the said engine valve controlling means (64),said control sig-

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 532

nals duration comprising the algebraic sum of a basic signal duration (508) and a correction signal duration (510)

means (504) for generating a basic signal duration determined by the controller as a function of engine operating conditions and being equal for all engine intake valves and equal for all engine exhaust valves; and

means (500,502) for generating a correction signal predetermined for each of the engine valve controlling means as a measure of the extent the performance of each engine valve controlling means varies from a predetermined standard, said correction signal generating means being operative in timed sequence to supply to the controller said predetermined correction signal just prior to a respective engine valve controlling means being activated.

2. A system as claimed in claim 8, wherein said correction signal generating means (50,502) comprises:

a rotatable member (502) having individual codings thereon in spaced sequence, each coding representing a specific engine valve controlling means and containing information on the correction signal required by the said specific engine valve controlling means; and

a sensor (500) installed in proximity of the said rotatable member, said sensor being capable of reading the information contained in each coding on the rotatable member as it passes the sensor and transmitting said reading as a correction signal to said controller.

3. A system as claimed in claim 2, wherein each said coding is in the form of a tag and each tag is affixed to said rotatable member;

means for rotating said rotatable member during engine operation with an angular velocity equal to half the crankshaft velocity on a four-stroke engine and equal to crankshaft velocity on a two-stroke engine, whereby said sensor will read the information on individual tags successively passing the proximity of the sensor and transmit a respective correction signal to the controller, the location of individual tags on said rotatable member being such that the information on each tag is read and sent to the control system just before the engine valve controlling means for which the tag was coded must be actuated.

4. A system as claimed in claim 1, including:

a high pressure source of fluid and a low pressure source of fluid;

a cylinder head member adapted to be affixed to the engine and including a plurality of enclosed cavities; a plurality of poppet valves, each being associated with a respective one of said plurality of enclosed cavities;

each said poppet valve being shiftable between a first and second position within said cylinder head member;

a hydraulic actuator including a piston coupled to each said poppet valve and reciprocable within the respective enclosed cavity which thereby varies in displacement as each poppet valve moves;

said cylinder head member having a high pressure port extending between the enclosed cavities and the high pressure source of fluid and a low pressure port extending between the enclosed cavities and the low pressure source of fluid;

a high pressure valve and a low pressure valve for respectively regulating the flow of fluid in the high pressure and the low pressure ports of each of said plurality of enclosed cavities;

control means co-operating with the high and low pressure valves for selectively coupling the enclosed cavities to the high pressure and low pressure sources to oscillate each poppet valve in timed relation to engine operation, wherein the net fluid flow between the high pressure and low pressure sources is substantially less than the volume swept by the piston;

said control means including means for controlling (i) the notion of each said poppet valve by varying the timing and duration of the said control means actuation, (ii) the timing of the valve opening and closing motions of each poppet valve by varying the timing of said control means actuation, and (iii) the stroke of each said poppet valve by varying the duration of said control means actuation; and

means for varying the pressure of the pressurised fluid whereby the acceleration, velocity and travel time of each poppet valve may also be controlled.

5. A system as claimed in claim 4, wherein said control means includes said individual engine valve controlling means for each said poppet valve, whereby the duration of the control signal may be individually adjusted for each engine valve controlling means in all cylinders so as to assure equal poppet valve strokes in all cylinders.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 533




Fig-1

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 534




Fig-2c




Fig-2b




Fig-2a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 535




Fig-3c




Fig-3b




Fig-3a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 536




Fig-4

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 537




Fig-5

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 538




Fig-7




Fig-6

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 539




Fig-8c

Fig-8b

Fig-8a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 540




Fig-9c

Fig-9b

Fig-9a

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 541




Fig-10

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 542





Fig-10a


KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 543

Fig-11




KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 544

Fig-11a




KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 545

Fig-12




KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 546

Fig-12a




KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 547

Fig-13



KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 548

Fig-13a



KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 549




Fig-14

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 550




Fig-15

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 551




Fig-16
(Prior Art)




Fig-17

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 552




Fig-18




Fig-19

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 553

Electronic Acknowledgement Receipt

EFS ID:	13689625
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Barden Todd Patterson
Filer Authorized By:	
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	07-SEP-2012
Filing Date:	25-MAY-2012
Time Stamp:	17:17:07
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	no

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Information Disclosure Statement (IDS) Form (SB08)	SAFO0012USP1_IDS_07SEP2012.pdf	180779 6aa3eda2482cdeb5fec0d0e7b9161784f0ea9bfd	no	6

Warnings:	
Information:	

This is not an USPTO supplied IDS fillable form					
2	Foreign Reference	JP7042856A.pdf	271281 c0b4dc5ac1fccf3bfb27a2d5cb3daac904a28b07	no	6
Warnings:					
Information:					
3	Foreign Reference	WO0225612A1.pdf	851450 b88f51eab433f0cc6b4d3515e8de32a0b40a1140	no	26
Warnings:					
Information:					
4	Foreign Reference	EP0647770A2.pdf	1219309 d72c72f79bebb53c419251ca09769a9fb1c27d0a	no	28
Warnings:					
Information:					
5	Non Patent Literature	Versa_Series_B_Valves.pdf	761550 3793854531e7a0174feb21e3f5c4efb3182bfe66	no	8
Warnings:					
Information:					
6	Non Patent Literature	Rotowink_Indicators.pdf	107432 16a9d2c53b0291637ec0f3af48316ee1485121f9	no	2
Warnings:					
Information:					
		Total Files Size (in bytes):	3391801		

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111

If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371

If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office

If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NUMBER	FILING or 371(c) DATE	GRP ART UNIT	FIL FEE REC'D	ATTY.DOCKET.NO	TOT CLAIMS	IND CLAIMS
13/480,704	05/25/2012		560	SAFO/0012USP1	21	3

CONFIRMATION NO. 9598

FILING RECEIPT

26290
PATTERSON & SHERIDAN, L.L.P.
3040 Post Oak Blvd.
Suite 1500
Houston, TX 77056

OC000000054645053

Date Mailed: 06/07/2012

Receipt is acknowledged of this non-provisional patent application. The application will be taken up for examination in due course. Applicant will be notified as to the results of the examination. Any correspondence concerning the application must include the following identification information: the U.S. APPLICATION NUMBER, FILING DATE, NAME OF APPLICANT, and TITLE OF INVENTION. Fees transmitted by check or draft are subject to collection. Please verify the accuracy of the data presented on this receipt. **If an error is noted on this Filing Receipt, please submit a written request for a Filing Receipt Correction. Please provide a copy of this Filing Receipt with the changes noted thereon. If you received a "Notice to File Missing Parts" for this application, please submit any corrections to this Filing Receipt with your reply to the Notice. When the USPTO processes the reply to the Notice, the USPTO will generate another Filing Receipt incorporating the requested corrections**

Applicant(s)

David Lymberopoulos, Houston, TX;
Benjamin R. Matthews, Missouri City, TX;

Power of Attorney: The patent practitioners associated with Customer Number 26290

Domestic Priority data as claimed by applicant

This appln claims benefit of 61/551,319 10/25/2011
and is a CIP of 13/195,662 08/01/2011
which claims benefit of 61/370,721 08/04/2010
and claims benefit of 61/415,238 11/18/2010

Foreign Applications (You may be eligible to benefit from the **Patent Prosecution Highway** program at the USPTO. Please see http://www.uspto.gov for more information.)

If Required, Foreign Filing License Granted: 06/04/2012

The country code and number of your priority application, to be used for filing abroad under the Paris Convention, is **US 13/480,704**

Projected Publication Date: 09/13/2012

Non-Publication Request: No

Early Publication Request: No
**** SMALL ENTITY ****

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 556

Title

SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

Preliminary Class

PROTECTING YOUR INVENTION OUTSIDE THE UNITED STATES

Since the rights granted by a U.S. patent extend only throughout the territory of the United States and have no effect in a foreign country, an inventor who wishes patent protection in another country must apply for a patent in a specific country or in regional patent offices. Applicants may wish to consider the filing of an international application under the Patent Cooperation Treaty (PCT). An international (PCT) application generally has the same effect as a regular national patent application in each PCT-member country. The PCT process **simplifies** the filing of patent applications on the same invention in member countries, but **does not result** in a grant of "an international patent" and does not eliminate the need of applicants to file additional documents and fees in countries where patent protection is desired.

Almost every country has its own patent law, and a person desiring a patent in a particular country must make an application for patent in that country in accordance with its particular laws. Since the laws of many countries differ in various respects from the patent law of the United States, applicants are advised to seek guidance from specific foreign countries to ensure that patent rights are not lost prematurely.

Applicants also are advised that in the case of inventions made in the United States, the Director of the USPTO must issue a license before applicants can apply for a patent in a foreign country. The filing of a U.S. patent application serves as a request for a foreign filing license. The application's filing receipt contains further information and guidance as to the status of applicant's license for foreign filing.

Applicants may wish to consult the USPTO booklet, "General Information Concerning Patents" (specifically, the section entitled "Treaties and Foreign Patents") for more information on timeframes and deadlines for filing foreign patent applications. The guide is available either by contacting the USPTO Contact Center at 800-786-9199, or it can be viewed on the USPTO website at http://www.uspto.gov/web/offices/pac/doc/general/index.html.

For information on preventing theft of your intellectual property (patents, trademarks and copyrights), you may wish to consult the U.S. Government website, http://www.stopfakes.gov. Part of a Department of Commerce initiative, this website includes self-help "toolkits" giving innovators guidance on how to protect intellectual property in specific countries such as China, Korea and Mexico. For questions regarding patent enforcement issues, applicants may call the U.S. Government hotline at 1-866-999-HALT (1-866-999-4158).

LICENSE FOR FOREIGN FILING UNDER

Title 35, United States Code, Section 184

Title 37, Code of Federal Regulations, 5.11 & 5.15

GRANTED

The applicant has been granted a license under 35 U.S.C. 184, if the phrase "IF REQUIRED, FOREIGN FILING LICENSE GRANTED" followed by a date appears on this form. Such licenses are issued in all applications where the conditions for issuance of a license have been met, regardless of whether or not a license may be required as set forth in 37 CFR 5.15. The scope and limitations of this license are set forth in 37 CFR 5.15(a) unless an earlier

license has been issued under 37 CFR 5.15(b). The license is subject to revocation upon written notification. The date indicated is the effective date of the license, unless an earlier license of similar scope has been granted under 37 CFR 5.13 or 5.14.

This license is to be retained by the licensee and may be used at any time on or after the effective date thereof unless it is revoked. This license is automatically transferred to any related applications(s) filed under 37 CFR 1.53(d). This license is not retroactive.

The grant of a license does not in any way lessen the responsibility of a licensee for the security of the subject matter as imposed by any Government contract or the provisions of existing laws relating to espionage and the national security or the export of technical data. Licensees should apprise themselves of current regulations especially with respect to certain countries, of other agencies, particularly the Office of Defense Trade Controls, Department of State (with respect to Arms, Munitions and Implements of War (22 CFR 121-128)); the Bureau of Industry and Security, Department of Commerce (15 CFR parts 730-774); the Office of Foreign AssetsControl, Department of Treasury (31 CFR Parts 500+) and the Department of Energy.

NOT GRANTED

No license under 35 U.S.C. 184 has been granted at this time, if the phrase "IF REQUIRED, FOREIGN FILING LICENSE GRANTED" DOES NOT appear on this form. Applicant may still petition for a license under 37 CFR 5.12, if a license is desired before the expiration of 6 months from the filing date of the application. If 6 months has lapsed from the filing date of this application and the licensee has not received any indication of a secrecy order under 35 U.S.C. 181, the licensee may foreign file the application pursuant to 37 CFR 5.15(b).

SelectUSA

The United States represents the largest, most dynamic marketplace in the world and is an unparalleled location for business investment, innovation and commercialization of new technologies. The USA offers tremendous resources and advantages for those who invest and manufacture goods here. Through SelectUSA, our nation works to encourage, facilitate, and accelerate business investment. To learn more about why the USA is the best country in the world to develop technology, manufacture products, and grow your business, visit SelectUSA.gov.

PATENT APPLICATION FEE DETERMINATION RECORD

Substitute for Form PTO-875

Application or Docket Number: 13/480,704

APPLICATION AS FILED - PART I

FOR	(Column 1) NUMBER FILED	(Column 2) NUMBER EXTRA	SMALL ENTITY RATE($)	SMALL ENTITY FEE($)	OR	OTHER THAN SMALL ENTITY RATE($)	OTHER THAN SMALL ENTITY FEE($)
BASIC FEE (37 CFR 1.16(a), (b), or (c))	N/A	N/A	N/A	95		N/A	
SEARCH FEE (37 CFR 1.16(k), (i), or (m))	N/A	N/A	N/A	310		N/A	
EXAMINATION FEE (37 CFR 1.16(o), (p), or (q))	N/A	N/A	N/A	125		N/A	
TOTAL CLAIMS (37 CFR 1.16(i))	21 minus 20 =	* 1	x 30 =	30	OR		
INDEPENDENT CLAIMS (37 CFR 1.16(h))	3 minus 3 =	*	x 125 =	0.00			
APPLICATION SIZE FEE (37 CFR 1.16(s))	If the specification and drawings exceed 100 sheets of paper, the application size fee due is $310 ($155 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).			0.00			
MULTIPLE DEPENDENT CLAIM PRESENT (37 CFR 1.16(j))				0.00			
* If the difference in column 1 is less than zero, enter "0" in column 2.			TOTAL	560		TOTAL	

APPLICATION AS AMENDED - PART II

		(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	SMALL ENTITY RATE($)	SMALL ENTITY ADDITIONAL FEE($)	OR	OTHER THAN SMALL ENTITY RATE($)	OTHER THAN SMALL ENTITY ADDITIONAL FEE($)
AMENDMENT A	Total (37 CFR 1.16(i))	*	Minus	**	=	x =		OR	x =	
	Independent (37 CFR 1.16(h))	*	Minus	***	=	x =		OR	x =	
	Application Size Fee (37 CFR 1.16(s))									
	FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))							OR		
						TOTAL ADD'L FEE		OR	TOTAL ADD'L FEE	

		(Column 1) CLAIMS REMAINING AFTER AMENDMENT		(Column 2) HIGHEST NUMBER PREVIOUSLY PAID FOR	(Column 3) PRESENT EXTRA	RATE($)	ADDITIONAL FEE($)	OR	RATE($)	ADDITIONAL FEE($)
AMENDMENT B	Total (37 CFR 1.16(i))	*	Minus	**	=	x =		OR	x =	
	Independent (37 CFR 1.16(h))	*	Minus	***	=	x =		OR	x =	
	Application Size Fee (37 CFR 1.16(s))									
	FIRST PRESENTATION OF MULTIPLE DEPENDENT CLAIM (37 CFR 1.16(j))							OR		
						TOTAL ADD'L FEE		OR	TOTAL ADD'L FEE	

* If the entry in column 1 is less than the entry in column 2, write "0" in column 3.

** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 20, enter "20".

*** If the "Highest Number Previously Paid For" IN THIS SPACE is less than 3, enter "3".

The "Highest Number Previously Paid For" (Total or Independent) is the highest found in the appropriate box in column 1.

UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NUMBER	FILING OR 371(C) DATE	FIRST NAMED APPLICANT	ATTY. DOCKET NO./TITLE
13/480,704	05/25/2012	David Lymberopoulos	SAFO/0012USP1

CONFIRMATION NO. 9598

26290
PATTERSON & SHERIDAN, L.L.P.
3040 Post Oak Blvd.
Suite 1500
Houston, TX 77056

POA ACCEPTANCE LETTER

OC000000054645046

Date Mailed: 06/07/2012

NOTICE OF ACCEPTANCE OF POWER OF ATTORNEY

This is in response to the Power of Attorney filed 05/25/2012.

The Power of Attorney in this application is accepted. Correspondence in this application will be mailed to the above address as provided by 37 CFR 1.33.

/bto/

Office of Data Management, Application Assistance Unit (571) 272-4000, or (571) 272-4200, or 1-888-786-0101

PTO/SB/81 (07-08)
Approved for use through 12/31/2008. OMB 0651-0035
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

POWER OF ATTORNEY OR REVOCATION OF POWER OF ATTORNEY WITH A NEW POWER OF ATTORNEY AND CHANGE OF CORRESPONDENCE ADDRESS

Application Number	Not Yet Assigned
Filing Date	Herewith
First Named Inventor	David Lymberopoulos
Title	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
Art Unit	Unknown
Examiner Name	Unknown
Attorney Docket No.	SAFO/0012USP1

I hereby revoke all previous powers of attorney given in the above-identified application.

☐ A Power of Attorney is submitted herewith.

OR

☒ I hereby appoint Practitioner(s) associated with the following Customer Number as my/our attorney(s) or agent(s) to prosecute the application identified above, and to transact all business in the United States Patent and Trademark Office connected therewith: 26290

OR

☐ I hereby appoint Practitioner(s) named below as my/our attorney(s) or agent(s) to prosecute the application identified above, and to transact all business in the United States Patent and Trademark Office connected therewith:

Name	Registration Number	Name	Registration Number

Please recognize or change the correspondence address for the above-identified application to:

☒ The address associated with the above-mentioned Customer Number:

OR

☐ The address associated with Customer Number:

OR

☐ Firm or Individual Name

Address

I am the:

☒ Applicant/Inventor.

OR

☐ Assignee of record of the entire interest. See 37 CFR 3.71.
Statement under 37 CFR 3.73(b) (Form PTO/SB/96) submitted herewith or filed on _____

SIGNATURE of Applicant or Assignee of Record

Signature		Date	5/24/12
Name	David Lymberopoulos	Telephone	713-306-7531

NOTE: Signatures of all the inventors or assignees of record of the entire interest or their representative(s) are required. Submit multiple forms if more than one signature is required, see below*.

*TOTAL OF 2 FORMS ARE SUBMITTED.

2290020

PTO/SB/81 (07-08)
Approved for use through 12/31/2008. OMB 0651-0035
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

POWER OF ATTORNEY OR REVOCATION OF POWER OF ATTORNEY WITH A NEW POWER OF ATTORNEY AND CHANGE OF CORRESPONDENCE ADDRESS

Application Number	Not Yet Assigned
Filing Date	Herewith
First Named Inventor	David Lymberopoulos
Title	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
Art Unit	Unknown
Examiner Name	Unknown
Attorney Docket No.	SAFO/0012USP1

I hereby revoke all previous powers of attorney given in the above-identified application.

☐ A Power of Attorney is submitted herewith.

OR

☒ I hereby appoint Practitioner(s) associated with the following Customer Number as my/our attorney(s) or agent(s) to prosecute the application identified above, and to transact all business in the United States Patent and Trademark Office connected therewith: 26290

OR

☐ I hereby appoint Practitioner(s) named below as my/our attorney(s) or agent(s) to prosecute the application identified above, and to transact all business in the United States Patent and Trademark Office connected therewith:

Name	Registration Number	Name	Registration Number

Please recognize or change the correspondence address for the above-identified application to:

☒ The address associated with the above-mentioned Customer Number:

OR

☐ The address associated with Customer Number:

OR

☐ Firm or Individual Name

Address

I am the:

☒ Applicant/Inventor.

OR

☐ Assignee of record of the entire interest. See 37 CFR 3.71.
Statement under 37 CFR 3.73(b) (Form PTO/SB/96) submitted herewith or filed on

SIGNATURE of Applicant or Assignee of Record

Signature	BR Matt	Date	5/24/12
Name	Benjamin R. Matthews	Telephone	720-470-7531

NOTE: Signatures of all the inventors or assignees of record of the entire interest or their representative(s) are required. Submit multiple forms if more than one signature is required, see below*.

*TOTAL OF 2 FORMS ARE SUBMITTED.
2290020

Electronic Patent Application Fee Transmittal

Application Number:	
Filing Date:	
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Filer:	Barden Todd Patterson/Sharlyn Guthrie
Attorney Docket Number:	SAFO/0012USP1

Filed as Small Entity

Utility under 35 USC 111(a) Filing Fees

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Basic Filing:				
Utility filing Fee (Electronic filing)	4011	1	95	95
Utility Search Fee	2111	1	310	310
Utility Examination Fee	2311	1	125	125
Pages:				
Claims:				
Claims in excess of 20	2202	1	30	30
Miscellaneous-Filing:				
Petition:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD($)
Patent-Appeals-and-Interference:				
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				
Miscellaneous:				
		Total in USD ($)		**560**

Electronic Acknowledgement Receipt

EFS ID:	12865967
Application Number:	13480704
International Application Number:	
Confirmation Number:	9598
Title of Invention:	SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE
First Named Inventor/Applicant Name:	David Lymberopoulos
Customer Number:	26290
Filer:	Barden Todd Patterson/Sharlyn Guthrie
Filer Authorized By:	Barden Todd Patterson
Attorney Docket Number:	SAFO/0012USP1
Receipt Date:	25-MAY-2012
Filing Date:	
Time Stamp:	12:08:02
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	Credit Card
Payment was successfully received in RAM	$560
RAM confirmation Number	9760
Deposit Account	
Authorized User	

File Listing:

Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)

1		SAFO0012USP1PA.pdf	2348281 eee0c6b470fe5c74ff949aba5b845a9ba63905e9	yes	49
	Multipart Description/PDF files in .zip description				
	Document Description		**Start**	**End**	
	Specification		1	44	
	Claims		45	48	
	Abstract		49	49	
Warnings:					
Information:					
2	Drawings-only black and white line drawings	SAFO0012USP1DRAWINGS.pdf	327349 97c8a86eb3925e519a725963d241a12934fbc46b	no	15
Warnings:					
Information:					
3	Oath or Declaration filed	SAFO0012USP1DEC.pdf	144004 20e6ef6b143aef388af8e6be490cde012f7fc343	no	3
Warnings:					
Information:					
4	Power of Attorney	SAFO0012USP1POA.pdf	92567 d82c4fbacfd124fa904990c469d4a06c7a275128	no	2
Warnings:					
Information:					
5	Fee Worksheet (SB06)	fee-info.pdf	36654 a44fc4741296082b16fd07da06875874b8f3c526	no	2
Warnings:					
Information:					
		Total Files Size (in bytes):	2948855		

This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503.

New Applications Under 35 U.S.C. 111

If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application.

National Stage of an International Application under 35 U.S.C. 371

If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course.

New International Application Filed with the USPTO as a Receiving Office

If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.

UNITED STATES PATENT APPLICATION FOR:

SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

INVENTORS:

DAVID LYMBEROPOULOS

BENJAMIN ROBERT MATTHEWS

ATTORNEY DOCKET NUMBER: SAFO/0012US.P1

Customer Number: 26290
PATTERSON & SHERIDAN, L.L.P.
3040 Post Oak Blvd. Suite 1500
Houston, TX 77056

SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

CROSS REFERENCE TO RELATED APPLICATION

[0001] This application claims benefit of U.S. Provisional Patent Application Serial No. 61/551,319, filed October 25, 2011, and is a continuation-in-part of co-pending U.S. Patent Application Serial No. 13/195,662, filed August 1, 2011, which claims benefit of U.S. Provisional Patent Application Serial No. 61/370,721, filed August 4, 2010, and U.S. Provisional Patent Application Serial No. 61/415,238, filed November 18, 2010, the disclosures of which are herein incorporated by reference in their entirety.

BACKGROUND OF THE INVENTION

Field of the Invention

[0002] Embodiments of the invention relate to a wellhead control system for oil and gas wells. In particular, embodiments of the invention relate to systems and methods of an emergency shut down control system for surface and subsurface safety valves. Embodiments of the invention further relate to systems and methods of a relief valve control system.

Description of the Related Art

[0003] A wellhead system may be used to control the flow of fluids recovered from an oil and gas well in a safe and efficient manner. The wellhead system may include a variety of flow control devices, such as valves, which are operable direct fluid flow through a tubing system connected to the wellhead system. Fluids can be directed downstream of the wellhead system via the tubing system for further processing and/or storage.

[0004] The wellhead system may include surface and subsurface safety valves that are connected to the tubing system and are operable to shut off fluid flow through the tubing system in the event of an emergency in the well or at a location

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 569

downstream of the wellhead system. Prior art safety valves are generally in fluid communication with the tubing system, and utilize the fluids therein for operation. For example, the pressure in the tubing system may be directly tied into the safety valves to actuate the valves into an open position, thereby allowing fluid flow through the system. In the event of an emergency, such as a rupture in the tubing system downstream of the safety valve or a drop in pressure in the well, as the pressure in the tubing system drops, so does the pressure in the safety valves. The safety valves are configured to move into a closed position after the pressure therein falls below a minimum pressure, thereby closing fluid flow through the tubing system and shutting in the wellhead system. Some safety valves may also be equipped with relief valves that are operable to block pressure from entering the valve and exhaust the pressure in the valve, thereby allowing the valve to move into a closed position.

[0005] There are numerous drawbacks to the prior art safety valve systems. One drawback includes the reliance of the safety valves on fluid pressure in the tubing system. These safety valves cannot be unilaterally operated as desired. Another drawback includes regular, manual maintenance of the safety valves to ensure that they are fully operational. Another drawback includes the potential pollution to the environment when fluid in the safety valves are exhausted into the atmosphere.

[0006] In some wellbore operations, such as when conducting a fracking operation, a high volume pressurized fluid is pumped to a manifold, which directs the fluid to one or more wells for fracturing the formation below. In the event that flow through the flow or fluid lines to the manifold and/or in the wells experience an interruption or become plugged, the highly pressurized fluid volume can cause catastrophic failure of the fluid lines, the wells, and any other equipment surrounding the wellsite, which can even potentially harm workers at the wellsite. Conventional relief valve systems are inefficient at detecting a failure, have slow response times, and/or are only one-time use, which require complete replacement in the event of operation.

[0007] Therefore, there is a need for a new and improved safety control valve system that is self reliant, can be remotely operated and monitored real-time, and can automatically shut in and/or relieve a wellhead system in the event of an emergency or when desired.

SUMMARY OF THE INVENTION

[0008] In one embodiment, a control system for controlling a safety valve attached to a flow line at a wellsite is provided. The control system includes a housing. The control system further includes a controller assembly disposed within the housing. The controller assembly is configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property. Further, the control system includes a valve assembly disposed within the housing and in communication with the controller assembly. The control system further includes a compressor assembly disposed within the housing and in communication with the controller assembly. Additionally, the control system includes a power source disposed within the housing. The power source is configured to supply power to the controller assembly, the valve assembly, and the compressor assembly. The controller assembly is operable to cause the compressor assembly to supply pneumatic fluid to the safety valve to actuate the safety valve to an open position, wherein the controller assembly is operable to cause the valve assembly to actuate the safety valve to a closed position.

[0009] In one embodiment, a method for controlling a safety valve attached to a flow line at a wellsite is provided. The method includes the step of positioning a control system adjacent the safety valve. The control system has a controller assembly, a compressor assembly, and a power source disposed within a housing of the control system. The method further includes the step of supplying pneumatic fluid from the compressor assembly to the safety valve to open the safety valve. The method also includes the step of receiving a signal in the controller assembly corresponding to a sensed physical property in the flow line. Additionally, the method

includes the step of closing the safety valve in response to a comparison of the sensed physical property to a pre-set condition.

[0010] In one embodiment, a control system for controlling a safety valve attached to a flow line at a wellsite may comprise a controller assembly configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property; a valve assembly in communication with the controller assembly; and a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the safety valve to actuate the safety valve to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the safety valve to a second position.

[0011] In one embodiment, a method for controlling a safety valve attached to a flow line at a wellsite may comprise providing a control system for positioning adjacent to the safety valve, wherein the control system includes a housing, a controller assembly, a fluid drive assembly, and a valve assembly; supplying fluid to the safety valve using the fluid drive assembly to actuate the safety valve into a first position; monitoring a physical property in the flow line using the controller assembly; and actuating the valve assembly using the controller assembly to actuate the safety valve into a second position based upon a comparison of the monitored physical property to a predetermined condition.

[0012] In one embodiment, a method for controlling a safety valve attached to a flow line at a wellsite may comprise providing a remotely operable control system for positioning adjacent to the safety valve; actuating the safety valve into a closed position using the control system; monitoring fluid pressure in the flow line using a transducer in communication with the control system while maintaining the safety valve in the closed position; and actuating the safety valve into an open position using the control system when the monitored fluid pressure reaches or exceeds a predetermined fluid pressure to relieve fluid pressure in the flow line.

BRIEF DESCRIPTION OF THE DRAWINGS

[0013] So that the manner in which the above recited features of the invention can be understood in detail, a more particular description of the invention, briefly summarized above, may be had by reference to embodiments, some of which are illustrated in the appended drawings. It is to be noted, however, that the appended drawings illustrate only typical embodiments of this invention and are therefore not to be considered limiting of its scope, for the invention may admit to other equally effective embodiments.

[0014] Figure 1 illustrates a wellhead control system according to one embodiment.

[0015] Figure 2 illustrates a safety valve control system according to one embodiment.

[0016] Figure 3 illustrates a surface safety valve according to one embodiment.

[0017] Figure 4 is a sectional view of a gate valve, an actuator, a mechanical override, and a safe mode indicator.

[0018] Figure 5 is a sectional view of the gate valve in an open position after a manual operation of the mechanical override.

[0019] Figure 6 is a sectional view of the gate valve in the open position after an automatic operation of the actuator and with the safe mode indicator indicating that the gate valve is operating in a safe mode.

[0020] Figure 7 is a sectional view of the gate valve in the open position after the automatic operation of the actuator, the mechanical override having been partially actuated, and the safe mode indicator indicating that the gate valve is not operating in the safe mode.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 573

[0021] Figure 8 is a cross-sectional view of the mechanical override along section line 8-8 in Figure 4.

[0022] Figure 9 is a sectional view of the gate valve in an open position after an automatic operation of the actuator.

[0023] Figures 10A-10H and 11-11D illustrate a valve assembly according to one embodiment.

[0024] Figure 12 is a sectional view of a valve in a fail-safe opened position.

[0025] Figure 13 illustrates a safety valve control system according to one embodiment.

[0026] Figure 14 illustrates a well control system according to one embodiment.

[0027] Figure 15 illustrates the well control system according to one embodiment.

DETAILED DESCRIPTION

[0028] Figure 1 illustrates a wellhead control system 100 of an oil/gas well according to one embodiment. The wellhead control system 100 is configured to control the recovery of fluids, such as hydrocarbons, from a reservoir through a primary wellbore 105. The wellhead control system 100 includes a tree 110 having a series of valve and flow control devices, a surface safety valve 120 in communication with the tree 100 via tubing 115, and a subsurface safety valve 130 in communication with the tree 100 via tubing 125. The subsurface safety valve 130 may also be in communication with a well production flow line 145 used to recover oil and/or gas from the oil/gas well. The surface safety valve 120 may also be in communication with a surface production flow line 135 used to direct any recovered fluids to one or more locations downstream of the wellhead control system 100 for further processing and/or storage. In one embodiment, the safety valves 120, 130 may include pneumatically or hydraulically actuated valves. In one embodiment, the safety valves

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 574

120, 130 may include pneumatic valves that are operated using hydraulic fluid. Each of the safety valves 120, 130 may include a self contained emergency shut down ("ESD") control system, identified as items 200, 300, and 700, respectively, that (1) may be operable to automatically close the safety valves 120, 130; (2) may be operable to be continuously monitored and/or operated (opened and closed) in real-time from a remote location; and (3) may be operable to verify at all times the operating condition/characteristics of the safety valves 120, 130, and various other components of the control system.

[0029] The ESD control systems 200, 300 may be "self-contained," which means that they do not depend on any external pneumatic, hydraulic, mechanical, or electrical sources for their operation to shut down the oil/gas well. For example, if there is a rupture of a production flow line downstream from the surface safety valve 120, and/or if there is a loss of well pressure at the subsurface safety valve 130, the ESD control systems 200, 300 are operable to effectively close the safety valves 120, 130, thereby shutting in the oil/gas well, and alert the appropriate personnel that a shut-in has occurred without the assistance of any additional external pneumatic, hydraulic, mechanical, or electrical power sources. All of the operating fluids and mechanisms necessary to operate the safety valves 120, 130 are maintained within the ESD control systems 200, 300 so that there is no pollution of the environment, and so that any fluids and/or gases from the oil/gas well may be effectively contained therein without any additional external dependencies.

[0030] Figure 2 illustrates the ESD control system 200 according to one embodiment. Embodiments of the ESD control system 200 described herein are equally applicable to the ESD control system 300 (and vice versa). The ESD control system 200 may include a housing 210 for supporting a controller assembly 220, a power source 230, a pump assembly 240, a fluid reservoir 250, a valve assembly 260, and a solar panel assembly 270. The ESD control system 200 may also include one or more transducers/devices 280, 282, 284, 286, and 288 for monitoring and/or measuring one or more physical properties (further described below). In

embodiment, the ESD control system 200 may be configured to control one or more valves, such as flow control valves or choke valves, that are in communication with the flow lines of the valves 120, 130 to control fluid flow through the wellhead control system 100

[0031] The housing 210 may include any structural support member, such as an explosion-proof container, for protecting the components stored therein from damage and environmental elements. Appropriate ventilation of the housing 210 may be provided by ventilation holes and/or an independent solar powered fan mounted in or through the housing 210. The housing 210 may further include an access panel or door for ease of access to the housing's interior, and may be configured for attachment to the tree 110 or the respective surface and subsurface safety valve 120, 130. One or more manifold assembles 212, 214, 216 may be provided on the housing 210 for fluid and/or electrical connections between the housing 210 (and the components within the housing 210) and the safety valves 120, 130, the solar panel assembly 270, and the transducer 280. In one embodiment, the manifold assembly 216 includes a solar converting charger device. In one embodiment, the structural components of the ESD control systems 200, 300, to the extent possible, may be made from stainless steel.

[0032] The controller assembly 220 may be disposed in the housing 210 and may include a microprocessor unit 222, a display screen 224, and a keypad 226. In one embodiment, the controller assembly 220 may be weather-proof, and may be intrinsically safe to provide power as necessary to one or more components of the ESD control systems 200, 300. In one embodiment, the controller assembly 220 may be positioned external to and/or adjacent to the housing 210. The microprocessor unit 222 may include a programmable logic controller, including a supervisory control and data acquisition system (SCADA) that is in communication with the one or more transducers/devices 280, 282, 284, 286, and 288, as well as the pump and valve assemblies 240, 260. The microprocessor unit 222 may include a current regulator to provide low current transmission between the controller assembly 220 and the

various components of the control system. A watchdog sensor 228 may be used to monitor the operation of the microprocessor unit 222 and provide an alarm in the event of a failure. The controller assembly 220 may be operable to send and receive signals with a computer system 150 (such as a desktop computer, laptop computer, or personal digital assistant (PDA)) at a remote location from the wellhead control system 100. In one embodiment, the signals may be sent and/or received between the controller assembly 220 and the computer system 150 via wired and/or wireless telemetry means, including but not limited to electrical wires, fiber optical cables, radio frequency, infrared, microwave, satellite, and/or laser light communication. In this manner, the ESD control systems 200, 300, 700 can be monitored and operated remotely from one or more locations on-site or off-site relative to the wellhead control system 100. In one embodiment, the ESD control systems 200, 300, 700 may be configured for manual and/or remote operation on-site at the wellhead control system 100. In one embodiment, the controller assembly 220 may be programmed with one or more trigger points, such as upstream and/or downstream high and/or lower pressure points, that will automatically trigger operation of the ESD control system 200, 700 upon sensing a pressure outside of the trigger point ranges. In one embodiment, the controller assembly 220 may be configured with a "master/slave" polling protocol or a "master/master" polling protocol as known in the art to retrieve and communicate information regarding the ESD control system 200, 700 as desired.

[0033] In one embodiment, the controller assembly 220 may be in communication with a pressure transducer 280 that is connected to the surface production flow line 135 as illustrated in Figure 1. The pressure transducer 280 can measure the pressure in the flow line 135 and communicate a signal corresponding to the measured pressure to the controller assembly 220. The pressure transducer 280 can be connected at various other locations within the wellhead control system 100, such as at the tree 110 or the tubing 115, 125. In one embodiment, the transducer 280 can be used to measure fluid flow rate or detect hydrogen sulfide. In one embodiment, one or more transducers 280 may be used to measure and/or detect

additional well characteristics at the wellhead control system 100 and communicate the measured/detected well characteristics to the controller assembly 220 via a signal corresponding to the measurement or detection for comparison to one or more predetermined conditions.

[0034] Regarding the pressure transducer 280, the signal may be recorded and/or communicated to the computer system 150 via the controller assembly 220 to provide real-time monitoring of the pressure in the flow line 135. The measured pressure may be displayed on the display screen 224 and/or on a display screen of the computer system 150. In response to the measured pressure, the controller assembly 220 may be configured to operate the respective safety valve 120, 130 to which it is connected. For example, the controller assembly 220 may be used to direct the pump assembly 240 and the valve assembly 260 to supply fluid from the fluid reservoir 250 to the surface safety valve 120 to open the valve. Upon receiving the signal from the controller assembly 220, the valve assembly 260 may be configured to open a circuit defined by lines 211, 213, 215 between the surface safety valve 120 and the fluid reservoir 250 to allow the pump assembly 240 to direct pressurized fluid from the fluid reservoir 250 to the surface safety valve 120, thereby opening the surface safety valve 120. The surface safety valve 120 may be maintained in the open position while the pressure transducer 280 continuously monitors the pressure in the flow line 135. The controller assembly 220 may be programmed to close the surface safety valve 120 upon receiving a signal from the pressure transducer 280 that corresponds to a pressure measurement that is greater than or less than a predetermined condition, such as a pre-set pressure range. The pre-set pressure range may be input into the controller assembly 220 by manual entry using the keypad 226 and the display screen 224. The pre-set pressure range may also be input into the controller assembly 220 remotely from the computer system 150. When the signal is received from the pressure transducer 280 that the pressure in the flow line 135 falls outside of the pre-set pressure range stored in the microprocessor unit 222, the controller assembly 220 may automatically direct the

valve assembly 260 and/or the pump assembly 240 to return the fluid from the surface safety valve 120 to the fluid reservoir 250. Upon receiving the signal from the controller assembly 220, the valve assembly 260 may be configured to open a circuit defined by lines 211, 217 between the surface safety valve 120 and the fluid reservoir 250 to allow the pressurized fluid to dump into the fluid reservoir 250, thereby closing the surface safety valve 120. In one embodiment, a closing pressure generated by the surface safety valve 120 may be used to force the fluid into the fluid reservoir 250. Continuous real-time monitoring of the pressure in the flow line 135 may be used to verify that the surface safety valve 120 has been closed.

[0035] The ESD control systems 200, 300, 700 may be adjusted at anytime and can be configured to shut in the wellhead control system 100 at anytime manually and/or remotely. In particular, the microprocessor unit 222 can be programmed with one or more pre-set conditions, manually using the display screen 224 and keypad 226 and/or remotely via the computer system 150. The pre-set conditions may be changed at anytime. And when a signal is received from one or more of the various transducers/devices and/or the computer system 150 that conflicts with the pre-set conditions when compared, the controller assembly 220 may be operable to automatically close the safety valve 120, 130 to which it is connected. The controller assembly 220 may be operable when the signal is above the pre-set condition or when the signal is below the pre-set condition. Continuous real-time monitoring of the ESD control systems 200, 300, 700 may be used to verify the operating condition/characteristics of the wellhead control system 100 components at all times.

[0036] In one embodiment, the ESD control systems 200, 300, 700 may communicate an auditory, visual, or other similar type of sensory signal that the wellhead control system 100 has been shut in. In one embodiment, the controller assembly 220 may send a signal to the computer system 150 that can be converted into an alarm to alert an operator of the shut-in. In one embodiment, the controller assembly 220 may send a signal to trigger an indication device 282, such as an

auditory and/or visual alarm disposed interior or exterior of the housing 120, to alert an operator within close proximity of the wellhead control system 100 of the shut-in.

[0037] In one embodiment, the ESD control systems 200, 300, 700 may include an emergency shutdown device 284 manually and/or remotely operable to automatically give an alarm and send a signal to the controller assembly 220 to shut in the wellhead control system 100. In one embodiment, the ESD control systems 200, 300, 700 may include a fire device 286 that senses heat, and automatically gives an alarm and shuts in the wellhead control system 100 via the controller assembly 220 when the measured heat exceeds a certain temperature. In one embodiment, the ESD control systems 200, 300, 700 may include an anti-intrusion device 288 that when activated automatically gives an alarm and shuts in the wellhead control system 100 via the controller assembly 220, for example when a theft is attempted or the control system sustains some type of structural damage. In one embodiment, one or more of the transducers 282, 284, 286, 288 may be used to detect hydrogen sulfide (H2S), other gases and vapors, and/or the level of fluid in one or more storage tanks that are in fluid communication with the valves 120, 130. Each of the devices 284, 286, 288 may be continuously monitored real-time using the controller assembly 220 via the computer system 150 to verify operating conditions/characteristics of the wellhead control system 100.

[0038] Power may be provided to the controller assembly 220 and the pump assembly 240 from the power source 230. The power source 230 may be operable to provide a low current (amp) stream to the controller assembly 220 and/or the pump assembly 240. In one embodiment, the power source 230 may include an intrinsically-safe battery, such as a 12 or 24 volt, direct current, explosion-proof power supply. In one embodiment, the power source 230 may include a watchdog sensor 232 to communicate to the computer system 150 via the controller assembly 220 a failure of the power source. The watchdog sensor 232 may also give an auditory or visual alarm to alert an operator onsite that the power source 230 is low and/or dead. The controller assembly 220 may be configured to automatically shut in

the wellhead control system 100 upon receiving a signal from the sensor 232. In one embodiment, the power source 230 may be a (re-chargeable) power supply that is supported by the solar panel assembly 270. The solar panel assembly 270 may include one or more solar panels 272 connected to the exterior of the housing 210 to consume light energy from the sun to generate electricity. The solar panels 272 may be connected to the exterior of a housing 730 in the ESD control system 700. An intrinsically safe voltage controller 274 may deliver electrical current at an appropriate voltage, 12 or 24 volts for example, to the power source 230, which in turn supplies power to the controller assembly 220 and/or pump assembly 240. In one embodiment, the solar panel assembly 270 may be configured to provide enough power to the ESD control systems 200, 300, 700 to open and close the safety valves 120, 130 ten or more times from about two hours of sunlight per day.

[0039] In one embodiment, the pump (or fluid drive) assembly 240 may include an intrinsically safe motor 242 and a pump 244, which may each be located in the explosion-proof housing 210. The pump 244 may include a rotary piston pump with about a 100 to 10,000 psi range. The pump assembly 240 may pump pneumatic and/or hydraulic fluid from the fluid reservoir 250 to actuate the safety valve 120, 130 to which it is connected.

[0040] In one embodiment, the fluid reservoir 250 may be configured to store an amount of operating fluid sufficient to actuate the safety valve 120, 130 to which it is connected. The operating fluid may include air, water, propylene glycol, and other valve operating fluids known in the art. In one embodiment, the fluid reservoir 250 may include a level gauge 252, such as a sight glass, to indicate the level of fluid in the fluid reservoir 250. The fluid reservoir may also include a level sensor 252 that is in communication with the controller assembly 220 and is operable to monitor in real-time the level of fluid in the fluid reservoir 250. In the event that the level of fluid falls below a pre-set limit, due to evaporation of the fluid for example, the level sensor 252 may provide an alarm to alert an operator on-site at the wellhead control system 100 and/or at the remote location via the controller assembly 220 and the computer

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 581

system 150. The controller assembly 220 may automatically shut in the wellhead control system 100 upon receiving a signal from the level sensor 252.

[0041] In one embodiment, the valve assembly 260 may include one or more (intrinsically safe) valves 262 to control and direct communication between the pump assembly 240, the fluid reservoir 250, and the safety valve 120, 130 to which it is connected. The one or more valves 262 may include solenoid valves, shuttle valves, and/or any other type of valves operable to open and close the fluid circuits between the pump assembly 240, the fluid reservoir 250, and the safety valve 120, 130 to which it is connected. The valve assembly 260 may include an internal relief valve and/or circuit to rapidly expel the fluid from the safety valves 120, 130 to the fluid reservoir 250 to ensure quick closure of the safety valves 120, 130. The valve assembly 260 may include one or more gauges, such as pressure gauge 264, which can be visually inspected to monitor the pressure in the valve assembly 260 flow lines. In one embodiment, the pressure gauge 264 may be configured to shut off the pump assembly 240 when the pressure in the actuator of the safety valves 120, 130 reaches a pre-determined pressure setting. The one or more valves 262 may be controlled by the controller assembly 220 as described above.

[0042] In one embodiment, the display screen 224 and/or one or more gauges may be mounted through a front panel of the housing 210, 730 to indicate pressure within the various valves and lines in fluid communication with the ESD control systems 200, 300, 700 and the wellhead control system 100.

[0043] Figure 3 illustrates a surface safety valve 120 according to one embodiment. The surface safety valve 120 may include a valve actuator 122 for moving a gate valve 124 between an open and closed position. Pressurized fluid from the fluid reservoir 250 of the ESD control system 200 or pressurized fluid from the ESD control system 700 may be supplied to a chamber 123 of the valve actuator 122 via tubing 201 to open the gate valve 124. A biasing member 127, such as a spring disposed within the valve actuator 122 may be used to close the gate valve

124 when the force of the biasing member exceeds the fluid pressure in the valve actuator chamber 123. The valve actuator 122 may also include a top shaft 126 that can be used to manually actuate the valve actuator 122 by rotation of a hand wheel 128 to open and close the gate valve 124. The top shaft 126 may also be used as a visual indication to determine whether the gate valve 120 is in an open or closed position. For example, when the top shaft 126 is fully extended outward from the upper end of the valve actuator 122, the gate valve 124 may be in a closed position, and when the top shaft 126 is retracted into the upper end of the valve actuator 122, the gate valve 124 may be in an open position.

[0044] In one embodiment, the ESD control systems 200, 300, 700 may include a position indication assembly 290 that is operable to indicate whether the surface safety valve 120 is in an open or closed position, including any partial open/closed position therebetween, based on the location of the top shaft 126. As illustrated in Figure 3, when the top shaft 126 is in a fully extended position, the surface safety valve 120 is in the closed position. As the surface safety valve 120 begins to open and is moved either manually or automatically to the open position, the top shaft 126 will retract into the upper end of the valve actuator 122. The position indication assembly 290 may include one or more sensors 292 operable to sense the extension and retraction of the top shaft 126. The sensors 292 may communicate a signal to the controller assembly 220 corresponding to the measured position, which may then send a signal to the computer system 150 and display the measured position on a display screen. In this manner, an operator can continuously monitor and verify the position of the surface safety valve 120 at all times. The position indication assembly 290 can also be used to verify that the surface safety valve 120 is closed in the event that one of the other ESD control system 200, 700 components initiated a shut-in of the wellhead control system 100. In one embodiment, the sensors 292 may include magnetic sensors operable to sense a magnetic material of the top shaft 126. For example, one or more sensors 292 may be positioned at various locations along the longitudinal stroke of the top shaft 160 during opening and closing of the gate valve

124. When the top shaft 160 is fully extended, all of the sensors 292 may sense the magnetic material of the shaft, thereby indicating that the gate valve 124 is closed. However, when the top shaft 160 is fully retracted, only the sensors 292 closest to the upper end of the valve actuator 122 may sense the magnetic material of the shaft, thereby indicating that the gate valve 124 is open. In one embodiment, the sensors 292 may include other types of position sensors known in the art to monitor and measure the position of the top shaft 126.

[0045] In one embodiment, the ESD control system 200, 300, 700 can be used to partially stroke the safety valves 120, 130. In one embodiment, the controller assembly 220 may be configured to direct the pump assembly 240 and valve assembly 260 to supply an amount of operating fluid to the safety valves 120, 130 to partially open the safety valves. In one embodiment, the controller assembly 220 may be configured to direct the pump assembly 240 and valve assembly 260 to return an amount of operating fluid from the safety valves 120, 130 to partially close the safety valves. The controller assembly 220 may be programmed to automatically conduct a partial stroke of the safety valves 120, 130 after a pre-set amount of time or other condition. The controller assembly 220 may be manually and/or remotely operable to conduct a partial stroking of the safety valve to which it is connected when desired. The sensors 292 of the position indication assembly 290 can be used to monitor and verify the partial stroke of the safety valves 120, 130, based on the position of the top shaft 126. The partial stroking of the safety valves 120, 130 can assist in preventing/removing build-up of debris within the valves from the fluids flowing therethrough, which can potentially prevent complete opening and/or closing of the valves when necessary.

[0046] In one embodiment, the ESD control systems 200, 300, 700 may be configured to perform a specific sequential opening and closing of the safety valves 120, 130 when starting up or shutting in the wellhead control system 100. In one embodiment, either ESD control system 200, 300, 700 may initiate closure or opening of the surface safety valve first 120, and then closure or opening of the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 584

subsurface safety valve 130. In one embodiment, either ESD control system 200, 300, 700 may initiate closure or opening of the subsurface safety valve first 130, and then closure or opening of the surface safety valve 120. In one embodiment, if one of the ESD control system 200, 700 components initiates a shut-in, the controller assembly 220 may automatically send a signal to the computer system 150, which may then automatically send a signal to the controller assembly of the ESD system 300 to initiate closing of the subsurface safety valve 130. After closure of the subsurface safety valve 130 is verified by the ESD control system 300 via the computer system 150, another signal may be sent to the ESD control system 200, 700 to then initiate closing of the surface safety valve 120. The reverse process may be performed beginning with the ESD control system 300 if closure of the surface safety valve 120 is required prior to closure of the subsurface safety valve 130.

[0047] In one embodiment, a method for controlling a wellhead control system having a plurality of valves, including a surface safety valve and a subsurface safety valve, may include producing power with solar panel assembly and delivering the produced power to a controller assembly and to a pump assembly that supplies operating fluid to the valves, the control assembly operable to monitor a variety of conditions in an oil/gas well and at the wellhead control system. The controller assembly may be used to control the operation of the pump assembly and the valves manually, remotely, automatically, and/or in response to one or more pre-set conditions programmed in the controller assembly. The solar panel assembly may provide to a power source or directly to a pump assembly to operate a motor of the pump assembly, which in turn operates a pump of the pump assembly. The motor may be controlled by the controller assembly. The controller assembly may include a microprocessor and its related apparatuses, circuits, devices, switches, etc. The power produced by the solar panel assembly may be stored in a power source, such as in one or more battery apparatuses for use on demand. The use and flow of the stored power may be controlled and/or monitored by the controller assembly. The pump assembly may supply operating fluid (hydraulic and/or pneumatic) at a low or

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 585

high pressure to operate either of both of the safety valves as directed by the controller assembly. The pre-set condition may include a fluid flow parameter, a flow line condition, an alarm, an emergency condition, and/or an intrusion of the components of the wellhead control system, including the valves and the controller assembly.

[0048] The voltages of power from the solar panel assembly may be controlled with a voltage controller having a sensor provide an alert signal, an alarm signal, and/or a shut-off signal if a pre-set voltage is exceeded or is not provided. One or more sensors may be provided to sense an amount and/or pressure of available operating fluid in any or all of the flow lines used and/or in a fluid reservoir, the sensor(s) providing a signal to indicate fluid volume and/or fluid pressure to the controller assembly. In response to the signal, the controller assembly may operate one or more of the valves and/or shut in the wellhead control system. The controller assembly may signal other devices, such as the pump assembly or a valve assembly to increase fluid pressure and/or fluid amount in some or all of the flow lines. A sensor may signal the controller assembly when a fire is detected and provide a fire alarm. The controller assembly may provide a fire alarm signal to a remote location and/or operate the valves to shut in the wellhead control system. The signals of alarm, intrusion, etc. may be provided at the immediate area of the wellhead control system and to a remote location via known transmission methods.

[0049] The controller assembly may be operable to monitor the various components of the wellhead control system and employing intrinsically safe components. A single controller assembly may be operable to control a surface safety valve, a subsurface safety valve, as well as one or more additional valves in communication with the wellhead control system. The controller assembly may be operable to control the subsurface safety valve with an electric submersible pump. The controller assembly may be operable to remotely shut in the wellhead control system using switches interconnected therewith, telephone, radio, SCADA, DCS and/or satellite signals. One or more sensors may be use to detect dangerous gases

in the oil/gas well and/or at the wellhead control system and producing an alarm signal in response. A thermoelectric generator may be used instead of or in addition to a solar panel assembly. The pre-set condition(s) may include one or more of the following: the presence of fire or dangerous gases, intrusion by unwanted humans or animals, vandalism, damage, or destruction of equipment used in the wellhead control system, or too low to too high fluid pressures, fluid volumes, power amperages, or power voltages. In one embodiment, that various components of the control system may be weather proof and "intrinsically safe," i.e. that they require vastly reduced power levels and therefore minimize the risk of sparks and explosions, e.g. less than 100 milliamps.

[0050] Figure 4 is a sectional view of a mechanical override 400, an actuator 401, a gate valve 402, and a safe mode indicator 403. The actuator 401 couples to a valve body 404 of the gate valve 402. A bonnet assembly can provide an interface between the gate valve 402 and the actuator 401. During an automatic operation of the gate valve 402, hydraulic or pneumatic pressure enters a chamber 406 of the actuator 401 defined by a cover 408 of the actuator 401 and a diaphragm 410 positioned over an operator member 412. The operator member 412 moves in response to the hydraulic or pneumatic pressure within the chamber 406 and against a biasing force supplied by a spring 418. A valve stem 414 coupled to a sliding gate 416 of the gate valve 402 moves in response to the movement of the operator member 412. In this manner, the automatic operation of the actuator 401 moves the sliding gate 416 of the gate valve 402 between a closed position shown in Figure 4 and an open position as shown in Figure 6.

[0051] In one embodiment, the actuator 401 may be selected from the pneumatic and hydraulic actuators described in detail in U.S. Patent No. 6,450,477 which is herein incorporated by reference in its entirety. The actuator 401 may be selected from any other actuator known in the industry for moving the sliding gate 416 of the gate valve 402 between the open and closed positions by automatic operation.

[0052] When using the automatic operation of the actuator 401, the biasing force of the spring 418 is configured to act as a fail-safe mechanism. When the pressure in the actuator 401 is removed, inadvertently or otherwise, the spring 418 will move the gate valve 402 into a fail-safe closed position illustrated in Figure 4 or a fail-safe opened position illustrated in Figure 12. Although the mechanical override 400 may provide an additional means to actuate the gate valve 402 in the event of a failure, such as a loss of pressure, it may also override the fail-safe mechanism. The mechanical override 400 may prevent the spring 418 from moving the gate valve 402 into the fail-safe closed position or the fail-safe opened position. The gate valve 402 is operating in a safe mode when the fail-safe mechanism has not been overridden by the mechanical override and is not prevented or inhibited from moving into the fail-safe closed position or the fail-safe opened position. Therefore, the safe mode indicator 403 is configured to provide a signal, such as a visual indication, communicating to a valve operator that the valve is or is not operating in the safe mode. The signal from the safe mode indicator 403 may also communicate that (1) the valve will move to the fail-safe closed position or the fail-safe opened position in the event of a pressure loss in the actuator, (2) the valve has been automatically actuated into the open position, and/or (3) the mechanical override will not disable or interfere with the fail-safe mechanism.

[0053] As illustrated in Figure 4, the mechanical override 400 is connected to the actuator 401 to provide a manual operation for moving the sliding gate 416 between open and closed positions. The mechanical override 400 includes a top shaft 460, a lever for manual rotation of the top shaft 460, such as a handwheel 500, a housing 450 having a longitudinal bore therethrough, a drive sleeve 504 rotationally locked to the housing 450, and a top seal cartridge 550. The housing 450 passes through an aperture 452 in the cover 408 of the actuator 401. A shoulder 454 formed by a portion of the housing 450 with an increased outer diameter provides a stop for positioning the housing 450 in the aperture 452 of the cover 408. The housing 450

may be secured to the cover 408 by any known means such as a thread or by welding.

[0054] The housing 450 includes an upper bore 509, an inner shoulder 511, a top bore 510, and a bottom bore 512. The inner shoulder 511 is disposed below the upper bore 509, the top bore 510 is disposed below the inner shoulder 511, and the bottom bore 512 is disposed below the top bore 510. The bottom bore 512 has an inner diameter greater than the top bore 510. A tapered shoulder 515 is located at the interface between the top bore 510 and the bottom bore 512.

[0055] The top seal cartridge 550 is disposed in the upper bore 509 and can be removed for replacement as a single unit without disassembling the actuator 401 or the mechanical override 400. The top seal cartridge 550 is preferably formed of a plastic-like material such as Delrin and is held in place by at least one retainer ring 552 which is preferably stainless steel. Accessibility to the retainer ring 552 without disassembly of the actuator 401 permits removal of the retainer ring 552 from the top of the housing 450, thereby allowing removal and replacement of the top seal cartridge 550. The top seal cartridge 550 contains dual reciprocating top shaft seals 556 and dual static seals 558 to ensure seal integrity and long life. The top seal cartridge 550 incorporates rod wiper 554 to keep a shaft sealing region therebelow clean of dirt, grease, and other contaminants for longer life of the top shaft seals 556. The rod wiper 554 is preferably made from Molythane 90. These and other seals may be T-seals or other substantially elastomeric seals, such as O-ring seals.

[0056] The top shaft 460 extends through the longitudinal bore of the housing 450, the top seal cartridge 550, and the drive sleeve 504. The inner diameter of the inner shoulder 511 is greater than the outer diameter of the top shaft 460, but smaller than the outer diameter of the drive sleeve 504. The inner shoulder 511 permits axial movement of the top shaft 460 therethrough while providing a backstop for the drive sleeve 504. The top shaft 460 may also include a shoulder configured to engage an

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 589

upper shoulder of the drive sleeve 504 to prevent removal of the top shaft 460 from the upper end of the drive sleeve 504.

[0057] The drive sleeve 504 is disposed in the housing 450 and is movable within the top bore 510 and the bottom bore 512. The drive sleeve 504 includes a threaded bore 516 that corresponds with a drive thread 514 on an outside surface of the top shaft 460. In one embodiment, the drive thread 514 is an Acme thread capable of functioning under loads and includes a small number of threads per inch, such as five, in order to decrease the work required to manually operate the actuator 401. The drive thread 514 permits unassisted rotation of the top shaft 460 with the handwheel 500. The threaded engagement permits relative axial movement between the top shaft 460 and the drive sleeve 504 within the housing 450. The outer diameter of the upper portion of the drive sleeve 504 is substantially the same as the inner diameter of the top bore 510 of the housing 450. One or more seals 518, such as o-rings, are provided on the outer diameter of the upper portion of the drive sleeve 504 to form a sealed engagement with the top bore 510 of the housing 450. One or more seals 519, such as o-rings, are provided on the inner diameter of the upper portion of the drive sleeve 504 to form a sealed engagement with the top shaft 460.

[0058] In one embodiment, the lower end of the drive sleeve 504 is configured to move axially relative to the bottom bore 512 of the housing 450 while being rotationally locked relative to the housing 450. Any known rotational locking assembly that prevents rotation of the drive sleeve 504 while permitting the drive sleeve 504 (and the top shaft 460) to move axially within the housing 450 during the automatic operation of the actuator 401 may be used. Figure 8 illustrates a new rotational locking assembly by showing one embodiment of a cross-section at sectional line 8-8 in Figure 4. Figure 8 illustrates the outer diameter of the lower end of the drive sleeve 504 having an oval shape that corresponds to an oval shape of the inner diameter of the housing 450. The oval shaped diameters provide a physical interference that rotationally locks the drive sleeve 504 to the housing 450 without

inhibiting axial movement of the drive sleeve 504 relative to the housing 450. The outer diameter of the drive sleeve 504 and the bore of the housing 450 may be formed in a number of ways known by one of ordinary skill in the art to prevent relative rotational movement while permitting relative axial movement. In one embodiment, the lower portion of the drive sleeve 504 may have one or more splines that extend into one or more corresponding longitudinal grooves formed in the bottom bore 512 of the housing 450 to permit relative axial movement but prevent relative rotational movement. In one embodiment, the lower portion of the drive sleeve 504 may be keyed to the bottom bore 512 with a pin that extends through corresponding longitudinal grooves in the drive sleeve 504 and the bottom bore 512.

[0059] A coupling assembly 458 prevents longitudinal separation between a retaining nut 462 secured to the operator member 412 and the top shaft 460 while isolating rotational movement of the top shaft 460 from the actuator 401 and the gate valve 402. The coupling assembly 458 includes a female coupler 464 and ball bearings 468. The lower end of the top shaft 460 rotates around the upper end of the retaining nut 462 and against the ball bearings 468. A bottom shoulder 472 on the top shaft 460 is secured against the ball bearings 468, which are positioned on the upper end of the retaining nut 462, by the female coupler 464. The female coupler 464 is connected to the upper end of the retaining nut 462 and includes an upper shoulder that engages the bottom shoulder 472 of the top shaft 460 to prevent separation of the shaft from the retaining nut 462 and thus the actuator 401 and the gate valve 402. The top shaft 460 freely rotates relative to the retaining nut 462 and eliminates the transmission of torque to the valve stem 414, the sliding gate 416, and/or components of the actuator 401 when using the mechanical override 400.

[0060] Embodiments of the invention do not require the coupling assembly connecting the top shaft 460 with the operator member 412. The top shaft 460 of the mechanical override 400 may contact and apply force directly to a portion of the actuator 401, such as the retaining nut 462 or the operator member 412 depending on the type of actuator used. For example, the end of the top shaft 460 may directly

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 591

contact the upper end of the retaining nut 462. The solid retaining nut 462 may include a separate locking device to prevent the retaining nut 462 from unthreading from the operator member 412 since the top shaft 460 rotates during the manual operation of the mechanical override 400. Alternatively, other known rotation isolation means may be provided to prevent transference of the rotation of the top shaft 460 to other components within the actuator 401 and the gate valve 402.

[0061] Referring to Figure 6, a chamber 610 is formed within the housing 450 between the top seal cartridge 550 and the drive sleeve 504. The chamber 610 is sealed at an upper end by the engagement between the top seal cartridge 550, the upper bore 509, and the top shaft 460, and at a lower end by the engagement between the drive sleeve 504, the top bore 510, and the top shaft 460. Fluid communication may be established between the chamber 610 and the actuator 401 when the drive sleeve 504 is moved into the bottom bore 512, as shown in Figure 6. In particular, the seals 518 of the drive sleeve 504 are moved across the tapered shoulder 515 into the bottom bore 512, thereby releasing the sealed engagement with the top bore 510. When the drive sleeve 504 is located in the bottom bore 512 and fluid communication is established between the chamber 610 and the actuator 401, the gate valve 402 is operating in the safe mode. When the gate valve 402 is operating in the safe mode, the valve may be moved to the fail-safe closed position (shown in Figure 4) or the fail-safe opened position (shown in Figure 12) by the fail-safe mechanism without interference from the mechanical override 400.

[0062] The safe mode indicator 403 communicates to a valve operator when the valve is operating in the safe mode. The safe mode indicator 403 includes an indication device 600, such as a sensor, that is connected to the housing 450. The indication device 600 is in fluid communication with the chamber 610 via an orifice 615 located through the housing 450. The pressure in the chamber 610 may be used to actuate the indication device 600 to communicate a signal to the valve operator.

[0063] In one embodiment, when the chamber 610 is at a first pressure, the indication device 600 may communicate a first signal to the valve operator to indicate that the valve is not operating in the safe mode. When the chamber 610 is at a second pressure that is different than the first pressure, the indication device 600 may communicate a second signal that is different than the first signal to the valve operator to indicate that the valve is operating in the safe mode. The pressure in the chamber 610 may be the pressure directed into the actuator 401 when fluid communication is established between the chamber 610 and the actuator 401, as shown in Figure 6. The pressure in the chamber 610 is communicated to the indication device 600 through the orifice 615 to actuate the indication device 600. In one embodiment, the first and/or second pressures may be in a range from about 0 PSI to about 80 PSI, 150 PSI, or greater. In one embodiment, the first and/or second signals may be a visual indication, such as a colored light or marker, an auditory indication, and any other type of signal known to one of ordinary skill.

[0064] In one embodiment, the indication device 600 may be any commercial sensor, such as a pressure sensor, that can be used to indicate a pressure change in the chamber 610. In one embodiment, the indication device 600 may be a Rotowink Indicator, commercially available through Norgen Ltd. The Rotowink Indicator is a spring-loaded device actuated by air pressure for use in visual monitoring of pneumatic or fluidic circuits. The device uses two contrasting colors (e.g. black, red, yellow, green) on a rotating ball that can be viewed from any angle to indicate the presence or absence of pressure.

[0065] The operation of the invention illustrated in Figures 4, 5, 6, 7, 12 will now be described. Figure 4 illustrates the gate valve 402 in the fail-safe closed position. The spring 418 provides a force configured to bias the valve stem 414, the operator member 412, the top shaft 460, and the drive sleeve 504 in an upward direction, thereby positioning the sliding gate 416 in the closed position. Seating of the sliding gate 416 in the closed position limits the upward axial movement of the top shaft 460 and the drive sleeve 504. The mechanical override 400 is in an un-actuated position

and does not interfere with the closing of the gate valve 402. The bias of the spring 418 raises the top shaft 460 to an extended position providing a visual indication that the gate valve 402 is in the closed position. The safe mode indicator 403 may provide a first visual indication that the gate valve 402 is not automatically actuated into the operating safe mode and/or the chamber 610 is not pressurized or has experienced a pressure change.

[0066] Figure 12 illustrates the gate valve 402 in the fail-safe opened position. The spring 418 provides a force configured to bias the valve stem 414, the operator member 412, the top shaft 460, and the drive sleeve 504 in an upward direction, thereby positioning the sliding gate 416 in the opened position. Seating of the sliding gate 416 in the opened position limits the upward axial movement of the top shaft 460 and the drive sleeve 504. The mechanical override 400 is in an un-actuated position and does not interfere with the opening of the gate valve 402. The bias of the spring 418 raises the top shaft 460 to an extended position providing a visual indication that the gate valve 402 is in the opened position. The safe mode indicator 403 may provide a first visual indication that the gate valve 402 is not automatically actuated into the operating safe mode and/or the chamber 610 is not pressurized or has experienced a pressure change.

[0067] Figure 5 illustrates the gate valve 402 in an open position after a manual operation of the actuator 401 using the mechanical override 400. To move the sliding gate 416 to the open position using the mechanical override 400, the valve operator manually turns the handwheel 500 to provide rotation to the top shaft 460. Rotation of the handwheel 500 rotates the top shaft 460 to advance the top shaft 460 through the drive sleeve 504 across the length of the drive thread 514. As the top shaft 460 rotates, the top shaft 460 advances through the drive sleeve 504 until the upper portion of the drive thread 514 is located at the lower portion of the threaded bore 516 of the drive sleeve 504. During the manual operation, the inner shoulder 511 provides the backstop that prevents the drive sleeve 504 from moving relative to the housing 450. The manual rotation of the handwheel 500 mechanically advances

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 594

the top shaft 460 through the housing 450 to either directly or indirectly axially move the valve stem 414 to place the gate valve 402 in the open position. The top shaft 460 is mechanically driven against the bias of the spring 418, thereby compressing the spring 418. The top shaft 460 lowers during the manual operation to a retracted position and provides a visual indication that the gate valve 402 is in the open position. The valve operator may also check the safe mode indicator 403 to determine whether the gate valve 402 is operating in the safe mode. The pressure in the chamber 610 should not have significantly changed between the operation of the gate valve 402 from the fail-safe closed position, shown in Figure 4, to the open position by manual operation, shown in Figure 5. Thus, the safe mode indicator 403 communicates the same first visual indication to the valve operator, which has not changed by the mechanical operation of the gate valve 402. The safe mode indicator 403 may therefore indicate that the gate valve 402 is not operating in the safe mode, has not been automatically actuated, has been actuated (at least partially) using the mechanical override 400, and/or may be prevented from moving into the fail-safe closed position or the fail-safe opened position.

[0068] Figure 6 illustrates the gate valve 402 in the open position after an automatic operation of the actuator 401. Pressure is directed into the chamber 406 of the actuator 401 to overcome the bias of spring 418 and advance the top shaft 460, the drive sleeve 504, the operator member 412, and the valve stem 414 in a downward direction to position the sliding gate 416 into the open position. The top shaft 460 and the drive sleeve 504 are moved together axially within the bore of the housing 450 until the seals 518 on the drive sleeve 504 are moved across the tapered shoulder 515 and into the bottom bore 512. Fluid communication is established between the chamber 610 and the chamber 406. The pressure in the chamber 406 is communicated to the indication device 600 via the orifice 615, thereby actuating the indication device 600. The pressure change in the chamber 610 actuates the safe mode indicator 403 to communicate a second visual indication that is different than the first visual indication. Since the top shaft 460 also lowers

during the automatic operation to the retracted position and provides a visual indication that the gate valve 402 is in the open position, the valve operator may use the safe mode indicator 403 to determine whether the gate valve 402 is operating in the safe mode. The second visual indication may therefore indicate that the gate valve 402 is operating in the safe mode, has not been mechanically actuated, has been automatically actuated, and/or will move into the fail-safe closed position or the fail-safe opened position upon release of pressure in the actuator 401. When operating in the safe mode, the upper end of the drive sleeve 504 is located at least a distance X from the inner shoulder 511 of the housing 450. In this position, the mechanical override 400 will not disable or interfere with the fail safe mechanism. When the pressure in the actuator 401 is released, the drive sleeve 504 is located a sufficient distance from the inner shoulder 511 so as not to limit upward axial movement of the top shaft 460 and thus the valve stem 414 and the sliding gate 416. In this manner, the sliding gate 416 may move into the fail-safe closed position or the fail-safe opened position.

[0069] Figure 7 illustrates the gate valve 402 in an open position after an automatic operation of the actuator 401 and a partial operation of the mechanical override 400. Before and/or after automatic actuation of the gate valve 402, the mechanical override 400 may be actuated at least partially, inadvertently or otherwise. If the handwheel 500 has been rotated one or more times, the top shaft 460 and the drive sleeve 504 will move relative to each other in an offset position illustrated in Figure 7. When in the offset position and if the valve is automatically actuated, then the upper end of the drive sleeve 504 may be positioned a distance Y from the inner shoulder 511, which would prevent the gate valve 402 from moving to the fail-safe closed position or the fail-safe opened position. In one embodiment, the distance Y may be any distance that is less than the distance X identified in Figure 6. When the pressure in the actuator 401 is released, the upper end of the drive sleeve 504 would backstop on the inner shoulder 511 before the sliding gate 416 closes, and limit the upward axial movement necessary to move the sliding gate 416 into the

fail-safe closed position or the fail-safe opened position. Depending on the amount of offset between the drive sleeve 504 and the top shaft 460, the sliding gate 416 may be located in a partially open/closed position. Also, when in the gate valve 402 is automatically actuated and the drive sleeve 504 is located the distance Y from the inner shoulder 511, the chamber 610 remains isolated from fluid communication with the chamber 406 by the seals 518 and 519. Any slight actuation of the mechanical override 400 may offset the top shaft 460 and the drive sleeve 504 enough to prevent the seals 518 from moving across the tapered shoulder 515 during automatic actuation.

[0070] Since the top shaft 460 may still visually indicate that the valve 402 is in the open position in Figure 7, the valve operator may also check the safe mode indicator 403 to determine whether the gate valve 402 is operating in the safe mode. The pressure in the chamber 610 should not have significantly changed since it is isolated from the chamber 406 by the seals 518 and 519. Thus, the safe mode indicator 403 communicates the same first visual indication to the valve operator, which has not changed by the automatic actuation of the gate valve 402. The safe mode indicator 403 may therefore indicate that the gate valve 402 is not operating in the safe mode, has been actuated (at least partially) using the mechanical override 400, and/or may be prevented from moving into the fail-safe closed position or the fail-safe opened position. While the actuator 401 is pressurized, the valve operator may rotate the handwheel 500 to advance the drive sleeve 504 into the bottom bore 512 until the gate valve 402 is operating in the safe mode. The valve operator may rotate the handwheel 500 until the safe mode indicator 403 changes from the first visual indication to the second visual indication, e.g. when fluid communication is established between the chamber 406 and the chamber 610, to ensure that the gate valve 402 is operating in the safe mode. Alternatively, the valve operator may release the pressure in the actuator 401 to permit the drive sleeve 504 to backstop against the inner shoulder 511, and then rotate the handwheel 500 to move the mechanical override 400 into the un-actuated position so that the top shaft 460 and

the drive sleeve 504 are not in an offset position as described above. The actuator 401 may be re-actuated automatically so that the safe mode indicator 403 indicates that the valve is operating in the safe mode.

[0071] Figure 9 illustrates the gate valve 402 in an open position after an automatic operation of the actuator 401 according to one embodiment. The gate valve 402, the actuator 401, and the mechanical override 400 illustrated in Figure 9 may each include the embodiments described above with respect to Figures 4-8. Figure 9 further illustrates a bore 462 disposed through the top shaft 460, a check valve 464 disposed in a lower end of the top shaft 460 and in communication with the bore 462, and a retaining member 466 coupled to the top shaft 460 to support the check valve 464 in the lower end of the top shaft 460. In one embodiment, the bore 462 may be disposed through the top shaft 460 in any manner known by one of ordinary skill in the art to allow fluid communication between the chamber 610 and the chamber 406. In one embodiment, the check valve 464 may be any type of valve known by one of ordinary skill in the art, such as a one-way valve, that is operable to control the flow of fluid through the bore 462 in either direction. In one embodiment, the retaining member 466 may be any type of member known by one of ordinary skill in the art, such as a retainer ring, that is operable to maintain the check valve 462 in engagement with the top shaft 460 and/or the bore 462. The top shaft 460 illustrated in Figure 9 may be used in any of the embodiments described with respect to Figure 4-8.

[0072] In operation, the bore 462 may be configured to relieve any fluid pressure that is located in the chamber 610, which may cause a pressure lock and prevent the fail-safe mechanism from closing the gate valve 402. For example, when the gate valve 402 is operating in the safe mode as illustrated in Figure 9, the chamber 610 is in fluid communication with the chamber 406 of the actuator 401 and is filled with pressurized fluid. As the pressure in the chamber 406 is reduced, the spring 418 begins to move the gate valve 402 into the closed position, as illustrated in Figure 4, and the chamber 610 is sealed upon engagement of the seals 518 with the inner

surface of the top bore 510. Any fluid that may be retained in the chamber 610 is relieved through the bore 462 into the chamber 460. In one embodiment, the fluid may be forced through the bore 462 and the check valve 464 under its own pressure and/or as it is pressurized as the volume of the chamber 610 is reduced by movement of the drive sleeve 504 toward the shoulder 511 via the spring 418. The check valve 464 may allow fluid to flow from the upper end of the top shaft 460, through the bore 462 and into the chamber 406, and prevent fluid from flowing into the bore 462 and thus into the chamber 610 from the lower end of the top shaft 460. In one embodiment, the top shaft 460 may include one or more ports 468 located adjacent to the outlet of the check valve 464 to assist with venting fluid pressure into the chamber 406. In one embodiment, one or more seals 519 may be situated between the top shaft 460 and the drive member 504 to prevent any unintended leak paths from communicating fluid to the bore 462 during operation of the gate valve 402.

[0073] In one embodiment, the ESD Control Systems 200, 300, 700 described herein with respect to Figures 1-3 and 13 may be used in combination with the mechanical override 400, the actuator 401, the gate valve 402, and/or the safe mode indicator 403 as described herein with respect to Figures 4-9. In one embodiment, the pressure transducer 280 illustrated in Figure 2 can be connected to the housing 450, similar to the indication device 600 illustrated in Figures 6, 7, and 9. The pressure transducer 280 may be operable to measure the pressure in the chamber 610 via the orifice 615 and send a signal to the controller assembly 220 corresponding to the measured pressure. The controller assembly 220 may then send a signal to the computer system 150 via wired or wireless telemetry for monitoring and display of the measured pressure in real time. In this manner, the ESD control systems 200, 300, 700 can be used to remotely monitor and verify whether the gate valve 402 is operating in the safe mode as described above.

[0074] Figures 10A-10H and 11-11D illustrate a valve assembly 1000 according to one embodiment. Figures 10A-10H illustrate a top perspective view, a left side view,

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 599

a bottom perspective view, a front view, a top view, a right side view, a bottom view, and a rear view, respectively, of the valve assembly 1000. Figure 11 illustrates a top view of the valve assembly 1000, and Figures 11A-11D illustrate cross sectional views A-A, B-B, C-C, and D-D, respectively, of the valve assembly 1000. The valve assembly 1000 may be used as the valve assembly 260 described above. The valve assembly 1000 includes a first body portion 1010, a second body portion 1015, a first seat 1020, and a second seat 1030. The first and second body portions 1010, 1015 may be formed from a single piece of material, or may include two separate pieces of material that are connected together. The first and/or second seats 1020, 1030 may be removably secured to the first body portion 1010 for accessing a gate 1055 that is movably disposed in the first body portion 1010 to control fluid communication therethrough. The first and second body portions 1010, 1015 may be provided with one or more mounting holes 1011, 1012, 1013 for securing the valve assembly 1000 within the housing 210 and/or to one or more components of the ESD control systems 200, 300. The first body portion 1010 may include a first fluid inlet 1040 for receiving fluid from the pump assembly 240. The first fluid inlet 1040 may include a fluid path 1041 disposed through the first body portion 1010 from a first end to a second end, adjacent to the first seat 1020. Second and third fluid inlets 1042, 1045 (the third fluid inlet 1045 being disposed through the first seat 1020) may optionally be provided to receive fluid from the pump assembly 240. As illustrated, the optional second and third fluid inlets 1042, 1045 are plugged with one or more sealing members, but include fluid paths that are in communication with the fluid path 1041 of the first fluid inlet 1040. The first body portion 1010 may also include a first fluid outlet 1050 for directing fluid to the actuator of the surface and/or subsurface safety valves 120, 130 to actuate the valves. The first fluid outlet 1050 may also include a fluid path 1051 disposed through the first body portion 1010 from a first end to a second end, adjacent to the second seat 1030. The first body portion 1010 may further include a fluid path 1052 that extends from the first seat 1020 to the second seat 1030 to provide fluid communication between the first fluid inlet 1040 and the first fluid outlet 1050. The gate 1055 may be disposed in the fluid path 1052 between

the first and second seats 1020, 1030 to control fluid communication between the first fluid inlet 1040, the first fluid outlet 1050, and a first relief outlet 1060 of the second seat 1030 as described below. One or more machining holes 1051, 1052 (illustrated as being plugged) may be formed in the first body portion 1010 to form the fluid paths disposed through the body as described herein.

[0075] During operation, fluid may flow through at least one of the fluid inlets 1040, 1042, 1045 past the gate 1055 that is disposed within the fluid path 1052 of the first body portion 1010 between the first and second seats 1020, 1030, and then through the fluid outlet 1050. While fluid is flowing through the valve assembly 1000 to the actuators of the valves 120 and/or 130, the pressure in the first body portion 1010 forces the gate 1055 to seal off communication with the first relief outlet 1060. The first relief outlet 1060 provides fluid communication to the fluid reservoir 250, to dump the fluid in the first body portion 1010 and the valve actuators when desired during operation. A second relief outlet 1070 may also be provided to quickly release fluid from the first body portion 1010 and the valve actuators. The second relief outlet 1070 may include a fluid path 1071 that intersects the fluid path 1041 of the first fluid inlet 1040, but which includes an in-line relief valve to release fluid from the fluid paths to the fluid reservoir 250 in the event that the pressure in the first body portion 1010 exceeds a pre-determined pressure. A pressure switch port 1019 may be disposed through the first body portion 1010 that intersects the fluid path 1051 of the first fluid outlet 1050. The pressure switch port 1019 may be used as a means to communicate the pressure in the first body portion 1010 to one or more sensors/transducers that are in communication with the ESD control systems 200, 300 and/or the controller assemblies 220, 320. Using the pressure measured by the sensors/transducers via the pressure switch port 1019, the controller assemblies 220, 320 may selectively control, e.g. turn on and off, the pump assemblies 240, 340 to actuate the valves 120, 130 as described herein.

[0076] The second body portion 1015 may include a fluid control outlet 1090 that directs flow from the fluid path 1041 of the first fluid inlet 1040 via a fluid path 1091 to

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 601

a control valve assembly, such as a solenoid valve assembly. The solenoid valve assembly may also be in communication with the controller assemblies 220, 320 to control operation (e.g. open and close) of the valve assembly 1000 to thereby control actuation of the valves 120, 130 as desired. The second body portion 1015 may further include a second fluid control outlet 1080 to release fluid from the fluid paths in the second body portion 1015 via a fluid path 1081 and the control valve assembly to the fluid reservoir 250. When the control valve assembly is actuated to dump fluid pressure to the fluid reservoir 250, the pressure release in the fluid path 1041 of the first fluid inlet 1040 and the back pressure in the fluid path 1051 of the first fluid outlet 1050 may move the gate 1055 to a position within the first body portion 1010 where the fluid in the first body portion 1010 and the valve actuators is quickly released to the fluid reservoir 250 via the first relief outlet 1060, the second relief outlet 1070, and/or the second fluid control outlet 1080. In this manner, the valve assembly 1000 may be selectively used to supply and maintain fluid in one or more valve actuators of the valves 120, 130, and to selectively release and dump fluid from the valve actuators to the fluid reservoir 250.

[0077] Figure 13 illustrates the ESD control system 700 according to one embodiment. Embodiments of the ESD control system 700 described herein may be applicable to the ESD control system 300. For convenience, the components in the ESD control system 700 that are similar to the components in the ESD control system 200 will be labeled with the same number indicator. The ESD control system 200 may include the housing 730 for supporting the controller assembly 220, the power source 230, a compressor (or fluid drive) assembly 740, a check valve 715, a pressure switch 710, a filter/dryer assembly 705, and the solar panel assembly 270. In one embodiment, the controller assembly 220 and/or any of the other components may be disposed external to and/or adjacent to the housing 730.

[0078] The ESD control system 700 may be "self-contained" or "stand-alone unit," which means that the ESD control system 700 does not depend on any external pneumatic, hydraulic, mechanical, or electrical sources for its operation to shut down

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 602

the oil/gas well. In other words, the power source 230, the compressor assembly 740 and other components are within the housing 730 and thus the ESD control unit 700 is an integral portable unit. For example, if there is a rupture of a production flow line downstream from the surface safety valve 120, and/or if there is a loss of well pressure at the subsurface safety valve 130, the ESD control system 700 is operable to effectively close the safety valves 120, 130, thereby shutting in the oil/gas well, and alert the appropriate personnel that a shut-in has occurred without the assistance of any additional external power sources, such as external compressors or motors.

[0079] The ESD control system 700 may also include one or more transducers/devices 280, 282, 284, 286, and 288 for monitoring and/or measuring one or more physical properties as described herein. The ESD control system 700 may be configured to control one or more valves, such as flow control valves or choke valves that are in communication with the flow lines of the valves 120, 130 to control fluid flow through the wellhead control system 100. The ESD control system 700 may also include a quick dump valve 725 in line 211. The quick dump valve 725 is a manual valve that is configured to exhaust pneumatic fluid to an area outside of the housing 730. Additionally, the check valve 715 may be located in the line 211. The check valve 715 is a valve that allows fluid flow in one direction, from the compressor assembly 744 to the valve 120, and restricts fluid flow in the opposite direction.

[0080] The housing 730 may include any structural support member, such as an explosion-proof container, for protecting the components stored therein from damage and environmental elements. Appropriate ventilation of the housing 730 may be provided by ventilation holes and/or an independent solar powered fan mounted in or through the housing 730. The housing 730 may further include an access panel or door for ease of access to the housing's interior, and may be configured for attachment to the tree 110 or the respective surface and subsurface safety valve 120, 130. In one embodiment, the structural components of the ESD control system 700,

to the extent possible, may be made from stainless steel. The controller assembly 220 may be disposed in the housing 730 and may include a microprocessor unit 222, a display screen 224, and a keypad 226. In one embodiment, the controller assembly 220 may be weather-proof, and may be intrinsically safe to provide power as necessary to one or more components of the ESD control system 700. The microprocessor unit 222 may include a programmable logic controller, including a supervisory control and data acquisition system (SCADA) that is in communication with the one or more transducers/devices 280, 282, 284, 286, and 288, as well as the compressor assembly 740 and valve assemblies 710, 720.

[0081] In one embodiment, the compressor assembly 740 may include an intrinsically safe motor 742 and a compressor 744, which may each be located in the explosion-proof housing 730. As set forth herein, the compressor assembly 740 may supply pneumatic fluid from a location outside the housing 730 to actuate the safety valve 120, 130 to which it is connected. The pneumatic fluid may be ambient fluid, such as air, outside the housing 730. In one embodiment, the compressor assembly 740 may have multiple compressors and/or motors in parallel.

[0082] In one embodiment, the pneumatic fluid may be supplied from an optional reservoir 735 located outside of the housing 730. The reservoir 735 may be connected to the filter/dryer assembly 705 for supplying fluid to the compressor assembly 740. The reservoir may also be connected to the valve assembly 720 and/or valve 725 for receiving fluid exhausted from the system. The reservoir 735 may include a level gauge, such as a sight glass, to indicate the level of fluid in the reservoir 735. The reservoir 735 may also include a level sensor that is in communication with the controller assembly 220 and is operable to monitor in real-time the level of fluid in the reservoir 735. In the event that the level of fluid falls below a predetermined limit (e.g. pre-set limit), due to evaporation of the fluid for example, the level sensor may provide an alarm to alert an operator on-site at the wellhead control system 100 and/or at the remote location via the controller assembly 220 and the computer system 150. The controller assembly 220 may automatically

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 604

shut in the wellhead control system 100 upon receiving a signal from the level sensor.

[0083] As set forth herein, the signal from the pressure transducer 280 may be recorded and/or communicated to the computer system 150 via the controller assembly 220 to provide real-time monitoring of the pressure in the flow line 135. The measured pressure may be displayed on the display screen 224 and/or on a display screen of the computer system 150. In response to the comparison of the measured pressure to one or more predetermined conditions, the controller assembly 220 may be configured to operate the respective safety valve 120, 130 to which it is connected. For example, the controller assembly 220 may be used to direct the compressor assembly 740 to supply pneumatic fluid, such as ambient air, to the surface safety valve 120 to open the valve. Upon receiving the signal from the controller assembly 220, the valve assembly 720 may be configured to open a circuit defined by lines 211, 215 between the surface safety valve 120 and the filter/dryer assembly 705 to allow the compressor assembly 740 to direct fluid from the fluid entering the filter/dryer assembly 705 to the surface safety valve 120, thereby opening the surface safety valve 120. The surface safety valve 120 may be maintained in the open position while the pressure transducer 280 continuously monitors the pressure in the flow line 135. The controller assembly 220 may be programmed to close the surface safety valve 120 upon receiving a signal from the pressure transducer 280 that corresponds to a pressure measurement that is greater than or less than a pre-set pressure range. The pre-set pressure range may be input into the controller assembly 220 by manual entry using the keypad 226 and the display screen 224. The pre-set pressure range may also be input into the controller assembly 220 remotely from the computer system 150. When the signal is received from the pressure transducer 280 that the pressure in the flow line 135 falls outside of the pre-set pressure range stored in the microprocessor unit 222, the controller assembly 220 may automatically direct the compressor assembly 740 to stop supplying pressurized fluid to the surface safety valve 120 and/or allowing the valve

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 605

assembly 720 to exhaust the pneumatic fluid, thereby closing the surface safety valve 120. Continuous real-time monitoring of the pressure in the flow line 135 may be used to verify that the surface safety valve 120 has been closed.

[0084] Power may be provided to the controller assembly 220 and the compressor assembly 740 from the power source 230. The power source 230 may be operable to provide a low current (amp) stream to the controller assembly 220 and/or the compressor assembly 740. The controller assembly 220 is configured to control the pressure switch 710, which can be visually inspected to monitor the pressure in the line 211. In one embodiment, the pressure switch 710 may be configured to shut off the compressor assembly 740 when the pressure in the actuator of the safety valves 120, 130 reaches a predetermined pressure setting.

[0085] Figure 14 illustrates a well control system 800 at a wellsite for conducting a wellbore operation, such as a fracturing operation. The well control system 800 may be configured with one or more of the control systems 200, 300, 700 as described herein. The well control system 800 includes a fluid supply 810, such as a reservoir or tank, or a vehicle comprising a storage tank for storing fluid. A pump 820, or other fluid drive assembly, is provided for pumping fluid from the fluid supply 810 to a well. In particular, fluid from the fluid supply 810 is pumped through flow or fluid line 811 to a manifold 830, which directs the pressurized fluid to one or more wellheads 840, 841, 842, 843 via fluid lines 831, 832, 833, 834, respectively. As illustrated, the wellhead 840 may control the pressurized fluid flow into a well 850 that intersects a formation 860 for conducting a fracturing operation as conventionally known in the art.

[0086] A fluid line 812 is in fluid communication with the fluid line 811 at a location downstream of the pump 820. The fluid line 812 may also be in fluid communication with the fluid supply 810 or with any other fluid reservoir type assembly. The safety valve 120 is in-line with the fluid line 812 for controlling fluid flow from the fluid line 811 to the fluid supply 810. The safety valve 120 may be configured as a fail-safe

open relief valve or a fail-safe close safety valve, and is operable using one or more of the control systems 200, 300, 700. The safety valve 120 is operable using a pneumatic/hydraulic working fluid, which may be supplied from a fluid reservoir internal or external of the control systems 200, 300, 700 (as described herein) and/or from the fluid supply 812 directly or via one of the fluid lines. The transducer 280, such as a pressure transducer, measures the pressure in the fluid line 812 and communicates the measured characteristic to the controller assemblies of the control systems 200, 300, 700, which compare the measured characteristic to one or more predetermined conditions. The computer system 150 enables remote monitoring, control and operation of the safety valve 120 using the control systems 200, 300, 700 as described herein.

[0087] In one embodiment, one or more fluid lines 812 may be provided for fluid communication between fluid lines 811, 831, 832, 833, 834 (including the manifold and/or wellheads) and the fluid supply 810 or other fluid reservoir. In one embodiment one or more safety valves 120 and/or control systems 200, 300, 700 may provided in-line with one or more of the fluid lines 811, 831, 832, 833, 834 (including the manifold and/or wellheads). In one embodiment, one or more transducers 280 may be provided for measuring physical properties (e.g. pressure, temperature, flow rate, flow volume, etc.) of one or more of the fluid lines 811, 831, 832, 833, 834 (including the manifold and/or wellheads).

[0088] In operation, the pump 820 may be actuated to pump fluid from the fluid supply 810 to the manifold 830 via fluid line 811. The safety valve 120 may be actuated into a closed position using a working fluid as directed by the control systems 200, 300, 700 to prevent or substantially restrict fluid flow through fluid line 812. The pressurized fluid may therefore be directed from the manifold 830 to the wellheads 840, 841 842, 843 via fluid lines 831, 832, 833, 834 for conducting a fracturing operation, such as in well formation 860. The safety valve 120 may be continuously monitored remotely using the computer system 150. The transducer 280 may also continuously monitor and measure physical properties, such as fluid

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 607

pressure, in fluid line 811 and communicate the measured physical properties to the control system 200, 300, 700 for comparing to one or more predetermined conditions. In the event that the pressure in the fluid line 811 exceeds a predetermined condition (as programmed into the controller assembly of the control system), the control system is operable to release the working fluid from maintaining the safety valve 120 in the closed position, and the safety valve 120 is operable to automatically move into the open position (such as by spring 418 or other biasing member) to relieve the pressure in the fluid line 811 and dump the pressurized fluid back into the fluid supply 810 or other reservoir via fluid line 812. The well control system 800 is therefore operable to prevent over pressurization or other conditions of the fluid lines 811, 831, 832, 833, 834 (including the manifold and/or wellheads) that can lead to failure.

[0089] After any remedial operations necessary to remove any restriction to flow to the wellheads, the control system 200, 300, 700 may be operable to actuate the safety valve 120 into the closed position to continue with one or more wellbore operations. Advantages of the well control system 800 include the ability to relieve high fluid volume, flow, and pressure quickly, efficiently, and repeatedly to prevent failure of the wellbore system. Additional advantages include the ability to remotely monitor and control the system 800.

[0090] In one embodiment, the control system 200, 300, 700 may be configured to actuate the safety valve 120 at a predetermined condition, such as a set pressure, which is below the rated working pressure of one or more of the fluid lines, manifolds, and/or wellheads. In the event that the pressure in the fluid lines reach or exceed the predetermined set pressure (as measured by the transducer 280), the control system 200, 300, 700 will actuate the safety valve 120 into the open position to relieve the excessive fluid pressure. In one embodiment, the control system 200, 300, 700 may be configured with a predetermined condition, such as a reset pressure. For example, in the event of actuation of the safety valve 120 due to a failure, the control system 200, 300, 700 may prevent operation of the safety valve 120 back into the

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 608

closed position until the transducer 280 measures the predetermined reset pressure in the fluid lines.

[0091] In one embodiment, the control system 200, 300, 700 may be configured to actuate the safety valve 120 in anticipation of a failure. For example, the control system 200, 300, 700 may include an electronic wave generator for generating a wave signal that corresponds to fluid flow volume, rate, pressure, etc., and which is monitored by the controller assembly for any changes or fluctuations that indicate a failure at one or more points in the well control system 800. In the event of an indication of failure, the control system 200, 300, 700 can operate the safety valve 120 for actuation into the open position.

[0092] In one embodiment, the control system 200, 300, 700 can monitor, track, and record the operation of the safety valve 120 and/or the transducer 280 measurements. In one embodiment, the control system 200, 300, 700 may be configured with one or more mechanical and/or electrical overrides for independent, manual, or direct operation of the safety valve 120. In one embodiment, a transducer 280 may be coupled to the safety valve 120 to monitor the working pressure within the valve actuator, which can help determine life of the valve, force required to actuate, and whether maintenance is required.

[0093] In one embodiment, the control system 200, 300, 700 may be configured to trigger or actuate one or more alarms or alerts (audio/visual) to indicate a potential or actual failure; that the safety valve 120 has been actuated; and/or one or more other conditions have been detected, such as H2S (or other harmful gases), fire, and/or damage to the control system. In one embodiment, the alarms or alerts may be communicated through the computer system 150. In one embodiment, the control system 200, 300, 700 may be configured to prevent remote operation in the event that the safety valve 120 has been actuated, and may require manual re-setting of the system.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 609

[0094] In one embodiment, the control system 200, 300, 700 may include a geographical positioning system for tracking the location of the control system and the safety valves, which may be displayed, monitored, and tracked using the computer system 100. In one embodiment, the control system 200, 300, 700 may store information related to a particular wellbore operation, including maintenance and operational history, employee contact information, and/or status of the safety valve. In one embodiment, the control system 200, 300, 700 may be configured to open and/or close the safety valve 120 within a predetermined time frame. In one embodiment, the control system 200, 300, 700 may be configured to actuate the safety valve 120 at one or more predetermined time intervals.

[0095] Figure 15 illustrates the well control system 800 according to one embodiment. The well control system 800 includes a gate valve 402 and a valve actuator 401, the operations of which are described above with respect to at least Figures 4-12. A pilot valve 870 (or other functionally similar type of mechanical, electrical, and/or hydraulic sensor) may be coupled to the valve actuator 401, and may be operable to control fluid communication between the valve actuator 401 and a fluid reservoir 875 via fluid line 872. A pump 876 may be provided to pump actuator fluid from the reservoir 875 to the valve actuator 401 to actuate the valve 402 into the closed position.

[0096] Upon actuation of the pilot valve 870, the actuator fluid may be released from the valve actuator 401 back to the reservoir 875, such that the valve 402 may be automatically biased into the open position. The pilot valve 870 may be actuated by fluid pressure via fluid line 871, which is in communication with fluid line 811. In the event that fluid pressure directed to the wellheads 840-843 exceeds a predetermined amount, the fluid pressure will actuate the pilot valve 870 (via fluid line 871) to release the actuator fluid from the valve actuator 401 to the reservoir 875 (via fluid line 872), and thereby automatically bias the valve 402 into the fail safe open position to release the excessive fluid pressure back to the fluid supply 810 (via fluid line 812) as described above.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 610

[0097] In one embodiment, the pilot valve 870 may operate as a check valve or one-way valve when in an un-actuated or first position, to allow actuator fluid to be pumped into the valve actuator 401 while preventing actuator fluid flow out of the valve actuator 401. When the pilot valve 870 is in an actuated or second position, actuator fluid may flow out of the valve actuator 401 to the reservoir 875. The pilot valve 870 may monitor and be in communication with the fluid pressure in any one of the flow lines 811 and 830-834. In one embodiment, the actuator fluid may be forced into the reservoir 875 by the biasing member 418 acting on the operating member 412 as described above.

[0098] While the foregoing is directed to embodiments of the invention, other and further embodiments of the invention may be devised without departing from the basic scope thereof, and the scope thereof is determined by the claims that follow.

Claims:

1. A control system for controlling a safety valve attached to a flow line at a wellsite, the control system comprising:

a controller assembly configured to receive a signal from a transducer connected to the flow line, wherein the signal corresponds to a measured physical property;

a valve assembly in communication with the controller assembly; and

a fluid drive assembly in communication with the controller assembly, wherein the controller assembly is operable to actuate the fluid drive assembly to supply fluid to the safety valve to actuate the safety valve to a first position, and wherein the controller assembly is operable to actuate the valve assembly to actuate the safety valve to a second position.

2. The system of claim 1, further comprising a housing for supporting the controller assembly, the valve assembly, and the fluid drive assembly.

3. The system of claim 2, wherein the fluid is supplied from a reservoir disposed outside of the housing.

4. The system of claim 1, wherein the fluid drive assembly is a compressor and the fluid is a pneumatic fluid.

5. The system of claim 1, wherein the fluid drive assembly is a pump and the fluid is a hydraulic fluid.

6. The system of claim 1, further comprising a power source for supplying power to the controller assembly, the valve assembly, and the fluid drive assembly.

7. The system of claim 1, wherein the first position a closed position and the second position is an open position.

8. The system of claim 1, further comprising a housing for supporting the fluid drive assembly, and a filter attached to the housing for filtering fluid entering the housing by the fluid drive assembly.

9. The system of claim 1, wherein the fluid is ambient air.

10. The system of claim 1, wherein the controller assembly is operable to communicate a signal corresponding to the measured physical property to a remote computer system.

11. The system of claim 1, wherein the controller assembly is a programmable logic controller, and wherein the valve assembly is operable to release or return fluid from the safety valve for actuating the safety valve to the second position.

12. A method for controlling a safety valve attached to a flow line at a wellsite, the method comprising:

providing a control system having a housing, a controller assembly, a fluid drive assembly, and a valve assembly;

supplying fluid to the safety valve using the fluid drive assembly to actuate the safety valve into a first position;

monitoring a physical property in the flow line using the controller assembly; and

actuating the valve assembly using the controller assembly to actuate the safety valve into a second position based upon a comparison of the monitored physical property to a predetermined condition.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 613

13. The method of claim 12, wherein the fluid is a pneumatic fluid disposed external to the housing, and further comprising filtering the pneumatic fluid as it enters the housing by the fluid drive assembly.

14. The method of claim 12, wherein the fluid is a hydraulic fluid disposed in a reservoir within the housing that is in fluid communication with the fluid drive assembly.

15. The method of claim 12, further comprising measuring the physical property using a transducer configured to communicate a signal corresponding to the measured physical property to the controller assembly.

16. The method of claim 12, wherein the first position is a closed position and the second position is an open position.

17. The method of claim 12, wherein the fluid is a pneumatic fluid, and wherein the fluid drive assembly is a compressor.

18. The method of claim 12, wherein the fluid is a hydraulic fluid, and wherein the fluid drive assembly is a pump.

19. The method of claim 12, further comprising communicating a signal from the controller assembly to a remote computer system, wherein the signal corresponds to an operational characteristic of the safety valve.

20. The method of claim 12, further comprising actuating the safety valve by communicating a signal from a remote computer system to the controller assembly.

21. A method for controlling fluid flow through a flow line at a wellsite, the method comprising:

providing a control system having a safety valve, a valve actuator, and a sensor;

actuating the safety valve into a closed position by supplying actuator fluid to the valve actuator;

monitoring fluid pressure in the flow line using the sensor while maintaining the safety valve in the closed position; and

actuating the sensor using fluid pressure in the flow line, thereby releasing the actuator fluid from the valve actuator and moving the safety valve into an open position to relieve fluid pressure in the flow line.

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 615

ABSTRACT OF THE DISCLOSURE

A safety valve control system may include a remotely operable control assembly, a first transducer, a valve assembly, and a compressor assembly in communication with the control assembly. The control assembly is operable to actuate the pump and valve assemblies to supply fluid to actuate the safety valve into open and closed positions, in response to one or more signals received from the first transducer. A method of operation may include maintaining the safety valve in an open or closed position while sensing a physical property with the control system; communicating a signal corresponding to the sensed physical property to the control system; and automatically closing or opening the safety valve in response to a comparison of the sensed physical property to a pre-set condition.

2209829_1

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 616




FIG. 1



150
270
200
272
274
210
282
284
286
288
226
224
222
220
214
228
280
264
212
120
262
260
211
232
217
250
240
213
252
230
242
244
215
216

FIG. 2




FIG. 3



500
552
460
550
556
554
450
509
558
403
511
400
518
504
519
510
516
514
515
8
8
472
464
468
512
452
454
462
458
406
410
408
401
412
418
414
404
402
416

FIG. 4




FIG. 5



500
550
400
600
403
511
460
615
610
510
X
515
518
512
504
406
401
412
418
414
402
416

FIG. 6



500
450
600
403
460
615
Y
610
504
515
516
512
514
401
406
412
418
414
402
416

FIG. 7




FIG. 8



500
550
400
600
403
511
460
615
610
510
X
462
515
518
519
512
504
406
401
464
466
468
412
418
414
402
416

FIG. 9




FIG. 10A




FIG. 10E




FIG. 10B




FIG. 10D




FIG. 10F




FIG. 10H




FIG. 10C




FIG. 10G

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 626




FIG. 11A




FIG. 11C




FIG. 11




FIG. 11D




FIG. 11B

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 627



500
552
460
550
556
554
450
509
558
403
511
400
518
504
519
510
516
514
515
8
8
472
464
468
512
452
454
462
458
406
410
408
401
412
418
414
404
402
416

FIG. 12



150
270
700
272
274
730
282
284
286
288
226
224
222
220
214
228
280
212
725
120
720
211
232
710
740
715
230
742
744
705
735
216
215

FIG. 13



150
200, 700
812
812
120
280
P
811
820
811
810
834
843
833
830
800
832
842
831
841
840
850
860

FIG. 14



150
875
872
401
870
871
812
812
876
402
P
811
820
811
810
834
843
833
830
800
832
842
831
841
840
850
860

FIG. 15

PTO/SB/01 (04-09)
Approved for use through 06/30/2010. OMB 0651-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

DECLARATION FOR UTILITY OR DESIGN PATENT APPLICATION (37 CFR 1.63)

[X] Declaration Submitted With Initial Filing *OR* [ ] Declaration Submitted after Initial Filing (surcharge (37 CFR 1.16 (f)) required)

Attorney Docket Number	SAFO/0012USP1
First Named Inventor	David Lymberopoulos
COMPLETE IF KNOWN	
Application Number	Not Yet Assigned
Filing Date	Herewith
Art Unit	Unknown
Examiner Name	Unknown

I hereby declare that: (1) Each inventor's residence, mailing address, and citizenship are as stated below next to their name; and (2) I believe the inventor(s) named below to be the original and first inventor(s) of the subject matter which is claimed and for which a patent is sought on the invention entitled:

SAFETY VALVE CONTROL SYSTEM AND METHOD OF USE

(Title of the Invention)

the specification of which

[X] is attached hereto

OR

[ ] was filed on (MM/DD/YYYY) [ ] as United States Application Number or PCT International Application Number [ ] and was amended on (MM/DD/YYYY) [ ] (if applicable).

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment specifically referred to above.

I acknowledge the duty to disclose information which is material to patentability as defined in 37 CFR 1.56, including for continuation-in-part applications, material information which became available between the filing date of the prior application and the national or PCT International filing date of the continuation-in-part application.

Authorization To Permit Access To Application by Participating Offices

[ ] If checked, the undersigned hereby grants the USPTO authority to provide the European Patent Office (EPO), the Japan Patent Office (JPO), the Korean Intellectual Property Office (KIPO), the World Intellectual Property Office (WIPO), and any other intellectual property offices in which a foreign application claiming priority to the above-identified patent application is filed access to the above-identified patent application. See 37 CFR 1.14(c) and (h). This box should not be checked if the applicant does not wish the EPO, JPO, KIPO, WIPO, or other intellectual property office in which a foreign application claiming priority to the above-identified patent application is filed to have access to the application.

In accordance with 37 CFR 1.14(h)(3), access will be provided to a copy of the above-identified patent application with respect to: 1) the above-identified patent application-as-filed, 2) any foreign application to which the above-identified application claims priority under 35 USC 119(a)-(d) if a copy of the foreign application that satisfies the certified copy requirement of 37 CFR 1.55 has been filed in the above-identified patent application; and 3) any U.S. application from which benefit is sought in the above-identified application.

In accordance with 37 CFR 1.14(c), access may be provided to information concerning the date of filing the Authorization to Permit Access to Application by Participating Offices.

DECLARATION — Utility or Design Patent Application

Claim of Foreign Priority Benefits

I hereby claim foreign priority benefits under 35 U.S.C. 119(a)-(d) or (f), or 365(b) of any foreign application(s) for patent, inventor's or plant breeder's rights certificate(s), or 365(a) of any PCT international application which designated at least one country other than the United States of America, listed below and have also identified below, by checking the box, any foreign application for patent, inventor's or plant breeder's rights certificate(s), or any PCT international application having a filing date before that of the application on which priority is claimed.

Prior Foreign Application Number(s)	Country	Foreign Filing Date (MM/DD/YYYY)	Priority Not Claimed	Certified Copy Attached? YES	NO
			☐	☐	☐
			☐	☐	☐

☐ Additional foreign application numbers are listed on a supplemental priority data sheet PTO/SB/02B attached hereto.

DECLARATION — Utility or Design Patent Application

Direct all correspondence to: ☒ The address associated with Customer Number: 26290 OR ☐ Correspondence address below

Name		
Address		
City	State	ZIP
Country	Telephone	Email

WARNING:

Petitioner/applicant is cautioned to avoid submitting personal information in documents filed in a patent application that may contribute to identity theft. Personal information such as social security numbers, bank account numbers, or credit card numbers (other than a check or credit card authorization form PTO-2038 submitted for payment purposes) is never required by the USPTO to support a petition or an application. If this type of personal information is included in documents submitted to the USPTO, petitioners/applicants should consider redacting such personal information from the documents before submitting them to the USPTO. Petitioner/applicant is advised that the record of a patent application is available to the public after publication of the application (unless a non-publication request in compliance with 37 CFR 1.213(a) is made in the application) or issuance of a patent. Furthermore, the record from an abandoned application may also be available to the public if the application is referenced in a published application or an issued patent (see 37 CFR 1.14). Checks and credit card authorization forms PTO-2038 submitted for payment purposes are not retained in the application file and therefore are not publicly available. Petitioner/applicant is advised that documents which form the record of a patent application (such as the PTO/SB/01) are placed into the Privacy Act system of records DEPARTMENT OF COMMERCE, COMMERCE-PAT-7, System name: *Patent Application Files.* Documents not retained in an application file (such as the PTO-2038) are placed into the Privacy Act system of COMMERCE/PAT-TM-10, System name: *Deposit Accounts and Electronic Funds Transfer Profiles.*

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under 18 U.S.C. 1001 and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

NAME OF SOLE OR FIRST INVENTOR: ☐ A petition has been filed for this unsigned inventor

Given Name (first and middle [if any]), Family Name or Surname

David Lymberopoulos

Inventor's Signature: DL Date 5-24-12

Residence: City, State, Country

11421 Todd Street
Houston, Texas 77055
U.S.A.

Citizenship: U.S.A.

Mailing Address: Same as above

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 633

NAME OF SECOND INVENTOR:	☐ A petition has been filed for this unsigned inventor
Given Name (first and middle [if any]), Family Name or Surname Benjamin R. Matthews	
Inventor's Signature: BR Matthews	Date 5/24/12
Residence: City, State, Country 3522 Rolling Green Lane Missouri City, Texas 77459 U.S.A. Citizenship: U.S.A.	
Mailing Address: Same as above	

KLX Energy Services LLC v. Safoco, Inc.
Safoco – Exhibit No. 2004
IPR2024-00198
Page 634