



US006092117A

United States Patent [19]
Gladwin et al.

[11] **Patent Number:** **6,092,117**
[45] **Date of Patent:** **Jul. 18, 2000**

- [54] **SYSTEM AND METHOD FOR
AUTOMATICALLY RECONNECTING A
WIRELESS INTERFACE DEVICE TO A
HOST COMPUTER**
- [75] Inventors: **S. Christopher Gladwin**, Chicago;
James Y. Wilson, Crystal Lake, both of
Ill.
- [73] Assignee: **Packard Bell NEC**, Sacramento, Calif.
- [21] Appl. No.: **08/543,425**
- [22] Filed: **Oct. 16, 1995**

Related U.S. Application Data

- [63] Continuation-in-part of application No. 08/300,500, Sep. 2,
1994.
- [51] **Int. Cl.⁷** **G06F 13/00**
- [52] **U.S. Cl.** **709/239; 709/230; 709/200**
- [58] **Field of Search** 364/146, 424.1,
364/514 BS, 514 B; 379/58; 455/91; 375/219;
395/200.01–200.09, 200.11, 200.14, 200.2,
200.3, 200.54, 200.67, 200.8, 200.69

- [56] **References Cited**

U.S. PATENT DOCUMENTS

4,005,388	1/1977	Morley et al.	341/23
4,310,720	1/1982	Check, Jr.	380/25
4,876,742	10/1989	Vacon et al.	455/66
4,878,051	10/1989	Andros et al.	340/825.44
4,916,441	4/1990	Gombrich	345/169
4,942,534	7/1990	Yokoyama et al.	364/468.23
4,974,173	11/1990	Stefik et al.	345/331
5,047,958	9/1991	Comins et al.	345/516
5,049,862	9/1991	Dao et al.	345/179
5,084,667	1/1992	Drori et al.	323/298
5,148,155	9/1992	Martin et al.	345/173
5,155,837	10/1992	Liu et al.	395/200.51
5,157,384	10/1992	Greanias et al.	345/156
5,194,852	3/1993	More et al.	345/182
5,204,768	4/1993	Tsakiris et al.	359/148
5,210,854	5/1993	Beaverton et al.	395/500
5,239,652	8/1993	Seibert et al.	395/750.05

5,241,303	8/1993	Register et al.	345/168
5,260,697	11/1993	Barrett et al.	345/173
5,261,055	11/1993	Moran et al.	395/858
5,276,839	1/1994	Robb et al.	711/103
5,305,384	4/1994	Ashby et al.	380/29
5,307,297	4/1994	Iguchi et al.	364/708.1
5,309,351	5/1994	McCain et al.	364/132
5,313,051	5/1994	Brigada et al.	235/375
5,315,711	5/1994	Barone et al.	395/200.38
5,321,840	6/1994	Ahlin et al.	395/712

(List continued on next page.)

FOREIGN PATENT DOCUMENTS

0 279 558 8/1988 European Pat. Off. .

OTHER PUBLICATIONS

Communications and consistency in mobile file systems by
Honeyman et al., 1995 IEEE publication, pp. 44–48, Dec.
1995.

“Real-Time Extension to X-Windows Provide Determinis-
tic Graphics,” by Computer Technology Review, May, 1993,
vol. 13, No. 6, pp. 27–31.

“Flash Memory BIOS for PC and Notebook Computers,”
Jerry Jex, IEEE, pp. 692–695, (1991).

“Embedded Processor Applications for SONET Telecom-
munication Systems,” Doug Bush, WESCON/95 Confer-
ence, IEEE, pp. 377–381, (1995).

“A Wireless Network in MosquitoNet”, IEEE/Micro, Stuart
Cheshire pp. 44–52, (1996).

“Mobile IP, Ad-Hoc Networking and Nomadicity,” COMP-
SAC, 1996, IEEE, pp. 472–476.

Primary Examiner—Zami Maung


Attorney, Agent, or Firm—Fitch, Even, Tabin & Flannery

[57]

ABSTRACT

A wireless interface device is adapted to be connected to a
host computer. On power-up, a list of available hosts is
identified in a dialog box on the display of the wireless
interface device. Once a host is selected, the node address
for the selected host is stored in an EEPROM. On a
subsequent power-up of the wireless interface device, a
connection is automatically made to the last selected host.

9 Claims, 90 Drawing Sheets



U.S. PATENT DOCUMENTS

5,327,531	7/1994	Bealkowski et al.	395/182.04	5,519,878	5/1996	Dollin, Jr.	395/800
5,329,625	7/1994	Kannan et al.	345/173	5,526,023	6/1996	Sugimoto et al.	345/173
5,341,503	8/1994	Gladstein et al.	395/750.08	5,526,287	6/1996	French	364/550
5,347,295	9/1994	Aguinick et al.	345/156	5,528,231	6/1996	Patarin	340/825.34
5,355,414	10/1994	Hale et al.	380/25	5,528,660	6/1996	Heins et al.	379/21
5,355,503	10/1994	Soffel et al.	395/750.04	5,528,743	6/1996	Tou et al.	707/541
5,371,738	12/1994	Moelard et al.	370/331	5,533,147	7/1996	Arai et al.	382/179
5,372,161	12/1994	Logan et al.	137/625.17	5,534,893	7/1996	Hansen, Jr. et al.	345/179
5,375,230	12/1994	Fujimori	395/750.05	5,535,357	7/1996	Moran et al.	711/103
5,396,443	3/1995	Mese et al.	364/707	5,543,588	8/1996	Bisset et al.	178/18.06
5,404,458	4/1995	Zetts	395/893	5,553,296	9/1996	Forrest et al.	395/750.05
5,421,009	5/1995	Platt	395/200.51	5,555,157	9/1996	Moller et al.	361/683
5,423,045	6/1995	Kannan et al.	395/750.04	5,561,446	10/1996	Montlick	345/173
5,430,877	7/1995	Naylor	395/712	5,564,020	10/1996	Rossi	395/118
5,434,972	7/1995	Hamlin	395/200.68	5,568,645	10/1996	Morris et al.	395/200.33
5,440,502	8/1995	Register	364/708.1	5,583,542	12/1996	Capps et al.	345/173
5,455,822	10/1995	Dixon et al.	370/342	5,590,373	12/1996	Whitley et al.	395/828
5,457,478	10/1995	Frank	345/158	5,594,462	1/1997	Fishman et al.	345/2
5,461,667	10/1995	Remillard	379/93.24	5,594,731	1/1997	Reissner	370/338
5,467,102	11/1995	Kuno et al.	345/1	5,597,307	1/1997	Redford et al.	434/118
5,485,171	1/1996	Copper et al.	345/160	5,600,801	2/1997	Parks et al.	395/282
5,487,069	1/1996	O'Sullivan et al.	370/404	5,602,854	2/1997	Luse et al.	370/313
5,491,495	2/1996	Ward et al.	345/173	5,623,677	4/1997	Townesley et al.	395/750.02
5,495,593	2/1996	Elmer et al.	711/103	5,628,055	5/1997	Stein	455/89
5,504,746	4/1996	Meier	370/85.13	5,636,371	6/1997	Yu	395/500
5,508,713	4/1996	Okouchi	345/1	5,642,185	6/1997	Altreith, III et al.	399/81
5,515,509	5/1996	Rom	395/200.58	5,682,379	10/1997	Mahany et al.	370/311
5,519,843	5/1996	Moran et al.	711/103	5,706,508	1/1998	Chen et al.	707/200

Fig. 1




Fig. 2





Fig. 3






Fig. 5




Fig. 6





Fig. 7






Fig. 9




Fig. 11a





Fig. 11f






Fig. 11b




Fig. 12

Fig. 11a
Fig. 11b
Fig. 11c





Fig. 12a

Fig. 12b




Fig. 12c




Fig. 12d




Fig. 12

Fig. 12a	Fig. 12c	Fig. 12e	Fig. 12g
Fig. 12b	Fig. 12d	Fig. 12f	Fig. 12h

Fig. 12e




Fig. 12f





Fig. 12g







Fig. 12h







Fig. 13a

Fig. 13b

Fig. 13b

Fig. 13c






Fig. 13d




Fig. 14a




Fig. 14b




Fig. 14c

















Fig. 14d












Fig. 17b












Fig. 17a













Fig. 19b





Fig. 19g




Fig. 19h




Fig. 19i





Fig. 19j

Fig. 19c






Fig. 19d




Fig. 19k







Fig. 19l







Fig. 19

Fig. 19a	Fig. 19c	Fig. 19e
Fig. 19b	Fig. 19d	Fig. 19f








Fig. 21a




Fig. 21b




Fig. 21c





Fig. 21d






Fig. 21i




Fig. 21f




Fig. 21h




Fig. 21g

Fig. 21c	Fig. 21e	Fig. 21i
-------------	-------------	-------------

Fig. 22a




Fig. 22b




Fig. 22c




Fig. 22d





Fig. 23a






Fig. 23c





Fig. 23e





Fig. 24a









Fig. 25a








Fig. 26a

Fig. 26b




Fig. 26c




Fig. 26d




Fig. 27a




Fig. 276





Fig. 27c






Fig. 28a

Fig. 28c

Fig. 28b






Fig. 29d




Fig. 29e







Fig. 29f










Fig. 30c




Fig. 30d




Fig. 30e





Fig. 31

Fig. 32




Fig. 33






Fig. 34*Fig. 35*



Fig. 36*Fig. 37*




Fig. 38*Fig. 40*


Fig. 40a




Fig. 41*Fig. 42**Fig. 43*

Fig. 44




Fig. 45

Prior Art




Fig. 46







Fig. 47*Fig. 48**Fig. 49*

Fig. 50






Fig. 51*Fig. 52*





Fig. 55





Fig. 56






Fig. 57


Fig. 58


Fig. 59a


Fig. 59b



Fig. 60*Fig. 61*


Fig. 62a


Fig. 62b

Fig. 62c






Fig. 62

Fig. 62a

Fig. 62b

Fig. 62c

Fig. 63




*Fig. 64b*






Fig. 64c

Fig. 65a

*Fig. 65b*






Fig. 66c




Fig. 66d

SYSTEM AND METHOD FOR AUTOMATICALLY RECONNECTING A WIRELESS INTERFACE DEVICE TO A HOST COMPUTER

CROSS-REFERENCE TO RELATED CASES

This case is a continuation-in-part of to the following copending application: STRUCTURE AND METHOD FOR CONTROLLING A HOST COMPUTER USING A REMOTE HAND-HELD INTERFACE DEVICE, by B. R. Banerjee, S. C. Gladwin, A. Maskatia and A. Soucy, filed Sep. 2, 1994, Ser. No. 08/300,500. This case is also related to the following copending applications, all filed on even date: REMOTE CONTROL INTERFACE, by B. R. Banerjee, S. C. Gladwin, A. Maskatia and A. Soucy Ser. No. 08/543,700; RADIO FLASH UPDATE, by D. Bi, H. Hsiung and J. Wilson, Ser. No. 08/543,463; MOUSE EMULATION WITH PASSIVE PEN, by D. Bi, G. Cohen, M. Cortopassi, J. George, S. C. Gladwin, H. Hsiung, P. Lim, J. Parham, A. Soucy, D. Voegeli and J. Wilson, Ser. No. 08/543,786, now abandoned in favor of continuation U.S. patent application Ser. No. 08/957,398, filed on Oct. 23, 1997; RESUME ON PEN CONTACT, by M. Cortopassi, S. C. Gladwin and D. Voegeli, Ser. No. 08/543,510; SCREEN SAVER DISABLER, by D. Bi, S. C. Gladwin and J. Wilson, Ser. No. 08/543,698; IPX DRIVER FOR MULTIPLE LAN ADAPTERS, by D. Bi, Ser. No. 08/553,808; DISASTER RECOVERY JUMPER, by M. Cortopassi, J. George, J. Parham and D. Voegeli, Ser. No. 08/543,423; RC TIME CONSTANT, by M. Cortopassi, Ser. No. 08/543,697; DOUBLE PEN UP EVENT, by D. Bi and J. George, Ser. No. 08/543,787; REMOTE OCCLUSION REGION, by J. Wilson, Ser. No. 08/543,701; BROADCAST SEARCH FOR AVAILABLE HOST, by D. Bi, S. C. Gladwin and J. Wilson, Ser. No. 08/543,599; REMOTE KEYBOARD MACROS ACTIVATED BY HOT ICONS, by S. C. Gladwin and J. Wilson, Ser. No. 08/543,788; HOST/REMOTE CONTROL MODE, by M. Cortopassi, J. George, S. C. Gladwin, H. Hsiung, P. Lim, J. Parham, D. Voegeli and J. Wilson, Ser. No. 08/551,936; PASSWORD SWITCH TO OVERRIDE REMOTE CONTROL, by D. Bi, S. C. Gladwin and J. Wilson, Ser. No. 08/543,785; and PORTABLE TABLET, by G. Cohen, S. C. Gladwin, P. Lim, J. Smith, A. Soucy, K. Swen, G. Wong, Ken K. Wood and G. Wu, Ser. No. 29/045,319, now U.S. Design Pat. No. 385,857 issued on Nov. 14, 1997.

BACKGROUND OF THE INVENTION

1. Field of the Invention

The present invention relates to a wireless interface device and more particularly to a wireless interface for interfacing with a host computer. On power-up, the wireless interface device ascertains the available hosts for connection. Once a host is selected, the node address for that host is stored in an EEPROM, such that on subsequent power-ups the wireless interface device will automatically be connected to the last host selected.

2. Description of the Prior Art

Both wired and wireless LAN systems are known in the art. Such systems enable various desktop and/or portable personal computers to be connected in a local area network in order to share resources. Wireless LAN systems are normally used in an office environment to enable the various users to share common resources while obviating the need for direct wire connections between the personal computers connected to the LAN.

The personal computers connected to a wireless LAN configuration are normally equipped with a wireless LAN card and a radio interface which typically includes a spread-spectrum type radio to reduce interference.

As mentioned above, portable personal computers have been known to be used in such wireless LAN systems. However, portable personal computers, even such notebook-size portable personal computers, are cumbersome to transport in an office environment. Unfortunately, the resources of the LAN system are often needed at locations other than where the personal computers connected to the LAN are located.

In both wired and wireless LAN systems, the node addresses of the personal computers to be connected to the LAN must be known before any communication is established. Thus, interfacing abilities of such systems are rather limited.

SUMMARY OF THE INVENTION

It is an object of the present invention to solve various problems of the prior art.

It is yet another object of the present invention to provide a wireless interface device that is adapted to be connected to one of a plurality of available hosts and automatically reconnected to the last selected host on power-up.

Briefly, the present invention relates to a wireless interface device for connection to a host computer. On power-up, a list of available hosts is identified in a dialog box on the display of the wireless interface device. Once a host is selected, the node address for the selected host is stored in an EEPROM. On a subsequent power-up of the wireless interface device, connection is automatically made to the last selected host.

BRIEF DESCRIPTION OF THE DRAWING

These and other objects of the present invention will be readily understood upon consideration of the following detailed description and attached drawing, wherein:

FIG. 1 is a block diagram of the hardware configuration of a wireless interface device in accordance with the present invention and a host computer;

FIG. 2 is a block diagram illustrating the access of the wireless interface device in accordance with the present invention and a wired local area network;

FIG. 3 is a diagram illustrating the software structure for the wireless interface device in accordance with the present invention;

FIG. 4 is a block diagram showing one implementation of the wireless interface device of FIG. 1;

FIG. 5 is a state diagram illustrating the six internal power management states of the wireless interface device;

FIG. 6 is a block diagram illustrating the operational states of the wireless interface device under the control of dedicated Viewer Manager software in accordance with the present invention;

FIG. 7 is a block diagram of the software environment under which the wireless interface device and the host computer operate to provide remote control of the host computer;

FIG. 8 is a block diagram which shows in further detail the software environment in the host computer, running an application program under a Windows environment;

FIG. 9 is a block diagram which shows in further detail the software environment in the wireless interface device, running in a normal operation state;

FIG. 10 is a block diagram illustrating the method used in the wireless interface device to anticipate a pen/mouse mode decision;

FIGS. 11–30 are schematic diagrams of the wireless interface device in accordance with the present invention;

FIGS. 31–35 are flow charts relating to mouse emulation with a passive pen;

FIG. 36 is a plan view of the wireless interface device illustrating the hot icon area and viewing area of the display;

FIG. 37 illustrates the hot icons in the hot icon area of the display;

FIGS. 38, 39 and 40 are flow charts relating to a system for disabling the screen saver to reduce LAN traffic;

FIG. 40A is a flow chart relating to a host access protection password system;

FIGS. 41–43 are flow charts relating to a system for handling pen-up events;

FIG. 44 is a configuration diagram illustrating the wireless interface device interfacing with a wired LAN system;

FIG. 45 is a diagram of the software structure of a known network system;

FIG. 46 is a diagram of the software structure of network system which enables the wireless interface device to interface with the wired LAN system, illustrated in FIG. 44;

FIGS. 47–52 are flow charts relating to the seamless integration of wired and wireless LANS;

FIGS. 53–57 are illustrations of various set-up dialog boxes available on the wireless interface device;

FIG. 58 is a flow chart relating to the host control mode;

FIG. 59 is a flow chart relating to a system for broadcasting for available hosts;

FIGS. 60 and 61 are flow charts relating to a system for providing remote keyboard macros on the wireless interface device;

FIGS. 62 and 63 are flow charts relating to a wireless flash ROM programmer;

FIGS. 64A and 64B are flow charts relating to a system for providing automatic reconnection of the host;

FIGS. 65A and 65B are flow charts relating to providing a remote occlusion region on the wireless interface device; and

FIGS. 66A–66D illustrate the various configurations of an on-screen keyboard available on the wireless interface device.

DETAILED DESCRIPTION OF THE INVENTION

1. General

The present invention relates to a system which allows wireless access and control of a remote host computer, which may be either a desktop, tower or portable computer to enable remote access of the various files and programs on the host computer. The system not only allows access to remote host computers that are configured as stand-alone units but also provides access to both wired and wireless local area networks (LAN).

The system includes a wireless interface device which includes a graphical user interface (GUI) which allows various types of input. In particular, input to the wireless interface device is primarily by way of a passive stylus, which can be used in a pen mode or a mouse mode.

In a pen mode, a trail of ink tracking the path of the stylus (pen paradigm) provides visual feedback to the user by way

of a pen digitizer. In a mouse mode, however, a cursor may be generated which follows the “tip” of the pen, but the path of cursor motion is not inked.

A virtual keyboard is also provided as part of the GUI. Activation of the keys on the virtual keyboard is by way of the stylus or by finger input. In addition, the system also supports a full-size external keyboard.

FIG. 1 illustrates a block diagram of the system 10 in accordance with the present invention. In particular, a wireless interface device 100, in accordance with the present invention, enables wireless access of a remote host computer 101, configured as either a stand-alone unit or as a part of a wired or wireless local area network (LAN). When the remote host computer 101 is in a stand-alone configuration, as illustrated in FIG. 1, communication between the remote host computer 101 and the wireless interface device 100 is by way of a wireless communication link, provided by a communication subsystem 118 in which the remote host computer 101 is provided with a transceiver 115 for radio communication with a transceiver 116 in the wireless interface device 100. For example, the desktop or remote host computer 101 can be provided with a PCMCIA interface which can be used with a wireless transceiver card to communicate with the transceiver 116 in the wireless interface device 100.

Alternatively, an Industry Standard Architecture (ISA) card transceiver can be installed in the host computer 101 in a spare ISA expansion slot. In particular, the transceivers 115 and 116 may be implemented as 2.4 GHz radio frequency (RF) transceiver modules with a Wireless Media Access Control function, available from Proxim Inc., Mountain View, Calif., configured with either an ISA or PCMCIA interface.

As mentioned above, the wireless interface device 100 can also be used with a wireless LAN in a peer-to-peer network or a wired LAN. FIG. 2 illustrates the communication between the wireless interface device 100 and a wired LAN 114, which includes a server 108 in a, for example, Novell Netware or Microsoft LAN Manager environment. In this mode, the transceiver 116 in the wireless interface device 100 communicates with an access point 109 by way of a transceiver (not shown), which interfaces the wireless interface device 100 with a wired LAN 114 which includes a server 108. Alternatively, the wireless interface device 100 can be used in a wireless network in a Windows for Workgroups or Personal Netware environment, for example.

The configuration of the radio communication subsystem between the wireless interface device 100 and the remote host computer 101 or access point 109 conforms to the Open System Interconnection (OSI) reference model for data communications and implements the lower two layers of the seven-layer OSI model. In particular, with reference to FIG. 3, the physical layer 107 (WIRELESS PHY) may be a 2.4 GHz spread spectrum frequency hopping radio which replaces the LAN cable normally connected between workstations. The radio operates within the 2.4000–2.4835 GHz band, the unlicensed Industrial Scientific and Medical (ISM) band, and is divided into eighty-two 1 MHz channels. In a spread-spectrum, frequency-hopping radio, data is broadcast on one particular channel for a predetermined time (i.e. 400 msec); and then the system hops to another channel in a predetermined pattern to avoid interference.

The wireless media access control (WIRELESS MAC) 106 is used to interface to higher level software 105 (i.e. NOS SHELL, NOVELL, MICROSOFT) through network drivers 104 (i.e. LINK LEVEL INTERFACE (ODI, NDIS)).

The MAC conforms to the industry standard protocol is in accordance with IEEE 802.11.

As shown in FIG. 1, the wireless interface device **100** includes a central processing unit (CPU) **112**, a local memory system **111**, a pen-based input subsystem (STYLUS) **110**, a display subsystem **113** and a transceiver **116**. As will be discussed in more detail below, the wireless interface device **100** includes a Viewer Manager software **200** (FIG. 6) which performs three (3) basic functions: (i) collecting and transmitting input positional information from a stylus input subsystem **110** to the host computer **101**, (ii) receiving from the host computer **101** a video image to be displayed on the display subsystem **113**, and (iii) managing the communications link between the wireless interface device **100** and the host computer **101**.

The wireless interface device **100** is thus able to control and access various programs such as Windows and Windows application programs and files residing at the host computer **101** and display the results in its display **113**.

2. Description of the Block Diagram

FIG. 4 is a block diagram of the wireless interface device **100**. As shown in FIG. 4, the wireless interface device **100** has both a processor or "local bus" **150** and an ISA bus **151**. The local bus **150** operates at the clock rate of the CPU **112**, while the ISA bus **151** operates at the industry standard 8 MHz clock rate. The CPU **112** may be implemented by a microprocessor, which allows suspension and resumption of operation by halting and restarting the system clock to reduce battery consumption. Because power management in a portable device is important, the CPU **112** should preferably support power management functions, such as System Management Mode (SMM) and System Management Interrupt (SMI) techniques known in the industry. One example of a suitable microprocessor is the AMD386DXLV, available from Advanced Micro Devices, Inc., Sunnyvale, Calif., which operates at up to 25 MHz at a 3.0 V supply voltage.

The CPU **112** interfaces over local bus **150** with a system controller **129**. The system controller **129** manages (i) system operation, including the local and ISA buses **150** and **151**, (ii) memory, and (iii) power to the system. The system controller **129** may be, for example, a Model No. 86C368 integrated circuit, available from PicoPower Technology, Inc., San Jose, Calif.

The present implementation takes advantage of the several levels of power management supported by the system controller **129**. Power management in the present implementation is described in further detail below.

The system controller **129** provides a dynamic random access memory (DRAM) controller and a non-volatile random access memory (NVRAM) controller to control the DRAM **111A** and a non-volatile RAM, NVRAM **111B**, which form a portion of the memory subsystem **111** (FIG. 1) in the wireless interface device **100**. As shown in FIG. 4, the DRAM **111A** in the wireless interface device **100** may be provided by four 16-bit by 256 K DRAM memory chips, to provide a total of 2 megabytes of memory, while the NVRAM **111B**, used to store configuration data and passwords, for example, may be implemented using E²PROM technology to provide permanent storage.

All devices on the ISA bus **151** are managed by an integrated peripheral controller (IPC) **128**. The IPC **128** provides various functions including direct memory access (DMA) control, interrupt control, a timer, a real time clock (RTC) controller, and a memory mapper for mapping peripheral devices to the system memory space as illustrated

in Table 4 below. The IPC **128** may be implemented by a stylus, a pen controller **110A** and a digitizer panel **110B**. The pen controller **110A** controls the digitizer panel **110B** and provides positional information of pen or stylus contact. The pen controller **110A** can be implemented, for example by a Model No. MC68HC705J2 microcontroller, available from Motorola, Inc. In this implementation, the digitizer panel **110B** can be, for example, an analog-resistive touch screen, so that the stylus is sensed by mechanical pressure. Using a digitizer panel which senses mechanical pressure allows a "dumb" stylus, or even the human finger, to be used as an input device. When using a dumb stylus, switching between mouse and pen modes is accomplished by selecting an icon as discussed below. Alternately, other styli, such as a "light pen" or an electronic stylus with various operating modes, can also be used. In some electronic stylus', switching between pen and mouse modes can be achieved by pushing a "barrel button" (i.e. a switch located on the barrel of the stylus).

As mentioned above, the wireless interface device **100** includes a display subsystem **113** which, in turn, includes a liquid crystal display (LCD) **113C**. The LCD **113C** is controlled by a video controller **113A**, and supported by video memory **113B**. The video controller **113A** can be implemented by a Model No. CL-GD6205 video controller, available from Cirrus Logic Corporation, Milpitas, Calif. The LCD **113C** can be, for example, a monochrome display, such as the Epson EG9015D-NZ (from Epson Corporation), or an active matrix color display. The video memory **113B** may be implemented as DRAMs, organized as 256 K by 16 bits.

The video controller **113A** communicates with video memory **113B** over a separate 16-bit video bus **113D**. In this implementation, the video controller **113A** provides "back-lighting" support through a backlight control pin BACKLIGHT-TEON that is de-asserted to conserve power under certain power management conditions as discussed below.

As discussed above, the communication subsystem **118** allows communication with a remote host computer **101** in either a stand-alone configuration or connected to either a wired or wireless LAN. The communication system **118** includes the transceiver **116**, an antenna **116A**, and an RF controller **114A** for interfacing with the local ISA bus **151**.

The wireless interface device **100** also includes a keyboard controller **125** which performs, in addition to controlling an optional keyboard by way of a connector, various other functions including battery monitoring and LCD status control. The keyboard controller **125** can be implemented by a Model No. M38802M2 integrated circuit from Mitsubishi Corporation, Tokyo, Japan. Battery power to the wireless interface device **100** may be provided by an intelligent battery pack (IBP) **131**, for example, as described in U.S. patent application Ser. No. 07/975,879, filed on Nov. 13, 1992, hereby incorporated by reference, connected to a system power supply module **133** by way of a battery connector **132**. The IBP **131** maintains and provides information about the remaining useful battery life of IBP **131**, monitored by keyboard controller **125**. Upon the occurrence of a significant event relative to the IBP **130**, e.g. battery remaining life falling below a preset value, the keyboard controller **125** generates an interrupt signal.

A serial port is provided and implemented by way of a universal asynchronous receiver transmitter (UART) **134**,

which can be accessed externally via a serial port connector 135. As will be discussed in more detail below, the serial port connector 135 allows for disaster recovery for the flash memory 117, which may be used to store the basic input/output (BIOS) for the CPU 112.

3. Power Management

In order to conserve battery power, the wireless interface device 100 incorporates power management. While a user of the wireless interface device 100 would normally only be aware of four power management states: “off”; “active”; “suspend”; and “sleep” modes, internally six power management states are implemented as shown in FIG. 5. More particularly, with reference to FIG. 5, before the wireless interface device 100 is powered up, the wireless interface device 100 is in an “off” state; indicated by the reference numeral 160. In an “off” state 160, no power is supplied to the system. A state 161 (the “active” state) is entered when the power switch (FIG. 28) to the wireless interface device 100 is turned to the “on” position. In the active state 161, all components of wireless interface device 100 are active. From active state 161, the wireless interface device 100 enters a “local standby” state 162. The local standby state 162 is transparent to the user of the wireless interface device 100. From the user’s point of view, in the local standby state 162, the wireless interface device 100 is in active mode. In this state 162, specific inactive devices are each put into a static state after a predetermined time-out period of inactivity for that device. In a static state, each device consumes minimal power. In the local standby state 162, devices that can be put into static states include the CPU 112, the video controller 113A, the pen controller 11A, the UART 134, and the transceiver 116. Backlighting of the LCD video display is also disabled in local standby state 162. If not, input activities are detected by the keyboard controller 125 or pen controller 110A. After the later of their respective present time-out periods, these devices are placed in a static state. These devices emerge from the static state once an activity relevant to its operation is detected, e.g. a pen event is detected.

The user of the wireless interface device 100 can place the wireless interface device 100 in a “sleep” mode 163 by selecting an icon (FIG. 37) labelled “sleep” from the GUI as will be discussed below. Alternatively, the “sleep” mode may be entered from the active state 161 after a preset period of inactivity. In a “sleep” mode, corresponding to either “sleep” state 163 or “active sleep” state 164, the display subsystem 113 is switched off; and most devices are placed in static states. When a keyboard or pen event is detected, the sleep state 163 and active sleep state 164 are exited, and the wireless interface device 100 enters the active state 161. From the sleep state 163, an active sleep state 164 is entered when a communication packet is received from the host computer 101. Although the display subsystem 113 is turned off, the received communication packet can result in an update to an image stored in the video memory 113B. The CPU 112 handles the communication packet from the host computer 101 and activates the video controller 113A to update such an image. The active sleep state 164 is transparent to the user of the wireless interface device 100, since the updated image is not displayed on the LCD screen 113C. When the communication packet is handled, the wireless interface 100 returns to a sleep state 163. The device activities in wireless interface device 100 in “sleep” mode 163 are illustrated in Table 1 below.

TABLE 1

	DEVICE	STATE	CLOCKS DISABLED	COMMENTS	WAKEUP SOURCE
5	Micro-processor	Static Suspend	Clock Stop Control by the system controller	Static Mode entered when clock stopped	Clock Restarted and Controlled by the system controller
10	System Controller	Static Suspend	Clock Stopped/32 KHz Left on		Activity on EXACT, SWITCH, or RING pins
	Peripheral Controller	Static	32 KHz Source		Any Interrupts
15	Main Memory	Slow Refresh	System controller 38 KHz	Memory Refreshed at 128 mS	
	Video	Static	14 MHz disconnected	Controlled through use of system controller power management pins	When system is resumed
20	Video Memory	Slow Refresh	32 KHz	Memory Refreshed at 128 mS	Video Controller
25					automatically adjusts refresh rate depending on mode
	LCD Module	OFF	NA	Power to Module will never be applied in Sleep	Controlled by Video controller power up sequencing
30	LCD Backlight	OFF	NA	Backlight will never be on in Sleep	Controlled by Video controller power up sequencing
35	UART	Static	1.84 MHz	Part has no direct power management	
	UART Trans.	Off	NA	Part turned off, until access to UART. Inactivity timer will start, and look for a time-out of two minutes before turning off transceiver	Access to serial port
40					
45	ROM	Static	NA	After ROM is shadowed, the CS and OE line will be driven high to keep these parts in a static mode	
50					
55	NVRAM	Static	NA	After NVRAM is read, the CS line will be high which forces part into a static mode	
60	Pen Controller	Sleep	Own 4.0 MHZ	Sleeps after each point is processed as long as the pen is not pressing the screen	Pen Down wakes up Pen controller. Pen controller asserts the PEN_ACTIVITY signal which will wake up the
65					

TABLE 1-continued

DEVICE	STATE	CLOCKS DISABLED	COMMENTS	WAKEUP SOURCE
Hook	Active	Own 32 KHz	Keeps the last display as told by the keyboard controller	entire system. NA
Clock Generator	Active	All Clocks Running	Clocks needed in order to wake system back up	
Radio	Sleep	Internal	Radio Handles its own power management	Wakes up on periodic basis in order to keep SYNC. When a packet is ready, the Radio will assert the activity pin to the EXPACT input of the system controller which will wake up the system

Upon expiration of a timer, the wireless interface device 100 enters into an internal state “suspend” mode 165. In a suspend mode, the wireless interface device 100 is essentially turned off and communication packets from the host computer 101 are not handled. The wireless interface device 100 emerges from suspend state 165 into active state 161 when a pen event is detected.

As mentioned above, the video controller 113A supports various power management modes internal to the display subsystem 113. Power is conserved in display subsystem 113 by entering “standby” and “suspend” modes. In the video controller 113A’s “standby” mode, which can be entered by (i) expiration of a timer internal to the video controller 113A, (ii) firmware in the video controller 113A, or (iii) a signal received from system controller 129 on the video controller 113A’s “STANDBY” pin. In the video controller 113A’s standby mode, the LCD 113C is powered down and the video clock is suspended. The video controller 113A exits the standby mode either under firmware control, or upon system controller 129’s de-asserting video controller 113A’s STANDBY pin. Upon exiting standby mode, the LCD 113C is powered and the video clock becomes active. In this implementation, the LCD 113C includes multiple power planes (“panels”). For reliability reasons, in a powering up or powering down operation, these panels in the LCD display are preferably powered in a predetermined sequence specified by the manufacturer.

Maximum power is conserved in the display subsystem 113 when video controller 113A enters the “suspend” mode. The suspend mode can be entered either by asserting a signal from the system controller 129 on the SUSPEND pin of video controller 113A, or under firmware control. In this implementation, if the suspend mode is entered from the SUSPEND pin, the CPU 112 is prevented from accessing the video RAM 113B and video bus 113D. In that state, the contents of configuration registers in the video controller 113A are saved, to be restored when suspend mode is exited. In the suspend mode, the video RAM 113B is refreshed using the lowest possible refresh clock rate.

4. General Description of Operation

FIG. 6 is a block diagram illustrating the operational states of wireless interface device 100 under the control of

the Viewer Manager software 200. As shown in FIG. 6, on power up, the wireless interface device 100 enters into a “TABLET SECURITY” state 201, in which an optional security step is performed. In the state 201, either the device 100 automatically shuts off after an idle period or the user performs a “log on” procedure which, as a security measure, identifies and validates the user. Then, at decision point 202, the Viewer Manager software 200 then determines if a procedure to set up a communication link is preconfigured. If so, a communication link is established automatically with the host computer 101 and the Viewer Manager software 200 goes into the normal operation state 205, which is described in further detail below. If a communication link is not preconfigured, a manual procedure is performed in state 203, in which the desired host computer 101 is identified and connected. From state 203, either the device 100 automatically shuts off after an idle period or the user continues on and enters normal operation state 205.

In normal operation state 205, the wireless interface device 100 controls the program running in the host computer 101, in accordance with the input data received from stylus input subsystem 110. The positions of the stylus in stylus input subsystem 110 are delivered to the host computer 101, which generates display commands to the wireless interface device 100. The CPU 112 executes the display commands received, which may result in an update of the LCD 113C. In this embodiment, either a direct user command or inactivity over a predetermined time period causes the wireless interface device 100 to enter a “HOT-STANDBY” minimum power state (“sleep” mode), represented in FIG. 6 by block 204. In the minimum power state 204, to preserve battery power, the various operations of the wireless interface device 100’s functional units are placed on standby status. If the status is put in contact with the digitizer panel, the wireless interface device 100 is reactivated, and control of the host computer 101 is resumed by re-entering state 205. Thereupon, wireless interface device 100 enters into a state 206, in which an auto-disconnect procedure is executed, which releases control of the host computer 101 and powers down the wireless interface device 100.

The user may also relinquish control of the host computer 101 from state 205 by selecting a manual disconnect function. When the manual disconnect function is selected, the wireless interface device 100 enters manual disconnect state 207, in which the connection to the host computer 101 is terminated. The wireless interface device 100 is then returned to state 201 to accept the next user validation.

FIG. 7 is a block diagram of the software environment 240 in which the wireless interface device 100 and the host computer 101 operate to provide the wireless interface device 100 remote control of the host computer 101. As shown in FIG. 7, a wireless communication system 250 is provided for communication between the host computer 101 and the wireless interface device 100. On the side of the wireless interface device 100, i.e. software environment 230A, a communication output manager software routine 252 controls transmissions of pen events over the wireless communication link 250 to a host communication input manager 262 in the host computer 101 (i.e. software environment 230B). The pen events include the position information of the stylus and tip-up and tip-down information. A pen event buffer 251 queues the pen events for transmission through a communications manager 252. In the software environment 230A, the communications input manager 254 receives from the wireless communication system 250 video events transmitted by host communication output manager

260 in the software environment 230B. These video events include graphical commands for controlling the LCD 113C. In the software environment 230A, the received video commands are queued in the video event buffer 256 to be processed by the CPU 112 as graphical instructions to the LCD 113C.

In the software environment 230B, i.e. in host computer 101, pen events are queued in pen event buffer 264, which may then be provided to the Pen Windows module 266. The Pen Windows module 266 processes the pen events and creates video events in a video event buffer 267, which is then transmitted to the wireless interface device 100 over wireless communication system 250.

FIG. 8 is a block diagram which shows in further detail the software environment 230B (FIG. 7) in the host computer 101; running an application program 270 under a Windows operating system 272. As shown in FIG. 8, the pen events queued in the pen event buffer 264 are provided to a pen event injector 274, which provides the pen events from the pen event buffer 264, one pen event at a time, to a buffer ("RC buffer") 275 of the Recognition Context Manager module (the "RC manager") 276 in Pen Windows. The RC buffer 275 holds a maximum of four pen events. The RC Manager 276 assumes that pen events are received at RC buffer 275 as they occur. Thus, if the Pen Windows system is presented with pen events faster than they are retrieved from RC buffer 275 without pen event injector 274, the pen events that arrive at RC buffer 275 when it is full are lost. The pen event injector 274 prevents such data loss. To provide this capability, the pen event injector 274 includes both Windows virtual device (VxD) and device driver (DRV) codes (not shown). The DRV portion removes a single pen event from pen event buffer 264 and delivers it to the RC buffer 275 using the normal Pen Windows add and process pen event mechanisms. Then the VxD portion reactivates the DRV code after a minimum time delay using a virtual machine manager service to retrieve the next pen event from pen event buffer 264. Those of ordinary skill in the art would appreciate that, under the terminology used in Windows, DRV code refers to a dynamically linked library in Windows which interacts with a hardware device (in this case, pen device buffer 264), and VxD code refers to a dynamically linked library which manages a sharable resource (in this case, the DRV code).

The RC Manager 276 examines each pen event in the RC buffer 275, and according to the context of the pen event in its possession, the RC Manager 276 determines whether the stylus is in the pen mode or in the mouse mode. In this embodiment, as will be discussed in more detail below, an icon allows the user to use the stylus as a "mouse" device. The icon, called "mouse button toggle", allows the user to switch between a "left" button and a "right" button as used in an industry standard mouse device. The selected button is deemed depressed when the stylus makes contact with the pressure-sensitive digitizer panel. A rapid succession of two contacts with the display is read by the RC Manager 276 as a "double click", and dragging the stylus along the surface of the display is read by the RC Manager 276 as the familiar operation of dragging the mouse device with the selected button depressed.

If the stylus is in the pen mode, the RC Manager 276 provides the pen event to a recognizer 277 to interpret the "gesture". Alternatively, if the pen event is a mouse event, the RC Manager 276 provides the pen event as a mouse event for further processing in a module 278. The interpreted gestures or mouse events are further processed as input data to the Windows operating system 272 or the application program 270.

The output data from an application program, such as Windows 272 or application program 270, is provided to the video event buffer 267. These video events are transmitted to the host communications output manager 260 for transmission to the wireless interface device 100.

FIG. 9 is a block diagram which shows in further detail the software environment 230A in the wireless interface device 100 in the normal operation state 205 of the Viewer Manager 200. In FIG. 9, the stylus in the stylus input subsystem 110 and LCD video display 113C in the video display subsystem 113 are shown collectively as a digitizer-display device 279. In a normal operation state 205, the Viewer Manager 200 interacts with the application program 270 in the wireless interface device 100 by way of the Communications Output Manager 252 and the Communications Input Manager software 254. In addition, the Viewer Manager software 200 also receives digitized data from a digitizer 280, which, in turn, receives digitized data from stylus input subsystem 110. The Viewer Manager software 200 uses the digitized data to provide visual feedback to the user, which is discussed in further detail below. The Viewer Manager software 200 generates local video commands to a display driver 281. The display driver 281 also receives from video event buffer 256 video display commands from the host computer system 101.

At the core of the wireless interface device 100's user interface is the stylus's behavior under Pen Windows. Of significance in wireless interface device 100's design is the emulation of the natural "pen-and-shaper" interaction with the user. That is, in a pen mode, the stylus must leave ink as it moves across the surface of the screen in the same way that a pen leaves ink on paper. However, using Pen Windows software, the RC Manager 276, residing in the host computer 101, determines for each pen event whether the mouse or the pen mode is used.

If the wireless interface device 100 simplistically accesses the host computer 101 as a local device access, the wireless link between the host computer 101 and the wireless interface device 100 would be required to carry a minimum of 200 inking messages per second (100 stylus tip locations plus 100 line drawing commands). To maintain the pen-and-paper emulation, the wireless interface device 100 is further required to have a total processing delay (hence response time), including the overhead of the communication protocols, which is near or below the human perception level. In addition, noise in the transmission medium often leads to momentarily interruption of data transmission, or results in data corruption that requires re-transmission, thereby further reducing the throughput of the wireless link. To provide an acceptable level of performance, i.e., a high message-per-second communication rate and an acceptable propagation delay, a technique referred to as "local inking" is developed and applied to the wireless interface device 100's design, in accordance with the present invention. Without local inking, a high bandwidth communication link is required to meet the propagation delay requirement. Such a high bandwidth communication link is impractical, both in terms of cost and its impact on the portability of the resulting wireless access device.

With local inking, the Viewer Manager software 200 provides inking on the LCD 113C locally before the corresponding inking video events are received from the host computer 101. In this manner, visual feedback is provided virtually immediately without requiring either highly complex networking equipment, or very high performance and costly components in both the wireless interface device 100 and the host computer 101. Local inking provides both a real

time response and an orderly handling of the stylus's data stream. Since local inking reduces the need for processing at the peak pen event rate of the stylus's data stream, the host computer **101** can thus apply normal buffering techniques, thereby reducing the bandwidth requirement on the communication network.

In one proposed industry standard for a stylus or pen-based system, namely the Microsoft Windows for Pen Computing system ("Pen Windows"), the pen mode requires (i) a pen driver that can deliver stylus tip locations every five to ten milliseconds (100 to 200 times per second), so as to achieve a resolution of two hundred dots per inch (200 dpi), and (ii) a display driver than can connect these dots in a timely manner. By these requirements, Pen Windows attempts to provide a real time response to maintain the pen paradigm. The Windows for Pen Computing system is promoted by Microsoft Corporation, Redmond, Wash. Details of the Pen Windows system are also provided in Windows version 3.1 Software Developer Kit obtainable from Microsoft Corporation. Under one implementation of the Pen Windows, a maximum of four stylus locations can be stored in a buffer of a module called "PENWIN.DLL" (for "Pen Window Dynamically Linked Library"). Consequently, in that implementation, the maximum latency allowed is twenty to forty milliseconds before any queue tip location is written. Each time the system fails to process a pen event within twenty to forty milliseconds of queuing, a stylus tip location is lost and there is a corresponding impact on the accuracy of the line being traced.

As mentioned above, the stylus is used in both pen mode and mouse mode. Since the RC Manager **276**, running on the host computer **101**, rather than a software module on the wireless interface device **100**, determines whether a given pen event is a mouse mode event or a pen mode event, the Viewer Manager software **200** must anticipate which of these modes is applicable for that pen event. Further, should the anticipated mode prove to be incorrect, the Viewer Manager software **200** is required to correct the incorrectly inked image in video display subsystem **113**.

FIG. **10** illustrates the method used in the wireless interface device **100** to anticipate the RC Manager **276**'s mode decision and to correct the image in the video display subsystem **113** when a local inking error occurs. As shown in FIG. **10**, when the normal operational state **205** is entered, a pen control program (represented by the state diagram **282**) in the Viewer Manager software **200** is initially in the mouse mode in state **283**. However, even in the mouse mode, the trajectory of the stylus in contact with the pen digitizer is stored in the pen event buffer **284** until a mode message is received from the host computer **101**. The pen event buffer **284** is separate from pen event buffer **251**, which is used to transmit the pen events to the host computer **101**. If the RC Manager **276** confirms that the stylus **110** is in a mouse mode, the accumulated pen events are discarded and the pen control program **282** waits for the last point on which the pen tip is in contact with the pen digitizer. Then the pen control program **282** returns to a state **283**, in which the trajectory of the pen is again accumulated in the pen event buffer **284** until receipt of a mode message from the host computer **101**. In state **283**, the control program **282** assumes that the stylus will continue to be in the mouse mode.

Alternatively, while in state **283**, if a mode message is received indicating the stylus is in the pen mode, the control program **282** enters state **288**, in which the accumulated pen events are drawn locally onto the LCD screen of the video display subsystem **113** in accordance with the line style and

color specified in the mode message. After all accumulated pen events in the pen event buffer **284** are drawn, the control program **282** enters a state **289**, in which control program **282** continues to ink the trajectory of the tip of the stylus for as long as contact with the pen digitizer is maintained. Once the tip of the stylus breaks contact with the pen digitizer, the control program **282** enters state **287**.

In state **287** the control program **282** assumes that the stylus will continue to be in the pen mode. Thus, local ink will follow the trajectory of the stylus while the top of the stylus remains in contact with the pen digitizer, or until a mode message is received from the host computer **101**, whichever arrives earlier. Since the initial policy decision is a guess, the local inking is drawn using a single pixel-wide style and an XOR ("exclusive OR") operation, in which the pixels along the trajectory of the stylus are inverted. While in state **287**, the pen events associated with the trajectory of the stylus are accumulated in the pen event buffer **284**.

If the mode message received in state **287** indicates that the stylus is in mouse mode, i.e. the policy decision was wrong, the control program **282** then enters a state **290**, in which the accumulated pen events in pen event buffer **284** are used to erase the stylus stroke. Since the initial draw is accomplished by a bit XOR ("exclusive OR") operation at the appropriate positions of the frame buffer, erasure is simply provided by the same XOR operation at the same positions of the frame buffer. The control program **282** then enters state **286**. However, if the mode message received in state **287** confirms that the stylus is in pen mode, the accumulated pen events of pen event buffer **284** are used to redraw on the LCD **113C**, using the line style and color specified on the mode message.

Under a convention of the Pen Windows software, starting a stroke of the stylus with the barrel button depressed (for active stylus systems) indicates an erase ink operation in pen mode. The control program **282** recognizes this convention and refrains from inking during this stroke without waiting for confirmation from the host computer **101**. In addition, the control program **282** does not change modes across an erasing stroke: i.e., if the stylus is in the pen mode prior to the erase stroke, the stylus remains in the pen mode after the erase stroke; conversely, if the stylus is in the mouse mode prior to the erase stroke, the stylus remains in the mouse mode after the erase stroke.

Since all the pen events used in local inking on the wireless interface device **100** are also processed in the host computer **101**, the trajectory of local inking must coincide identically with the line drawn at the host computer **101**. Because of local inking, processing by the host computer **101** within the human perceptual response time is rendered unnecessary. Thus, in the host computer **101**, the pen events can be queued at pen event buffer **264**, to be retrieved one at a time by pen event injector **274**. Hence, when pen event buffer **264** is suitably sized, data loss due to overflow by RC buffer **275** is prevented.

Alternatively, the control program **282** can also be implemented to follow a "retractable ball-point pen" paradigm. Under this paradigm, the user controls a local stylus mode of the stylus, such that inking occurs when the stylus is set to be in the local pen mode, and no inking occurs when the stylus is in the local mouse mode. If the local stylus mode conforms with the mode expected by Pen Windows, the image seen on the LCD display of the video display subsystem **113** is the same as described above with respect to state **287** of the control program **282**. If the local stylus mode is the mouse mode, and Pen Windows software expects

stylus **110** to be in the pen mode, the subsequent video events from host computer **101** would provide the required inking. Finally, if the local stylus mode is the pen mode and Pen Windows software expects the stylus to be in the mouse mode, inking would be left on the screen of video display subsystem **113**. Under this paradigm, the user would eliminate the erroneous inking by issuing a redraw command to Pen Windows.

5. Detailed Description of the Schematic Diagrams

One embodiment of the invention is illustrated in the schematic drawings, FIGS. **11–30**. Referring to FIG. **11**, the system may include a CPU **112**, such as an AMD Model No. AM386DXLV microprocessor. The CPU **112** includes a 32-bit data bus D[**0..31**] as well as a 32-bit address bus A[**2..31**]. Both the data bus D[**0..31**] as well as the address bus A[**2..31**] are connected to the processor bus **150** (FIG. **4**), for example, an AT bus. As will be discussed in more detail below, the system controller **129** (FIG. **4**) performs various functions including management of the processor bus **150**. In order to conserve power, a 3-volt microprocessor may be used for the CPU **112**. As such, a 3-volt supply 3 V CPU is applied to the power supply VCC pins on the CPU **112**. The 3-volt supply 3 V_{CPU} is available from a DC-to-DC converter **300** (FIG. **26**) by way of a ferrite bead inductor **302**. In particular, the DC-to-DC converter **300** includes a 3-volt output, 3 V_{CORE}. This output, 3 V_{CORE}, is applied to the ferrite bead inductor **302** and, in turn, to the power supply pins VCC of the CPU **112**. In order to prevent noise and fluctuations in the power supply voltage from affecting the operation of the CPU **112**, the power supply voltage 3 V CPU is filtered by a plurality of bypass capacitors **304** through **330**.

The 3-volt supply 3 V_{CPU} is also used to disable unused inputs as well as to pull various control pins high for proper operation. For example, the 3-volt power supply 3 V_{CPU} is applied to the active low N/A and BS16 pins of the CPU **112** by way of a pull-up resistor **332**. In addition, the signals BE[**0..3**], WIR, D/C, M/IO and ADS are pulled up by a plurality of pull-up resistors **334** through **348**.

The CPU **112** is adapted to operate at 25 megahertz (Mz) at 3.0 volts. A 25 MHz clock signal, identified as CPU CLK, available from a clock generator **398** (FIG. **13**), is applied to a clock input CLK2 on the CPU **112** by way of a resistor **348** and a pair of capacitors **351** and **353**. The AMD Model No. AMD386DXLV microprocessor supports a static state, which enables the clock to be halted and restarted at any time.

The wireless interface device **100** includes a speaker **355**. The speaker **355** is under the control of the system controller **129** (FIG. **12**). In particular, a speaker control signal SPKR from the system controller **129** is applied to a source terminal of a field-effect transistor (FET) **357** for direct control of the speaker **355**. The drain terminal is connected to the speaker **355** by way of a current-limiting resistor **359** and a bypass capacitor **371**. Normally, the speaker **355** is active all the time. In particular, the gate terminal of the FET **357** is connected to the system ground by way of a resistor **373**. The gate terminal of the FET **357** is also under the control of a speaker disable signal SPKRDISABLE, available from the keyboard controller **125** (FIG. **15**). The speaker disable signal SPKRDISABLE is active high. Thus, when the speaker disable signal SPKRDISABLE signal is low, the FET **357** is turned on to enable the speaker signal SPKR from the system controller **129** to control the speaker **355**. When the speaker disable signal SPKRDISABLE is high, the FET **357** is turned off to disable the speaker **355**.

Referring to FIG. **12**, the system controller **129** is connected between the local processor or AT bus **150** and the system ISA bus **151**. The system controller **129** performs a variety of functions including that of system controller, DRAM controller, power management, battery management and management of the local AT bus **150**. The system controller **129**, preferably a PicoPower Pine Evergreen **3**, Model No. 86C368 system controller, is a 208-pin device that operates at 33 MHz with a full 5-volt input or a hybrid 5-volt/3.3 volt input. At 3.3 volts the system controller **129** is adapted to reliably operate at 20 Mhz and perhaps up to 25 Mhz.

The system controller **129** includes several system features including support of several clock speeds from 16 to 33 MHz. In addition, the system controller **129** includes two programmable non-cacheable regions and two programmable chip selects, used for universal asynchronous receiver transmitter (UART) interface **134** and the radio interface **114B** as discussed below.

The system controller **129** supports both fast GATE A20 and a fast reset control of the CPU **112**. In particular, the system controller **129** includes a 32-bit address bus A[**0..31**] that is connected to the local AT bus **150**. The address line A[20] is used to develop a signal CPUA20, which is applied to the A20 pin on the CPU **112** and also applied to an AND gate **379** (FIG. **11**) to support a port 92 H for a fast GATE A20 signal A fast reset signal RSTCPU is also generated by the system controller **129**. The fast reset signal RSTCPU is applied to the reset pin RESET of the CPU **112** for fast reset control.

The system controller **129** also provides various other system level functions. For example, the system controller **129** includes a register at address 300 H. By setting bit 12 of this registers a ROM chip select signal ROMCS is generated, which enables writes to the flash memory system **117** (FIG. **25**), which will be discussed below. A keyboard controller chip select signal KBDCS for the keyboard controller **125** (FIG. **15**), as well as general purpose chip select signals GPCS1 and GPCS2 for selecting between the RF controller **114A**, the UART **134** (FIG. **16**) or the pen controller **110A** (FIG. **21**), are generated by the system controller **129**.

The system controller **129** is connected to the system ISA bus **151** by way of a 16-bit system data bus SD[**0..15**] and a 24-bit system address bus SA[**0..23**] of which only 8-bits SA[**0..7**] are used. The system controller **129** is also connected to the 32-bit local processor data bus D[**0..31**], as well as the local processor address bus A[**0..31**].

All of the ground pins GND on the system controller **129** are tied to the system ground. Both 3-volt and 5-volt power supplies are applied to the system controller **129**. In particular, a 5-volt supply 5 V_{EG} is applied to the power supply pins VDD of the system controller **129**. The 5-volt supply 5 V_{EG} is available from DC-to-DC converter **300** (FIG. **26**) by way of a ferrite bead inductor **381** (FIG. **12**). More particularly, a 5-volt supply signal 5 V_{CORE} from the DC-to-DC converter is applied to the ferrite bead inductor **381**, which, in turn, is used to generate the 5-volt supply signal 5 V_{EG}. In order to stabilize the 5-volt supply signal 5 V_{EG}, a plurality of bypass capacitors **1101–1111** (FIG. **13**) are connected between the 5-volt supply 5 V_{EG} and system ground.

A 3-volt power supply 3 V_{EG} is also applied to the system controller **129** and, in particular, to the power supply pins VDD/3 V. This 3-volt supply 3 V_{EG} is also obtained from the DC-to-DC converter **300** (FIG. **26**) by way of a

ferrite bead inductor **358**. More particularly, 3-volt supply 3 V_{CORE}, available at the DC-to-DC converter **300**, is applied to the ferrite bead inductor **358**, which, in turn, is used to generate the 3-volt power supply signal 3 V_{EG}. A plurality of bypass capacitors **360**, **362** and **364** are connected between the 3-volt supply 3 V_{EG} and system ground for stabilizing.

The system controller **129** is reset by a reset signal RCRST (FIG. **20**) on power up. The reset signal RCRST is developed by the 3-volt power supply 3 V_{EG}, available from the DC-to-DC converter **300** (FIG. **26**) and circuitry which includes a resistor **359**, a capacitor **361** and a diode **363**. Initially on power up, the capacitor **361** begins charging up from the 3-volt supply 3 V_{EG} through the resistor **359**. During this state, the diode **363** is non-conducting. As the capacitor charges, the level of the reset signal RCRST rises to reset the system controller **129**. Should the system be turned off or the 3-volt supply 3 V_{EG} be lost, the diode **363** provides a discharge path for the capacitor **361**.

In order to assure proper operation of the system controller **129**, a number of signals are pulled up to either five volts or three volts or pulled down by way of various pull-down resistors. More specifically, the signals IOCS16, MASTER, MEMCS16, REFRESH, ZWS, IOCHCK, GPI01/MDDIR and GPI02/MDEN are pulled up to the 5-volt supply 5 V_{EG} by way of a plurality of pull-up resistors **1113**–**1129**, respectively. Similarly, the signals BUSY, FERR, LOCAL, SMIADS and RDY are pulled up by a plurality of pull-up resistors **1131** through **1139**. In addition, the general purpose chip select signals GPCS1 and GPCS2 are pulled up to the 5-volt power supply signal 5 V_{EG} by way of a pair of pull-up resistors **375** and **377**. Certain signals are pulled low by way of pull-down resistors in order to assure their operating state. In particular, the signals KBC-PO4, LB/EXTACT, RING, EXTACT/VLCLK and HRQ206 are pulled down by the pull-down resistors **388** to **396**. The signal BLAST is tied directly to the system ground.

As mentioned above, the system controller **129** is capable of running at different clock frequencies, depending upon the voltage applied, while supplying a clock signal to the CPU **112**. Even though the system controller **129** can supply either a 1X or a 2X clock signal to the CPU **112**, the system controller **129** requires a 2X clock for proper operation. Thus, a 2X clock signal CLK2IN, available from a clock generator circuit **398** (FIG. **13**); is applied to the clock 2X pin CLK2IN of the system controller **129**. In addition, 32 kilohertz (KHz) and 14 megahertz (MHz) clock signals are also applied to the system controller **129**, available from the clock generator circuit **398**, for proper operation. The system controller **129**, in turn, provides a CPU clock signal CPU-CLK to the CPU **112** and in particular to its clock 2-pin CLK2 by way of a resistor **1141** and the capacitors **1143** and **1145**.

The system controller **129** is adapted to be configured during an RC-RESET mode. In particular, the DRAM memory address lines MA[0..10], normally used for addressing the DRAM **111A** (FIGS. **18** and **24**), are pulled high or low in order to configure the system controller **129**. More particularly, the DRAM memory address lines MA[0..10] are applied to either pull-up or pull-down resistors for configuration as illustrated in FIG. **17**. Table 2 below illustrates the configuration shown.

TABLE 2

System Controller Configuration Table		
NAME	FUNCTION	DEFAULT STATE
MA0	386 Select (Low = 46)	High
MA1	Low Power Select (High Selects Intel LP CPU, Low For Other)	Low
MA2	1X CPU Clock Select (Low = 2X CPU CLK)	Low
MA3	Not Used	Low
MA4	Not Used	Low
MA5	368 Pin Select (Low = pin compatible with 268)	High
MA6	Miscellaneous Configuration - 0	Low
MA7	Not Used	High
MA8	Not Used	Low
MA9	Not Used	Low
MA10	Not Used	Low

As shown, the DRAM memory address lines MA[0..10] are shown with bits MA0, MA5 and MA7 pulled high to the 3-volt power supply voltage 3 V_{EG} by way of a plurality of pull-up resistors **400**, **402** and **404**. The remaining DRAM address line bits MA1, MA2, MA3, MA4, MA6, MA8, MA9 and MA10 are pulled low by a plurality of pull-down resistors **406** through **420**, respectively. The DRAM memory address lines MA[0..8] are also coupled to a plurality of coupling resistors **422** to **438** form a 9-bit DRAM address bus BMA[0..8].

The system controller **129** functions as a DRAM controller and is capable of supporting up to 64 megabytes of memory, divided among one of four banks and can support 256K, 512K, 1M, 2M and 4M of memory in any width. The system controller **129** includes a pair of registers associated with each bank of DRAM. The first register stores the total amount of DRAM connected to the system while the second identifies the starting address for each bank. Referring to FIGS. **18** and **24**, two 1 Mbyte banks are connected to the DRAM memory address bus BMA[0..8] and to the processor data bus **150**, D[0..31].

In order to conserve power, 3-volt DRAM **111A** is used. The 3-volt power supply 3 V_{RAM} is applied to the VCC terminals of each of the DRAMS **111A**. The 3-volt power supply 3 V_{RAM} is available from the DC-to-DC converter **300** (FIG. **26**) by way of a ferrite bead inductor **440** (FIG. **18**). In particular, a 3-volt supply 3 V_{CORE} available at the DC-to-DC converter **300** is applied to the ferrite bead inductor **440** to generate the 3-volt DRAM supply 3 V_{RAM}. A plurality of bypass capacitors **425**–**439** (FIG. **18**) are connected between the DRAM supply voltage 3 V_{RAM} and system ground.

The system controller **129** generates the appropriate row address strobes (RAS) and column address strobes for the DRAM **111A**. In particular, the column address strobe lines CAS0[0..3] are applied to the upper and lower column address strobe pins (UCAS and LCAS) on the DRAM **111A** by way of a plurality of coupling resistors **442** to **450** (FIG. **12**). Similarly, the row address signals RAS0 and RAS1 are applied to the row address strobe pins on the DRAM **111A** by way of a plurality of coupling resistors **448** and **450**. Writing to the DRAMS **111A** is under the control of a DRAM write enable signal BRAMW, applied to the write enable pin WE on the DRAM **111A**. The DRAM write enable signal BRAMW is generated by the system controller **129** by way of a coupling resistor **452**.

An EEPROM or NVRAM 111B (FIG. 12) may be used to maintain system configuration parameters when the system is powered off. All user changeable parameters are stored in the EEPROM 111B. For example, pen calibration data and passwords, used during boot up, may be used in the EEPROM 452. The contents of the EEPROM 111B may be shadowed into a CMOS memory when the system is active. Communication with the EEPROM 111B is under the control of the system controller 129 and in particular, a pair of programmable input/output pins GPIO1 and GPIO2. The GPIO1 provides a clock signal to the EEPROM 111B while the pin GPIO2 is used for data transfer.

As discussed above, the wireless interface device 100 also includes the flash memory 117 (FIG. 25), which is used for storing the BIOS. The system controller 129 allows for direct shadowing of the BIOS by enabling the appropriate address space to read the FLASH/DRAM write mode which allows all reads to come from the flash device with writes to the DRAM 111A memory devices.

A main memory map as well as an I/O memory map are provided in Tables 3 and 4.

TABLE 3

Main Memory Map		
000000	Main System Memory	512K of Video Memory
0A0000 - 0BFFFF		
0C0000 - 0DFFFF		
0E0000 - 0FFFFFFF		
100000	Expansion 1 Meg DRAM	128K for BIOS ROM
1FFFFFFF		
200000	NOT USED	1-3/4 Meg of Application ROM
5FFFFFFF		
600000	2 Meg of Application and BIOS ROM	
7FFFFFFF		

TABLE 4

I/O MEMORY MAP	
Memory Space Description	Memory Locations (HEX)
DMA Controller #1	00 - 0F
Not Used	10 - 1F
Interrupt Controller #1	20 - 21
Not Used	22 - 23
Evergreen Configuration Address	24
Not Used	25
Evergreen Configuration Data	26
Not Used	27 - 3F
Counter/Timer	40 - 43
Not Used	44 - 5F
Keyboard Controller	60
Port B	61
Not Used	62 - 63
Keyboard Controller	64
Not Used	65 - 6F
NMI Enable, Real-Time Clock	70, 71

TABLE 4-continued

I/O MEMORY MAP	
Memory Space Description	Memory Locations (HEX)
Not Used	72 - 7F
DMA Page Registers	80 - 8F
Not Used	90 - 91
Port A	92
Not Used	93 - 9F
Interrupt Controller #2	A0 - A1
Not Used	A2 - CF
DMA Controller #2	D0 - DE
Not Used	DF - 2FF
Pen Controller	300
Not Used	301 - 3AF
Graphics Controller	3B0 - 3DF
RF Controller	3E0 - 3EF
UART COM1	3E8 - 3EF
Not Used	3F0 - 3FF

In addition to system control features and DRAM control, the system controller 129 provides various other functions. The power management function and NVRAM controller have been discussed above. The system controller 129 also controls all operations on the local AT bus 150. The AT bus clock is derived from the clock CLK2IN pin that is divided to achieve an 8 MHz bus rate.

The system controller 129 also includes a number of programmable pins which enhance its flexibility. For example, four general purpose input/output pins GPIO[0..3] are provided; each of which may be independently set for input or output. The GPIO1 and GPIO2 pins are used for the EEPROM 1111 as discussed above. The GPIO0 pin and GPIO3 pin may be used for various purposes. In addition to the programmable input/output pins, the system controller 129 includes two general purpose chip select pins GPCS1 and GPCS2 as well as a plurality of programmable output pins PC[0..9]. The programmable chip selects GPCS1 and GPCS2 are used for the pen controller 110A, UART 134 and the radio interface 114B.

Peripheral devices connected to the system ISA bus 151 are controlled by an integrated peripheral controller 128 as discussed above. The integrated peripheral controller 128 may be a PicoPower Model No. PT82C206F which can be operated at either 3.3 or 5 volts. As will be discussed in more detail below, the integrated peripheral controller 128 includes several subsystems such as: DMA Control; Interrupt Control; Timer Counter; RTC Controller; CMOS RAM and Memory Mapper.

The IPC 128 includes two type 8259A compatible interrupt controllers which provide 16 channels of interrupt levels, one of which is used for cascading. The interrupt controller processes all incoming interrupts in order as set forth in Table 5.

TABLE 5

INTERRUPT TABLE	
INTERRUPT	DESCRIPTION
Level 0	Timer Channel 0
Level 1	Keyboard Controller 2 Cascade
Level 2	Second Interrupt Controller
Level 3	Not Used
Level 4	COM1
Level 5	Pen Controller
Level 6	Not Used

TABLE 5-continued

INTERRUPT TABLE	
INTERRUPT	DESCRIPTION
Level 7	Not Used
Level 8	RTC Controller
Level 9	Not Used
Level 10	Radio Controller
Level 11	Not Used
Level 12	Not Used
Level 13	Not Used
Level 14	Not Used
Level 15	Not Used

The integrated peripheral controller (IPC) 128 (FIG. 14) is connected to the system data bus SD[0..15]. Addressing of the IPC 128 is accomplished by two bits SA0 and SA1 from the system address bus SA[0..23] and eight bits A[2..9] from the local address bus A[0..31]. The address bits from the local address bus A[2..8] are converted to 5 volts by way of a 3-to 5-volt signal converter 453 (FIG. 14) to develop the 5-volt address signals XA[2..8]. A 32-kilohertz clock signal 32-KHz from the clock generator 398 (FIG. 13) is applied to the clock input OSC1 of the IPC 128.

Referring to FIG. 20, in order to prevent spurious operation of the IPC 128 before the system power supply is stabilized, a power good signal PWRGOOD is applied to a power good pin PWRGD. The power good signal PWRGOOD is a delayed signal which assures that the 5-volt power supply has stabilized before the IPC 128 is activated. In particular, a 5-volt power supply 5 V_CORE is applied to a delay circuit which includes a resistor 454, a diode 456 and a capacitor 458. Initially, the 5-volt power supply signal 5 V_CORE is dropped across the resistor 454. While the capacitor 458 is charging, the diode 456 is in a non-conducting state. As the capacitor 458 begins to charge, the voltage at the anode of the diode 456 increases as a function of the RC time constant. When the capacitor 458 is fully charged, it approaches the value of the power supply voltage 5 V_CORE. When the capacitor 458 becomes fully charged, the power good signal PWRGOOD is applied to a power good pin PWRGD at the IPC 128 for enabling the IPC 128 after the power supply has stabilized. The diode 456 provides a discharge path for the capacitor 458 when the power supply is shut off. The power good signal PWRGOOD is also used to reset the keyboard controller 125.

A 5-volt power supply 5 V_CORE from the DC-to-DC converter 300 (FIG. 26) is applied to a ferrite bead inductor 460 (FIG. 13) to develop a 5-volt power supply 5 V_206, which, in turn, is applied to the power supply pins VCC of the IPC 128. In order to delay application of the 5-volt power supply 5 V_206 as discussed below, a charging circuit which includes a serially coupled resistor 462 and a capacitor 464 are connected between the power supply voltage 5 V_ and the system ground. A power supply reset signal PSRSTB, an active low signal, is applied to the junction between the resistor 462 and the capacitor 464 to discharge the capacitor 464 when the power supply is reset. Moreover, in order to stabilize the voltage of the power supply 5 V_206, a plurality of bypass capacitors 466 and 468 are connected between the power supply 5 V_206 and system ground.

In order to assure proper operation of the circuit, various pins of the IPC 128 are pulled low while various other pins are pulled high. In particular, the input/output read and write signals IOR and IOW are pulled up to the power supply

voltage 5 V_206 by a pair of pull-up resistors 470 and 472. In addition, the interrupt request pin IRQ10 is pulled up to the power supply voltage 5 V_CORE by a pull-up resistor 474. The signals OUT2, REFREQ, AEN16 and AEN8 are pulled low by pull-down resistors 455-461 while the signal TEST_MODE2 is pulled up to the supply voltage 5 V_CORE by a pull-up resistor 463.

Even though the IPC 128 includes a direct memory access (DMA) controller, this function is not required by the system. As such, the direct memory access request pins DREQ[0..7] are pulled low by a pull-down resistor 476 to system ground. In addition, as set forth in Table 5 above, various interrupt levels are unused. For example, as shown in Table 5, interrupt levels IRQ3, IRQ6, IRQ7, IRQ9, IRQ11, IRQ12, IRQ14, and IRQ15 are not used. Thus, these interrupt levels are pulled low by a pull-down resistor 478.

As illustrated in Table 5, interrupt levels IRQ4 and IRQ5 are used for the COM1 and pen controller interrupt levels, IRQ4 and IRQ5. To assure that these levels are proper, the IRQ4 and IRQ5, which are active high, are pulled low by pull-down resistors 480 and 482.

Interrupts by the system controller 129 and IPC 128 INTR_EG and INTR206 are applied to the CPU 112 by way of a diode 479 and pull-up resistor 481 (FIG. 14). In particular, the interrupt signals INTR_EG and INTR206 from the system controller 129 and IPC 128, respectively, are applied to the cathode of the diode 479 while the anode is pulled up to the power supply voltage 3 V_CORE by the pullup resistor 481. The logic level of the anode is set by the interrupt signal INTR, which is applied to the CPU 112. When the interrupt signals INTR206 and INTR_EG are high, the diode 479 does not conduct and the CPU 112 interrupt signal INTR will be high. When either of the interrupt signals INTR_EG or INTR206 are low, the diode 479 conducts, forcing the CPU 112 interrupt signal INTR low.

The IPC 128 also includes a type 8254 compatible counter/timer which, in turn, contains three 16-bit counters that can be programmed to count in either binary or binary-coded decimal. The zero counter output is tied internally to the highest interrupt request level IRQ0 so that the CPU 112 is interrupted at regular intervals. The outputs of the timers 1 and 2 are available for external connection. In particular, internal timer 1 generates one signal, OUT1, which is used to generate a DRAM refresh request signal REFREQ to the CPU 112. The internal timer 2 generates an output signal OUT2 that is used to generate speaker timing. All three internal timers are clocked from a timer clock input TMR-CLK at 1.2 megahertz from the system controller 129.

As mentioned above, the IPC 128 includes a real time clock (RTC) controller which maintains the real time. The real operational time is maintained in a CMOS RAM that can be accessed through registers 70H and 71H. The memory map for the CMOS memory is provided in Table 6 as shown below.

TABLE 6

CMOS MEMORY MAP	
INDEX	FUNCTION
00H	Seconds
01H	Seconds Alarm
02H	Minutes
03H	Minutes Alarm
04H	Hours

TABLE 6-continued

CMOS MEMORY MAP	
INDEX	FUNCTION
05H	Hours Alarm
06H	Day of Week
07H	Day of Month
08H	Month
09H	Year
0AH	Registry
0BH	Register B
0CH	Register C
0DH	Register D
0EH-7EH	User RAM

The area designated as User RAM is used by the system BIOS to save the status of the system configuration registers. The alarm bytes may be used to set and generate an interrupt at a specific time. When periodic interrupt is required, the two most significant bits in the alarm register can be set high.

The various clock signals used for the system are provided by the clock generator circuit 398 (FIG. 13). The clock circuit 398 includes a clock generator, for example, an Integrated Circuit Designs Model No. ICD2028. A 14.318 MHz crystal 484 and a 32.768 KHz crystal 486 are applied to the clock generator 488. In particular, the crystal 484 is applied to a pair of X1 and X2 input pins along with a plurality of capacitors 489, 490, 492 and an input resistor 494. Similarly, the crystal 486 is applied to input pins XSYSB1 and XSYSB2. A pair of capacitors 496 and 498 are connected across the crystal 486.

The clock generator IC 488 provides three clock outputs CLKA, CLKB and CLKD. The clock A output CLKA is used to develop an 8-MHz clock signal for the keyboard controller 125 by way of a resistor 500 and capacitors 502 and 504. The clock B output CLKB is used to develop a clock 2X output signal CLK2IN for the system controller 129 by way of the resistors 506, 508 and 510 and a pair of capacitors 512 and 514. The clock D output signal CLKD is used to generate a 1.84 MHz signal for use by the Universal Asynchronous Receiver Transmitter (UART) 134 by way of a resistor 516 and capacitors 518 and 520. As mentioned above, the system controller 129 also requires a 14 MHz clock signal. This clock signal is developed by way of a system bus output pin SYSBUS, a resistor 522 and a pair of capacitors 524 and 526.

Selection of the various clock output signals is available by way of the select pins S0, S1 and S2. These pins S0, S1 and S2 are pulled up to the 3-volt power supply 3 V_{CORE} by way of pull-up resistors 521, 523 and 525. The 3-volt power supply signal 3 V_{CORE} is available from the DC-DC converter 300 (FIG. 26).

The clock generator 488 utilizes a 3-volt power supply CLOCK_VCC (FIG. 13). The 3-volt power supply CLOCK_VCC is available from the DC-to-DC converter 300 (FIG. 26) by way of an in-line ferrite bead inductor 530. In particular, the 3-volt power supply 3 V_{CORE} is applied to the ferrite bead inductor 530 to generate the power supply for the CLOCK_VCC for the clock generator 488. This power supply CLOCK_VCC is applied to the power supply pin VDD. The power supply signal CLOCK_VCC is also used as analog supply AVDD to the clock generator IC 488 and is applied to the analog supply AVDD by way of the resistor 532 and a pair of capacitors 534 and 536. The power supply signal CLOCK_VCC is also applied to the battery pin VBATT of the clock generator IC 488 by way of a diode 537 to prevent any back feeding.

A number of the circuits in the system operate at either 3.3 volts or 5 volts. Thus, a plurality of bi-directional signal level translators 542 and 544 (FIG. 14) are provided, as well as the translator 453 previously discussed. The signal level translators 453, 542 and 544 may be as supplied by Integrated Circuit Technology, Model No. FCT164245T. Each of the signal level translators 453, 542 and 544 includes a 3-volt supply 3 V_{CORE} and a 5-volt supply 5 V_{CORE}, available from the DC-to-DC converter 300 (FIG. 26) In order to stabilize the voltage of the 3- and 5-volt power supplies, 3 V_{CORE} and 5 V_{CORE}, a plurality of bypass capacitors are utilized. In particular, the bypass capacitors 546 through 552 are connected between the 3-volt supply 3 V_{CORE} and system ground. Similarly, the bypass capacitors 554 through 560 are connected between the 5-volt supply 5 V_{CORE} and system ground. The ground terminals of each of the signal level translators 542, 544 and 453 are also tied to system ground.

Each of the signal level translators 542, 544 and 453 includes two 8-bit programmable input/output pins. More particularly, the first 8-bit group 1A/1B[1..8] is under the control of an operate/enable pin 1OE, which is active low, while the second bank 2A/2B[1..8] is under the control of an output/enable pin 2OE, also active low. The direction of the input pins and output pins (i.e., A relative to B) is under the control of direction pins 1DIR and 2DIR. The direction pin 1DIR controls the direction of the pins 1A/1B[1..8], while the pin 2DIR controls the direction of the pins 2A/2B[1..8].

The signal level translator 453 is used to convert the local data bus bits D[16..31] and the system data bus bits SD[0..15]. Both the local data bus D[16..31] as well as the system data bus SD[0..15] are bi-directional. In this application the processor bus 150 data bits D[31..16] are being mapped to the system data bus bits SD[15..0].

The direction of the signal level translator 542 is under the control of a signal direction signal SDIR, available at the system controller 129. The signal direction signal SDIR is applied to both the direction control pins 1DIR and 2DIR of the signal level translator 542. The operate/enable inputs 1OE and 2OE are under the control of system data enable inputs signals, SDEN3 and SDEN2, respectively; also under the control of the system controller 129.

The signal level translator 544 is used to map the signal levels of the local address bus bits A[23..8] to the system address bus bits SA[23..8]. More particularly, the local address bits A[23..16] are applied to pins 1A[1..8] while the local address bits A[15..8] are applied to the pins 2A[1..8]. Similarly, the system address bits SA[23..16] are connected to the pins 1B[1..], while the system address bits SA[15..8] are applied to the pins 2B[1..8]. In this case, the operate/enable pins 1OE and 2OE, both active low, are connected to system ground in order to permanently enable the signal level translator 544. The direction control pins 1DIR and 2DIR are permanently set such that the data always flows from A to B. In particular, the directional pins 1DIR and 2DIR are connected to the 3-volt power supply 3 V_{CORE} by way of a pull-up resistor 562.

The signal level translator 542 is used to convert the signal levels of the 3-volt clock output signals 14 Mhz, 1.84 Mhz, 32 KHz and 8 Mhz to 5-volt levels, as well as to convert the 3-volt local address bits A[2..8] to 5-volt address bits XA[2..8] for use by the IPC 128, as discussed above. More particularly, the system address bits, A[2..8] are applied to the pins 1A[1..8] The clock signals 14 MHz, 1.84 MHz, 32 KHz and 8 MHz are applied to the pins 2A1, 2A3, 2A6 and 2A8, respectively, to produce corresponding 5-volt

25

level signals 14 MHz_5 V, 1.84 MHz_5 V, 32 KHz_5 V and 8 MHz_5 V signals at pins 2B1, 2B3, 2B6 and 2B8, respectively. The unused pins 1A8 and 2B8 are pulled low by way of pull-down resistors 564 and 565, respectively. The operate/enable pins 1OE and 2OE are tied to system ground to permanently enable the signal level translator 542. The directional pins 1DIR and 2DIR are pulled up to the 3-volt power supply voltage 3 V_CORE by way of a pull-up resistor 566 to permanently force the direction from A to B.

Referring to FIG. 15, the system includes a keyboard controller 125, which performs several functions, including battery monitoring, LCD status control, brightness and contrast control, as well as keyboard control. In addition, the system also maintains the status of the remaining battery life, and also provides information to the system controller 129 when the battery voltage is low or other critical battery condition has occurred. In operation, the keyboard controller 125 will maintain the current status of the battery level until data is requested. When a critical battery condition event occurs, the keyboard controller 125 generates an SMI interrupt. As discussed above, the intelligent battery pack (IBP) 130 provides an indication of the percentage of remaining battery capacity. Communication between the IBP 130 and the keyboard controller 125 is by way of a bi-directional serial data bus, which includes a clock line BATCLK and a data line BATDATA. The data line BATDATA is a bi-directional line, which allows for bi-directional communication with the IBP 130. The clock line BATCLK is driven by the IBP 130, but may be pulled low by the keyboard controller 125.

The bi-directional serial data bus is connected to the port pins P4.2 and P4.3 on the keyboard controller 125. In particular, the port pin P4.2 is used for the serial battery data BATTDATA. An NPN transistor 570 is connected to the port pin P4.2 to disconnect the keyboard controller 125 from the IBP 130 during power down. In particular, the collector terminal of the NPN transistor 570 is connected to the port pin P4.2, while the emitter terminal forms a battery data signal BATTDATA. The base of the NPN transistor 570 is biased on by way of a biasing resistor 572 that is connected to a 5-volt power supply 5 V_KBD. The collector is pulled high by way of a pull-up resistor 574 connected to the 5-volt power supply 5 V_KBD.

Similarly, the battery clock signal BATTCLK is connected to the port 4.3 on the keyboard controller 125 by way of an NPN transistor 576. The collector terminal of the NPN transistor 576 is connected to the port 4.3 as well as to a pull-up resistor 578 and the 5-volt power supply 5 V_KBD. The NPN transistor 576 is turned on anytime the power supply to the keyboard 5 V_KBD is powered up by way of a biasing resistor 580. The emitter of the NPN transistor 576 forms the battery clock signal BATTCLK.

In addition to battery management, the keyboard controller 125 also supports an external PS/2-type keyboard, as well as a PS/2-type bar code reader, connected to a keyboard connector 140 (FIG. 29). Communication between the keyboard or bar code reader (not shown) is by way of a standard type PS-2 two-wire bus connected to serial ports P4.6 and P4.7. In particular, the keyboard data KDATA is pulled up to the 5-volt voltage supply 5 V_CORE by way of a pull-up resistor 582 while the keyboard clock signal KCLK is pulled up the 5-volt supply 5 V_CORE by way of a pull-up resistor 584.

Referring to FIG. 29, the keyboard connector 140 may be a 6-pin MINI-DIN connector or a DB-8 connector as shown. Pins 6-9 are connected to system ground. Pin 4 of the

26

connector 140 is pulled up to the power supply voltage 5 V_CORE by way of a fuse 579 and is filtered by a capacitor 581 and an inductor 583. The data signal KDATA is applied to pin 1 by way of a current-limiting resistor 585, while the clock signal KCLK is applied to pin 5 by way of a current-limiting resistor 587 and a pair of capacitors 589 and 591. These clock and data signals KCLK and KDATA are connected to the ports P4.6 and P4.7, respectively, for serial communication with an external keyboard or bar code reader.

Additionally, the keyboard controller 125 may be used to control the brightness level as well as the contrast level of the LCD display. More particularly, referring to FIG. 27, a contrast signal CONTRAST, available at port 0, pin 1 of the keyboard controller 125 (FIG. 15) is used to adjust the contrast level of the LCD display. The contrast signal CONTRAST is applied to an adjustment terminal ADJ of a negative 24-volt DC voltage supply, which can be incrementally adjusted in steps by a 24-volt DC supply 586 (FIG. 27), for example, a Maxim Model No. 749, which provides for 64-step adjustment. Thus, each high pulse will increment the contrast of the LCD display by one step. With a 64-step device, sixty-three pulses rolls the counter over and decreases the contrast by 1. The 24-volt DC supply 586 is under the control of an enable signal ENAVEE, available from the video controller 113A (FIG. 19).

In order to assure proper operation, the 24-volt supply 586 is connected in a circuit as shown in FIG. 27, which includes a plurality of capacitors 588, 590, 592, 594; a plurality of resistors 596, 598, 600 an inductor 602; a PNP transistor 604; and a zener diode 606. The output of the circuitry is a nominal negative 24-volt signal LCDVEE, which is adjustable in 64 increments by way of the CONTRAST signal, as discussed above, to vary the contrast level of the LCD display.

The keyboard controller 125 also controls the brightness of the LCD display. In particular, brightness adjustment signals BRIGHTNESS_UP, BRIGHTNESS_DOWN (FIG. 15) are available at port 1, pins 6 and 7. These signals BRIGHTNESS_UP and BRIGHTNESS_DOWN are normally pulled up to the 5-volt supply 5 V_KBD by way of a pair of pull-up resistors 608 and 610. These signals BRIGHTNESS_UP and BRIGHTNESS_DOWN are applied to a digital output potentiometer 612 (FIG. 27), for example a Dallas Semiconductor Model No. DS1669-50. The digital output potentiometer 612 is powered by a 5-volt power supply 5 V_CORE, which is also used to pull up an unused output terminal, RH.

The brightness control signals BRIGHTNESS_UP and BRIGHTNESS_DOWN are applied to the increment and decrement terminals, UC and DC of the digital output potentiometer 612. The output of the digital output potentiometer 612 is a variable resistance signal, which forms the brightness control signal BRIGHTNESS. This brightness control signal BRIGHTNESS is pulled down by a pull-down resistor 614.

The brightness control signal BRIGHTNESS from the digital output potentiometer 612, as well as a backlight control signal BACKLITEON and a backlight power signal BACKLITEPOWER are connected to the system by way of a 6-pin connector 615 (FIG. 27). The backlight control signal BACKLITEON is connected to pin 4 of the connector 615 and pulled low by way of a pull-down resistor 617. The power control signal BACKLITEPOWER is applied to pins 1 and 2 while the backlight brightness control signal BRIGHTNESS is applied to pin 3. The backlight control

signal BACKLITEON is available from the video controller 113A (FIG. 19) and is used to power the backlight on the LCD. The backlight power signal BACKLITEPOWER, available from an FET 619 (FIG. 20), is under the control of the backlight power control signal BACKLITEON, available from the video controller 113A (FIG. 19).

The FET 619 (FIG. 20) is used to control power to both the LCD as well as the backlight. In particular, referring to FIG. 20, the backlight power control BACKLITEON, is used to control an NPN transistor 617 by way of a current-limiting resistor 621. The NPN transistor 621, in turn, is used to control the FET 619 to generate the backlight power signal BACKLITEPOWER at the drain terminal D1. The main power signal POWER (FIG. 28) is connected to the collector of the NPN transistor 617 by way of a resistor 623. The main power signal POWER is also applied to a source terminal S1 of the FET 615. A gate terminal G1 of the FET 615 is connected between the resistor 623 and the collector of the NPN transistor 625. The backlight power control signal BACKLITEON is used to conserve power under certain power management conditions discussed above. This signal BACKLITEON controls the NPN transistor 625. In particular, in a normal state, the backlight power control signal BACKLITEON is high, which turns ON the NPN transistor 625. When the NPN transistor 625 is ON, the gate terminal G1 of the FET 619 is connected to system ground, which turns the FET 619 ON, thereby connecting the main power signal POWER to the drain terminal D1 of the FET 619 to provide a power signal BACKLITEIN, which is filtered by a ferrite bead inductor 625 (FIG. 28) to provide the backlight power signal BACKLITEPOWER, that is applied to the LCD by way of the connector 615 (FIG. 27). When the backlight power control signal is low, for example, during a power management mode, the NPN transistor 625 turns OFF, thereby connecting the gate G1 of the FET 619 to the main power signal POWER by way of the resistor 623, thereby turning the FET 619 OFF, disconnecting power to the LCD.

The FET 619 may be supplied as a dual element with two FETs in a single package. As shown in FIG. 20, the gate G2, source S2 and drain D2 terminals of the FET 619 are used to control power to the LCD, under the control of an LCD enable signal ENAVDD, available from the video controller 113A (FIG. 19). In particular, the LCD enable signal ENAVDD is normally high and is de-asserted to disable the LCD power supply LCD_POWER. This LCD enable signal ENAVDD is pulled low by a pull-down resistor 627 and applied to an inverter 629, whose output is connected to the gate terminal G2 of the FET 619. The LCD power supply signal LCD_VCC (FIG. 19) is applied to the source terminal S2 of the FET 619, while the drain terminal D2 represents the LCD power signal LCD_POWER, filtered by an inductor 629 and a capacitor 631. The LCD power signal LCD_POWER is connected to the LCD by way of the connectors 732 or 734 (FIG. 22). In operation, the LCD power enable signal ENAVDD is high, which turns on the FET 619 to enable the LCD power supply LCD_POWER. When the LCD power enable signal ENAVDD is de-asserted, the FET 619 is turned OFF.

The keyboard controller 125 (FIG. 15) is connected to the system data bus SD [0..7]. The system address bit SA2 is used for addressing the keyboard controller 125. In particular, the address terminal of the keyboard controller 125 is connected to bit SA2 of the system address bus SA[0..23].

Power to the keyboard controller 125 is provided by way of a 5-volt supply 5 V_KBD, supplied to the power supply

terminal VCC. The 5-volt supply 5 V_KBD, provided by the DC-to-DC converter 300 (FIG. 26) by way of an in-line ferrite bead inductor 618. In addition to supplying power to the keyboard controller 125, the 5-volt supply 5 V_KBD is used to pull-up various pins by way of pull-up resistors 620, 622, 624, 626, 628, 630, 632 and 634. In order to stabilize the 5-volt power supply 5 V_KBD, a plurality of bypass capacitors 636 and 638 are connected between the power supply 5 V_KBD and system ground.

As mentioned above, the keyboard controller 125 has various functions. One of those functions is to monitor when AC power is plugged into the machine from an AC adapter plug 633 (FIG. 29), connected to the external power supply signal AC/DCIN by way of a pair of EMI filters 641 and 643, and a connector 645. In particular, an AC power signal ACPWR, available from an FET 635 (FIG. 20), is applied to port 3, pin 1 FIG. 15) by way of an inverter 636. The external power supply signal AC/DCIN, available from the AC plug 633, is used to control the gate terminal of the FET 635, normally pulled down a pull-down resistor 637. A 5-volt supply 5 V_CORE is connected to the drain terminal while the source terminal is used for the AC power signal ACPWR, pulled down by a pull-down resistor 639. Then an external power source is not connected to the FET 635, the signal ACPWR will be low. Once external power is connected to the connector 633, the signal AC/DCIN from the IBP 130 goes low, which, in turn, turns on the FET 635 to cause the signal ACPWR to go high.

The keyboard controller 125 also monitors the status of the radio. As such, an output from the radio TX/RX_LED pin is applied to pin 2 of port 3 of the keyboard controller 125 by way of an inverter 638. When pin 1 of port 3 is high, the keyboard controller 125 interprets that the radio is in a transmit mode. Another signal from the radio CD_LED is used to provide an indication to the keyboard controller 125 that that radio is in a receive mode. This signal CD_LED is applied to pin 2 of port 3.

An 8 MHz clock signal 8 MHz_5 V is used to drive the keyboard controller 125. The clock signal 8 MHz_5 V is developed by the clock generator 398 and converted to a 5-volt level by way of the translator signal level translator 452.

The video controller 113A (FIG. 19) controls the video functions. The video controller 113A, for example, a model number CL-GD 6205 from Cirrus Logic, can support various video modes including a mono STN and a color TFT panel with up to 640x480 with 64 shades of gray. In addition, the video controller 113A will support 1024 by 768 resolution with 16 colors on a CRT through the aid of its on-board digital to analog converter.

The video controller 113A utilizes two clock sources for timing, generated by an internal clock generator to produce the required frequencies for the display and memory timing. Two separate analog power supply sources AVCCMCLK and AVCCVCLK are provided to the analog power supply inputs AVCCIVCLK and AVCC4MCOK on the video controller 113A. These analog power supply sources AVCCMCLK and AVCCVCLK are derived from the 3-volt power supply 3 V_CORE, available at the DC-to-DC converter 300 (FIG. 26). In particular, the 3-volt power supply 3 V_CORE is used to develop a 3-volt power supply VGA_VCC by way of an in-line ferrite bead inductor 642. The power supply VGA_VCC, in turn, is filtered by a plurality of bypass capacitors 644-642, connected between the power supply VGA_VCC and system ground. The 3-volt power supply VGA_VCC is used to develop the analog power

29

supplies AVCCMCLK and AVCCVCLK by way of a plurality of resistors **654** and **656** as well as a plurality of by pass capacitors **658** to **664**, connected to an analog ground AGND. The analog ground AGND is tied to the digital ground GND by way of a ferrite bead conductor **664**.

The keyboard controller **125** also provides various miscellaneous system functions by way of its I/O ports **0**, **1**, and **3**. Five port bits **P0.0–P0.5** of port **0** are used for system control. Bit **0** is used to generate a signal KBC_P00, an active high signal, which disables the general purpose chip select signals GPCS1 and GPCS2, available at the system controller **129** (FIG. 12) during boot-up, until the signals GPCS1 and GPCS2 are properly configured. As discussed above, the general purpose chip select signals GPCS1 and GPCS2 are used for selecting the pen controller **110A** (FIG. 21), the radio interface **114B** (FIG. 16) and the UART (**134**). Bit **P0.1** is used to generate a contrast signal CONTRAST, normally pulled low down by a pull-down resistor **639** (FIG. 5) for contrast control of the LCD as discussed above. Briefly, the contrast signal CONTRAST is used to step the 24-volt supply **586** (FIG. 27). Bit **P0.2** is used to generate a keyboard shutdown signal KBSHUTDOWN. This signal KBSHUTDOWN, discussed below, is active low, and in conjunction a pen shutdown signal PEN_SHUTDOWN, available at the pen controller **110A** (FIG. 21), is used to generate a shutdown signal SHUTDOWN to shutdown the AC-to-DC converter **300** (FIG. 26) during low power conditions. More particularly, the keyboard shutdown signal KBSHUTDOWN, pulled up by a pull-up resistor **641**, and the pen shutdown signal PEN_SHUTDOWN, pulled low by a pull-down resistor **643**, are diode ORed by a pair of diodes **645** and **647**. The cathodes of the diodes **645** and **647** are joined to form the active low shutdown signal SHUTDOWN. If the keyboard shutdown signal KBSHUTDOWN is asserted, the shutdown signal SHUTDOWN will be forced low, which, in turn, is used to disable the DC-to-DC converter **300** (FIG. 26). Bit **P0.3** is used to generate a signal FLASHVPP to enable the flash memory devices **742–748** (FIG. 25) to be programmed. In particular, when the signal FLASHVPP is low, the flash memory devices **742–748** can be programmed. Bit **P0.4** is used to generate a signal KBC_P04. The signal KBC_P04 is an active high signal and is used to indicate to the system controller **129** (FIG. 12) that a low battery condition has occurred. Bit **P0.5** is used for speaker control as discussed above. The pen **P0.5** is used to generate the speaker disable signal SPKRDISABLE, an active high signal.

Port **1**, bits **P1.1**, **P1.5**, **P1.6**, and **P1.7** of the keyboard controller **125** are used for system functions. Bit **P1.1** is configured as an input and is used to indicate to the keyboard controller **125** that the system is in a test mode. As discussed above, the test mode signal TEST_MODE is used to enable the flash memory device **742** (FIG. 25) to be programmed. In particular, as discussed above, the test mode signal TEST_MODE is used to generate a decode signal FLIP_SA18 (FIG. 17) for decoding of the flash memory device **742**. Port **1**, bits **P1.5**, **P1.6**, and **P1.7** are used for LCD control. In particular, the pen **P1.5** may be used for LCD status control. the pens **P1.6** and **P1.7** are used for brightness control of the LCD as discussed above.

Port **3**, bits **P3.1**, **P3.2**, **P3.3**, **P3.4**, **P3.5**, and **P3.7** are configured as inputs. As discussed above, a signal ACPWR, available from the source of the FET **635** (FIG. 20), is applied to the pin **P3.1**. This signal ACPWR notifies the keyboard controller **125** that an external power source is connected to the system. The signal CD_LED is applied to the pin **P3.2**. This signal, CD_LED, available from the radio

30

interface (FIG. 16), indicates that the radio is receiving a signal. A signal TX/RX_LED, also available from the radio interface, is applied to the pin **P3.3**. This signal TX/RX_LED indicates that the radio is in a transmit mode. A signal DOCKACK/ may be applied to the pin **P3.4**. This signal may be used to indicate to the keyboard controller **125** that a device is docked to the UART **134**. The development of the signal DOCKACK/ does not form a part of the present invention. A second test mode signal TEST_MODE_2 may be applied to the pin **P3.5** for added functions. A signal PC5_P37 is applied to the pen **P3.7**. This signal PC5_P37 is available from the system controller **129** (FIG. 12) and indicates that the system is in a sleep state as discussed above.

The video controller **113A** is connected to the system database SD[**0..15**] as well as the system address bus SA[D.**23**] and is adapted to support the video memory **113B** of either 256K by 16-bit or 256K by 4-bit video memory chips **666** or **668**. These video memory chips **666** and **668**, for example 256 K by 16 dram memory chips, as manufactured by Toshiba Model No. NE4244170-70, are connected to a 16-bit video memory databus VMDATA[**0..15**] and the 9-bit video memory address bus VMADR[**0..8**]. The video memory chips **666** and **668** are accessed in the range from A000H–BFFFFH and are switched to allow access to a full 512 kilobyte range. The video memory chips **666** and **668** are provided with dual column address strobe (CAS) pins to allow byte selection. The video memory column address strobes LCAS and UCAS are under the control of the high and low video memory column address strobe low and high signals, VMCASL and VMCASH, which are applied to the LCAS and UCAS pins by way of a pair of current-limiting resistors **670** and **672** to generate the buffered CAS the lower and high CAS signals VMCISLBUF and VMCASHBUF. The row address strobe signal VMRAS from the video controller **113A**, as well as the write/enable signal VMWE, are also applied to the video memory **666** and **668** by way of current limiting resistors **674** and **676** respectively. The output/enable pin on the video memory chips **666** and **668** is under the control of a video memory operate/enable signal VMOE. This video memory operate enable signal VMOE is generated by the video controller **113** and is applied directly to the video memory chip **666** and **668**.

Various power supply signals VGA_VCC, LCD_VCC, VGABUS_VCC and VMEM_VCC are applied to the video controller **113A**. The power supply VMEM_VCC is applied to the VMEM_VCC pins on the video controller **113A** and is also used as the power supply for the video memory chips **666** and **668**. The video memory power supply VMEM_VCC may be supplied as either a 3-volt or 5-volt power supply. More particularly, both a 3-volt and 5-volt power supply 3 V_CORE and SV_CORE. Depending on whether 3-volt or 5-volt operation is selected, only one of the component positions illustrated as ferrite bead inductors **680** or **682** will be populated to produce the power supply VMEM_VCC.

As will be discussed in more detail below, the system also includes an LCD controller to control the LCD screen **113C**. The power supply for the LCD controller LCD_VCC can likewise be supplied as either three volt or five volt by way of the 3- and 5-volt power supply voltages 3 V_CORE and 5 V_CORE, available at the DC-to-DC converter **320** (FIG. 26). Depending on the voltage selected, only one of the component locations **684** and **686** will be populated to provide the LCD power supply voltage LCD_VCC. In addition, a power supply voltage VGABUS_VCC is used for the VGA bus. This power supply voltage VGABUS_VCC

VCC is generated by the DC-to-DC converter **320** by way of a ferrite bead inductor **688**.

In order to filter noise out of the power supply signals, various bypass capacitors are connected between the power supply signals and system ground. For example, a plurality of bypass capacitors **690–696** are coupled between the power supply signal VMEM_VCC and the system ground. Similarly, a pair of bypass capacitors **698** and **700** are connected between the power supply signal LCD_VCC and the system ground. Lastly, a plurality of bypass capacitors **702** to **706** is connected between the power supply signal VGABUS_VCC and the system ground.

Additional filtering is provided for the analog subsystem. In particular, a filter consisting of a pair of capacitors **708** and **710** and a resistor **712** is connected to a filter terminal VFILTER and analog ground AGND. Similarly, another pair of capacitors **714** and **716** and a resistor **718** are connected between a signal MFILTER and analog ground AGND.

The video controller **113A** requires two separate clock signals: 14 MHz; and 32 KHz. The 14 MHz clock signal is used for most timing including the LCD panel memory and the bus cycle while the 32 KHz clock signal is used for video memory refreshing when the system is suspended. These clock signals are supplied by the clock generator **398** (FIG. **13**) by way of the signal level translator **452** (FIG. **14**). More particularly, 32 KHz and 14 MHz clock signals 32 KHz and 14 MHz from the clock generator **398**, respectively, are applied to the signal level translator **452** to transform these respective signals into 5-volt signals 32 KHz_5 V and 14 MHz_5 V to provide a suitable clock signal voltage for the video controller **113A**.

RGB data from the video controller **113A** (FIG. **19**) is supplied to the LCD screen **113C** by way of a data bus PDATA[0..17]. This data bus PDATA[0..17] is applied to a plurality of current limiting resistors **708–742**, respectively, to generate the buffer signals PDBUF[0..17]. These buffer signals PDBUF[0..17] are connected to the LCD panel **113** along with various control signals by way of a pair of connectors **732** and **734**.

The BIOS as well as other data is stored in flash memory, for example, 512 K by 8-bit memory devices **742–748** (FIG. **25**). These flash memory devices **742–748** are connected to the local ISA bus **150** by way of the system address bus SA[0..23] and the system data bus SD[0..15]. The chip enable pins CE of the flash memory devices **742–748** are selected by a decoder circuit (FIG. **17**), as will be discussed in more detail below. The output enable pins OE on the flash memory devices **742–748** are under the control of a memory read signal MEMR. The memory read signal MEMR is under the control of the system controller **129**. The write/enable pins WE, which are active low, are under the control of a memory right gate signal MEMWGATE. This signal MEMWGATE is only enabled when the flash memory devices **742–748** are being programmed. As discussed above, programming of the flash memory devices **742–748** is under the control of a flash program signal FLASHVPP, available at port **0.3** of the keyboard controller **125** (FIG. **15**). This programming signal FLASHVPP, normally pulled high by a pull-up resistor **749** (FIG. **17**), is ORed with a memory write signal MEMW by way of an OR gate **751** to generate a signal MEMGATE, an active low signal.

The power supply for the flash memory devices **742–748** is developed by a 5-volt power supply signal 5 V_ROM. The 5-volt power supply signal 5 V_ROM is available from the DC converter **300** (FIG. **20**) by way of a ferrite bead inductor **751**. This power supply signal 5 V_ROM is also connected to a plurality of by-pass capacitors **752–758**, for stabilization.

Decoding of the flash memory devices **742–748** is provided by the circuitry that includes the buffers **760**, **762**, the inverters, **764**, **766**, and **768** and OR **770** and a 3- to 8-bit multiplexer, Model No. 74HCT138, for example, as manufactured by Motorola and a pair of resistors **772** and **774** (FIG. **17**). In particular, the system address bits SA[19..21] are applied to a 3- to 8-bit multiplexer **776**. The system address bit SA18 is applied to the inverter **760** to develop a FLIP_SA18 signal that is pulled down by the pull-down resistor **774**. During a normal boot-up, the FLIP_SA18 signal will be same as the system address bit SA18. However, during a test mode boot-up, the FLIP_SA18 signal will be low until a control signal available at the control signal GPI00, available at the system controller **129**, goes low in order to enable the system to boot from the BIOS in the flash memory device **742** as will be discussed in more detail below. Once the GPI00 signal goes low, the FLIP_SA18 signal will be the same as the system address bit SA18.

The multiplexer **776** is under the control of a flash memory rewrite signal MRW. This signal MRW and the system address bit SA[23]. The flash memory read write signal MRW is under the control of an OR gate **780**. The OR gate **780**, in turn, is under the control of memory read and write signals MEMW and MER, which are applied to a pair of inverters **782** and **784**, respectively, and, in turn, to the OR gate **780**. The memory read MEMR and memory write MEMW signals are available from the system controller **129**.

The output of the multiplexer **776** is used to generate the chip select signals CS60, CS68 and CS70. In order to provide the ability of the flash memory device **742** to be addressed during a test mode, the chip select signal CS78 is under the control of an OR gate **770** and a plurality of inverters **764–768**. During a normal mode of operation, the chip select signal CS78 will be under the control of the multiplexer **776**. During a normal boot up, the chip select signal CS78 for the flash memory device **742** will be 00 under the control of a ROM chip select signal ROMCS, available at the system controller **129** in order to enable the system BIOS to be shadowed into the DRAM **111A**.

In order to provide the ability of the system to update the BIOS in the flash memory device **742** and to recover from a corruption of the BIOS data in the flash memory device **742**, a uniform asynchronous receiver transmitter (UART) **788** (FIG. **23**) is provided. The UART **788** is connected to the system data bus SD[0..15] and the system address bus bits SA[0..2]. The UART **788** is powered by the 5-volt power signal 5 V_CORE, available at the DC-to-DC converter **320** (FIG. **26**). A 1.84 MHz clock signal, 1.84 MHz_5 V, available at the signal level translator **452**, is used to drive the UART **788**.

A serial interface **790** (FIG. **30**), consisting of a standard DB-9 connector, enables external serial data to be received by the UART **788** (FIG. **23**). The UART signals are filtered by way of a plurality of resistors **792–806** and bypass capacitors **802–822** and applied to an optional disaster recovery adapter **824**, an RS-232 interface, connected to the rear of the DB-9 connector **790** and permits the flash memory devices **742–748** (FIG. **25**) to be updated by an external source in the event of a flash disaster. The flash recovery adapter **824** may be implemented as a DB-9 connector and is connected to the 5-volt power supply 5 V_CORE, which, in turn, is connected to a plurality of bypass capacitors **826** and **828**. An additional four capacitors **830–836** are connected to the module **824** as shown.

The power supply for the system includes the DC-to-DC converter **300** which has the ability to provide both 3-volt

and 5-volt power supplies signals to the various subsystems as discussed. The DC-to-DC converter includes a switching power supply **850**, for example, a Maxim type **786**. One source of power to the DC-to-DC converter **300** is the IBP **130**, for example, 7.2 volts nominal, as well as from an external source of AC power connected to the plug **633** (FIG. 29).

Input power to the DC-to-DC converter **300** may be from an AC/DC converter (not shown) connected to the plug **633**, which has a DC output voltage between 5.5–15 volts DC, applied to a power supply terminal AC/DCIN (FIG. 28) as well as internal batteries, for example, the IBP **130**, connected to the system by way of a connector **850** (FIG. 26). The battery supply voltage from the IBP **130** is connected to the battery positive terminal BATT (FIG. 28). The two supplies BATT and AC/DCIN are alternatively used to develop a main power signal POWER (FIG. 28), that is applied to a switching power supply **851**, for example, a Maxim type **786** by way of a pair of FETS **854** and **856** (IL. 26), under the control of a main power switch **855** (FIG. 28). The main power signal POWER is applied to a drain input D2 on each of the FETS **854** and **856**. A bypass capacitor **860** is connected to the drain terminal D2 of the FET **856** and system ground. The source terminals S2 of each of the FETS **854** and **856** is connected to the switching power supply **851** to provide 5- and 3-volt references by way of the zener diodes **860** and **862**, respectively. The gate terminals G1 and G2 of the FETS **854** and **856** are under the control of the switching power supply **851**.

The switching power supply **851** provides both a 3-volt and 5-volt output voltages 3 V_{CORE} and 5 V_{CORE} by way of filters which include a plurality of resistors **866** and **868**, a plurality of inductors **870** and **872**, and a plurality of capacitors **874–882** as well as a capacitor **879**. For proper operation, the D1 and D2 terminals on the switching power supply **851** are connected to the system ground along with the ground pins PGND and GND. The SS3 and SS5 pins are connected to system ground by way of a pair of capacitors **884** and **886**.

The frequency of the switching power supply **851** is under the control of a pair resistors **888** and **890** and a capacitor **892**, connected to the SYNC and reference terminals on the switching power supply **851**. A HOOK-VCC signal is applied to the VH and VL pins of the switching power supply **851**. This signal HOOK-VCC is available from the module **894** (FIG. 29), discussed above. The signal HOOK-VCC signal is connected to the switching power supply **851** by way of a resistor **896** (FIG. 26); a plurality of capacitors **898**, **900** and **902**; and an FET **904**.

As mentioned above, both the pen controller **110A** (FIG. 21) and keyboard controller **125** (FIG. 15) are used to develop a shutdown signal SHUTDOWN. The shutdown signal SHUTDOWN is pulled low by a pull-down resistor **906** and applied to an active low shutdown pin SHDN* on the switching power supply **851**. The shutdown signal SHUTDOWN (FIG. 20) is indicative of a shutdown by the keyboard controller **125** (FIG. 15).

As mentioned above, one source of power for the system is the IBP **130** which accounts for temperature and discharge rates and sends it to the keyboard controller **125** (FIG. 15). Two predefined levels are set in the IBP **130** to indicate low battery and critical battery. The IBP **130** will inform the keyboard controller **125** of a low battery when there is approximately five minutes left. When the battery charge is between 5 minutes to 2 minutes, the IBP **130** will report a battery critical condition. Within the final thirty seconds the

IBP **130** will force an immediate shutdown. The IBP **130** will report the battery status approximately once every 2.5 seconds. If the system is changing to a power savings mode, a command will be sent to the IBP **130** to put the IBP **130** into a power-saving state. The IBP **130** will trl-state its communication lines and discontinue reporting battery status to the system.

A charge control signal CHGCTRL from the IBP **130** is used to control charging. Referring to FIG. 28, the charge control signal CHGCTRL is applied to a zener diode **910**, for example, a 5.1 V zener diode. The zener diode **910** controls whether the IBP **130** is fast charged or trickle charged as a function of the magnitude of the charge control signal CHGCTRL.

In particular, if the magnitude of the charge control signal CHGCTRL is less than the zener breakdown voltage (i.e., less than 5.1 volts), the IBP **130** is trickle-charged by way of series pass transistor **912**, a pair of resistors **914** and **916** from the external power signal POWER by way of a diode **918**, a fuse **920** and a filter consisting of an inductor **922** and a capacitor **924**.

Should the charge control signal CHGCTRL be greater than the zener breakdown voltage of the zener diode **910**, the IBP **130** will be fast charged by way of an FET **928** whose source terminal is connected to the AC/DC converter by way of the diode **918** and drain terminal, connected to the battery positive terminal BATT by way of the fuse **920** and the inductor **922**.

The series pass transistor **912** that controls trickle charging is under the control of an FET **930**. The drain terminal of the FET **930** is connected to the system ground while the source terminal is connected to the base terminal of the PNP series pass transistor **912**. Normally, the series pass transistor **912** is turned off with its base terminal being high by way of its connection to a pair of biasing resistors **932** and **934**, which, in turn, are connected to the main power signal POWER by way of the diode **918**. When the charge control signal CHGCTRL is less than the breakdown voltage of the zener diode **910**, the charge control signal CHGCTRL turns on the FET **930** by way of the biasing resistors **936** and **938** a coupling capacitor, connected to its gate terminal. Once the FET **930** is turned on, it, turns on the series pass transistor **912** to provide a charging path between the main power signal POWER and the battery positive terminal BATT.

As mentioned above, fast charging of the battery is under the control of the FET **928**. The FET **928**, in turn, is under the control of a PNP transistor **926**. The PNP transistor **926**, which includes a pair of biasing resistors **940** and **942**, is connected to the collector terminal of an NPN transistor **942**. The base of the NPN transistor **942** is connected to a pair of biasing resistors **944** and **946** and, in turn, to a collector terminal of another NPN transistor **948** and the main power signal POWER. The NPN transistor **948** is biased by way of a pair of biasing resistors **950** and **952** and, in turn, to the anode of the zener diode **910**.

In operation, when the charge control signal CHGCTRL exceeds the breakdown voltage of the zener diode **910**, the zener diode **910** conducts thereby biasing the NPN transistors **942** and **948**, turning them ON. Once the NPN transistor **942** is turned ON, the base terminal of the PNP transistor **926** is connected to ground, thereby turning the PNP transistor **926** ON. The PNP transistor **926**, in turn, connects the main power signals POWER to the gate terminal of the FET **928** by way of the diode **918**, thereby turning the FET **928** ON to enable the battery positive terminal BATT to be fast charged from the AC-to-DC converter.

As mentioned above, the wireless interface device **100** includes a radio system which allows for wireless interfacing with a host computer and also wireless interfacing to both a wired local area network (LAN) and a wireless LAN. The radio subsystem has been discussed above. It is implemented by way of an interface **960** (FIG. 16), implemented by way of a 25x2 header, which connects the radio subsystem to the balance of the circuitry in the wireless interface device **100**. In particular, the system data bus SD[0..15], as well as the system address bus bits SA[0..2] are connected to the interface **960**. The radio interface **960** is under the control of the system controller **129** (FIG. 12), such as I/O write (IOW), I/O read (IOR) and an address enable signal (AEN).

Output signals from the radio interface **960** include the signals CD_LED, TX/RX_LED, IRQ10 and IOCS16. As discussed above, the signal CD_LED indicates a connection has been made with a host computer **101**. The signal TX/RX_LED indicates that a signal is either being sent or received through the radio interface **960**. As mentioned above the peripheral controller **128** (FIG. 13) is responsible for interrupt control. Thus, the radio subsystem interrupt IRQ10 is applied to the peripheral controller **128**. Power supply for the radio interface **960** is by way of a 5-volt power supply signal 5 V_CORE, available at the DC-to-DC converter **300** (FIG. 26), which is filtered by a pair of bypass capacitors **962** and **964**.

The interrupts for both the radio interface **960** IRQ10, as well as the UART **788** (FIG. 23) IRQ4, are formed into a common signal IRQ10/4 and applied to the system controller **129** by way of a resistor **966**. In particular, the radio interface interrupt signal IRQ10 is applied to an inverter **962**, whose output is ORed by way of the OR gate **964** with the UART **788** interrupt signal IRQ4. The output of the OR gate **964** forms the combined interrupt signal IRQ10/4.

The radio interface **960**, as well as the UART **788** (FIG. 23), are selected by the chip select signals RADIOCS and URTCS. These signals are available at the output of a pair of the OR gates **968** and **970**, respectively. The system address bit SA3 is inverted by way of an inverter **972** and ORed with a general purpose chip select gate signal GPC-SIGATE by way of the OR gate **970** to generate the UART chip select signal URTCS. The system address bit SA3 is applied directly to the OR gate **968** and ORed with the general purpose chip select gate signal GPCS1GATE to generate the radio chip select signal RADIOCS. The general purpose chip select signal gate signal GPCS1GATE is available at the output of an OR gate **974**. In particular, a general purpose chip select signal GPCS1, available from the system controller **129** (FIG. 12), is ORed with an output from pin 0 of port 0 of the keyboard controller **125** (FIG. 15) to cause the radio interface **960** to be addressed at address 3E0-3E7 and the UART **788** to be addressed at address 3EA-3EF. The signal KBC_P00 is normally pulled up to the 5-volt power supply voltage 5 V_CORE by way of a pull-up resistor **976**.

The pen controller **110A** is illustrated in FIG. 21 and is adapted to cooperate with an analog-resistive type digitizer **106**. The pen controller **110A** includes a controller **980**, for example a Motorola type MC68HC705J2 microcontroller, with the firmware being programmed within the part. The controller **980** communicates with the system by way of the system data bus SD[0..15]. In particular, serial data from a port PB6 on the controller **980** is applied to a shift register **982**, which, in turn, is connected to an 8-bit parallel buffer **984**, which, in turn, is connected to the serial data bus SD[0..15]. The controller **980** is adapted to be used with an

analog-resistive touch screen digitizer, for example a drawing No. 8313-34 Rev. C4, as manufactured by Dynapro. XY information from the digitizer **106** is received by the controller **980** by way of a connector **986**. The X and Y information from the digitizer is connected to a 12-bit analog-to-digital (A/D) converter and also applied to port PA5 of the microcontroller **980**. In particular, the X- data from the digitizer is applied to the A1 terminal of the A/D converter **988** by way of a pull-up resistor **990** and an FET **992**. The FET **992** is under the control of a charge pump **994**, for example a Linear Technology Model No. LTC1157C58. The Y- data from the digitizer is applied to the terminal A1 of the A/D converter **988** by way of a current-limiting resistor **994**. A pair of bypass capacitors **996** and **998** are tied between the terminals A0 and A1 of the A/D converter **988** and an analog ground PEN_AGND. The X+, Y+, X-, Y- inputs from the digitizer are also applied to the controller ports PA[0..4] by way of a plurality of transistors **1000**, **1006**, **1010**, **1016** and **1018**; a plurality of resistors **1002**, **1008**, **1012**, **1014**, **1020**, **1022**, **1028**, **1032** and **1034**; an inductor **1004**; and a plurality of capacitors **1024** and **1026**. The transistor **1018**, as well as the transistors **992** and **998**, are used to prevent leakage in a suspend state.

Power from both analog and digital power supply and grounds are supplied to the system. In particular, a 5-volt digital power supply PEN_VCC, developed from the 5-volt supply 5 V_CORE, is available from the DC-to-DC converter **300** (FIG. 26) by way of an in-line ferrite bead inductor **1028**. An analog power supply PEN_AVCC is developed from the digital supply PEN_VCC by way of an in-line ferrite bead inductor **1030**. The digital power supply PEN_VCC is applied to the microcontroller **980** and filtered by a bypass capacitor **1030**. The analog supply PEN_AVCC is utilized by the 12-bit analog-to-digital converter **988** and filtered by way of a bypass capacitor **1032**.

A separate clock supply is used for the microcontroller **980**. This clock supply includes a 4.0 MHz crystal **1034**, a resistor **1036** and a pair of parallel coupled capacitors **1038** and **1040**. The clock supply is applied to the oscillator terminals OSC1 and OSC2 of the microcontroller **980**.

A 5-volt signal PENACT_5 V, available at the port P5 V pin of the microcontroller is converted to a 3-volt signal PENACT_3 V by way of a pair of voltage dividing resistors **1042** and **1044**. This signal PENACT_3 V is applied to a 3-volt terminal of the system controller **129** (FIG. 12). As discussed above, the power supply for the FETs **992** and **1018** is provided by the charge pump **994**. The power supply for the charge pump **994** is a 5-volt power supply signal 5 V_CORE, available at the DC-to-DC converter **300** (FIG. 26). A ground terminal of the charge pump **994** is connected to system ground by way of a pull-down resistor **1050**. The 5-volt power supply PEN_VCC is also utilized by the shift register **982** and the data buffer **984** and buffered by way of a pair of bypass capacitors **985** and **987**.

The chip select signal PENCs for the data buffer **984** is generated by an OR gate **1052**. The general purpose chip select signal GPCS2 is available from the system controller **129** (FIG. 12), as well as a signal KBC_P00, available from the keyboard controller **125** (FIG. 15) are applied to the inputs of the OR gate **1052**.

A pen shut-down signal PEN_SHUTDOWN is used to develop a shut-down signal SHUTDOWN as discussed above for turning on the switching power supply **851** (FIG. 26). The pen shutdown signal PEN_SHUTDOWN is developed by the circuit that includes the transistors **1060**, **1062** and **1064**; a plurality of resistors **1066**, **1068**, **1069**, **1070** and

1072; and a capacitor 1074. In particular, a 5-volt power supply signal 5 V_{CORE} is applied to a pair of voltage-dividing resistors 1070 and 1072, which, in turn, is used to bias the transistor 1064 on. The base-emitter voltage is held fairly constant by the capacitor 1074. Once the transistor 1064 is turned on, it is used to control the FET 1062. A main power supply signal POWER is applied to the gate of the FET 1062 by way of the resistor 1069. Wake up of the system by way of the pen subsystem is discussed below.

6. Flash Disaster Recovery

As mentioned above, the wireless interface device 100 includes the flash memory devices 742-748 (FIG. 25). As will be discussed in more detail below, the flash memory devices enable user software upgrades by way of the radio interface 960 (FIG. 16). Should power be lost during the programming, the data within the flash memory devices 742-748 will be corrupted, which could result in the system failing to boot.

In order to enable recovery from such a condition, recovery BIOS is stored in a protected sector of the flash memory device 742, which will be unaffected during reprogramming. In addition, a serial port interface 790 (FIG. 30) is provided to enable the flash memory devices 742-748 to be programmed in such a condition by an alternative wired source following a normal boot-up. Unfortunately, the configuration of the flash memory device 742 may result in the system failing to boot. More particularly, disaster recovery BIOS is not stored at the uppermost address of the flash memory device 742. Each flash memory device 742-748 are 512 Kx8-bit devices. With reference to Table 5 above, the flash memory device 742 is mapped to the address range \$0C0000-\$0FFFFFF. The recovery BIOS is contained in the lower half of that range (i.e. \$0E0000-\$0FFFF).

On a normal boot-up, the system begins executing code at the top of the address range (i.e. \$0C0000-\$0FFFFFF) flash memory device 742 by way of the system address bit SA18. More particularly, on a normal boot-up a test mode signal TEST_MODE, available at port 1.1 of the keyboard controller 125 (FIG. 15) is pulled high by the keyboard controller 125 during boot-up, which enables the buffer 762 (FIG. 17) which, in turn, enables another buffer 760 to enable the system address bit SA18 during boot-up. When the system address bit SA18 is enabled, the system begins executing code at the top of the address range (\$0C0000) of the flash memory device 742. However, during a condition when the data in the top half of the address range (\$0C0000-\$0FFFFFF) becomes corrupt as a result of a problem occurring during reprogramming, the system may not boot during such a condition.

In order to solve this problem, the system address bit SA18 is forced low. By forcing the system address bit SA18 low, the system will begin executing code from the protected area of the flash device 742 in the address range (\$0E0000-\$0FFFF) during such a condition where the disaster recovery BIOS resides in a protected sector. In particular, the system address bit SA18 is applied to the buffer 760 (FIG. 17), which is under the control of the test mode signal TEST_MODE by way of the buffer 762. The output of the buffer 760 is a signal FLIP_SA18, which is applied to the address pin A18 (FIG. 25) on the flash memory device 742.

During a normal boot-up, the test mode signal TEST_MODE will enable the buffer 762 (FIG. 17) and, in turn, the buffer 760 to cause the system address bit SA18 to drive the signal FLIP_SA18. During a condition when the code in the

flash memory device 742 becomes corrupt, the test mode signal TEST_MODE is forced low, which, in turn, forces the signal FLIP_SA18 low, resulting in the system executing code from the protected area (i.e. \$0E0000-\$0FFFF) of the flash memory device 742 during such a condition to enable the flash memory device 742 (FIG. 25) to be reprogrammed by way of the serial interface 790 (FIG. 30).

There are various ways in which to force the test mode signal TEST_MODE low during reprogramming of the flash memory device 742 by way of the serial interface 790. One way is to externally ground the test mode signal TEST_MODE during such a condition. In particular, the test mode signal TEST_MODE may be connected to one pin of a two-pin header 1100 (FIG. 30). The other pin of the header 1100 is connected to system ground. During reprogramming of the flash memory device 742, an external jumper (not shown) is inserted into the header 1100 to shunt the test mode signal TEST_MODE to system ground to enable the system to execute code from the protected or boot block area of the flash memory device 742 in order to enable the system to be booted. Once the system is booted, the flash memory device 742 is reprogrammed by way of the serial interface 894 (FIG. 29). Once reprogramming is complete, the shunt is removed from the header 1100 (FIG. 30) and the adapter plug 790 is removed, restoring the system to normal operation.

7. Resume on Pen Contact

In order to conserve battery power, the wireless interface device 100 goes into a suspend mode when the system is not in use. As discussed above, a shut down signal SHUTDOWN (FIGS. 20 and 26) is used to shut down the power supply 851 (FIG. 26) during such a condition, which essentially disables the power to all but the circuitry required to detect a pen down event by way of the main power signal POWER (FIG. 28).

Three sources control the shut down signal SHUTDOWN: the keyboard controller 125 (FIG. 15); the pen controller 110A (FIG. 21) and a signal HOOK_VCC, connected to the switching power supply 851 (FIG. 26) by way of the FET 904. These sources are diode ORed to the shut down signal SHUTDOWN by way of the diodes 645 and 647 (FIG. 20) and a diode 1102 (FIG. 28). During a normal state, the shut down signal SHUTDOWN is high, which enables the power supply 851 (FIG. 26). When the shut down signal SHUTDOWN goes low, the power supply 851 goes into an inactive state. During the inactive state, minimum power is supplied to the pen detection circuitry as discussed above.

As will be discussed in more detail below, once the system is turned on by the main power switch 855 (FIG. 28), the shut down signal SHUTDOWN will be under the control of the pen shutdown signal PEN_SHUTDOWN, available from the pen controller 110A (FIG. 21) and the keyboard controller shut down signal KBSHUTDOWN (FIG. 20).

The keyboard controller 125 (FIG. 15) can place the system in a suspend state by way of a command, which, in turn, causes the keyboard controller shut down signal KBSHUTDOWN, available at port P0.2, to go low. More particularly, during normal operation, only the keyboard shutdown signal KBSHUTDOWN is high, placing control of the suspend state solely in the keyboard controller 125. The keyboard controller 125 can then force the system into a suspend state by forcing port P0.2 low, which, in turn, places the power supply 851 (FIG. 26) in an inactive state.

The pen shut down control signal PEN_SHUTDOWN is used to wake the system from a suspend state. More

particularly, as mentioned above, during a suspend state, power from the main power supply POWER (FIG. 28) is applied to the collector of the transistor 1064 (FIG. 21) and to the drain of the FET 1062. Since the 5-volt power supply 5 V_{CORE} is unavailable during a suspend state, the transistor 1064 will be OFF, allowing power to appear at the gate of the FET 1062, thus turning the FET 1062 ON. Once the FET 1062 is turned ON, the main power signal POWER is applied to the XPLUS terminal of the digitizer panel. Thus, a pen (or finger) down event will result in the YPLUS terminal being connected to the XPLUS terminal by way of a finite resistance (i.e. 500–1500 Ohms) to apply power to the YPLUS terminal, which, in turn, is connected to the drain of the P-channel FET 1060 while its source is used as the pen shutdown signal PEN_SHUTDOWN. The FET 1060 is under the control of a leakage signal LEAKAGE, available at the output of the charge pump 994. Since the leakage signal LEAKAGE will be low during a suspend state, the FET 1060 will turn on in response to the pen down event, thereby connecting the YPLUS terminal to the pen shut down signal PEN_SHUTDOWN. As mentioned above, the YPLUS terminal will be high in response to a pen down event following a suspend state. As such, the pen shut down signal PEN_SHUTDOWN will go high. Since the pen shut down signal PEN_SHUTDOWN is diode ORed with the shut down signal SHUTDOWN, the shut down signal SHUTDOWN will thus be forced high in response to a pen down event following a suspend state, which, in turn, will wake up the power supply 851 (FIG. 26). Once the system is wakened, the keyboard controller shutdown line KB_SHUTDOWN goes high, latching the system ON. The resistors 1070, 1072 and the capacitor 1074 are used to delay turning ON the transistor 1064 and the turning OFF of the FET 1062 before the keyboard shutdown signal KB_SHUTDOWN is pulled high which would cause the pen shut down signal PEN_SHUTDOWN to go low before the keyboard shutdown signal KB_SHUTDOWN goes high.

The FETs 992, 998 and 1018 are used to prevent current leakage in a suspend state. In particular, these FETs 992, 998 and 1018 are under the control of the leakage control signal LEAKAGE, available at the charge pump 994, which turns the FETs 992, 998 and 1018 ON in normal operate and OFF in a suspend state.

The sensing of suspend state is done by the charge pump 994, which monitors the 5-volt power supply signal 5 V_{CORE}. When the 5-volt power supply signal 5 V_{CORE} goes low, indicating a suspend state, the leakage control signal LEAKAGE goes high, turning off the FETs 992, 998 and 1018, blocking leakage into the pen circuitry from the XPLUS terminal.

8. RC Time Constant

The system ON/OFF switch 855 (FIG. 28) enables the system to be completely shut off. When the switch 855 is closed, power from either the IBP 130 or the external AC-to-DC converter supplies power to the system. In order to wake up the system from an OFF state, a shutdown line SHUTDOWN must be held high until the keyboard controller 125 pulls its shutdown pin KB_SHUTDOWN high. As discussed above, the keyboard shutdown signal KB_SHUTDOWN is diode ORed relative to the shutdown signal SHUTDOWN, which controls the power supply 851 (FIG. 26). Until the time when the keyboard shutdown signal KB_SHUTDOWN is pulled high, a signal HOOK_VCC is used to force the shut down signal SHUTDOWN high. As mentioned above, the HOOK_VCC signal is also

diode ORed relative to the shutdown signal SHUTDOWN by way of the diode 1102 (FIG. 28). However, for proper operation of the system, the shutdown signal SHUTDOWN will be under the control of the keyboard controller 125 (FIG. 15) after the system is turned on. Thus, a 5-volt power supply signal HOOK_VCC, available at the power supply 851 (FIG. 26), forces the shut down signal SHUTDOWN high until the keyboard controller 125 (FIG. 15) has time to pull its keyboard shutdown signal KB_SHUTDOWN high. The 5-volt power supply signal HOOK_VCC is always high when the main power switch 855 is turned on. On power-up, the 5-volt power supply signal HOOK_VCC forces the shutdown signal SHUTDOWN (FIG. 28) high by way of an FET 1104 and the diode 1102, which, in turn, wakes up the power supply 851 (FIG. 26). Once the power supply 851 is enabled, a power supply signal MAX786_VCC is used to turn off the FET 1104 to place the control of the shut down signal SHUTDOWN under the control of the keyboard controller 125 as discussed above. In order to provide sufficient time for the keyboard controller 125 to pull its keyboard shutdown signal KB_SHUTDOWN high, the turn OFF of the FET 1104 is delayed by way of a resistor 1106 and a capacitor 1108. In particular, once the main power switch 855 is closed, the power supply signal MAX786_VCC will be low, thereby causing the FET 1104 to be turned ON, which connects the power supply signal HOOK_VCC to the shutdown signal SHUTDOWN by way of the diode 1102. Once the power supply 851 is enabled, the signal MAX786_VCC, applied to the gate of the FET 1104, turns off the FET 1104, placing the shutdown signal SHUTDOWN under the control of the keyboard controller shutdown signal KB_SHUTDOWN as discussed above. The resistor 1106 and capacitor 1108 delay the turning off of the FET 1104 after the signal MAX786_VCC goes high for a sufficient time to allow the keyboard controller 125 to pull its keyboard shut down signal KB_SHUTDOWN high.

An inhibit circuit (FIG. 26), which includes a plurality of resistors 1110–1120, a diode 1122, a transistor 1124 and an FET 1126, is used to prevent the system from being turned ON during low battery conditions when the system is being supplied solely by the IBP 130. During a normal condition (i.e. when the system is being supplied power by the AC/DC converter or by the battery, the signal MAX786_VCC is connected to the main power signal POWER by way of the FET 1126. The FET 1126 is under the control of the transistor 1124. During conditions when the AC/DC converter is supplying power to the system, a signal AC/DCIN will be high, thereby turning ON the transistor 1124, which, in turn, turns ON the FET 1126, connecting the main power signal POWER to the signal MAX786_VCC. The collector of the transistor 1124, in turn, controls the FET 904, which connects the power supply signal HOOK_VCC to the enable terminals ON3 and ON5 on the power supply 851. When AC power is not available, the AC/DCIN goes low, leaving the control of the transistor 1124 under the control of an inhibit signal INHIBIT, available from the IBP 130 by way of the connector 850. During a normal battery condition, the inhibit signal is high, keeping the transistor 1124 turned ON, thereby enabling the power supply 851 by way of the FET 904. Should a low battery condition occur, the inhibit signal goes low, turning OFF the transistors 904, 1124, as well as the FET 1126, to prevent the system from being turned ON.

9. Mouse Emulation with Passive Pen

As mentioned above, the wireless interface device 100 includes a digitizer 110B and utilizes a passive pen as an

input device. FIGS. 31–35 illustrate a method for emulating the functions of a mouse, for example a two-button mouse, to provide standard mouse functions with the passive pen.

There are three aspects of the mouse emulation. One aspect relates to emulation of a double click of a mouse button, required by some application programs.

Another aspect relates to emulating both the left and right buttons of a two-button mouse. The third aspect relates to emulating both the movement of the mouse (MOVE MODE) and the clicking of a mouse button (TOUCH MODE) with a passive pen as an input device.

Referring first to FIG. 31, the mouse emulation system is event-driven by the passive pen. Initially the system checks to see if the passive Den has touched anywhere on the LCD 113C (FIG. 36), which includes a display area 1200 and a hot icon area 1202. If a pen-down event has been detected, the system checks in step 1204 if the wireless interface device 100 has been placed in a calibration mode. If so, a calibration handler is called in step 1206. The calibration handler does not form part of the present invention. If the wireless interface device 100 is not in the calibration mode, the system then checks to determine if the pen has been lifted from the LCD 113C in step 1208. If a pen-up event occurs subsequent to a pen-down event, control is passed to a hot icon identification (ID) processor (FIG. 32) in step 1210, which, as will be discussed below, processes the pen position to determine which of the hot icons in the hot icon area 1202 of the LCD screen 113C was selected. If the pen was not lifted from the LCD 113C, the system checks in step 1212 if the previous event in a previous cycle was a pen-up event. If the previous pen event in the previous cycle was a pen-down event, the current pen event is processed by a mouse mode handler (FIG. 33) in step 1214, which, as will be discussed in more detail below, determines if the pen is being used in a mouse MOVE or mouse TOUCH MODE. In step 1216, the coordinates of the current pen-down event are processed to determine if the current pen-down event occurred in the hot icon area 1202 of the LCD 113C. If the pen-down event occurred in the hot icon area 1202 (FIG. 36), a flag is turned on indicating the hot icon area 1202 was selected in step 1218. If the system determines the current pen-down event occurred in the display area 1200 (FIG. 36) of the LCD screen 113C, an audio click is generated in step 1220; different from the hot icon audio click.

Steps 1204–1220 are driven by each pen event in order to determine the location of the pen-down event (i.e. hot icon area 1202 or display area 1200). Once the system determines where the pen event occurred, the pen data is converted to mouse data in step 1222 and a cursor is displayed in the viewing area 1200, corresponding to the location of the pen touch in step 1224. After the cursor is displayed, the system determines in step 1226 whether the mouse data is to be used locally by the wireless interface device 100 for local applications or the application running on the host computer 101. As mentioned above, the wireless interface device 100, through its graphical user interface, provides a virtual or on-screen keyboard (OSK). Thus, if the OSK has been activated and the pen event occurs in the OSK area, the mouse data is used locally by the wireless interface device 100 in step 1228. If the wireless interface device 100 is running a host application, the mouse data is sent to the host computer 101 application over the wireless interface as discussed above in step 1230.

As mentioned above, the system is able to emulate both left and right mouse buttons. This emulation is accomplished by way of left/right mouse button hot icon 1232 (FIG. 37).

A left mouse button is configured to be the default setting. This hot icon 1232 is set up as a toggle. Thus, when the system is first turned on, the pen events from the mouse mode handler are translated to be left mouse button events. Anytime the left/right mouse button hot icon 1232 is selected, the system will toggle and translate subsequent pen events to be right mouse button events. A subsequent pen-down event on the hot icon 1232 causes subsequent pen events from the mouse mode handler to be translated as left mouse button events and so on.

The hot icons in the hot icon area 1202 (FIG. 36) are triggered by a pen-down event followed by a pen-up event. As discussed above, such a sequence of pen events is processed by hot icon ID processor 1210, illustrated in FIG. 32. The hot icon ID processor 1210 first determines if the pen event occurred in the viewing area 1200 (FIG. 36) of the LCD 113C by determining from the mouse mode handler 1214 (FIG. 33) whether the system is in the TOUCH in step 1234, since this mode only occurs for pen events in the viewing area 1200 of the LCD display 113C. If the system is not in a TOUCH mode, the system checks in step 1236 whether the system is in the MOVE mode. If the pen event (i.e. pen-down followed by a pen-up event) did not occur in the viewing area 1200 of the LCD display 113C, the system compares the coordinates of the pen-down event with the locations of the various hot icons displayed in FIG. 37 in step 1238. In step 1240 (FIG. 32), the system determines if the left/right mouse button hot icon 1232 was selected. If not, the system proceeds directly to step 1242 to uplevel software for processing. If the system determines that the left/right mouse hot icon 1232 was selected, the system emulates a left or right mouse button in step 1244, depending on the last status of the left/right mouse button emulation and utilizes the emulated left or right mouse button status in the uplevel software in step 1242.

Pen events in the hot icon area 1202 of the LCD display 113C are handled by the hot icon ID processor 1210 (FIG. 32), while pen events in the viewing area 1200 are handled by the mouse mode handler 1214 (FIG. 33). The mouse mode handler 1214 emulates two mouse actions: moving without either button being depressed and released (MOVE); and button depression and release events (TOUCH). As discussed above, both left and right mouse button events can be emulated in the TOUCH.

As discussed above, a current pen-down event preceded by a pen-down event activates the mouse mode handler 1214 (FIG. 33). In step 1246, the system first determines if the hot icon flag is on. As discussed above, the hot icon flag is turned on anytime a pen-down event occurs in the hot icon area 1202 (FIG. 36) of the LCD display 113C. If the hot icon flag is not on, the pen-down event is translated to a mouse button down event by a mouse TOUCH handler in step 1248. If the hot icon flag is on, the system determines in step 1250 whether the coordinates of the current pen-down event to determine if the current pen-down event occurred in the hot icon area 1202. If so, the pen coordinate data is dropped in step 1252 since such data will be processed by the hot icon ID processor 1210 (FIG. 32) discussed above. If the current pen event occurred in the viewing area 1200, the pen coordinate data is translated to mouse move data.

A mouse button double click is emulated by two pen-down events separated by a pen-up event in the viewing area 1200 of the LCD 113C. In particular, when the host computer 101 is running a Windows application, a pen driver translates the two pen-down events separated by a pen-up event and passes four mouse messages: mouse button down; mouse button release, mouse button down and mouse button release to the host Windows application.

As will be discussed in more detail below, the host manager Windows module **1260** modifies a Windows configuration file. (WIN.INI) and, in particular, the distance and time limitations for a mouse button double click. In particular, the Windows system checks the Windows configuration file WIN.INI in order to compare the distance between the mouse locations for each of the clicks as well as the time between clicks. More particularly, the Windows systems will only pass double click data to a Windows application program if the distance (i.e. height and width) between mouse locations for the two clicks is less than 16 for both height and width and the time between the clicks is less than 1.0 seconds.

With a pen-based system two pen-down events separated by a pen-up event normally take longer and occur at greater distances between pen-down events than allowed by the Windows system to generate a double click. Thus, the host manager Windows module **1260** modifies the time and distance parameters to enable two pen-down events separated by a pen-up event to enable Windows to emulate a mouse double click that can be passed on to the Windows application program running in the host computer **101**. In particular, the host manager Windows module **1260** includes an initializer **1262** which loads the host manager Windows module **1260**, and an initial icon displayer **1264**, which displays that the host manager Windows module **1264** has been loaded. The host manager Windows module **1260** also includes a double click configuration modifier **1266**. The double click configuration modifier **1266** modifies the configuration of the Windows systems file WIN.INI by modifying the time or speed in step **1268**. The distance, broken down into width and length, between the successive pen-down events, is modified by a double click width modifier and a double click height modifier in steps **1270** and **1272**. The modified speed, width and height parameters are set in the Windows system file WIN.INI running in the host computer **101** in step **1274** to enable a mouse button double click to be emulated by two successive pen-down events.

Normally, the Window system file WIN.INI is in cache. The host manager Windows manager disables the in cache copy of the Windows system file WIN.INI, which allows the Windows system to go to the modified configuration file with the modified parameters.

10. Disable Screen Saver to Reduce LAN Traffic

As mentioned above, the wireless interface device **100** connects to a host computer **101** and displays whatever is being displayed on the host computer **101**. In particular, after a connection is made, all of the screen images on the host computer **101** are passed on to the LCD display **113C** on the wireless interface device **100**. Whenever the host computer **101** is running a screen saver, the host display will continually change, passing on all of the images to the LCD **113C** on the wireless interface **100**, which creates a lot of unnecessary LAN traffic, a host manager Windows module **1278** (FIG. 39) disables the screen saver on the host computer **101** anytime a connection is made between the host computer **101** and the wireless interface device **100**. Anytime the connection between the host computer **101** and the wireless interface device **100** is broken, the host manager Windows module re-enables the screen saver on the host computer **101**.

The connection status between the host computer **101** and the wireless interface device **100** is under the control of a host manager DOS module **1280** (FIG. 38), a terminate and

stay resident program. The host manager DOS module **1280** is driven by a timer tick interrupt and checks the connection status at each timer tick interrupt. If the connection status has changed, the host manager DOS module **1280** calls a host manager communicator **1282**, which passes the new status to the host manager Windows module **1278**.

Referring to FIG. 39, anytime the connection status between the host computer **101** and the wireless interface device **100** changes, the host manager Windows module **1278** checks the new status in step **1284**. If the connection has been lost, a screen saver disable module **1286** is called, which, in turn, calls several Windows modules: Windows Software Development kit functions; SystemParameters-Info; and WritePrivateProfileString to disable the screen saver. Should the current status indicate that the wireless interface device **100** is connected to the host computer **101**, the system proceeds to step **1288**, which calls the various Windows module.

Referring to FIG. 40, anytime the host manager DOS module **1280** is loaded, an initial connection status checker **1290** calls the host manager DOS module **1280** to obtain the current connection status between the wireless interface device **100** and the host computer **101**. Next, the system checks in step **1292** whether a connection exists between the host computer **101** and the wireless interface device **100**. If not, the system returns. If there is a connection, a virtual key poster **1294** posts a virtual key V_TAB into the Windows Systems queue to force the Windows program to disable the current active screen saver automatically, which, in essence, simulates the press of a key on a keyboard. Once the current active screen saver is disabled, the screen saver on/off flag in a Windows configuration file is turned off in step **1296** to disable the screen saver until there is a change in the connection status.

11. Host Access Protection Password

Whenever a connection is made between wireless interface device **100** and the host computer **101**, the user can optionally blank the screen on the host computer **101** and disable the keyboard and mouse inputs connected to the host computer **101**. These features prevent the host computer **101** from being accessed while the host computer **101** is under the control of the wireless interface device **100** at a remote location. Once the connection between the host computer **101** and the wireless interface device **100** is lost, the keyboard and mouse inputs on the host computer **101** are re-enabled under the control of the host manager program residing in the host computer **101**.

There are certain situations where the screen to the host computer **101** may not be enabled on disconnection, for example, when the disconnection occurs because the wireless interface device **100** is either out of power or out of range. In order to enable the user to access the host computer **101** in such a situation, a host manager **1300** (FIG. 40A) first checks whether the connection status has changed in step **1302** in the manner as discussed above. If the system is connected, no action is required. However, if the connection has been broken, the system checks in step **1304** whether the screen is enabled. If not, the user will have normal access to the host computer **101**. If so, the latest log-in password by the user is stored in by the system in step **1306** Since the host manager DOS module controls the screen, the system checks in step **1308** to determine whether Windows is running in the host computer **101**. If DOS is running, the system compares the password entered on the keyboard with the latest log-in password in steps **1310** and **1312**. If the

password entered does not match the correct password, the system returns to step 1310 and awaits another keyboard input. If the correct password entered, the screen is turned on in step 1314.

Should the host computer 101 be running Windows, as determined in step 1308, the latest log-in password is passed to a host manager Windows module in step 1316. The system next checks in steps 1318 and 1320 whether the correct password was entered in a similar manner as discussed above. If so, since DOS handles the enabling of the screen on the host computer 101, the host manager DOS module is notified that the correct password was entered in step 1322, which, in turn, enables the screen in step 1314.

12. Double Pen-Up Events

The pen controller 110A (FIG. 21) normally generates a series of interrupts and, in turn, a series of pen packets whenever the pen touches the LCD 113C (a pen-down event) and is lifted from the LCD 113C (a pen-up event) and generates an interrupt. For each interrupt, a single packet is generated. The format of the possible packets is illustrated in Table 7 below, where x0 is bit 0 of the x coordinate of the pen location and y0 is bit 0 of the y coordinate of the pen location, etc.

TABLE 7

PACKET NAME	BIT 7	BIT 6	BIT 5	BIT 4	BIT 3	BIT 2	BIT 1	BIT 0
P1	1	1	0	x11	x10	x9	x8	x7
P2	0	x6	x5	x4	x3	x2	x1	x0
P3	0	0	0	y11	y10	y9	y8	y7
P4	0	y6	y5	y4	y3	y2	y1	y0
P5	1	0	0	0	0	0	0	0

The packets are generated in the following sequence (p1, p2, p3, p4), (p1, p2, p3, p4) . . . (p1, p2, p3, p4), (p5). The packets p1, p2, p3, p4 relate to pen-down events (a pen point); each group of packets (p1, p3, p3, p4) relating to one x-y coordinate of the pen. The packet p5 relates to a pen-up event. Thus, anytime the pen is lifted from the digitizer, one packet p5 is generated. Thus, when the pen first touches the digitizer panel and is moved across the digitizer, a plurality of pen points (p1, p2, p3, p4) are generated which correspond to the x, y locations of the points touched by the pen. Normally 110 pen points per second are generated by the pen controller 110A.

Whenever a 12-bit serial pen packet is generated by the pen controller 110A and read by a firmware module in step 1330 (FIG. 41), an interrupt is generated in step 1332. A pen packet assembler assembles the packets into pen points (p1, p2, p3, p4). These pen points (p1, p2, p3, p4) are processed and passed to the applications program. In order to process each pen point (p1, p2, p3, p4), the interrupts must be disabled. During the time when the interrupts are disabled, the pen point packets (p1, p2, p3, p4) and the pen-up packets p5 are generated by the pen controller 111A but not processed and thus are garbled or lost. Lost or garbled pen point packets (p1, p2, p3, p4) do not affect mouse emulation. However, since mouse emulation is based on both pen-down and pen-up events, lost pen-up packets p5 can result in the mouse emulation being hampered, possibly resulting in the system being stuck in the state preceding the pen-up event.

In order to solve this problem, a firmware module 1330 generates two pen-up packets p5. More particularly, with reference to FIG. 42, the firmware module 1330 reads in the 12-bit serial data from the pen controller 110A into packets

in step 1334. Next, the system checks in step 1336 whether the packet was a pen-up packet p5. If not, the system proceeds to the pen driver in step 1332 (FIG. 41). If the packet is a pen-up packet p5, the system checks to determine if the pen-up packet p5 is the first pen-up packet in step 1338. If not, the system passes the packet to the pen driver in step 1332 as discussed above. If the system determines in step 1338 that the pen-up packet p5 is the first pen-up packet p5, the serial data for second pen-up packet p5 is generated in step 1340 and assembled in step 1334. In addition, the first pen-up packet p5 is passed to the pen driver.

The pen driver 1332 (FIG. 43) is responsive to an interrupt that is generated each time a packet is assembled. In response to an interrupt, the pen driver reads the packet in step 1342. In step 1344, the pen driver determines whether the packet is a pen-up packet p5. If not, the pen packet assembler processes the packet in step 1346. If the system determines in step 1344 that the packet is a pen-up packet, it next checks in step 1346 whether the packet is the second pen-up packet. If so, indicating that the first pen-up packet was processed, the second pen-up packet is dropped in step 1348. If not, the packet is determined to be a first pen packet, which is processed by the pen packet assembler in step 1346.

13. Seamless Integration of Wired and Wireless LANS

The wireless interface device 100 may be connected to host computer 101 by way of a wireless LAN. The wireless LAN protocol is Novell open data link interface IPXODI protocol. Since the IPXODI protocol is also used for wired LAN's, it would be desirable to connect the wireless interface device 100 to a wired LAN system and utilize the Novell IPXODI protocol. Unfortunately, the IPXODI protocol can only communicate with a single LAN card at a time, either a wired LAN card or a wireless LAN card at one time.

The standard Novell LAN stack configuration is illustrated in FIG. 45. The LAN card is identified with the reference numeral 1352. Communication between the LAN card 1352 and the IPXODI protocol is by way of a driver 1354. The driver 1354 communicates with the IPXODI protocol (IPXODI.COM) 1355 by way of a link support layer LSL.COM 1356. The Novell IPXODI protocol passes data between the applications programs 1358 and the link support layer LSL.COM 1356. Even though the link support layer LSL.COM can support multiple LAN cards, the IPXODI protocol only supports a single LAN card.

In order to enable the Novell IPXODI protocol to support a configuration as illustrated in FIG. 44 to enable the wireless interface device 100 to connect to both a wired LAN card 1352 and a wireless LAN card 1360, an additional layer IPXMUX.COM (FIG. 46) is provided for multiplexing incoming and outgoing packets to and from the wired LAN card 1352 and the wireless LAN card 1360. The multiplexer IPXMUX.COM manipulates the data packet source and destination addresses to simulate a single LAN card so as to be compatible with the IPXODI protocol. By providing the additional layer IPXMUX.COM, the host computer 101, as well as the wireless interface device 100, will be able to access all of the LAN resources 1350 (FIG. 44).

Referring to FIG. 46, the additional layer IPXMUX.COM is stacked between the Novell IPXODI protocol IPXODI.COM 1355 and the link support layer LSL.COM 1356. As mentioned above, the link support layer LSL.COM 1356 can support two LAN cards. Thus, a wireless LAN card 1360 and a corresponding wireless LAN card driver 1362, which

communicates with the link support layer LSL.COM 1356 along with the wired LAN card 1352 and its corresponding driver 1354, can communicate with IPXODI.COM by way of the driver.

The multiplexer IPXMUX.COM 1364 multiplexes or interleaves the data from both the wireless LAN card driver 1354 and the wired LAN card driver 1362 to the IPXODI protocol by manipulating the source and destination addresses of incoming and outgoing packets, so that as far as the Novell IPXODI protocol is concerned, it is only communicating with a single LAN card. Similarly, communication from the host computer 101, as well as applications 1358, which may be running on the wireless interface device 100, to both the wired LAN card 1352 and the wireless LAN card is formatted by the IPXODI.COM and multiplexed to either the wireless LAN card 1360 or wired LAN card 1352 by the multiplexer IPXMUX.COM by way of the link support layer. The multiplexer IPXMUX.COM 1364 is loaded after the wired LAN card driver 1354 and the wireless LAN card driver 1362 are loaded and before IPXODI.COM 1355.

The Novell LAN software includes a configuration file which checks the particular LAN cards 1352 being run by the LAN card driver 1354. The system is initialized by the routine illustrated in FIG. 47, which is run each time the multiplexer IPXMUX.COM 1364 is loaded. Initially, a command line parser 1366 is used to determine whether the user has issued commands to either load or unload IPXMUX.COM command in step 1368. If the command is an unload command, the system checks whether IPXMUX.COM 1364 has already been loaded in step 1370. If so, the system unloads IPXMUX.COM 1364 in step 1372. If IPXMUX.COM 1364 has not been loaded, the system exits the initialization routine.

If the command was to load IPXMUX, the system checks in step 1374 to determine if the link support layer LSL.COM 1356 has been loaded. If not, the system exits the initialization routine since IPXMUX.COM cannot be loaded until the link support layer LSL.COM has been loaded. If the link support layer LSL.COM 1356 was loaded, control is passed to a LAN configuration browser in step 1376 to browse the LAN configuration for the number of LAN cards and the frame types of the cards and the number of frame types (i.e. IEEE 802.2, 802.3, etc.) to find out which LAN card drivers are running. In addition, the browser finds and saves all relevant application program interface entry points to the link support layer LSL.COM and sets to those supported by IPXMUX.COM. The browser also sets the LSL interrupt vector to the interrupt vector supported by IPXMUX.COM, as well as finds and saves all logical board numbers.

In order to interleave the data from the wired LAN card 1352 (FIG. 46) and the wireless LAN card 1360 to IPXODI.COM to emulate a single LAN card, 2F interrupt calls from the application program by way of IPXODI.COM are trapped and handled by a separate routine. In particular, 2F interrupt calls are checked in step 1378 to determine if such calls are interrupt calls to LSL.COM. If not, the system exits. If so, the address of the LSL protocol support API handler supported by IPXMUX.COM is returned. Interrupt calls to LSL.COM from an application program are handled by a special interrupt handler. If the interrupt call is to LSL.COM, a LSL initialization entry point, supported by IPXMUX.COM is returned in step 1380. The LSL initialization entry point represents an address of the protocol initialization routine into LSL.COM.

Once the address of the LSL initialization entry point is known by the IPXODI protocol, the IPXODI protocol will

call that address for service. Thus, all LSL service calls are checked in step 1382 (FIG. 49) to determine if the call is a request for protocol support API entry point. If not, the multiplexer IPXMUX.COM will direct that call into LSL.COM. If so, an address of a special 2F interrupt handler (LSL Protocol Support API Handler) supported by IPXMUX.COM is returned to IPXODI.COM in step 1384.

The special interrupt handler, LSL Protocol Support API Handler, which forms a part of IPXMUX.COM, is illustrated in FIG. 50. Three services are handled by the LSL Protocol Support Handler, which is supported by the multiplexer IPXMUX.COM to set up an address for communication with a host on the network. These services are register protocol stack, bind stack and send a packet. The balance of the services are handled by LSL.COM.

The entry point of the LSL Protocol Support API Handler in IPXMUX.COM from the standpoint of IPXODI.COM is the protocol support API within the link support layer LSL. Since the link support layer LSL.COM supports various protocols, such as IPXODI and TCPIP, registration of the IPXODI.COM protocol is checked in step 1386. If the call to the link support layer LSL is to register a protocol stack, an IPXMUX register protocol stack application program interface (API) handler in step 1388 checks whether the protocol stack is IPXODI. If the protocol stack is IPXODI, the protocol stack handler sets a packet receive handler, supported by IPXMUX.COM and calls LSL.COM's protocol stack API to register the protocol. The protocol stack handler also saves the stack ID. Subsequently, in step 1390, an IPXMUX Receive Routine Linker sets the protocol stack IPXODI's receive routine address to the packet receive address supported by IPXMUX.COM.

If the protocol API call is not to register the protocol stack, the system then checks in step 1392 whether a special registration service, a bind stack service, is requested. A bind stack service, normally done before registration, is used to set up a protocol for communication, i.e. packet length, etc. If bind stack service is requested, an IPXMUX Bind Stack API handler in step 1394 is called, which forces IPXODI to bind to the wired LAN card 1352 to which IPXODI is bound before the wireless LAN card 1360 was installed in order to be compatible with the IPXODI protocol. The IPXMUX bind stack handler also saves the process ID of the binding for sending and receiving packets.

If the protocol API call is not a register protocol stack or a bind stack service, the system checks in step 1396 whether send packet service is requested. If not, the system exits and the service call is handled by LSL.COM. If so, an IPXMUX send packet routine is called in step 1398 and 1400 (FIG. 51), which sets the address of the wireless LAN card 1360 as the source node address in step 1402. The packet modifier also sets the node address of the wireless interface device 100 as the packet's destination mode address in step 1400 (FIG. 51). The send event service routine address is set to the address of the send event service routine in IPXMUX.COM before it returns.

Incoming packets are handled by an incoming packet handler illustrated in FIG. 32. In particular, incoming packets are checked in step 1404 whether the source address of the packet is from the wireless LAN card 1360. If not, the system returns. If so, the packet's source mode address is saved and set to the mode address of the wireless LAN card 1360 while the packet destination address is set to the address of the wired LAN card 1352 to which IPXODI is bound.

14. Host Control Mode

The wireless interface device 100 includes a hot icon 1408 (FIG. 37) in the hot icon area 1202 (FIG. 36) of the

LCD 113C for switching control of the host computer 101 from the wireless interface device 100 and the host computer 101. While the wireless interface device 100 has control of the host computer 101, the user has the option to dim the screen of the host computer 101, as well as lock out the keyboard and mouse inputs. In particular, with reference to FIG. 37, a set-up window hot icon 1410 may be selected. Activation of the set-up window icon causes one of five selectable set-up dialog boxes to be displayed in the viewing area 1200 (FIG. 36) of the LCD 113C on the wireless interface device 100. These dialog boxes are illustrated in FIGS. 53–57, which can be selected by a graphical button bar 1412 (FIG. 53). When the “host” button is selected, a list of host computer groups that are accessible by the wireless interface device 100 as well as the specific host to which the wireless interface device 100 is connected are displayed. When the wireless interface device 100 has control of the host computer 101, the host computer screen can be dimmed and the host keyboard and mouse can be locked out by placing the pen down in the box next to those functions in the dialog box illustrated in FIG. 53. FIG. 54 relates to setting up remote keyboard macros. FIG. 55 is a maintenance dialog box which enables various maintenance functions, such as calibration of the pen, rebooting of the host, and the like. FIG. 56 relates to power settings, and in particular includes an inactivity timer for timing periods of inactivity in order to place the wireless interface device 100 in a low-power state. FIG. 57 is selectable by the screen button and enables the brightness and contrast of the LCD 113C on the wireless interface device 100 to be adjusted.

FIG. 58 illustrates a method for disconnecting the host computer 101 from the wireless interface device 100 and automatically returning control of host screen, keyboard and mouse to the host computer 101. In addition, any configuration settings of the wireless interface device, such as contrast and brightness adjustment, are also saved in order to obviate the need to readjust the wireless interface device 100, the next time it is connected.

Initially in step 1414 (FIG. 58) the system determines if the hot icon area 1202 of the LCD 113C on the wireless interface device 100 was pressed. As illustrated in FIG. 37, the hot icon area 1202 includes several hot icons. Thus, the system checks in step 1416 whether the host control mode hot icon 1408 (FIG. 37) was selected. If not, the system loops back to step 1414 and waits for the hot icon area to be pressed. If the host control mode hot icon 1408 was selected, the wireless interface device 100 sends a private message (i.e. packet) to the host computer 101 in step 1418, requesting host control mode.

The system then checks in step 1420 whether the host computer 101 returned an acknowledgement that the private message was received. If an acknowledgement of the private message is not received by the wireless interface device 100, the attempt to enter the host control mode is aborted in step 1422. If an acknowledgement is received, the system checks in step 1424 if the mouse keyboard and mouse had been previously locked out by the wireless interface device 100 as discussed above. If so, the host keyboard and mouse are unlocked. Subsequently in step 1426, an internal flag is set indicating a request for termination of the connection with the host computer 101 in step 1428. The request for termination initiates a timer, which, when timed out, disconnects the wireless interface device 100 from the host computer 101. Thus, the system checks to determine if the host computer 101 is still connected to the wireless interface device 100 in step 1430. If so, the system determines if the request for termination has timed out in step 1432. If not, the

system waits for the timer to time out and disconnects the wireless interface device 100 from the host computer 100. Once the wireless interface device 100 is disconnected, control of the host computer 101 is returned to the host computer 101.

In order to obviate the need to reconfigure the wireless interface device 100 the next time the wireless interface device 100 is connected to the host computer 101, the system checks in step 1434 whether any of the configuration data (i.e. contrast, brightness (FIG. 57) was changed. If not, the wireless interface device 100 is placed in a suspend mode in step 1436. If the configuration data did change, the new configuration data is saved in the EEPROM 111B (FIG. 12) in step 1438.

15. Broadcast for Available Hosts

The wireless interface device 100 can determine the available hosts within range for wireless connection. The user can then select a host by way of a dialog box (FIG. 53), which will be discussed in more detail below. An important aspect of the wireless interface device 100 is that it can be connected to virtually any available hosts without any physical connections and without knowing the host address or node address beforehand, unlike known wireless and wired LAN systems where the node addresses of each of the personal computers in the network have a preassigned node address and are therefore known prior to any communications being established.

In order to initiate connection of the wireless interface device 100 to an available host 101, the set-up hot icon 1410 (FIG. 37) is selected in step 1439 (FIG. 59) which causes a set-up dialog box, as illustrated in FIG. 53 to be displayed in the viewing area 1202 (FIG. 36) of the LCD 113C. Subsequently, in step 1440, the wireless interface device 100 broadcasts network packets to be received by all available hosts 101 in range that are on the same channel and domain as the wireless interface device 100. After the network packets are broadcast, the wireless interface device 100 listens for a predetermined time period in steps 1442 and 1444 for return acknowledgement packets from the available hosts 101, which contain, among other things, the node addresses of the available hosts 101. After the time-out period the wireless interface device 100 terminates listening for responses from the available hosts 101 in step 1446. After listening is terminated, the system checks the number of responses received in step 1448. If no responses are received, the wireless interface device 100 repeats the cycle (i.e. returns to step 1440) for a predetermined number of retries as determined in step 1450.

If a response is received, the system identifies the unique node address from the responding hosts 101 in step 1452 and saves the unique host node addresses in step 1454. The list of available hosts 101 is searched in step 1456 for duplicate serial numbers. Should duplicate serial numbers be found in step 1458, a warning is generated in step 1460, warning the user that a duplicate copy of software is running on one of the responding hosts 101. In step 1462, the currently connected host is forced to appear as unavailable on the dialog box illustrated in FIG. 53.

The responding hosts 101 are sorted first by group name and then by host name in step 1464. After the sorting, an internal status list of the available hosts 101 is designated as available in step 1466. Subsequently, the available hosts and groups are displayed in the dialog box illustrated in FIG. 53 in step 1468. Movement of the cursor (by a pen-down event) to the desired host 101 selects that host 101. A “connect”

button on the dialog box is then selected to connect the wireless interface device **100** to the selected host **101**.

16. Remote Keyboard Macros

FIGS. **60** and **61** relate to remote keyboard macros on the wireless interface device **100**. An important aspect of the wireless interface device **100** is that the remote keyboard macros are provided by way of a wireless connection. FIG. **60** relates to developing the macros while FIG. **61** is directed to using the macro.

Referring to FIG. **37**, the wireless interface device **100** includes two user-defined hot icons **1472** and **1474**, located in the hot icon area **1202** (FIG. **36**) of the LCD **113C**, that can be used for the macros. These hot icons **1472** and **1474** are configurable in a set-up mode, which, as discussed above, is under the control of the set-up hot icon **1410** (FIG. **37**). Once the set-up hot icon **1410** is selected, a hot key button **1470** on the dialog box illustrated in FIG. **54** is selected. As noted in FIG. **54**, the dialog box includes two configurable macros. These macros are configured by way of the two edit fields **1472** and **1474** (FIG. **54**). In order to configure the macros, the icon for the desired edit field **1472** or **1474** is selected. These edit fields **1472** and **1474** are configurable by way of a virtual on-screen keyboard (OSK), selectable by way of a hot icon **1480** (FIG. **37**).

Referring to FIG. **60**, the system checks in step **1476** whether there has been a pen-down event in the viewing area **1202** (FIG. **36**) of the LCD **113C** and, in step **1478**, whether the OSK hot icon **1480** (FIG. **37**) was selected. If not, the system loops back to step **1476**. If so, the selected key on the OSK is translated into a keyboard scan code in step **1480** and a visual indication of the key selected in the edit field **1472** or **1474** in step **1482**. The process is repeated until the macro (i.e. WIN, DIR), followed by a carriage return **1486**, is complete and the macro is saved in the EEPROM **111B** (FIG. **12**) in step **1484**. A clear button **1486** is provided in the dialog box illustrated in FIG. **54** for each edit field **1472** and **1474**. These clear buttons **1486** enable the edit fields to be cleared in the EEPROM **111B** (FIG. **12**).

Activation of the remote keyboard macros is accomplished by pressing down on the user-defined hot icons **1472** or **1474**, located in the hot icon area **1202** (FIG. **36**) of the LCD **113C**. The system checks in steps **1486** and **1488**, whether the user defined hot icons **1472** or **1474** are selected. If the user-defined hot icons **1472** or **1474** are not selected, the system returns to step **1486**. Once one of the user-defined hot icons **1472** or **1474** is selected, the keyboard scan code sequence, stored in the EEPROM **111B** (FIG. **12**), is retrieved for the selected hot icon **1472** or **1474** in step **1490**, which are then individually transmitted to the host **101** in step **1492**. These scan codes are then written to the keyboard buffer on the host **101** in step **1494**. Subsequently, in step **1496**, the host **101** processes the scan codes as though they originated from the host keyboard.

17. Wireless Flash Programmer

As mentioned above, the wireless interface device **100** includes several flash memory devices **742–748** (FIG. **25**). The flash memory device **742** includes a protected area which contains the system BIOS, and a sufficient amount of functionality to enable the wireless interface device **100** to be rebooted to enable reprogramming of the flash memory devices **742–748** by way of the serial port **788** (FIG. **23**) in the event of a flash disaster.

In order to upgrade the flash memory devices **742–748**, the upgrade disks are installed in an available host computer

101. In particular, the flash upgrade software is written to a predetermined directory on the host's **101** hard disk. After the flash upgrade disks are installed, the wireless interface device **100** is turned on in step **1498** (FIG. **62A**) by way of the main power switch **855** (FIG. **28**). Subsequently, in step **1500**, a connection between the host computer **101** and wireless interface device **100** is initiated in step **1500** by first selecting the configuration hot icon **1410** (FIG. **37**).

Subsequently, the maintenance button on the dialog box is selected to get to the dialog box illustrated in FIG. **55**. An upgrade button **1502** on the dialog box illustrated in FIG. **55** is selected in step **1504**. In order to prevent programming errors, the radio quality is checked in step **1506** before proceeding. If the radio quality is poor, the upgrade is aborted. If the radio quality is adequate, power management is disabled in step **1508** to prevent the wireless interface device **100** from going into a reduced power state as discussed above during programming of the flash memory devices **742–748**. After the power management is disabled, a portion of the DRAM memory **111A** (FIGS. **18** and **24**) in the wireless interface device **100** is set aside to receive a flash sector from the host computer **101** in step **1510**. Subsequently, the wireless interface device **100** polls the host computer **101** to determine the correct numbers of sectors in the flash update and whether the sectors are available on the hard disk of the host computer **101** in steps **1512** and **1514**. If the flash update files are not on the host hard drive or an incorrect number of sectors are available on the host hard disk, the update is aborted. Otherwise, the system requests the path/file data from the host computer **101** in step **1516**. Subsequently, each sector (file) in the flash update is read by the host computer **101** and uploaded over the radio to the DRAM **111A** in the wireless interface device **100** in step **1518**. After the sectors are written to the DRAM **111A** in the wireless interface device **100**, a BIOS call is made to write the sectors in the DRAM **111A** to the flash memory devices **742–748** in step **1520**.

In step **1522** the system checks for errors in writing to the flash memory devices **742–748**. Should any errors be detected, the update is aborted. If no errors are detected, the system checks in step **1524** whether all of the sectors from the DRAM **111A** have been written to the flash memory devices **742–748** in the wireless interface device **100**. If not, the system loops back to step **1516**. Once all of the files have been transferred to the flash memory devices **742–748**, the wireless interface device **100** is rebooted in step **1526**. Once the wireless interface device is rebooted, the system will be able to utilize the updated software in the flash memory devices **742–748**.

FIGS. **63A** and **63B** illustrate the routine for writing the flash update sectors from the DRAM **111A** to the flash memory devices **742–748**. Since the flash updates are stored in the DRAM memory **111A**, the programming is aborted if the AC power is turned off as determined in step **1528** since the flash update data in the DRAM **111A** will be lost when the battery is exhausted. In order to prevent errors during programming, interrupts, as well as the power management, are disabled on the wireless interface device **100** in steps **1530** and **1532**. After the interrupts and the power management are disabled, the flash memory device is erased in step **1534**. If errors occur during erasure, as determined in step **1536**, updating of the particular flash memory device **742–748** is aborted. If not, a sector from the DRAM **111A** is written to the flash memory devices **742–748** in step **1538**. After the sector is written to the flash memory devices **742–748**, the system checks in step **1540** whether any errors occurred. If so, the update is aborted. If not, the interrupts,

as well as the power management, are enabled in step 1542 when all sectors have been reflashed.

18. Automatic Reconnect

As mentioned above, the wireless interface device 100 can be connected to any of the available hosts 101 that appear in the dialog box illustrated in FIG. 53 in the manner described above. The system illustrated in FIGS. 64A and 64B obviates the need for the user to select a host 101 for connection each time the wireless interface device 100 is powered up, by automatically connecting the wireless interface device 100 to the last host 101 to which it was successfully connected. As will be discussed in more detail below, when a host 101 is selected from the dialog box illustrated in FIG. 53 for connection to the wireless interface device 100 and a connection is successfully achieved, the node address of that host 101 is stored in the EEPROM 111B (FIG. 12). Subsequently, once the wireless interface device 100 is powered up in step 1544, the system 10 reads the node address from the EEPROM 111B, and reads it to a specific location in DRAM 111A (FIGS. 18 and 24) in step 1546. After the node address is written to the DRAM 111A, the system checks the node address to determine whether it is valid in step 1548. Invalid node addresses occur anytime the wireless interface device 100 makes an attempt to connect to a host 101, which fails during automatic reconnecting or is later disconnected by the end user. Thus, if a successful connection is not made or if there is a manual disconnection, the node address is cleared from the DRAM 111A in step 1550 and thus will be invalid. Subsequently, if the automatic reconnect fails in order to facilitate connection of the wireless interface device 100 to another available host 101, the set-up dialog box illustrated in FIG. 53 is displayed on the display 113C of the wireless interface device 100 in step 1552. After the host selection set-up dialog box is displayed on the wireless interface device 100, the system checks in step 1554 whether the wireless interface device 100 is connected to an available host 101. Normally, if an invalid address is found in step 1548 and the host selection set-up dialog box appears on the display 113C of the wireless interface device 100, there will be no connection to an available host 101 and the system will jump to step 1556, where it checks if the hot icon area 1202 (FIG. 37) has been depressed. Normally in this situation, since the host selection dialog box is already being displayed on the screen 113C of the wireless interface device 100, the only hot icon that can affect the situation is a sleep-face hot icon 1558 (FIG. 37), which places the wireless interface device 100 in a low-power sleep mode. In a normal situation when the wireless interface device 100 is first powered up, the sleep-faced hot icon 1558 is not depressed and the system waits for the user to select an available host 101 from the host set-up dialog box illustrated in FIG. 53 as discussed above in step 1560. Once an available host 101 is selected, the system loops back to step 1562 and attempts to establish connection with the selected host 101.

In step 1564 the system checks whether or not the connection was successful. If not, the system goes to step 1550 and clears the node address for the selected host 101 from the DRAM 111A and displays the host selection set-up dialog box in step 1552. If the connection between the wireless interface device 100 and the host 101 is successful, the node address of the host 101 is saved in a specific DRAM location in step 1566, and in turn, written to the EEPROM 111B (FIG. 12) in step 1568. After the node address of the selected host 101 is stored in EEPROM 111B, the wireless interface device 100 will display whatever is being displayed on the host 101 in step 1570.

After a connection is established between the host 101 and the wireless interface device 100, the system continuously checks for hot icons being selected in step 1572. If no hot icons are selected, the system will loop back and continue to check for the selection of a hot icon. If the system determines that a hot icon is selected, the system checks in step 1574 whether the set-up dialog hot icon 1410 (FIG. 37) was selected. If so, the system loops back to step 1552 and displays the host selection set-up dialog box illustrated in FIG. 53 on the display 113C of the wireless interface device 100. If the set-up dialog hot icon 1410 is not selected, the system checks in step 1576 whether the sleep-face hot icon 1558 is selected in step 1576. If not, the system checks in step 1578 whether other hot icons in the hot icon area 1202 (FIG. 36) were selected and the appropriate action is taken. The system then goes to step 1570 and, in turn, and continually checks for the selection of other hot icons in step 1572.

If it is determined in step 1576 that the sleep-face hot icon 1410 is selected, the system checks in step 1580 whether a double pen-down event occurred at the location of the sleep-face hot icon 1410. As mentioned above, the sleep-face hot icon 1410 causes the wireless interface device 100 to go into a low-power mode. However, before placing the wireless interface device 100 in a low-power mode, the node address of the host 101 to which the wireless interface device 100 is connected is saved in a specific location of the DRAM 111A and, in turn, written to the EEPROM 111B in step 1582. After the node address is saved, the wireless interface device 100 is powered down in step 1584.

The system discussed above is thus able to automatically connect the wireless interface device 100 to the last host 101 to which it was connected. After the automatic reconnect, should the set-up window hot icon 1410 (FIG. 37) be selected, the host selection set-up dialog box illustrated in FIG. 53 will be displayed on the screen 113C of the wireless interface device 100. Subsequently, the system will go to step 1554 and check whether the wireless interface device 100 is connected to a host 101. In this case, since the wireless interface device 100 will still be connected to the available host, the system then checks in step 1586 whether a disconnect button on the host selection dialog box illustrated in FIG. 53 has been depressed. If not, the system goes to step 1556 and continuously waits for a hot icon in the hot icon area 1202 (FIG. 36) of the LCD 113C to be depressed. If the disconnect button in the host selection set-up dialog box illustrated in FIG. 53 is depressed, the node address for the host 101 to which the wireless interface device 100 is connected is erased from the specific location in the DRAM 111B in step 1588. Subsequently, the system goes to step 1556 and waits for a hot icon in the hot icon area 1202 (FIG. 37) to be depressed.

19. Remote Occlusion Region

As mentioned above, the wireless interface device 100 includes a virtual on-screen keyboard (OSK), as illustrated in FIG. 66. More particularly, the OSK is configurable by the buttons 1590, 1592, 1594 and 1596 in a control box located at the top of the OSK. These buttons 1590, 1592, 1594 and 1596 enable the OSK to be configured. For example, a button 1590 displays the OSK as illustrated in FIG. 66A with a full keyboard and numeric keypad. The button 1592 is a toggle which displays the keyboard without the numeric keyboard as illustrated in FIG. 66B. The button 1594 displays the numeric keypad with the NUM LOCK off as illustrated in FIG. 66C, or alternatively displays the OSK as a numeric keyboard NUM LOCK on as illustrated in FIG.

66D. The button 1596 allows the size of the OSK to be varied. The "X" button closes the window displaying the OSK.

As mentioned above, the display 113C on the wireless interface device 100 displays whatever is being displayed on the host 101 when a connection is made. Since the graphics for the OSK is generated locally at the wireless interface device 100, a remote occlusion region is generated at the host 101 to prevent the host 101 from painting over the OSK on the display 113C of the wireless interface device 100. The remote occlusion region is analogous to a window in the display of the host 101 in which the host 101 is prevented from using.

Referring to FIG. 65A, the system monitors the hot icon area 1202 (FIG. 36) to determine if any of the hot icons have been pressed. As discussed above, the system includes an OSK hot icon 1480 (FIG. 37), which displays the OSK on the LCD 113C of the wireless interface device 100 when depressed. If the system determines in step 1598 that a hot icon has been depressed, it checks in step 1600 whether the OSK hot icon 1480 was pressed. If not, the system loops back to 1598 and continually checks for hot icons being pressed. If the OSK hot icon 1480 has been depressed, the system determines the last configuration for the OSK in step 1602 (i.e. FIGS. 66A–66D). Once the configuration of the last OSK is determined in step 1602, the system then checks the operating system and video mode of the host 101 in step 1604. Depending on whether the host 101 is in text or graphics mode will determine whether the OSK image on the wireless interface device 100 is merely shadowed onto the display of the host 101 by way of a private message, as will be discussed in more detail below, or whether the remote occlusion region at the host 101 is established by drivers in the host software, which create the remote occlusion region by way of ASCII characters. Thus, in step 1606, if the system determines that the host 101 is in the text mode, an occlusion region on the display of the host 101 is created using the host control drivers in step 1608. In step 1610, the system checks whether the occlusion region was successfully established. If not, the system then checks in step 1612 whether the OSK is currently visible on the display 113C of the wireless interface device 100. If not, the display of the OSK is aborted in step 1614. If it is determined in step 1612 that the OSK is currently visible on the LCD 113C of the wireless interface device 100, any reconfiguration of the OSK is ignored and the configuration of the last OSK is continuously displayed in step 1614. If it is determined in step 1610 that the remote occlusion region is successfully established, the system goes to step 1616, which enables the OSK to be used.

If it is determined in step 1606 that the host 101 is not in a text mode, the system checks in step 1618 whether the host 101 is in a graphics mode. If not, the system goes to step 1620 and sets the video mode to VGA graphics in the wireless interface device 100 and subsequently proceeds to step 1608 to establish the occlusion region in the host 101 by host control drivers. If the host is in a graphics mode, the system next checks in step 1622 whether the host 101 is running a Windows application. If not, the system returns to step 1608 and establishes the occlusion region on the display of the host 101 using the host control drivers.

If it is determined in step 1622 that the host 101 is running a Windows application, the occlusion region on the host 101 is established by way of a private message sent by the wireless interface device 100 to the host 101 in step 1624. After the private message is sent, the system checks in step 1626 to determine if it was successfully sent. If not, the

system proceeds to step 1612 and checks to determine if an OSK is currently visible. If the private message is successfully sent, the system checks in step 1628 whether the private message was successfully received by the host 101. If so, the system goes to step 1630 and checks whether the private message was acknowledged by the host 101. If so, the system goes to step 1616 and draws the OSK at the user-requested coordinates. If not, the system goes to 1612. If it is determined in step 1628 that the private message has not been received, the system continually checks for receipt of the private message for a predetermined time-out period in step 1632. Should a time-out occur before the private message is acknowledged by the host 101, the system again will go to step 1612.

The OSK includes a control bar 1632 (FIG. 66A). The control bar 1632 enables the location of the OSK on the LCD 113C of the wireless interface device 100 to be changed by touching the control bar 1632 with the pen and dragging it to the desired location on the LCD 113C of the wireless interface device 100. Anytime the user changes the location of the OSK on the LCD 113C of the wireless interface device 100 as acknowledged by the system in step 1634, the system then returns to step 1604 to determine the video mode of the host computer 101. As discussed above, the video mode determines whether the remote occlusion region on the display of the host 100 is created by shadowing the OSK on the display of the host by way of the private message or whether the occlusion region on the display of the host is created by local drivers using ASCII characters. The system then goes to step 1606.

Obviously, many modifications and variations of the present invention are possible in light of the above teachings. Thus, it is to be understood that, within the scope of the appended claims, the invention may be practiced otherwise than as specifically described above.

What is claimed and desired to be secured by Letters Patent of the United States is:

1. A wireless interface device for use with one or more host computers, the wireless interface device comprising:

- means for communicating with one of said one or more host computers;
- means for enabling said wireless interface device to take control of one of said one or more host computers after communication is established;
- means for storing a node address corresponding to the last host computer to which the wireless interface was successfully connected;
- means for determining, on power up, the availability of a connection to the last host computer;
- means for updating said node address to indicate an alternative host computer upon determining that said connection is not available; and
- means for automatically connecting said wireless interface device to the host indicated by said node address.

2. A wireless interface device according to claim 1, said connecting means including means for checking a validity of said node address.

3. A wireless interface device according to claim 1, further including means for enabling said wireless interface device to enter a power down state.

4. A method for operating a wireless interface device in a system with one or more host computers:

- communicating with one of said one or more host computers;
- enabling said wireless interface device to take control of one of said one or more host computers after communication is established;

57

storing a node address corresponding to the last host computer to which the wireless interface was successfully connected;

means for determining, on power up, the availability of a connection to the last host computer;

updating said node address to indicate an alternative host computer upon determining that said connection is not available; and

automatically connecting said wireless interface device to the host indicated by said node address.

5. A method according to claim 4, further including: checking a validity of said node address.

6. A method according to claim 4, further including entering a power down state.

7. A wireless interface device for use with one or more host computers, the wireless interface device comprising:

means for communicating with one of said one or more host computers;

means for enabling said wireless interface device to take control of one of said one or more host computers after communication is established;

means for automatically connecting said wireless interface device to the last host to which it was successfully connected on power-up, said connecting means including means for identifying a node address of said last host, means for storing said node address, and means for checking a validity of said node address; and

means permitting said wireless interface device to enter a power down state, wherein said storing means is configured to store said address prior to said wireless interface device entering said power down state.

58

8. A method for operating a wireless interface device in a system with one or more host computers:

communicating with one of said one or more host computers;

enabling said wireless interface device to take control of one of said one or more host computers after communication is established;

automatically connecting said wireless interface device to the last host to which it was successfully connected on power-up;

identifying a node address of said last host;

checking a validity of said node address;

storing said address prior to said wireless interface device entering a power down state; and

entering said power down state.

9. A wireless interface device for use with one or more host computers, the wireless interface device comprising:

a radio transceiver for communicating with one of said one or more host computers;

a memory storing a node address corresponding to the last host computer to which the wireless interface was successfully connected;

a processor determining, on power up, the availability of a connection to the last host computer, and upon determining that said connection is not available, updating said node address to indicate an alternative host computer, said processor automatically connecting said wireless interface device to the host indicated by said node address.

* * * * *