



UNITED STATES PATENT AND TRADEMARK OFFICE

UNITED STATES DEPARTMENT OF COMMERCE
United States Patent and Trademark Office
Address: COMMISSIONER FOR PATENTS
P.O. Box 1450
Alexandria, Virginia 22313-1450
www.uspto.gov

APPLICATION NUMBER	FILING or 371(c) DATE	GRP ART UNIT	FIL FEE REC'D	ATTY. DOCKET NO	TOT CLAIMS	IND CLAIMS
61/064,618	03/17/2008		105	1052-29		

CONFIRMATION NO. 4188

Yossi Azancol
11 Amal Street
Rosh HaAyin, 48092
ISRAEL

FILING RECEIPT



OC000000029971790

Date Mailed: 05/19/2008

Receipt is acknowledged of this provisional patent application. It will not be examined for patentability and will become abandoned not later than twelve months after its filing date. Any correspondence concerning the application must include the following identification information: the U.S. APPLICATION NUMBER, FILING DATE, NAME OF APPLICANT, and TITLE OF INVENTION. Fees transmitted by check or draft are subject to collection. Please verify the accuracy of the data presented on this receipt. **If an error is noted on this Filing Receipt, please submit a written request for a Filing Receipt Correction. Please provide a copy of this Filing Receipt with the changes noted thereon. If you received a "Notice to File Missing Parts" for this application, please submit any corrections to this Filing Receipt with your reply to the Notice. When the USPTO processes the reply to the Notice, the USPTO will generate another Filing Receipt incorporating the requested corrections**

Applicant(s)

Yossi Azancol, Jerusalem, ISRAEL;
Amir Ben Shalom, Modi'in, ISRAEL;
Arik Rofe, Jerusalem, ISRAEL;
Oola Greenwald, Jerusalem, ISRAEL;
Dov Rhodes, Jerusalem, ISRAEL;

Power of Attorney: None

If Required, Foreign Filing License Granted: 05/15/2008

The country code and number of your priority application, to be used for filing abroad under the Paris Convention, is **US 61/064,618**

Projected Publication Date: None, application is not eligible for pre-grant publication

Non-Publication Request: No

Early Publication Request: No

**** SMALL ENTITY ****

Title

Transmission-guard for inductive power outlet

PROTECTING YOUR INVENTION OUTSIDE THE UNITED STATES

Since the rights granted by a U.S. patent extend only throughout the territory of the United States and have no effect in a foreign country, an inventor who wishes patent protection in another country must apply for a patent in a specific country or in regional patent offices. Applicants may wish to consider the filing of an international application under the Patent Cooperation Treaty (PCT). An international (PCT) application generally has the same

effect as a regular national patent application in each PCT-member country. The PCT process **simplifies** the filing of patent applications on the same invention in member countries, but **does not result** in a grant of "an international patent" and does not eliminate the need of applicants to file additional documents and fees in countries where patent protection is desired.

Almost every country has its own patent law, and a person desiring a patent in a particular country must make an application for patent in that country in accordance with its particular laws. Since the laws of many countries differ in various respects from the patent law of the United States, applicants are advised to seek guidance from specific foreign countries to ensure that patent rights are not lost prematurely.

Applicants also are advised that in the case of inventions made in the United States, the Director of the USPTO must issue a license before applicants can apply for a patent in a foreign country. The filing of a U.S. patent application serves as a request for a foreign filing license. The application's filing receipt contains further information and guidance as to the status of applicant's license for foreign filing.

Applicants may wish to consult the USPTO booklet, "General Information Concerning Patents" (specifically, the section entitled "Treaties and Foreign Patents") for more information on timeframes and deadlines for filing foreign patent applications. The guide is available either by contacting the USPTO Contact Center at 800-786-9199, or it can be viewed on the USPTO website at <http://www.uspto.gov/web/offices/pac/doc/general/index.html>.

For information on preventing theft of your intellectual property (patents, trademarks and copyrights), you may wish to consult the U.S. Government website, <http://www.stopfakes.gov>. Part of a Department of Commerce initiative, this website includes self-help "toolkits" giving innovators guidance on how to protect intellectual property in specific countries such as China, Korea and Mexico. For questions regarding patent enforcement issues, applicants may call the U.S. Government hotline at 1-866-999-HALT (1-866-999-4158).

LICENSE FOR FOREIGN FILING UNDER

Title 35, United States Code, Section 184

Title 37, Code of Federal Regulations, 5.11 & 5.15

GRANTED

The applicant has been granted a license under 35 U.S.C. 184, if the phrase "IF REQUIRED, FOREIGN FILING LICENSE GRANTED" followed by a date appears on this form. Such licenses are issued in all applications where the conditions for issuance of a license have been met, regardless of whether or not a license may be required as set forth in 37 CFR 5.15. The scope and limitations of this license are set forth in 37 CFR 5.15(a) unless an earlier license has been issued under 37 CFR 5.15(b). The license is subject to revocation upon written notification. The date indicated is the effective date of the license, unless an earlier license of similar scope has been granted under 37 CFR 5.13 or 5.14.

This license is to be retained by the licensee and may be used at any time on or after the effective date thereof unless it is revoked. This license is automatically transferred to any related applications(s) filed under 37 CFR 1.53(d). This license is not retroactive.

The grant of a license does not in any way lessen the responsibility of a licensee for the security of the subject matter as imposed by any Government contract or the provisions of existing laws relating to espionage and the national security or the export of technical data. Licensees should apprise themselves of current regulations especially with

respect to certain countries, of other agencies, particularly the Office of Defense Trade Controls, Department of State (with respect to Arms, Munitions and Implements of War (22 CFR 121-128)); the Bureau of Industry and Security, Department of Commerce (15 CFR parts 730-774); the Office of Foreign Assets Control, Department of Treasury (31 CFR Parts 500+) and the Department of Energy.

NOT GRANTED

No license under 35 U.S.C. 184 has been granted at this time, if the phrase "IF REQUIRED, FOREIGN FILING LICENSE GRANTED" DOES NOT appear on this form. Applicant may still petition for a license under 37 CFR 5.12, if a license is desired before the expiration of 6 months from the filing date of the application. If 6 months has lapsed from the filing date of this application and the licensee has not received any indication of a secrecy order under 35 U.S.C. 181, the licensee may foreign file the application pursuant to 37 CFR 5.15(b).

PROVISIONAL APPLICATION FOR PATENT COVER SHEET – Page 1 of 2

This is a request for filing a PROVISIONAL APPLICATION FOR PATENT under 37 CFR 1.53(c).

Express Mail Label No. _____

INVENTOR(S)		
Given Name (first and middle [if any])	Family Name or Surname	Residence (City and either State or Foreign Country)
Yossi	Azancol	Jerusalem, Israel
Amir	Ben Shalom	Modi'in, Israel
Arik	Rofe	Jerusalem, Israel
Oola	Greenwald	Jerusalem, Israel
Dov	Rhodes	Jerusalem, Israel

Additional inventors are being named on the _____ separately numbered sheets attached hereto

TITLE OF THE INVENTION (500 characters max):

Transmission-Guard for Inductive Power Outlet

Direct all correspondence to: **CORRESPONDENCE ADDRESS**

☐ The address corresponding to Customer Number: _____

OR

☒ Firm or Individual Name

Address 11, Amal Street

City Rosh HaAyn	State Israel	Zip 48092
Country Israel	Telephone +972 3 902 1057	Email morris@ipfactor.co.il

ENCLOSED APPLICATION PARTS (check all that apply)

☐ Application Data Sheet. See 37 CFR 1.76

☒ Drawing(s) Number of Sheets 4

☒ Specification (e.g. description of the invention) Number of Pages 12

☐ CD(s). Number of CDs _____

☐ Other (specify) _____

Fees Due: Filing Fee of \$200 (\$100 for small entity). If the specification and drawings exceed 100 sheets of paper, an application size fee is also due, which is \$250 (\$125 for small entity) for each additional 50 sheets or fraction thereof. See 35 U.S.C. 41(a)(1)(G) and 37 CFR 1.16(s).

METHOD OF PAYMENT OF THE FILING FEE AND APPLICATION SIZE FEE FOR THIS PROVISIONAL APPLICATION FOR PATENT

☐ Applicant claims small entity status. See 37 CFR 1.27.

☐ A check or money order is enclosed to cover the filing fee and application size fee (if applicable).

☒ Payment by credit card. Form PTO-2038 is attached

☐ The Director is hereby authorized to charge the filing fee and application size fee (if applicable) or credit any overpayment to Deposit

TOTAL FEE AMOUNT (\$) 105

Account Number: _____ A duplicative copy of this form is enclosed for fee processing.

USE ONLY FOR FILING A PROVISIONAL APPLICATION FOR PATENT

This collection of information is required by 37 CFR 1.51. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.11 and 1.14. This collection is estimated to take 8 hours to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

PROVISIONAL APPLICATION COVER SHEET
Page 2 of 2

PTO/SB/16 (07-07)

Approved for use through 06/30/2010. OMB 0651-0032

U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

The invention was made by an agency of the United States Government or under a contract with an agency of the United States Government.



No.



Yes, the name of the U.S. Government agency and the Government contract number are: _____

WARNING:

Petitioner/applicant is cautioned to avoid submitting personal information in documents filed in a patent application that may contribute to identity theft. Personal information such as social security numbers, bank account numbers, or credit card numbers (other than a check or credit card authorization form PTO-2038 submitted for payment purposes) is never required by the USPTO to support a petition or an application. If this type of personal information is included in documents submitted to the USPTO, petitioners/applicants should consider redacting such personal information from the documents before submitting them to the USPTO. Petitioner/applicant is advised that the record of a patent application is available to the public after publication of the application (unless a non-publication request in compliance with 37 CFR 1.213(a) is made in the application) or issuance of a patent. Furthermore, the record from an abandoned application may also be available to the public if the application is referenced in a published application or an issued patent (see 37 CFR 1.14). Checks and credit card authorization forms PTO-2038 submitted for payment purposes are not retained in the application file and therefore are not publicly available.

SIGNATURE /Yossi Azancot/ /Amir Ben Shalom/ /Arik Rofe/ /Oola Greenwald/ /Dov Rhodes/

Date 15th March 2008

TYPED or PRINTED NAME Yossi Azancot Amir Ben Shalom Arik Rofe Oola Greenwald

REGISTRATION NO. _____
(if appropriate)

Dov Rhodes

TELEPHONE +972 3 902 1057

Docket Number: 1052-29

Transmission-Guard for Inductive Power Outlet

Field of the Invention

The present invention is directed to inductive electrical power outlets. More specifically, the present invention relates to preventing power transmission from
5 inductive power outlets in the absence of an electric load.

Background

Inductive power coupling allows energy to be transferred from a power supply to an electric load without connecting wires. A power supply is wired to a primary coil and an oscillating electric potential is applied across the primary coil, thereby
10 inducing an oscillating magnetic field. The oscillating magnetic field may induce an oscillating electrical current in a secondary coil placed close to the primary coil. In this way, electrical energy may be transmitted from the primary coil to the secondary coil by electromagnetic induction without the two coils being conductively connected. When electrical energy is transferred from a primary coil to a secondary coil the coil
15 pair are said to be inductively coupled. An electric load wired in series with such a secondary coil may draw energy from the power source wired to the primary coil when the secondary coil is inductively coupled thereto.

Induction type power outlets may be preferred to the more common conductive power sockets because they provide seamless power transmission and
20 minimize the need for trailing wires.

Low power inductive electrical power transmission systems have been proposed. One such example is described in United States Patent No. 7,164,255 to Hui. In Hui's system a planar inductive battery charging arrangement is designed to enable electronic devices to be recharged. The system includes a planar charging
25 module having a charging surface on which a device to be recharged is placed. Within the charging module, and parallel to the charging surface, at least one, and preferably an array of primary windings are provided. The primary windings inductively couple energy to secondary windings within the device to be recharged.

Such systems are adequate for charging batteries in that they typically provide
30 a relatively low power inductive coupling. It will be appreciated however, that extended base units such as Hui's charging surface which transmit energy continuously, in a largely uniform manner over the whole area of the unit, are not

suitable for use with high energy systems, such as those required to power computers, light bulbs, televisions and the like.

Variable voltage in a high power primary coil produces a large oscillating magnetic field. Where a secondary coil is inductively coupled to the primary coil, the
5 resulting flux linkage causes power to be drawn by the secondary coil. Where there is no secondary coil to draw the power, the oscillating magnetic field causes high energy electromagnetic waves to be radiated in all directions which may have undesired side affects, such as wiping credit cards and may be harmful to bystanders particularly to those with pacemakers. In addition whereas in low power systems such as Hui's
10 charging surface excess heat may be readily dissipated, an uncoupled high power primary coil or its surroundings may become dangerously hot.

United States Patent No. 6,803,744, to Sabo, titled "Alignment independent and self aligning inductive power transfer system" describes an inductive power transfer device for recharging cordless appliances. Sabo's device includes a plurality
15 of inductors which serve as the primary coil of a transformer. The secondary coil of the transformer is arranged within the appliance. When the appliance is positioned proximate to the power transfer device with the respective coils in alignment, power is inductively transferred from the device to the appliance via the transformer.

The inductors of Sabo's system are arranged in an array and connected to a
20 power supply via switches which are selectively operable to activate the respective inductors. These selectively operable switches are provided to conserve power and to eliminate objectionable electromagnetic fields. '744 thus indicates the need for each primary coil to be energized from the power supply only when a secondary coil is within effective range. Nevertheless no mechanism is described by which such
25 switches may be remotely operated.

The need remains therefore for a practical transmission-guard for preventing power transmission from inductive power outlets in the absence of an electric load.

Summary of the Invention

It is an aim of the invention to provide a transmission-guard for preventing an inductive power outlet from transmitting power in the absence of an electric load inductively coupled thereto, the inductive power outlet comprising at least one
5 primary coil connectable to a power supply, for inductively coupling with a secondary coil wired to the electric load, the transmission-guard comprising at least one transmission-lock for preventing the primary coil from connecting to the power supply in the absence of a transmission-key.

Preferably, the transmission-lock comprises at least one magnetic switch and
10 the transmission-key comprises at least one magnetic element associated with the secondary coil. In certain embodiments magnetic element comprises a ferrite flux guidance core. Optionally, the transmission-lock comprises an array of magnetic switches configured to connect the primary coil to the power supply only when activated by a matching configuration of magnetic elements. Typically, the magnetic
15 switch comprises a magnetic sensor.

In certain embodiments, the transmission-guard comprises: at least one emitter for emitting a release-signal; and at least one detector for detecting the release signal; the transmission-key comprises at least one bridge associated with the secondary coil for bridging between the at least one emitter and the at least one detector, such that
20 when the secondary coil is brought into alignment with the primary coil the release signal is guided from the emitter to the detector. Optionally, the release-signal is an optical signal and the bridge comprises at least one optical wave-guide. Alternatively, the release-signal is a magnetic signal and the bridge comprises a magnetic flux guide. Alternatively, again, the release-signal is selected from the group comprising:
25 mechanical signals, audio signals, ultra-sonic signals and microwaves.

In other embodiments, the transmission-key comprises a release-signal emitted by an emitter associated with the secondary coil. Optionally, the release-signal is an optical signal such as an infra-red pulse received by an optical detector configured to release the transmission-lock. Alternatively, the release-signal is a magnetic signal,
30 such as may be emitted by the secondary coil. Alternatively, again, the release-signal is selected from the group comprising: mechanical signals, audio signals, ultra-sonic signals and microwaves.

In still other embodiments, a low-power power pulse transmitted by the primary coil, such that when the secondary coil is aligned to the primary coil the power pulse is transferred to the secondary coil and the transmission-key is triggered by the power pulse.

5 In preferred embodiments, the transmission-guard comprises: a first transmission-lock being released by a first transmission-key indicating the probable presence of a secondary coil and a second transmission-lock being released by a second transmission-key confirming the presence of the secondary coil. The first transmission-lock may initiate a power pulse transmitted from the primary coil, and
10 the second transmission key may be triggered by the power pulse being received by the secondary coil.

It is a further aim of the invention is to provide a transmission-key for use in the transmission-guard. Another aim is to provide a transmission-lock for use in the transmission-guard.

15 Still another aim of the invention is to provide an inductive power outlet protected by the transmission-guard.

Another aspect of the invention is to teach a method for preventing an inductive power outlet from transmitting power in the absence of an electric load, by protecting the inductive power outlet with the transmission-guard.

20

Brief Description of the Figures

For a better understanding of the invention and to show how it may be carried into effect, reference will now be made, purely by way of example, to the accompanying drawings.

5 With specific reference now to the drawings in detail, it is stressed that the particulars shown are by way of example and for purposes of illustrative discussion of the preferred embodiments of the present invention only, and are presented in the cause of providing what is believed to be the most useful and readily understood description of the principles and conceptual aspects of the invention. In this regard, no
10 attempt is made to show structural details of the invention in more detail than is necessary for a fundamental understanding of the invention; the description taken with the drawings making apparent to those skilled in the art how the several forms of the invention may be embodied in practice. In the accompanying drawings:

Fig. 1 is a block diagram representing the main components of a transmission-guard for an inductive power outlet according to a first embodiment of the present
15 invention;

Fig. 2 is a schematic representation of an inductive power outlet protected by an exemplary transmission-guard according to a second embodiment of the present invention wherein a transmission-lock is released by a magnetic key;

20 Figs. 3a-c are schematic representations of a transmission-guard according to a third embodiment of the invention in which a transmission-lock is releasable by a passive optical transmission-key; and

Fig. 4 is a schematic representation of a transmission-guard according to a fourth embodiment of the invention in which a transmission-lock is releasable by an
25 active optical transmission-key.

Description of the Preferred Embodiments

Reference is now made to Fig. 1 which shows a block diagram representing a
30 transmission-guard 100 for preventing an inductive power outlet 200 from

transmitting power in the absence of a secondary unit 300 connected to an electric load 340, according to a first embodiment of the invention.

5 The inductive power outlet 200 consists of a primary coil 220, wired to a power supply 240, for inductively coupling with a secondary coil 320 wired to an electric load 340.

The primary coil 220 is typically wired to the power supply 240 via a driver 230 which provides the electronics necessary to drive the primary coil 220. Driving electronics may include a switching unit providing a high frequency oscillating voltage supply, for example. Where the power outlet 200 consists of more than one
10 primary coil 220, the driver 230 may additionally consist of a selector for selecting which primary coil 220 is to be driven.

It is a particular feature of the present invention that a transmission-guard 100 is provided consisting of a transmission-lock 120 connected in series between the power supply 240 and the primary coil 220. The transmission-lock 120 is configured
15 to prevent the primary coil 220 from connecting to the power supply 240 unless it is released by a transmission-key 140. The transmission-key 140 is associated with the secondary unit 300 and serves to indicate that the secondary coil 320 is aligned to the primary coil 220.

With reference to Fig. 2, a schematic representation is shown of an inductive
20 power outlet 2200 protected by an exemplary magnetic transmission-guard 2100 according to a second embodiment of the present invention. Power may only be provided by the protected power outlet 2200 when an authenticated secondary unit 2300 is aligned thereto.

The protected power outlet 2200 includes a magnetic transmission-lock 2120
25 consisting of an array of magnetic switches 2122 electrically connected in series between the primary coil 2220 and the driver 2230. A magnetic transmission-key 2140 consisting of an array of magnetic elements 2142 is provided within the authenticated secondary unit 2300.

The configuration of magnetic elements 2142 in the transmission-key 2140 is
30 selected to match the configuration of magnetic switches 2122 in the transmission-lock 2120. The authenticated secondary unit 2300 may be aligned with the protected induction outlet 2200 by aligning both the transmission-key 2140 with the

transmission-lock 2120 and the secondary coil 2320 with the primary coil 2220. Once correctly aligned, all the magnetic switches 2122 in the transmission-lock 2120 are closed and the driver 2230 is thereby connected to the primary coil 2220.

Various examples of magnetic switches 2122 are known in the art including for example reed switches, Hall-effect sensors or such like. Such magnetic switches 2122 may be sensitive to any magnetic elements 2142 such as either North or South poles of permanent magnets or electromagnetic coils for example. It is further noted that Hall-effect sensors may be configured to sense magnetic fields of predetermined strength.

According to certain embodiments, the magnetic transmission-key 2140 may consist of a permanent magnet and a ferrite element incorporated within the secondary unit 300. The characteristics of the magnetic field produced by a transmission-key of this type depend upon the strength and position of the permanent magnetic as well as the dimensions and characteristics of the ferrite element. The magnetic transmission-lock 2120 may consist of an array of magnetic switches, such as unipolar Hall switches for example, which are strategically placed and orientated such that they connect the primary coil 2220 to the driver 2230 only when triggered by a particular combination of a permanent magnet and ferrite element.

It is noted that permanent magnets may commonly be provided to assist with alignment of the secondary coil 2320 to the primary coil 2220. Ferrite elements may also be commonly included in secondary units 300 for providing flux guidance from the primary coil 2220 to the secondary coil 2320. The magnetic transmission-lock 2120 may therefore be made sensitive to these components. Indeed a single magnetic transmission-lock 2120 may be provided which is configured to detect various secondary units and to selectively connect more than one primary coil 2220 depending on the secondary unit detected.

Referring back to Fig. 1, according to other embodiments of the transmission-guard 100, a power outlet 200 may be protected by a transmission-lock 120 which may be released when a release signal S_R is received by a detector 124. The release signal S_R may be actively emitted by the transmission-key 140 or alternatively the transmission-key may passively direct the release signal towards the detector 124.

One example of a passive transmission-key 3140 is shown in Figs. 3a-c which represent an optical transmission-guard 3100 according to a third embodiment of the invention.

5 The transmission-guard 3100 consists of an active optical transmission-lock 3120 incorporated within an inductive power outlet 3200 and a passive optical transmission-key 3140 incorporated within the secondary unit 3300.

10 With particular reference to Fig. 3a, the optical transmission-lock 3120 includes a switch 3122, an optical detector 3124, such as a photodiode, a phototransistor, a light dependent resistor or the like, and an optical emitter 3126 such as light emitting diode (LED). The switch 3122 is normally open but is configured to close when a release signal S_R is received by the optical detector 3124, thereby connecting a primary coil 3220 to a driver 3230. The optical emitter 3126 is configured to emit the optical release-signal S_R which is not directly detectable by the optical detector 3124.

15 Referring now to Fig. 3b, the optical transmission-key 3140 includes a bridging element 3142 such as an optical wave-guide, optical fiber, reflector or the like. The bridging element 3142 is configured to direct the optical release-signal S_R from the optical emitter 3124 towards the optical detector 3126, when a secondary coil 3320 is aligned with the primary coil 3220.

20 When the secondary unit 3300 is correctly aligned with the inductive power outlet 3200, as shown in Fig. 3c, the secondary coil 3320 aligns with the primary coil 3220 and the passive optical transmission-key 3140 aligns with the optical transmission-lock 3120. The optical release-signal S_R is thus detected by the optical detector 3126 and the switch 3122 is closed connecting the primary coil 3220 to the driver 3230.

25 It is noted that many materials are partially translucent to infra-red light. It has been found that relatively low intensity infra red signals from LEDs and the like, penetrate several hundred microns of common materials such as plastic, cardboard, Formica or paper sheet, to a sufficient degree that an optical detector 3124, such as a photodiode, a phototransistor, a light dependent resistor or the like, behind a sheet of from 0.1 mm to 2 mm of such materials, can receive and process the signal. For example a signal from an Avago HSDL-4420 LED transmitting at 850nm over 24

degrees, may be detected by an Everlight PD15-22C-TR8 NPN photodiode, from behind a 0.8 mm Formica sheet. For signaling purposes, a high degree of attenuation may be tolerated, and penetration of only a small fraction, say 0.1% of the transmitted signal intensity may be sufficient.

5 Although an optical transmission-key 3140 is described above, it will be appreciated that other passive transmission-keys may incorporate bridging elements configured to guide release-signals of other types. For example, a ferromagnetic bridge may be incorporated for transmitting magnetic release-signal from a magnetic element to a magnetic detector such as a Hall-effect sensor or the like. The magnetic
10 emitter in such a case may be the primary coil itself.

 Alternatively, audio signals through dense elements, or low power microwaves may be guided along microwave wave guides for example.

 An example of an active optical transmission-key 4140 is shown in Fig. 4 representing a transmission-guard 4100 according to a fourth embodiment of the
15 invention.

 The transmission-guard 4100 of the fourth embodiment includes a transmission-lock 4120 incorporated within an inductive power outlet 4200 and an active optical transmission-key 4140 incorporated within secondary unit 4300.

 The active optical transmission-key 4140 includes an optical emitter 4142,
20 configured to emit an optical release-signal S_R , and the transmission-lock 4120 includes a switch 4122 and an optical detector 4124. The transmission-lock 4120 is configured to close the switch 4122 thereby connecting a primary coil 4220 to a driver 4230 when the optical detector 4124 receives the release-signal S_R .

 When the secondary unit 4300 is aligned with the inductive power outlet 4200,
25 the transmission-key 4140 emits an optical release-signal S_R which is received by the optical detector 4124 of the transmission-lock 4120 and this closes the switch 4122. Thus the inductive power outlet 4200 is enabled to transfer power to the secondary coil 4320.

 It will be appreciated that a release signal S_R may be coded to provide a unique
30 identifier. Coding may be by modulation of frequency, pulse frequency, amplitude or the like. The code may be used, for example, to identify the type or identity of the secondary unit for authentication. Other data may additionally be encoded into the

release-signal. This data may include required power transmission parameters, billing information or other information for the use of the power outlet.

Although an optical active transmission-key 4140 is described above, it will be appreciated that other active transmission-keys may emit other types of release-
5 signals. For example, the secondary coil 4320 may be used to transmit a magnetic release-signal to a magnetic detector incorporated in the transmission-lock. This could be a Hall-effect sensor or the like or even the primary coil 4220 itself.

To actively emit a release-signal transmission-keys typically require a power source. In some cases, particularly where the secondary unit is incorporated into a
10 portable electrical device, power may be provided by internal power cells with the secondary unit. Alternatively, power may be drawn from a power pulse transferred from the primary coil to the secondary coil.

In certain embodiments of the invention, the inductive power outlet transfers a periodic low energy power pulse, for example a pulse of a few milliseconds duration
15 may be transmitted by the primary coil at a frequency of 1 hertz or so. When a secondary coil is brought into the vicinity of the primary coil the power may be transferred to the secondary coil and may be used to power an active transmission-key.

In other embodiments of the transmission-guard, a first transmission-lock
20 (preferably a passive transmission-lock) associated with the secondary unit, releases a first transmission-lock thereby indicating the probable presence of a secondary coil. A low energy power pulse is then emitted by the primary coil to power an active second transmission-key which may release a second transmission-lock thereby connecting the primary coil to a driver.

25 The scope of the present invention is defined by the appended claims and includes both combinations and sub combinations of the various features described hereinabove as well as variations and modifications thereof, which would occur to persons skilled in the art upon reading the foregoing description.

In the claims, the word "comprise", and variations thereof such as
30 "comprises", "comprising" and the like indicate that the components listed are included, but not generally to the exclusion of other components.

Claims

1. A transmission-guard for preventing an inductive power outlet from transmitting power in the absence of an electric load inductively coupled thereto, said inductive power outlet comprising at least one primary coil connectable to a power supply,
5 for inductively coupling with a secondary coil wired to said electric load, said transmission-guard comprising at least one transmission-lock for preventing said primary coil from connecting to said power supply in the absence of a transmission-key.
2. The transmission-guard of claim 1 wherein said transmission-lock comprises at
10 least one magnetic switch and said transmission-key comprises at least one magnetic element associated with said secondary coil.
3. The transmission-guard of claim 2 wherein said transmission-lock comprises an array of magnetic switches configured to connect said primary coil to said power supply only when activated by a matching configuration of magnetic elements.
- 15 4. The transmission-guard of claim 2 wherein said magnetic switch comprises a magnetic sensor.
5. The transmission-guard of claim 1 comprising: at least one emitter for emitting a release-signal; and at least one detector for detecting said release signal; said transmission-key comprises at least one bridge associated with said secondary coil
20 for bridging between said at least one emitter and said at least one detector, such that when said secondary coil is brought into alignment with said primary coil said release signal is guided from said emitter to said detector.
6. The transmission-guard of claim 5 wherein said release-signal is an optical signal and said bridge comprises at least one optical wave-guide.
- 25 7. The transmission-guard of claim 5 wherein said release-signal is a magnetic signal and said bridge comprises a magnetic flux guide.
8. The transmission-guard of claim 1 wherein said transmission-key comprises a release-signal emitted by an emitter associated with said secondary coil.
9. The transmission-guard of claim 8 wherein said release-signal is an optical signal.
- 30 10. The transmission-guard of claim 9 wherein said optical signal is an infra-red pulse received by an optical detector configured to release said transmission-lock.

11. The transmission-guard of claim 8 wherein said release-signal is a magnetic signal.
12. The transmission-guard of claim 11 wherein said emitter is said secondary coil.
13. The transmission-guard of claim 1 comprising a low-power power pulse
5 transmitted by said primary coil, such that when said secondary coil is aligned to said primary coil said power pulse is transferred to said secondary coil and said transmission-key is triggered by said power pulse.
14. The transmission-guard of claim 1 comprising: a first transmission-lock being released by a first transmission-key indicating the probable presence of a
10 secondary coil and a second transmission-lock being released by a second transmission-key confirming the presence of said secondary coil.
15. The transmission-guard of claim 14, said first transmission-lock initiating a power pulse transmitted from said primary coil, and said second transmission key being triggered by said power pulse being received by said secondary coil.
- 15 16. A transmission-guard of claim 2 wherein said magnetic element comprises a ferrite flux guidance core.
17. A transmission-guard of claim 5 wherein said release-signal is selected from the group comprising: mechanical signals, audio signals, ultra-sonic signals and microwaves.
- 20 18. A transmission-guard of claim 8 wherein said release-signal is selected from the group comprising: mechanical signals, audio signals, ultra-sonic signals and microwaves.
19. A transmission-key for use in said transmission-guard of claim 1.
20. A transmission-lock for use in said transmission-guard of claim 1.
- 25 21. An inductive power outlet protected by said transmission-guard of claim 1.
22. A method for preventing an inductive power outlet from transmitting power in the absence of an electric load, by protecting said inductive power outlet with said transmission-guard of claim 1.




Fig. 1







Fig. 2






Fig. 4

PATENT APPLICATION SERIAL NO. _____

**U.S. DEPARTMENT OF COMMERCE
PATENT AND TRADEMARK OFFICE
FEE RECORD SHEET**

03/18/2008 MBELETE1 00000034 61064610

01 FC:2005

105.00 OP

**PTO-1556
(5/87)**