

UNITED STATES PATENT AND TRADEMARK OFFICE

---

BEFORE THE PATENT TRIAL AND APPEAL BOARD

---

UNION ELECTRIC COMPANY,  
Petitioner,

v.

BIRCHTECH CORPORATION,  
Patent Owner.

---

Case: IPR2025-01322  
Patent 10,668,430

---

**PETITION FOR *INTER PARTES* REVIEW  
OF U.S. PATENT NO. 10,668,430**

## **TABLE OF CONTENTS**

|                                                                                                                               | <b><u>Page</u></b> |
|-------------------------------------------------------------------------------------------------------------------------------|--------------------|
| TABLE OF CONTENTS.....                                                                                                        | i                  |
| TABLE OF AUTHORITIES .....                                                                                                    | x                  |
| LISTING OF EXHIBITS.....                                                                                                      | xii                |
| TABLE OF CHALLENGED CLAIMS .....                                                                                              | xviii              |
| I. INTRODUCTION .....                                                                                                         | 1                  |
| II. MANDATORY NOTICES UNDER 37 C.F.R. 42.8.....                                                                               | 1                  |
| A. Real Parties-in-Interest (42.8(b)(1)) .....                                                                                | 1                  |
| B. Related Matters (42.8(b)(2)) .....                                                                                         | 1                  |
| C. Lead and Back up Counsel (42.8(b)(3)) .....                                                                                | 3                  |
| III. PAYMENT OF FEES .....                                                                                                    | 3                  |
| IV. GROUNDS FOR STANDING.....                                                                                                 | 3                  |
| V. IDENTIFICATION OF CHALLENGED CLAIMS AND RELIEF<br>SOUGHT .....                                                             | 4                  |
| VI. THE BOARD SHOULD NOT DENY INSTITUTION.....                                                                                | 4                  |
| VII. OVERVIEW .....                                                                                                           | 6                  |
| A. Level of Ordinary Skill .....                                                                                              | 6                  |
| B. Alleged Invention.....                                                                                                     | 6                  |
| 1. The Application for the ‘430 Patent Lacks Written<br>Description Support for the Challenged Claims .....                   | 8                  |
| 2. ‘343 Application Does Not Disclose Br <sub>2</sub> , HBr, Bromide<br>Compound, or a Combination Thereof Added to Coal..... | 9                  |
| (a) ‘343 Application Disclosure.....                                                                                          | 9                  |
| (b) Provisional Disclosure .....                                                                                              | 10                 |

|       |                                                                                                                                                                     |    |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| 3.    | The ‘343 Application Reveals that PO Was Not in Possession of Adding a Promoter to Coal at the Time of Invention .....                                              | 14 |
| 4.    | The Priority Applications Do Not Provide Written Description Support for Br <sub>2</sub> , HBr, Bromide Compound, or a Combination Thereof Being Added to Coal..... | 16 |
| (a)   | Legal Standards for Priority Claims .....                                                                                                                           | 17 |
| (b)   | Priority Applications Do Not Provide Written Description Support.....                                                                                               | 18 |
| 5.    | The Passages Cited When Adding or Amending Claims During Prosecution Do Not Provide Written Description Support .....                                               | 21 |
| 6.    | Breaks in Priority Preclude an Earlier Filing Date for the ‘430 Patent .....                                                                                        | 23 |
| (a)   | Break in Continuity of Disclosure from Improper Incorporation by Reference of Provisional.....                                                                      | 23 |
| (b)   | Provisional was “Essential Material” to Claims of Intervening Patents 8,168,147 and 10,589,225 .....                                                                | 24 |
| C.    | State of the Art .....                                                                                                                                              | 27 |
| 1.    | Mercury and Halogens .....                                                                                                                                          | 27 |
| 2.    | Coal Combustion.....                                                                                                                                                | 28 |
| 3.    | EPA Regulations .....                                                                                                                                               | 28 |
| 4.    | Activated Carbon and Halogens for Mercury Removal .....                                                                                                             | 29 |
| VIII. | CLAIM CONSTRUCTION .....                                                                                                                                            | 31 |
| IX.   | THE CITED REFERENCES QUALIFY AS PRIOR ART .....                                                                                                                     | 31 |
| A.    | Downs .....                                                                                                                                                         | 31 |
| B.    | Altman.....                                                                                                                                                         | 35 |
| C.    | Nelson .....                                                                                                                                                        | 37 |

|     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |    |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| D.  | Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 38 |
| E.  | Blankinship .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 39 |
| F.  | Olson-235.....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 41 |
| X.  | OBVIOUSNESS CONSIDERATIONS.....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 41 |
| A.  | Reasons to Combine .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 41 |
| 1.  | Downs/Altman or Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 42 |
| 2.  | Downs/Altman/Nelson or Vosteen/Altman/Nelson or<br>Blankinship/Olson-235 .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 44 |
| 3.  | Blankinship/Vosteen .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 44 |
| B.  | Simultaneous Invention .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 45 |
| XI. | INDEPENDENT CLAIMS 1 AND 28–29 ARE UNPATENTABLE<br>AS ANTICIPATED OR OBVIOUS .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 46 |
| A.  | Element 1(Preamble), 28(Preamble), 29(Preamble) – “A<br>method of separating mercury from a mercury-containing<br>gas, the method comprising:” .....                                                                                                                                                                                                                                                                                                                                                                                                   | 47 |
| 1.  | Ground 1 – Downs .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 47 |
| 2.  | Ground 2 – Downs/Altman.....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 47 |
| 3.  | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 47 |
| 4.  | Ground 4 –Blankinship .....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 47 |
| 5.  | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 47 |
| B.  | Element 1(a), 28(a), 29(a) – “combusting coal in a<br>combustion chamber, to provide the mercury-containing<br>gas, [wherein the mercury-containing gas comprises a<br>halogen or halide promoter comprising HBr, Br <sup>-</sup> , or a<br>combination thereof, –Cl. 28(a), 29(a)] wherein the coal<br>comprises an additive comprising Br <sub>2</sub> , HBr, a bromide<br>compound, or a combination thereof, wherein the additive<br>is added to the coal before the coal enters the combustion<br>chamber, or the combustion chamber comprises an |    |

|    |                                                                                                                                                                                                                                                                                                          |    |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
|    | additive comprising Br <sub>2</sub> , HBr, a bromide compound, or a combination thereof;” .....                                                                                                                                                                                                          | 48 |
| 1. | Grounds 1–2 – Downs, Downs/Altman.....                                                                                                                                                                                                                                                                   | 48 |
| 2. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                          | 49 |
| 3. | Ground 4 – Blankinship .....                                                                                                                                                                                                                                                                             | 50 |
| 4. | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                      | 50 |
| C. | Element 1(b), 28(b), 29(b) – “injecting a sorbent comprising activated carbon into the mercury-containing gas downstream of the combustion chamber [such that the activated carbon reacts with the halogen or halide promoter in the mercury-containing gas to form a promoted sorbent–cl. 29(b)];”..... | 51 |
|    | Element 1(c), 28(c), 29(c) – “contacting mercury in the mercury-containing gas with the [promoted–cl. 29(c)] sorbent; and” .....                                                                                                                                                                         | 51 |
|    | Element 1(d), 28(d), 29(d) – “separating the [promoted–cl. 29(d)] sorbent contacted with the mercury from the mercury-containing gas” .....                                                                                                                                                              | 51 |
| 1. | Ground 1 – Downs .....                                                                                                                                                                                                                                                                                   | 51 |
| 2. | Ground 2 – Downs/Altman.....                                                                                                                                                                                                                                                                             | 52 |
| 3. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                          | 52 |
| 4. | Ground 4 – Blankinship .....                                                                                                                                                                                                                                                                             | 53 |
| 5. | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                      | 54 |
| D. | Element 29(e) – “measuring the mercury content of the mercury-containing gas; and” .....                                                                                                                                                                                                                 | 54 |
|    | Element 29(f) – “modifying, in response to the measured mercury content,.....                                                                                                                                                                                                                            | 54 |
|    | an injection rate of injecting the sorbent into the mercury-containing gas, .....                                                                                                                                                                                                                        | 54 |

|                                                                                                                                                                                                                                                                                                                                                                                                                                                             |    |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| an amount of the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, added to the coal or the combustion chamber, or.....                                                                                                                                                                                                                                                                                                                | 54 |
| a combination thereof.”.....                                                                                                                                                                                                                                                                                                                                                                                                                                | 54 |
| 1. Ground 2 – Downs/Altman.....                                                                                                                                                                                                                                                                                                                                                                                                                             | 54 |
| 2. Ground 3 – Vosteen/Altman.....                                                                                                                                                                                                                                                                                                                                                                                                                           | 55 |
| 3. Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                      | 56 |
| XII. CLAIMS DEPENDING FROM CLAIM 1 ARE UNPATENTABLE .....                                                                                                                                                                                                                                                                                                                                                                                                   | 56 |
| A. Claim 2 – “the coal comprises the additive comprising the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber.” .....                                                                                                                                                                                                                         | 56 |
| 1. Grounds 1–2 – Downs, Downs/Altman.....                                                                                                                                                                                                                                                                                                                                                                                                                   | 56 |
| 2. Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                          | 56 |
| 3. Ground 4 – Blankinship .....                                                                                                                                                                                                                                                                                                                                                                                                                             | 56 |
| 4. Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                      | 57 |
| B. Claim 4 – “the coal is combusted in the combustion chamber at a coal-combustion facility, wherein the additive comprising the Br <sub>2</sub> , HBr, bromide compound, or combination thereof, is added to the coal before the coal enters the combustion chamber, wherein the addition of the additive comprising the Br <sub>2</sub> , HBr, bromide compound, or combination thereof, to the coal is performed at the coal-combustion facility.” ..... | 57 |
| 1. Grounds 1–2 – Downs, Downs/Altman.....                                                                                                                                                                                                                                                                                                                                                                                                                   | 57 |
| 2. Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                          | 57 |
| 3. Ground 4 – Blankinship .....                                                                                                                                                                                                                                                                                                                                                                                                                             | 57 |
| 4. Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                      | 57 |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |    |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| C. | Claim 6 – “the combustion chamber is an electric utility coal combustion chamber.”.....                                                                                                                                                                                                                                                                                                                                                                        | 58 |
| 1. | Ground 1 – Downs .....                                                                                                                                                                                                                                                                                                                                                                                                                                         | 58 |
| 2. | Ground 2 – Downs/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                  | 58 |
| 3. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                | 58 |
| 4. | Ground 4 – Blankinship .....                                                                                                                                                                                                                                                                                                                                                                                                                                   | 58 |
| 5. | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                            | 58 |
| D. | Claims 8–9 – “the coal comprises a [subbituminous–cl. 8; lignite–cl. 9] coal.....                                                                                                                                                                                                                                                                                                                                                                              | 59 |
| 1. | Grounds 1-2 – Downs, Downs/Altman.....                                                                                                                                                                                                                                                                                                                                                                                                                         | 59 |
| 2. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                | 59 |
| 3. | Ground 4 – Blankinship .....                                                                                                                                                                                                                                                                                                                                                                                                                                   | 59 |
| 4. | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                                                                                                                                                                                                                                                            | 59 |
| E. | Claims 10, 12 – “[measuring the mercury content of the mercury-containing gas; and–Cl. 10] modifying, in response to [a–cl. 12] [the–cl. 10] measured mercury content [of the mercury-containing gas–cl. 10], an injection rate of injecting the sorbent into the mercury-containing gas, an amount of the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, added to the coal or the combustion chamber, or a combination thereof.”..... | 60 |
| 1. | Ground 2 – Downs/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                  | 60 |
| 2. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                                                                                                                                                                                                                                                | 60 |
| 3. | Ground 5 – Blankinship/Vosteen or Blankinship/ Olson-235.....                                                                                                                                                                                                                                                                                                                                                                                                  | 60 |
| F. | Claim 13 – “the mercury-containing gas comprises about 1 g to about 30 g of the element bromine per 100 g of the sorbent.” .....                                                                                                                                                                                                                                                                                                                               | 61 |

|    |                                                                                                                                                                                                              |    |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| G. | Claim 14 – “the sorbent contacted with the mercury comprises the element bromine and mercury” .....                                                                                                          | 62 |
| 1. | Ground 2 – Downs/Altman or Downs/Altman/Nelson .....                                                                                                                                                         | 62 |
| 2. | Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson .....                                                                                                                                                     | 62 |
| 3. | Ground 5 – Blankinship/Vosteen or Blankinship/Olson-235 .....                                                                                                                                                | 63 |
| H. | Claims 15–16 – “removing greater than 70 wt % of the mercury in the mercury-containing gas [with the sorbent–Cl. 16].” .....                                                                                 | 63 |
| 1. | Ground 1 – Downs .....                                                                                                                                                                                       | 63 |
| 2. | Ground 2 – Downs/Altman .....                                                                                                                                                                                | 64 |
| 3. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                              | 64 |
| 4. | Ground 4 – Blankinship .....                                                                                                                                                                                 | 64 |
| 5. | Ground 5 – Blankinship/Vosteen .....                                                                                                                                                                         | 65 |
| I. | Claim 17 – “the sorbent in the mercury-containing gas comprises about 1 g to about 30 g of the added Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, per 100 g of the sorbent.” ..... | 65 |
| 1. | Ground 2 – Downs/Altman or Downs/Altman/Nelson .....                                                                                                                                                         | 66 |
| 2. | Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson .....                                                                                                                                                     | 66 |
| 3. | Ground 5 – Blankinship/Olson-235 .....                                                                                                                                                                       | 67 |
| J. | Claim 18 – “the Br <sub>2</sub> , HBr, or the bromide compound is contacted with the sorbent in vapor form, gaseous form, liquid form, or in an organic solvent.” .....                                      | 67 |
| 1. | Grounds 1–2 – Downs, Downs/Altman .....                                                                                                                                                                      | 67 |
| 2. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                              | 68 |
| 3. | Ground 4 – Blankinship .....                                                                                                                                                                                 | 68 |

|    |                                                                                                                                                                                                                                |    |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| 4. | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                            | 68 |
| K. | Claim 19 – “the activated carbon comprises powdered activated carbon, granular activated carbon, or a combination thereof.” .....                                                                                              | 68 |
| 1. | Ground 1 – Downs .....                                                                                                                                                                                                         | 68 |
| 2. | Ground 2 – Downs/Altman.....                                                                                                                                                                                                   | 69 |
| 3. | Ground 3 – Vosteen/Altman .....                                                                                                                                                                                                | 69 |
| 4. | Ground 4 – Blankinship .....                                                                                                                                                                                                   | 69 |
| 5. | Ground 5 – Blankinship/Vosteen.....                                                                                                                                                                                            | 69 |
| L. | Claim 20 – “the sorbent injected into the mercury-containing gas is a sorbent obtained by contacting a sorbent with a halogen or halide promoter prior to the injection of the sorbent into the mercury-containing gas.” ..... | 70 |
| 1. | Ground 2 – Downs/Altman/Nelson .....                                                                                                                                                                                           | 70 |
| 2. | Ground 3 – Vosteen/Altman/Nelson.....                                                                                                                                                                                          | 70 |
| 3. | Grounds 4–5 – Blankinship, Blankinship/Vosteen or Blankinship/Olson-235 .....                                                                                                                                                  | 71 |
| M. | Claim 21 – “the sorbent injected into the mercury-containing gas is free of contact with a halogen or halide promoter prior to injection of the sorbent into the mercury-containing gas.” .....                                | 71 |
| 1. | Ground 1 – Downs .....                                                                                                                                                                                                         | 71 |
| 2. | Ground 2 – Downs/Altman or Downs/Altman/Nelson .....                                                                                                                                                                           | 71 |
| 3. | Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson.....                                                                                                                                                                        | 72 |
| 4. | Grounds 4–5 – Blankinship or Blankinship/Vosteen .....                                                                                                                                                                         | 72 |
| N. | Claim 23 – “the mercury-containing gas is a flue gas.” .....                                                                                                                                                                   | 72 |
| 1. | Grounds 1-2 – Downs, Downs/Altman or Downs/Altman/Nelson.....                                                                                                                                                                  | 72 |

|       |                                                                                                                                                                   |    |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| 2.    | Ground 2 – Vosteen/Altman or Vosteen/Altman/Nelson .....                                                                                                          | 73 |
| 3.    | Grounds 4-5 – Blankinship or Blankinship/Vosteen .....                                                                                                            | 73 |
| O.    | Claim 24 – “the injection of the sorbent into the mercury-containing gas occurs upstream of a particulate separator, a scrubber, or a combination thereof.” ..... | 73 |
| 1.    | Ground 1 – Downs .....                                                                                                                                            | 73 |
| 2.    | Ground 2 – Downs/Altman or Downs/Altman/Nelson .....                                                                                                              | 73 |
| 3.    | Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson .....                                                                                                          | 75 |
| 4.    | Grounds 4–5 – Blankinship or Blankinship/Vosteen .....                                                                                                            | 75 |
| P.    | Claim 26 – “a halide sorbent enhancement additive comprises the added Br <sub>2</sub> , HBr, bromide compound, or combination thereof.” .....                     | 75 |
| 1.    | Grounds 1–2 – Downs or Downs/Altman .....                                                                                                                         | 75 |
| 2.    | Ground 3 – Vosteen/Altman .....                                                                                                                                   | 76 |
| 3.    | Ground 4 – Blankinship .....                                                                                                                                      | 76 |
| 4.    | Ground 5 – Blankinship/Vosteen .....                                                                                                                              | 76 |
| XIII. | CONCLUSION .....                                                                                                                                                  | 77 |

## TABLE OF AUTHORITIES

### Cases

|                                                                                                                             |        |
|-----------------------------------------------------------------------------------------------------------------------------|--------|
| <i>Acceleration Bay, LLC v. Activision Blizzard Inc.</i> , 908 F.3d 765 (Fed. Cir. 2018).....                               | 41     |
| <i>Amgen Inc. v. Sanofi</i> , 872 F.3d 1367 (Fed. Cir. 2017) .....                                                          | 32     |
| <i>Ariad Pharm., Inc. v. Eli Lilly &amp; Co.</i> , 598 F.3d 1336 (Fed. Cir. 2010).....                                      | 13     |
| <i>Becton, Dickinson &amp; Co. v. B. Braun Melsungen AG</i> , IPR2017–01586, Paper 8 at 17–18 (Dec. 15, 2017) .....         | 5      |
| <i>Callaway Golf Co. v. Acushnet Co.</i> , 576 F.3d 1331 (Fed. Cir. 2009).....                                              | 23     |
| <i>Dynamic Drinkware, LLC v. Nat’l Graphics, Inc.</i> , 800 F.3d 1375 (Fed. Cir. 2015) .....                                | 32     |
| <i>Geo. M. Martin Co. v. Alliance Mach. Sys. Int’l LLC</i> , 618 F.3d 1294 (Fed. Cir. 2010) .....                           | 46     |
| <i>In re Applied Materials, Inc.</i> , 692 F.3d 1297 (Fed. Cir. 2012).....                                                  | 62, 66 |
| <i>In re Riggs</i> , 131 F.4 <sup>th</sup> 1377 (Fed. Cir. 2025).....                                                       | 32     |
| <i>Koninklijke Philips N.V. v. Google LLC</i> , 948 F.3d 1330 (Fed. Cir. 2020).....                                         | 27     |
| <i>Lockwood v. Am. Airlines, Inc.</i> , 107 F.3d 1565 (Fed. Cir. 1997).....                                                 | 17     |
| <i>Medtronic, Inc. v. Teleflex Innov. SARL</i> , 70 F.4 <sup>th</sup> 1331 (Fed. Cir. 2023).....                            | 46     |
| <i>Midwest Energy Emissions Corp. v. Ameren, Inc. et al.</i> , Case No. 4:24-cv-00980 (E.D. Mo.).....                       | 1      |
| <i>Midwest Energy Emissions Corp. v. Arthur J Gallagher &amp; Co., et al.</i> , No. 1:19-cv-01334-RGA (D. Del.).....        | 2, 23  |
| <i>Midwest Energy Emissions Corp. v. Berkshire Hathaway Energy Company et al.</i> , Case No. 4:24-cv-00243 (S.D. Iowa)..... | 1      |
| <i>Midwest Energy Emissions Corporation v. Tucson Electric Power Company et al.</i> , Case No. 3:24-CV-8145 (D. Ariz) ..... | 1      |

|                                                                                                                              |        |
|------------------------------------------------------------------------------------------------------------------------------|--------|
| <i>NRG Energy, Inc. et al. v. Midwest Energy Emissions Corp.</i> , IPR2020-00832,<br>Paper 17 (P.T.A.B. Oct. 26, 2020) ..... | 2      |
| <i>PowerOasis, Inc. v. T-Mobile USA, Inc.</i> , 522 F.3d 1299 1304–05 (Fed. Cir.<br>2008) .....                              | 16, 17 |
| <i>Trustees of Columbia Univ. v. Illumina</i> , 620 Fed.Appx 916 (Fed. Cir. 2015) .....                                      | 47     |
| <i>Zenon Envtl., Inc. v. U.S. Filter Corp.</i> , 506 F.3d 1370 (Fed. Cir. 2007) .....                                        | 24     |

## **Statutes**

|                       |        |
|-----------------------|--------|
| 35 U.S.C. § 102 ..... | passim |
| 35 U.S.C. § 314 ..... | 4      |
| 35 U.S.C. § 325 ..... | 5      |

## **Other Authorities**

|                         |       |
|-------------------------|-------|
| M.P.E.P. § 201.08 ..... | 5, 16 |
|-------------------------|-------|

## LISTING OF EXHIBITS

| <b>Exhibit No.</b> | <b>Exhibit Description</b>                                                                                                                                                                                                                           |
|--------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1001               | United States Patent No. 10,668,430 ( <b>“430 Patent”</b> )                                                                                                                                                                                          |
| 1002               | Declaration of Dr. Radisav Vidic                                                                                                                                                                                                                     |
| 1003               | Curriculum Vitae of Dr. Radisav Vidic                                                                                                                                                                                                                |
| 1004               | U.S. Patent Publication No. US 2008/0107579 (May 8, 2008) ( <b>“Downs”</b> )                                                                                                                                                                         |
| 1005               | U.S. Provisional Patent Application No. 60/555,353 (filed Mar. 22, 2004) ( <b>“Downs-Provisional”</b> )                                                                                                                                              |
| 1006               | Redline comparison between U.S. Patent Publication No. US 2008/0107579 (Downs, EX1004) and U.S. Provisional Patent Application No. 60/555,353 (Downs-Provisional, EX1005) using Downs-Provisional as the original version ( <b>“Downs-Redline”</b> ) |
| 1007               | U.S. Patent No. 5,827,352 (Oct. 27, 1998) ( <b>“Altman”</b> )                                                                                                                                                                                        |
| 1008               | U.S. Patent Pub. No. 2004/0003716 to Nelson (published Jan. 8, 2004) ( <b>“Nelson”</b> )                                                                                                                                                             |
| 1009               | U.S. Provisional Patent Application No. 60/377,790 (filed May 6, 2002) ( <b>“Nelson-Provisional”</b> )                                                                                                                                               |
| 1010               | Redline comparison between U.S. Patent Pub. No. 2004/0003716 (Nelson, EX1008) and U.S. Provisional Patent Application No. 60/377,790 (Nelson-Provisional, EX1009) using Nelson-Provisional as the original version ( <b>“Nelson-Redline”</b> )       |
| 1011               | US Patent Publication No. 2004/0013589 (Jan. 22, 2004) ( <b>“Vosteen”</b> )                                                                                                                                                                          |
| 1012               | Steve Blankinship, “A Variety of Hg Capture Solutions Are Available,” Power Engineering, Vol. 113, Issue 6, (Jan. 6, 2009) ( <b>“Blankinship”</b> )                                                                                                  |
| 1013               | U.S. Patent No. 8,652,235 (Feb. 18, 2014) ( <b>“Olson-235”</b> )                                                                                                                                                                                     |
| 1014               | S. Julien et al., “The Effect of Halides on Emissions from Circulating Fluidized Bed Combustion of Fossil Fuels,” Fuel, 75(14):1644–1663 (1996) ( <b>“Julien”</b> )                                                                                  |
| 1015               | Hawley’s Condensed Chemical Dictionary, (Van Nostrand Reinhold, 13 <sup>th</sup> Ed.), Definition of “Compound,” 291 (1997)                                                                                                                          |
| 1016               | Hawley’s Condensed Chemical Dictionary, (Van Nostrand Reinhold, 13 <sup>th</sup> Ed.), Definitions of “Alkaline-Earth Metals,” “Calcium Hydroxide” and “Lime, Hydrated,” 33, 196, 671-672 (1997)                                                     |
| 1017               | U.S. Provisional Application No. 60/605,640 as filed with U.S. Patent and Trademark Office (USPTO) ( <b>“the Provisional”</b> )                                                                                                                      |
| 1018               | U.S. Application No. 11/209,163 as filed with USPTO ( <b>“163 Application”</b> )                                                                                                                                                                     |

| <b>Exhibit No.</b> | <b>Exhibit Description</b>                                                                                           |
|--------------------|----------------------------------------------------------------------------------------------------------------------|
| 1019               | U.S. Application No. 12/201,595 as filed with USPTO (“ <b>‘595 Application’</b> )                                    |
| 1020               | U.S. Application No. 12/419,219 as filed with USPTO (“ <b>‘219 Application’</b> )                                    |
| 1021               | U.S. Application No. 13/427,665 as filed with USPTO (“ <b>‘665 Application’</b> )                                    |
| 1022               | U.S. Application No. 13/966,768 as filed with USPTO (“ <b>‘768 Application’</b> )                                    |
| 1023               | U.S. Application No. 14/318,270 as filed with USPTO (“ <b>‘270 Application’</b> )                                    |
| 1024               | U.S. Application No. 14/712,558 as filed with USPTO (“ <b>‘558 Application’</b> )                                    |
| 1025               | U.S. Application No. 15/951,970 as filed with USPTO (“ <b>‘970 Application’</b> )                                    |
| 1026               | File History for United States Patent No. 10,668,430 (U.S. Application No. 15/974,343) (“ <b>‘343 Application’</b> ) |
| 1027               | Reserved                                                                                                             |
| 1028               | Redline comparison between U.S. Application No. 11/209,163 and 12/201,595                                            |
| 1029               | Redline comparison between U.S. Application No. 12/201,595 and 12/419,219                                            |
| 1030               | Redline comparison between U.S. Application No. 12/419,219 and 13/427,665                                            |
| 1031               | Redline comparison between U.S. Application No. 13/427,665 and 13/966,768                                            |
| 1032               | Redline comparison between U.S. Application No. 13/966,768 and 14/318,270                                            |
| 1033               | Redline comparison between U.S. Application No. 14/318,270 and 14/712,558                                            |
| 1034               | Redline comparison between U.S. Application No. 14/712,558 and 15/951,970                                            |
| 1035               | Redline comparison between U.S. Application No. 15/951,970 and 15/974,343                                            |
| 1036               | Reserved                                                                                                             |
| 1037               | US Patent Publication No. US 2018/0280870A1 (“ <b>Olson-870’</b> )                                                   |
| 1038               | Institution Decision, IPR2020–00832, Patent 10,343,114 (“ <b>832 DI’</b> )                                           |
| 1039               | Institution Decision, IPR2020–00834, Patent 10,343,114 (“ <b>834 DI’</b> )                                           |

| Exhibit No. | Exhibit Description                                                                                                                                                                                                                                                                                                                                |
|-------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1040        | Oxtoby et al., PRINCIPLES OF MODERN CHEMISTRY, 4 <sup>th</sup> ed (Saunders College Publishing: 1999) ( <b>“Oxtoby”</b> )                                                                                                                                                                                                                          |
| 1041        | Evan J. Granite et al., “Sorbents for Mercury Removal from Flue Gas,” DOE/FETC/TR–98–01, U.S. Department of Energy (Jan. 1998) ( <b>“Granite”</b> )                                                                                                                                                                                                |
| 1042        | Babcock & Wilcox, STEAM: ITS GENERATION AND USE, 40th ed. (The Babcock & Wilcox Company: 1992) ( <b>“B&amp;W: Steam”</b> )                                                                                                                                                                                                                         |
| 1043        | U.S. EPA, AP–42: External Combustion Sources, Chapter 1: Fifth Edition, Volume I (Sep. 1998), available at <a href="https://www3.epa.gov/ttn/chief/ap42/ch01/index.html">https://www3.epa.gov/ttn/chief/ap42/ch01/index.html</a> (last visited Apr 10, 2020) ( <b>“Chapter 1 of AP–42”</b> )                                                       |
| 1044        | Thomas J. Feeley, et al., “A Review of DOE/NETL’s Mercury Control Technology R&D Program for Coal-Fired Power Plants,” <i>DOE/NETL &amp; g R&amp;D Program Review</i> (April 2003) ( <b>“Feeley”</b> )                                                                                                                                             |
| 1045        | Clean Air Mercury Rule: Basic Information, available at <a href="https://web.archive.org/web/20050920005951/http://www.epa.gov/mercuryrule/basic.htm">https://web.archive.org/web/20050920005951/http://www.epa.gov/mercuryrule/basic.htm</a> ( <b>“Clean Air Mercury Rule”</b> )                                                                  |
| 1046        | EPA, “Mercury Study Report to Congress Volume VIII: An Evaluation of Mercury Control Technologies and Costs,” EPA Report No. EPA–452/R–97–010 (Dec. 1997), available at <a href="https://www3.epa.gov/airtoxics/112nmerc/volume8.pdf">https://www3.epa.gov/airtoxics/112nmerc/volume8.pdf</a> ( <b>“EPA 1997 Mercury Study Report Vol. VIII”</b> ) |
| 1047        | Deposition Transcript of Edwin Olson (Aug. 26, 2022) (excerpted), taken in Midwest Energy Emissions Corp., et al. v. Arthur J. Gallagher & Co., et al., No. 1:19-cv-01334-CJB.                                                                                                                                                                     |
| 1048        | Deposition Transcript of Michael Holmes (Aug. 24, 2022) (excerpted), taken in Midwest Energy Emissions Corp., et al. v. Arthur J. Gallagher & Co., et al., No. 1:19-cv-01334-CJB.                                                                                                                                                                  |
| 1049        | U.S. Patent No. 1,984,164 to Stock et al. (issued Dec. 11, 1934) ( <b>“Stock”</b> )                                                                                                                                                                                                                                                                |
| 1050        | B.R. Puri, <i>Surface Complexes on Carbons</i> , in CHEMISTRY AND PHYSICS OF CARBON 191 (Philip L. Walker, ed.) (Marcel Dekker: 1970) ( <b>“Puri”</b> )                                                                                                                                                                                            |
| 1051        | Roop Chand Bansal, et al., ACTIVE CARBON (Marcel Dekker:1988) 482 pages ( <b>“Bansal”</b> )                                                                                                                                                                                                                                                        |
| 1052        | Frank E. Huggins et al., “XAFS Examination of Mercury Sorption on Three Activated Carbons,” <i>Energy &amp; Fuels</i> 1999(13), p. 114–121 (1999) ( <b>“XAFS”</b> )                                                                                                                                                                                |

| Exhibit No. | Exhibit Description                                                                                                                                                                                                                                                                                  |
|-------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1053        | Charlene R. Crocker et al., “Mercury Control with the Advanced Hybrid Particulate Collector Technical Progress Report,” U.S. DOE–NETL (Nov. 2003) ( <b>“Crocker”</b> )                                                                                                                               |
| 1054        | C. Eckberg et al., “Mercury Control Evaluation of Halogen Injection into a Texas Lignite-Fired Boiler,” Track A, Session A3 (Mercury – Control), Presentation A3c, EUEC: 8TH ELECTRIC UTILITIES ENVIRONMENTAL CONFERENCE (Tucson, Arizona: January 25, 2005) ( <b>“Eckberg”</b> )                    |
| 1055        | US Patent Publication No. 2006/0048646 (Mar. 9, 2006) ( <b>“Olson-646”</b> )                                                                                                                                                                                                                         |
| 1056        | Vosteen, B. W. et al.: Mercury-Related Chemistry in Waste Incineration and Thermal Process Flue Gases. Poster, Air Quality IV Conference. September 22nd – 24th, 2003, Arlington VA. ( <b>“Vosteen poster”</b> )                                                                                     |
| 1057        | “Mercury Reduction Technology Shows Promise for Texas Lignite,” Power Engineering, Vol. 109, Issue 3, (Mar. 1, 2005)                                                                                                                                                                                 |
| 1058        | J. Bustard, S. Sjostrom, et al., “Full Scale Evaluation of Sorbent Injection for Mercury Control on Coal-Fired Power Plants,” International Conference on Air Quality III, Paper No. A5–4 (Sept. 9–12, 2002: Arlington, VA) ( <b>“Bustard”</b> )                                                     |
| 1059        | Sharon Sjostrom et al., “Field Studies of Mercury Control Using Injected Sorbents,” AWMA ANNUAL MEETING, Session Ae–1b (2002) ( <b>“Sjostrom-III”</b> )                                                                                                                                              |
| 1060        | Proposed National Emission Standards for Hazardous Air Pollutants; and, in the Alternative, Proposed Standards of Performance for New and Existing Stationary Sources: Electric Utility Steam Generating Units, 69 Fed. Reg. 4652–4752 [Volume 69, No. 20] (Jan. 30, 2004) ( <b>“EPA-Proposal”</b> ) |
| 1061        | Vosteen et al., “Energy Process Engineering and Environmental Protection,” Study commissioned by the State Environmental Agency of North Rhine-Westphalia (April 22, 2004)                                                                                                                           |
| 1062        | S. Sjostrom et al., “Full Scale Evaluation of Mercury Control by Injecting Activated Carbon Upstream of a Spray Dryer and Fabric Filter,” POWER GEN CONFERENCE (Orlando, Florida: Nov. 29 – Dec. 2, 2004) ( <b>“Sjostrom-I”</b> )                                                                    |
| 1063        | Sjostrom, S., “Evaluation of Sorbent Injection for Mercury Control,” Report No. 41986R04 (Oct. 29, 2004)                                                                                                                                                                                             |
| 1064        | Sjostrom, S., “Evaluation of Sorbent Injection for Mercury Control,” Report No. 41986R05 (Feb. 2, 2005)                                                                                                                                                                                              |

| Exhibit No. | Exhibit Description                                                                                                                                                                                                                                            |
|-------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1065        | Mercury Information Clearinghouse, “Quarter 6 – Mercury Control Field Demonstrations” (Apr. 2005)                                                                                                                                                              |
| 1066        | Sharon Sjostrom, “Full Scale Evaluations of Mercury Control Technologies with PRB Coals,” Track A, Session A3 (Mercury – Control), Presentation A3b, EUEC: 8TH ELECTRIC UTILITIES ENVIRONMENTAL CONFERENCE (Tucson, Arizona: January 25, 2005) (“Sjostrom-II”) |
| 1067        | Sharon Sjostrom, “Evaluation of Sorbent Injection for Mercury Control,” Report No. 41986R08 (Aug. 2, 2005)                                                                                                                                                     |
| 1068        | Chu, P. and Porcella, D. B. “Mercury stack emissions from U.S. electric utility power plants,” Water, Air, Soil Pollution, 80, 135-144, 1995.                                                                                                                  |
| 1069        | Meij, R. “The fate of mercury in coal-fired power plants and the influence of wet flue-gas desulfurization,” Water, Air, Soil Pollution, 56, 21, 1991.                                                                                                         |
| 1070        | Galbreath, K.C. and Zygarlicke, C.J. “Mercury transformations in coal combustion flue gas,” Fuel Processing Technology, 65–66, 289–310, 2000.                                                                                                                  |
| 1071        | Institution Decision, IPR2020–00928, Patent 8,168,147 (“928 DI”)                                                                                                                                                                                               |
| 1072        | Senior, C.L., Sarofim, A.F., Zeng, T., Helble, J.J., and Mamani-Paco, R. “Gas-phase transformations of mercury in coal-fired power plants,” Fuel Processing Technology, 63, 197–213, 2000.                                                                     |
| 1073        | Sliger, R.M., Kramlich, J.C., Marinov, N.M. “Towards the development of a chemical kinetic model for the homogeneous oxidation of mercury by chlorine species,” Fuel Processing Technology, 65–66, 423–438, 2000.                                              |
| 1074        | Chang, R. and Offen, G., “Mercury Emission Control Technologies: An EPRI Synopsis,” Power Engineering, Vol. 99, No. 11, pp. 51-57, 1995.                                                                                                                       |
| 1075        | Liu, W., Vidic, R.D., Brown, T.D. “Optimization of high temperature sulfur impregnation in activated carbon for permanent sequestration of mercury,” Environmental Science Technology, 34, 483-488, 2000.                                                      |
| 1076        | Liu, W., Vidic, R.D., Brown, T.D. “Impact of flue gas conditions on mercury uptake by sulfur-impregnated activated carbon,” Environmental Science Technology, 34, 154-159, 2000.                                                                               |
| 1077        | Brief in Support of Plaintiff’s Motion for Transfer of Actions to the Southern District of Iowa, filed in <i>In re Midwest Energy Emissions Corp. Patent Litigation</i> , No. 4:24-md-1332 (S.D. Iowa).                                                        |

| <b>Exhibit No.</b> | <b>Exhibit Description</b>                                                                                                                                                                                                 |
|--------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1078               | Granite, E.J., Pennline, H.W. and Hargis, R.A. “Novel sorbents for mercury removal from flue gas,” Industrial Engineering Chemistry Research, 39, 1020-1029, 2000.                                                         |
| 1079               | Lee, S.J., Seoa, Y-C., Jurng, J., Lee, T.J. “Removal of gas-phase elemental mercury by iodine- and chlorine-impregnated activated carbons,” Atmospheric Environment, 38, 4887–4893, 2004.                                  |
| 1080               | U.S. Patent No. 5,435,980 (“ <b>Felsvang</b> ”)                                                                                                                                                                            |
| 1081               | U.S. Patent No. 6,878,358 to Vosteen                                                                                                                                                                                       |
| 1082               | Declaration of Tracey J. Olanyk (6/2/2025), authenticating various exhibits including Blankinship EX1012                                                                                                                   |
| 1083               | Expert Report of Philip J. O’Keefe, PE Regarding Infringement (Oct. 25, 2022) (excerpted), submitted by Patent Owner in Midwest Energy Emissions Corp., et al. v. Arthur J. Gallagher & Co., et al., No. 1:19-cv-01334-CJB |
| 1084               | Buschmann, J, et al., “The KNX™ Coal Additive Technology A Simple Solution for Mercury Emissions Control,” POWER GEN CONFERENCE (Las Vegas, Nevada: Dec. 6 – Dec. 8, 2005)                                                 |
| 1085               | Vassileva, S.V., et al., “Contents, modes of occurrence and origin of chlorine and bromine in coal,” Fuel 79 (2000) 903–921.                                                                                               |
| 1086               | Reserved                                                                                                                                                                                                                   |
| 1087               | Reserved                                                                                                                                                                                                                   |
| 1088               | Reserved                                                                                                                                                                                                                   |
| 1089               | Patent Owner Preliminary Response, IPR2020–00926, Patent 8,168,147 (“ <b>926 POPR</b> ”)                                                                                                                                   |

All exhibits not containing consecutive page numbers, including the prosecution history, are cited in this Petition using page numbers added by Petitioner. All other exhibits are cited by their original page or paragraph numbers.

## **TABLE OF CHALLENGED CLAIMS**

| <b>Claim Element</b> | <b>Claim Language</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|----------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1(preamble)          | 1. A method of separating mercury from a mercury-containing gas, the method comprising:                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 1(a)                 | combusting coal in a combustion chamber, to provide the mercury-containing gas, wherein<br><p style="margin-left: 40px;">the coal comprises an additive comprising Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber, or</p> <p style="margin-left: 40px;">the combustion chamber comprises an additive comprising Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof or a combination thereof;</p> |
| 1(b)                 | injecting a sorbent comprising activated carbon into the mercury-containing gas downstream of the combustion chamber;                                                                                                                                                                                                                                                                                                                                                                                                       |
| 1(c)                 | contacting mercury in the mercury-containing gas with the sorbent; and                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| 1(d)                 | separating the sorbent contacted with the mercury from the mercury-containing gas.                                                                                                                                                                                                                                                                                                                                                                                                                                          |
| 2                    | 2. The method of claim 1, wherein the coal comprises the additive comprising the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber.                                                                                                                                                                                                                                                                            |
| 3                    | 3. The method of claim 1, wherein the combustion chamber comprises the additive comprising the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof.                                                                                                                                                                                                                                                                                                                                                       |
| 4                    | 4. The method of claim 1, wherein the coal is combusted in the combustion chamber at a coal-combustion facility, wherein the additive comprising the Br <sub>2</sub> , HBr, bromide compound, or combination thereof, is added to the coal before the coal enters the combustion chamber, wherein the addition of the additive comprising the Br <sub>2</sub> , HBr, bromide compound, or combination thereof, to the coal is performed at the coal-combustion facility.                                                    |

| Claim Element | Claim Language                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 5             | 5. The method of claim 1, wherein the sorbent has a composition comprising from about 1 to about 30 grams of the element bromine per 100 grams of activated carbon.                                                                                                                                                                                                                                                                                                |
| 6             | 6. The method of claim 1, wherein the combustion chamber is an electric utility coal combustion chamber.                                                                                                                                                                                                                                                                                                                                                           |
| 7             | 7. The method of claim 1, wherein the combustion chamber is a coal combustion furnace.                                                                                                                                                                                                                                                                                                                                                                             |
| 8             | 8. The method of claim 1, wherein the coal comprises a subbituminous coal.                                                                                                                                                                                                                                                                                                                                                                                         |
| 9             | 9. The method of claim 1, wherein the coal comprises a lignite coal.                                                                                                                                                                                                                                                                                                                                                                                               |
| 10            | 10. The method of claim 1, further comprising:<br>measuring the mercury content of the mercury-containing gas; and<br>modifying, in response to the measured mercury content of the mercury-containing gas,<br>an injection rate of injecting the sorbent into the mercury-containing gas,<br>an amount of the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, added to the coal or to the combustion chamber, or<br>a combination thereof. |
| 11            | 11. The method of claim 10, wherein the measuring of the mercury content comprises continuous measurement.                                                                                                                                                                                                                                                                                                                                                         |
| 12            | 12. The method of claim 1, further comprising:<br>modifying, in response to a measured mercury content,<br>an injection rate of injecting the sorbent into the mercury-containing gas,<br>an amount of the Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, added to the coal or the combustion chamber, or                                                                                                                                  |

| Claim Element | Claim Language                                                                                                                                                                                                                                 |
|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|               | a combination thereof.                                                                                                                                                                                                                         |
| 13            | 13. The method of claim 1, wherein the mercury-containing gas comprises about 1 g to about 30 g of the element bromine per 100 g of the sorbent.                                                                                               |
| 14            | 14. The method of claim 1, wherein the sorbent contacted with the mercury comprises the element bromine and mercury.                                                                                                                           |
| 15            | 15. The method of claim 1, comprising removing greater than 70 wt % of the mercury in the mercury-containing gas.                                                                                                                              |
| 16            | 16. The method of claim 1, comprising removing greater than 70 wt % of the mercury in the mercury-containing gas with the sorbent.                                                                                                             |
| 17            | 17. The method of claim 1, wherein the sorbent in the mercury-containing gas comprises about 1 g to about 30 g of the added Br <sub>2</sub> , HBr, the bromide compound, or a combination thereof, per 100 g of the sorbent.                   |
| 18            | 18. The method of claim 1, wherein the Br <sub>2</sub> , HBr, or the bromide compound is contacted with the sorbent in vapor form, gaseous form, liquid form, or in an organic solvent.                                                        |
| 19            | 19. The method of claim 1, wherein the activated carbon comprises powdered activated carbon, granular activated carbon, or a combination thereof.                                                                                              |
| 20            | 20. The method of claim 1, wherein the sorbent injected into the mercury-containing gas is a sorbent obtained by contacting a sorbent with a halogen or halide promoter prior to the injection of the sorbent into the mercury-containing gas. |
| 21            | 21. The method of claim 1, wherein the sorbent injected into the mercury-containing gas is free of contact with a halogen or halide promoter prior to injection of the sorbent into the mercury-containing gas.                                |
| 22            | 22. The method of claim 1, wherein the combustion chamber comprises a boiler.                                                                                                                                                                  |
| 23            | 23. The method of claim 1, wherein the mercury-containing gas is a flue gas.                                                                                                                                                                   |

| <b>Claim Element</b> | <b>Claim Language</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 24                   | 24. The method of claim 1, wherein the injection of the sorbent into the mercury-containing gas occurs upstream of a particulate separator, a scrubber, or a combination thereof.                                                                                                                                                                                                                                                                                                                                                                                                                        |
| 25                   | 25. The method of claim 24, wherein the particulate separator comprises a baghouse, an electrostatic precipitator, a fabric filter, or a combination thereof.                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| 26                   | 26. The method of claim 1, wherein a halide sorbent enhancement additive comprises the added Br <sub>2</sub> , HBr, bromide compound, or combination thereof.                                                                                                                                                                                                                                                                                                                                                                                                                                            |
| 27                   | 27. The method of claim 26, wherein the sorbent enhancement additive comprises the bromide compound.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| 28(preamble)         | 28. A method of separating mercury from a mercury-containing gas, the method comprising:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
| 28(a)                | combusting coal in a combustion chamber, to provide the mercury-containing gas, wherein the mercury-containing gas comprises a halogen or halide promoter comprising HBr, Br-, or a combination thereof, wherein:<br><br>the coal comprises an additive comprising Br <sub>2</sub> , HBr, a bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber, or<br><br>the combustion chamber comprises an additive comprising Br <sub>2</sub> , HBr, a bromide compound, or a combination thereof, or<br><br>a combination thereof; |
| 28(b)                | injecting a sorbent comprising activated carbon into the mercury-containing gas downstream of the combustion chamber;                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| 28(c)                | contacting mercury in the mercury-containing gas with the sorbent; and                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| 28(d)                | separating the sorbent contacted with the mercury from the mercury-containing gas.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| 29(Preamble)         | 29. A method of separating mercury from a mercury-containing gas, the method comprising:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |

| Claim Element | Claim Language                                                                                                                                                                                                                                                                                                                                                                                       |
|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 29(a)         | combusting coal in a combustion chamber, to provide the mercury-containing gas, wherein the mercury-containing gas comprises a halogen or halide promoter comprising HBr, Br <sup>-</sup> , or a combination thereof, wherein                                                                                                                                                                        |
| 29(b)         | <p>the coal comprises an additive comprising Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber, or</p> <p>the combustion chamber comprises an additive comprising Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof, or a combination thereof;</p>                          |
| 29(c)         | injecting a sorbent comprising activated carbon into the mercury-containing gas downstream of the combustion chamber such that the activated carbon reacts with the halogen or halide promoter in the mercury-containing gas to form a promoted sorbent;                                                                                                                                             |
| 29(d)         | contacting mercury in the mercury-containing gas with the promoted sorbent; and                                                                                                                                                                                                                                                                                                                      |
| 29(e)         | separating the promoted sorbent contacted with the mercury from the mercury-containing gas;                                                                                                                                                                                                                                                                                                          |
| 29(f)         | <p>measuring the mercury content of the mercury-containing gas; and</p> <p>modifying, in response to the measured mercury content,</p> <p>an injection rate of injecting the sorbent into the mercury-containing gas,</p> <p>an amount of the Br<sub>2</sub>, HBr, the bromide compound, or a combination thereof, added to the coal or the combustion chamber, or</p> <p>a combination thereof.</p> |

## **I. INTRODUCTION**

Petitioner requests IPR of claims 1-4 and 6-29 of U.S. Patent 10,668,430 (“430 Patent”). EX1001. Dr. Radisav Vidic provided his expert declaration in support. EX1002-EX1003.

## **II. MANDATORY NOTICES UNDER 37 C.F.R. 42.8**

### **A. Real Parties-in-Interest (42.8(b)(1))**

The real parties-in-interest are the Petitioner and its parent, Ameren Corporation. No other person or entity is funding this Petition, advising on strategy for the Petition, or exercising any control over Petitioner’s decision to file the Petition or any arguments therein.

### **B. Related Matters (42.8(b)(2))**

Patent Owner (“PO”) is currently asserting the Challenged Patent in the following proceedings:

- *Midwest Energy Emissions Corp. v. Ameren, Inc. et al.*, Case No. 4:24-cv-00980 (E.D. Mo.) (“the Missouri Case”);
- *Midwest Energy Emissions Corp. v. Berkshire Hathaway Energy Company et al.*, Case No. 4:24-cv-00243 (S.D. Iowa) (“the Iowa Case”);
- *Midwest Energy Emissions Corporation v. Tucson Electric Power Company et al.*, Case No. 3:24-CV-8145 (D. Ariz) (“the Arizona Case”);
- *Midwest Energy Emissions Corporation v. Evergy, Inc., et al.*, Case No. 4:25-CV-0050 (W.D. Mo.) (“the Western Missouri Case”);
- *Midwest Energy Emissions Corporation v. Wisconsin Power and Light Company*, Case No. 3:25-CV-0026 (W.D. Wis.) (“the Wisconsin Case”);

- *In re Midwest Energy Emissions Corp. Patent Litigation*, MDL Case No. 4:24-md-3132 (S.D. Iowa) (consolidating the Missouri, Iowa, Arizona, Western Missouri, and Wisconsin Cases) (“the MDL proceeding”).

Petitioner is a defendant in the Missouri case and MDL proceeding.

PO previously asserted the Challenged Patent in the District Court for the District of Delaware in *Midwest Energy Emissions Corp. v. Arthur J Gallagher & Co., et al.*, No. 1:19-cv-01334-RGA (D. Del.) (filed July 17, 2019) (“the Delaware Litigation”).

The Board previously granted institution of IPR on two Petitions against the Challenged Patent in the following proceedings:

- *NRG Energy, Inc. et al. v. Midwest Energy Emissions Corp.*, IPR2020-00832, Paper 17 (P.T.A.B. Oct. 26, 2020) (“IPR832 Institution”);
- *NRG Energy, Inc. et al. v. Midwest Energy Emissions Corp.*, IPR2020-00834, Paper 18 (P.T.A.B. Oct. 26, 2020) (“IPR834 Institution”).

The prior IPRs and district court matters involved Midwest Energy Emissions Corp. (“ME2C”) as Patent Owner/Plaintiff. On November 7, 2024, ME2C filed a notice with the USPTO that it had changed its name to Birchtech Corp. See Reel 069187, From 0413. ME2C has indicated that it will nevertheless continue in the district court litigations under the name ME2C.

**C. Lead and Back up Counsel (42.8(b)(3))**

| <b>Lead Counsel</b>                                                                                                                                                                                               | <b>Backup Counsel</b>                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Robert M. Evans, Jr., Reg. No. 36,794<br>LEWIS RICE LLC<br>600 Washington Avenue, Suite 2500<br>St. Louis, Missouri 63101<br>T: 314-420-2748<br>E: <a href="mailto:revans@lewisrice.com">revans@lewisrice.com</a> | Michael J. Hartley, Reg. No. 67,230<br>LEWIS RICE LLC<br>600 Washington Avenue, Suite 2500<br>St. Louis, Missouri 63101<br>T: 314-444-7869<br>E: <a href="mailto:mhartley@lewisrice.com">mhartley@lewisrice.com</a><br><br>Kathleen M. Petrillo, Reg. No. 35,076<br>LEWIS RICE LLC<br>600 Washington Avenue, Suite 2500<br>St. Louis, Missouri 63101<br>T: 314-374-6623<br>E: <a href="mailto:kpetrillo@lewisrice.com">kpetrillo@lewisrice.com</a> |

Service information for lead and backup counsel is provided in the designation of lead and backup counsel, above. Petitioner consents to electronic service to lead and backup counsel, using the email addresses above.

**III. PAYMENT OF FEES**

Payment of any fees is authorized from Deposit Account No. 50-0975.

**IV. GROUND FOR STANDING**

Petitioner certifies the '430 Patent is available for *inter partes* review and Petitioner is not barred or estopped from requesting such review. This petition is being filed within one year of Petitioner being served with a complaint alleging infringement.

## **V. IDENTIFICATION OF CHALLENGED CLAIMS AND RELIEF SOUGHT**

Petitioner requests (i) review of claims 1-4 and 6-29 of the ‘430 Patent (“Challenged Claims”) on the grounds set forth below and (ii) that these claims be found unpatentable.

| <b>Ground</b> | <b>Claim(s)</b>               | <b>Basis for Unpatentability</b>                                    |
|---------------|-------------------------------|---------------------------------------------------------------------|
| 1             | 1-4, 6-9, 15-16, 18-19, 21-28 | Anticipated by Downs                                                |
| 2             | 1-4, 6-29                     | Obvious over Downs and Altman or Downs, Altman and Nelson**         |
| 3             | 1-4, 6-29                     | Obvious over Vosteen and Altman or Vosteen, Altman and Nelson**     |
| 4             | 1-4, 6-9, 15-16, 18-28        | Anticipated by Blankinship                                          |
| 5             | 1-4, 6-29                     | Obvious over Blankinship and Vosteen or Blankinship and Olson-235** |

\*\*as evidenced by Julien for claims 28-29

## **VI. THE BOARD SHOULD NOT DENY INSTITUTION**

The Board should not deny institution under 35 U.S.C. § 314(a). First, the district court proceeding in Missouri is in its early stages and was consolidated with several other lawsuits for pretrial proceedings in an MDL in the Southern District of Iowa on 12/12/2024 (MDL No. 3132). The Iowa court entered a Case Management Order on 3/7/2025, but no depositions have been taken yet and the first Markman Brief is not due until 10/10/2025. The “Ready for Trial” date is 10/12/2026, but trial will be long after that as the Missouri court will have to receive the case back and set a trial date which will require at least six additional months – particularly given

that PO has stated it intends to pursue trial against other MDL defendants before trial against Petitioner. As the Iowa Court noted in an Order filed on 5/22/2025, “...the litigation is at a relatively early stage...” Doc. [131], 6. Accordingly, a Final Written Decision here will likely be issued well before trial in any of the lawsuits once they are returned to their original venues following the conclusion of the MDL.

Second, institution should not be denied under 35 U.S.C. § 325(d), because the Examiner did not consider Blankinship during prosecution. *See Becton, Dickinson & Co. v. B. Braun Melsungen AG*, IPR2017–01586, Paper 8 at 17–18 (Dec. 15, 2017) (factors (a)–(b) and (d) indicate the same art was not presented previously to the Office). While the ’430 Patent cites Downs, Altman and Olson-235—in a list spanning *16 columns* (9 pages) of cited references—none were used in a substantive rejection.<sup>1</sup> *Id.* at 17–18 (factors (a)–(d)). Further, Downs and Olson-235 are dated after the alleged earliest ’430 Patent priority date, and patent examiners accept applicant’s asserted priority date without making findings concerning priority. M.P.E.P. § 201.08.

---

<sup>1</sup> Olson–235 was only cited for obviousness–type double patenting, with the examiner stating that Olson–235 discloses the current claims “except for a mixture of coal and an additive the additive comprising a bromide compound that has been added to the coal.” EX1026, 281.

## VII. OVERVIEW

### A. Level of Ordinary Skill

A person of ordinary skill in the art at the time of the invention (“POSITA”) would have at least a bachelor’s degree in chemical, mechanical, or environmental engineering or a related field of study, and at least two years of experience with investigating, researching, or implementing pollution control in natural gas or coal power generation plants and/or industrial waste incineration. EX1002, ¶ 33.

### B. Alleged Invention

The ‘430 Patent relates to removal of mercury from a flue gas. EX1001, 1:39–44. It admits that known “mercury control methods” included “injection of fine sorbent particles into a flue gas duct” such as “activated carbon.” EX1001, 2:1–7.

The ‘430 Patent discloses preparing a **promoted** sorbent **outside** the mercury-containing flue gas as shown in Figure 1, below,<sup>2</sup> and then injecting the promoted sorbent **into** the flue gas **downstream** from the combustion chamber as shown in Figure 3, below. Figure 3 is thus limited to injections into flue gas.


Each independent claim requires both (1) adding particular bromine-containing species (*i.e.*, Br<sub>2</sub>, HBr, bromide compound, or a combination thereof) to coal and/or the combustion chamber and (2) injecting activated carbon sorbent to the mercury-containing gas. EX1001, Claims 1, 28-29. There is no support for adding


---

<sup>2</sup> This version of Figure 1 is what was originally filed, as explained in § VII.B.5.b.

a promoter to coal in the application as filed or in any of its priority applications.

EX1002, ¶¶ 36, 63-103.





EX1001, Figures 1, 3 (green, blue, purple and red annotations added).

# **1. The Application for the ‘430 Patent Lacks Written Description Support for the Challenged Claims**

The Challenged Claims are not entitled to a priority date before the 5/8/2018 filing date of the application for the ‘430 Patent (“the ‘343 Application”) for lack of written description support<sup>3</sup>. Each independent claim requires coal, a combustion chamber, or both comprising added “Br<sub>2</sub>, HBr, a bromide compound, or a

<sup>3</sup> Petitioner is asserting this lack of written description to determine the priority date. Petitioner is not asserting invalidity under Section 112, an issue outside the scope of an IPR.

combination thereof.” EX1001, Claims 1, 28-29. There is no disclosure of each such promoter being added to coal in the ‘343 Application.

**2. ‘343 Application Does Not Disclose Br<sub>2</sub>, HBr, Bromide Compound, or a Combination Thereof Added to Coal**

***(a) ‘343 Application Disclosure***

“Coal” is described in the ‘343 Application generally as a fossil fuel (EX1026, second page, 2:1-2; citations are to original page:line numbers in specification at pages 11-71 of EX1026) or in the context of coal combustion facilities or coal combustion flue gas (EX1026, 2:10-17; 9:17-18; 17:24-26; 35:1-3), and in examples where subbituminous, lignite or pulverized coal is introduced to a combustor (EX1026, 27:1-5, 26-29; 28:2-5; 32:6-8, 13-14). None of these disclosures describe promoter compounds such as Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof added to coal.

“Additive” is described generally in the ‘343 Application as “sorbent enhancement additives” (EX1026, 3:13-16), “optional additives discussed herein” (EX1026, 10:8-11), “additive to a treatment facility” (EX1026, 20:30-31) and “additive-sorbent ratios” (EX1026, 21:6-9). None of these disclosures describe a promoter added to coal as in the Challenged Claims.

In Example 10, “the halogen/halide promoted carbon sorbent was injected into the flue gas after the boiler. In general, however, the inventive sorbent can be injected where desired (e.g., before, after or within the boiler.)” EX1026, 32:9-12.

This disclosure is similar to the description for Figure 11 and it indicates the promoted sorbent was injected into the flue gas downstream from the boiler, but could be injected before or within the boiler. Promoted sorbent injection before the boiler is not a disclosure of a promoter added to coal. Nor is it a disclosure of adding Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof before the boiler because, in making the promoted sorbent, these promoters react with the activated carbon and no longer exist in the form of Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof.

PO asserted that a disclosure of “multiple injection points” for the promoted carbon sorbents provided support for adding a promoter to coal in an IPR for the ‘114 Patent. The Board properly rejected that argument because the “multiple injection points” disclosure refers to injection points in the flue gas stream, not multiple injection points at different points in the process, such as before combustion. EX1038, 28–29; EX1019, [0056]. *See also* EX1026, 14:3-5.

Thus, the ‘343 Application does not disclose a promoter added to coal.

***(b) Provisional Disclosure***

The ‘343 Application copies the entire disclosure of its earliest related application, 60/605,640 (“the Provisional”) into the specification. EX1001, 24:8–35:44. The Provisional section mentions mercury removal from “coal-fired utility or synthesis gas” (EX1026, 44:1-3; EX1017, 6), mercury within coal (EX1026, 44:17-20, 26-27; EX1017, 6), coal combustion flue gas (EX1026, 44:24-27; 46:1-4;

EX1017, 7), and a facility fired with lignite coal (EX1026, 54:9-10; EX1017, 14). None of these disclosures describe promoter compounds added to coal.

The Provisional includes Figure 2 showing a “coal fueled facility” burning “pulverized coal” where “additive can be injected where desired (e.g., before, after or within the boiler).” EX1026, 52:6-14, Figure 11; EX1017, 12, Figure 2. However, the term “additive” is undefined there. And additive injection “before, after or within the boiler” is not a disclosure of additive injection to coal. There are common system components that supply an additive to the airstream before, after or within a boiler (and not to the coal) such as a separate feed inlet, a secondary-air system, or a low-No<sub>x</sub> overfire air system. EX1002, 80.




FIG. 11

The rest of the Provisional is no help to PO, either. The Provisional provides “an outline of [15] examples of the invention.” EX1026, 38:15; EX1017, 2. But none discloses applying Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof as an “additive” to coal.

More particularly, Examples 1–4 disclose a modified carbon sorbent prepared by reacting carbon with a Br<sub>2</sub> solution, a Br<sub>2</sub> gas, an HBr solution or an HBr gas. EX1026, 38:18-25; 40:14-18; 40:28-41:3; 41:9-13); EX1017, 2–3. Provisional Examples 5 and 6 further include a sulfur or selenium reagent when preparing the promoted sorbent. EX1026, 41:17-25; EX1017, 4. Example 7 treats “carbon with a Group V or VI element combined with Group VII element, such as PBr<sub>3</sub>.” EX1026, 41:27-31; EX1017, 4. These Provisional Examples 1-7 disclose methods of preparing a promoted sorbent by reacting a carbon sorbent with the promoter. These Examples do not disclose applying the promoted sorbent to coal or applying Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof to coal.

Provisional Examples 1-3 may include an “additional promoting substance” in the Br<sub>2</sub> solution, Br<sub>2</sub> gas, or HBr solution used in preparing the promoted sorbent. EX1026, 38:22-23; 40:5-12, 25-26; 41:6-7; EX1017, 2-3. This additional promoter can be HBr. EX1026, 40:8; EX1017, 3. This additional substance is outlined under “1E” and “same additives as 1E” without indicating what the “additive” references. Again, this additional substance is used in preparing a promoted sorbent and not as an “additive” to coal, and only HBr and not Br<sub>2</sub> is disclosed. During ‘430 Patent prosecution, PO distinguished HBr from Br<sub>2</sub>. EX1026, 472, ¶ 17. A disclosure of one species (HBr) in the Provisional does not support the genus of “bromide compounds.” *See Ariad Pharm., Inc. v. Eli Lilly & Co.*, 598 F.3d 1336, 1350 (Fed. Cir. 2010). EX1002, ¶¶ 85-87.

Provisional Example 8 describes injecting the promoted sorbents of Provisional Examples 1-6 into a contaminated gas stream. EX1026, 42:1-6; EX1017, 4. Provisional Example 9 refers to the promoted sorbents as “additives (1-8)” and describes their use with sorbents to capture acid gases, further referring to these sorbents as “additives” or “additives of base chemistry.” EX1026, 42:8-19; 38:8-11; EX1017, 4, 1. Thus, Provisional Example 9 uses the term “additive” to describe sorbents. Provisional Examples 10-15 do not use the term “additive.”

As a further point, the “additive” is not the modified carbon sorbents of Provisional Examples 1–7 since Figure 11, above, separately depicts “sorbent injection,” and the figure description states “[i]n the example shown, the sorbent is injected into the flue gas after the boiler.” EX1026, 52:12-13, Figure 11; EX1017, 12, Figure 2.

The remaining mentions of “additive” in the Provisional disclosure do not disclose what the “additive” is, either. EX1026, 44:4-8; EX1017, 6 (“a combination of additives to remove pollutants”); 50:29-30; EX1017, 11 (“additive to a treatment facility”); 51:5-7; EX1017, 11 (“additive-sorbent ratios”).

Thus, the ‘343 Application fails to provide written description support for promoter compounds such as Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof being added to coal. EX1002, ¶ 63-91. Accordingly, none of the Challenged Claims have a priority date before the ‘343 Application filing date. Each reference

relied upon in Grounds 1–5 thus qualifies as prior art under the AIA and renders the Challenged Claims not patentable.

**3. The ‘343 Application Reveals that PO Was Not in Possession of Adding a Promoter to Coal at the Time of Invention**

The ‘343 Application teaches adding bromine by itself to the flue gas would not sufficiently oxidize mercury to allow easy capture by activated carbon, and so bromine was added to the activated carbon to make a promoted sorbent to add to the flue gas. EX1002, ¶¶ 72-73.

In particular, the ‘343 Application discloses:

1. Molecular bromine ( $\text{Br}_2$ ) does not react fast enough with elemental mercury to form oxidized mercury in flue gas using conventional ash control and its “reaction with hot flue gas components leave little to react with elemental mercury.” EX1026, 46:1-4, 17:19-21.
2. Elemental bromine ( $\text{Br}$ ) “is about a million times more reactive to mercury” but is in such “extremely low” concentration that it will not result in mercury oxidation in flue gas. EX1026, 46:4-7, 17:21-24.
3. A halide (*e.g.*, a hydrohalide such as  $\text{HBr}$ ) is “very much less reactive” than molecular halogen (*e.g.*,  $\text{Br}_2$ ) and “cannot therefore oxidize anything by itself.” EX1026, 46:8-12, 17:28-30.
4. The Provisional disclosure states for these reasons, “it is not obvious that a halide-halogen treated activated carbon would be effective at

oxidizing elemental mercury and provide effective capture of elemental mercury.” EX1026, 46:12-14. This Provisional disclosure was changed over time in the ‘343 Application to “[in] the conventional view therefore, a halide-salt-treated activated carbon will not effectively oxidize elemental mercury and capture elemental mercury,” recharacterizing PO’s rationale for nonobviousness of a promoted activated carbon sorbent into a “conventional view.” EX1026, 18:1-2.

A POSITA would have known that lignite or subbituminous coal contains very low amounts of bromine on the order of 1-3 ppm (median). EX1084, 1; EX1085, 905. Thus, a POSITA would have understood the ‘430 Patent’s disclosure of “extremely low” concentrations of elemental bromine (Br) being in the flue gas as meaning **native untreated coal** was being combusted in the ‘430 Patent, and **not coal to which HBr, Br<sub>2</sub>, a bromide compound or a combination thereof had been added.** EX1002, ¶ 74.

A POSITA would have known that any bromine source added to the combustion chamber would completely convert to hydrogen bromide (HBr). EX1014, 1658; EX1002, ¶ 75. Thus, had HBr, Br<sub>2</sub>, a bromide compound or a combination thereof been added to the coal before combustion, the concentration of elemental bromine (Br) would have been much higher driving a POSITA to the conclusion the named inventors never described adding a promoter to coal or to the combustion chamber. *Id.* Instead, the named inventors described a promoted

activated carbon sorbent which was introduced into the flue gas post-combustion.  
*Id.*

As the ‘430 Patent explains “adding HBr or Br<sub>2</sub> to the carbon forms a similar carbon bromide, in which the positive carbon oxidizes the mercury with the assistance of the bromide ion.” EX1026, 47:6-8. This carbon bromide results from the reaction between the promoter and activated carbon when making the promoted sorbent before the promoted sorbent is injected into the flue gas. It is not a disclosure of what occurs in the combustion chamber or of adding a promoter to coal.

**4. The Priority Applications Do Not Provide Written Description Support for Br<sub>2</sub>, HBr, Bromide Compound, or a Combination Thereof Being Added to Coal**

Grounds 1–5 of this Petition establish invalidity of the Challenged Claims in light of Downs, Altman, Nelson, Vosteen, Blankinship and Olson-235. Each of these references was published or was otherwise publicly available years before the filing date of the application for the ‘430 Patent. PO thus bears the burden to produce evidence “to prove entitlement to claim priority to an earlier filing date.” *PowerOasis, Inc. v. T-Mobile USA, Inc.*, 522 F.3d 1299, 1304–05 (Fed. Cir. 2008). Petitioner may rebut such arguments.

Notably, patent examiners generally do not make priority findings during prosecution, and generally accept applicant’s asserted priority date. *Id.* at 1305; M.P.E.P. § 201.08. Here, the examiner made no finding regarding priority to any earlier filed applications.

**(a) Legal Standards for Priority Claims**

“To receive the benefit of the filing date of an earlier application under 35 U.S.C. § 120, each application in the chain leading back to the earlier application must comply with the written description requirement of 35 U.S.C. § 112.” *Lockwood v. Am. Airlines, Inc.*, 107 F.3d 1565, 1571 (Fed. Cir. 1997). PO must prove the written description of each of the priority applications “convey[s] with reasonable clarity to those skilled in the art that, as of the filing date sought, [the inventor] was in possession of the invention. ... Entitlement to a filing date does not extend to subject matter which is not disclosed, but would be obvious over what is expressly disclosed.” *PowerOasis*, 522 F.3d at 1306.


Thus, “[t]he question is not whether a claimed invention is an obvious variant of that which is disclosed in the specification. Rather, **a prior application itself must describe an invention**, and do so in sufficient detail that one skilled in the art can clearly conclude the inventor invented the claimed invention **as of the filing date sought.**” *Lockwood*, 107 F.3d at 1571–72 (emphasis added). Thus, to claim priority back to the Provisional, PO must demonstrate that the Provisional, and all intervening applications, expressly or inherently discloses adding each of the claimed specific bromine-containing species (Br<sub>2</sub>, HBr, bromine compound and combinations thereof) to coal.

PO cannot meet this burden. Prior to May 8, 2018, a POSITA would not have concluded that the applicant was in possession of the subject matter of the

Challenged Claims because applications in the purported priority chain fail to disclose adding any type of bromine species to coal.

***(b) Priority Applications Do Not Provide Written Description Support***

The '343 Application is a descendant of the Provisional and a series of continuations and a divisional which, by definition, cannot introduce new subject matter to the prior application. *See* EX1001, 1:4–25. The following image shows the relationships between these applications:



Each priority application as filed and the file history for the '430 Patent are submitted as Exhibits EX1017-EX1026.

The disclosures in each intervening non-provisional application between the Provisional and the ‘343 Application have “coal” and “additive” disclosures as discussed in § VII.B.2, with the exception that only the 15/951,970 and ‘343 Applications include the Provisional disclosure copied into the specification. Thus, the Provisional disclosure was not included in the ‘163, ‘595, ‘219, ‘665, ‘768, ‘270, or ‘558 Applications, which are themselves essentially the same, with minor differences. *See* EX1028–EX1035 (redline comparisons of each successive non-provisional application as compared to its predecessor). Thus, the priority applications fail to provide written description support for the same reasons provided above for the ‘343 Application in § VII.B. EX1002, ¶ 98.

Indeed, the Board found in its Institution Decision in IPR2020–00832 for related U.S. Patent 10,343,114 that the first two non-provisional applications in the chain (the ‘163 and ‘595 Applications) do not disclose “(1) the addition of the promoter with the coal or the combustion chamber and (2) the injection of a sorbent material into the mercury-containing gas downstream of the combustion chamber,” both of which are required by each of the ‘430 Patent’s independent claims. EX1038, 28–29.

The Board found the disclosure as referenced in Example 10 of the ‘430 Patent where the “halogen/halide promoted carbon sorbent was injected into the flue gas after the boiler” describes “a **combination of promoter and sorbent material being added at one single point**”) (emphasis added). *Id.* The Board also considered

the disclosure in that same example that “[i]n general however, the inventive sorbent can be injected where desired (e.g., before, after, or within the boiler).” *Id.* The Board stated: “Although this describes other injection points (‘e.g., before, after, or within the boiler’), this disclosure regards the promoted sorbent material. As a result, it describes the addition of both the promoter and the sorbent material at a single point, not (1) the addition of the promoter with the coal or the combustion chamber and (2) the injection of the sorbent material into mercury-containing gas downstream of the combustion chamber.” *Id.* Thus, the Board did not find injection of a promoted sorbent before, after or within the boiler to support adding the promoter to coal and injecting the sorbent into flue gas downstream of the combustion chamber.

For all of these reasons, none of the intervening applications filed before the ‘970 Application contains such a disclosure, either.

#### **5. The Passages Cited When Adding or Amending Claims During Prosecution Do Not Provide Written Description Support**

As originally filed, the claims of the ‘343 Application covered a method of separating mercury in a mercury-containing gas by injecting a sorbent (activated carbon) **into the mercury containing coal-combustion gas (i.e. after combustion)**, wherein the sorbent is promoted in-flight with at least one promoter ( $\text{Br}_2$ ,  $\text{HBr}$ ,  $\text{Br}^-$ , or a combination thereof). EX1026, 58-60.

Applicant amended the claims to require, *inter alia*, that the promoter (Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof) is added to the coal. EX1026, 92, 585-589. *See, e.g.*, EX1001, Claim 1.

None of these amendments nor the issued claim language is supported by the specification. EX1002, ¶¶ 99-103.

Indeed, during prosecution, PO cited to Figure 11 as support for the concept “the additive is added to the coal.” *Id.* This argument fails as explained in § VII.B.2.b, above, concerning identical Figure 2 from the Provisional.

PO also cited to paragraph [0217] from the specification (US2018/0257030A1) to support “adding a promoter to coal.” Again to no avail. This paragraph corresponds to the paragraph describing Figure 2 from the Provisional as explained in § VII.B.2.b, above.

This cited paragraph and the corresponding figure does not provide written description support for adding a promoter to coal, much less adding Br<sub>2</sub>, HBr, bromine compound and combinations thereof to coal as recited in the Challenged Claims. EX1002, ¶¶ 100-103. There can be no earlier priority date.

**6. Breaks in Priority Preclude an Earlier Filing Date for the ‘430 Patent**

***(a) Break in Continuity of Disclosure from Improper Incorporation by Reference of Provisional***

The purported Provisional written description support for adding a promoter to coal, including the Provisional Figure 11 in the ‘430 Patent, was added to the ‘970 Application (and thus appeared in the subsequent ‘343 Application) in April 2018.

To incorporate another document, “the host document must identify with detailed particularity what specific material it incorporates and clearly indicate where that material is found in the various documents.” *Callaway Golf Co. v. Acushnet Co.*, 576 F.3d 1331, 1346 (Fed. Cir. 2009).

Here, four of the intervening non-provisionals between the Provisional and the ‘970 Application (*i.e.*, the ‘219, ‘665, 768 and ‘270 Applications) do not recite the Provisional in their specifications, and they only incorporate the Provisional by reference “to the extent appropriate.” EX1020-EX1023, [0001].

This limited incorporation language causes a break in the continuity of disclosure. *See Midwest Energy Emissions Corp. v. Arthur J. Gallagher*, No. 19-1334- CJB, 2023 WL 7411160, at \*3 (D. Del. Nov. 3, 2023) (holding Provisional was not properly incorporated into ‘517 Patent); *Zenon Env’tl., Inc. v. U.S. Filter Corp.*, 506 F.3d 1370, 1379, 1382 (Fed. Cir. 2007) (“The plain language expressly limits the incorporation to only relevant disclosures of the patents, indicating that

the disclosures are not being incorporated in their entirety.... thus a lack of continuity of disclosure exists in the family chain.”).

The Board previously held that the ‘219 Application “claims priority ‘to the extent appropriate’ and fails to identify with detailed particularity the specific material incorporated and fails to clear[ly] indicate where that material is found in the various documents ... This ambiguity creates an additional concern regarding the chain of priority for the ‘219 application.” EX1071, 32 (finding no priority to Provisional).

Since these four intervening applications fail to identify with detailed particularity the specific material incorporated from the Provisional and fail to clearly indicate where that material is found, there is a break in continuity of disclosure and priority that prohibits PO from introducing the Provisional disclosure into the subsequent ‘970 and ‘343 Applications or relying upon it for written description disclosure to support an earlier priority date.

***(b) Provisional was “Essential Material” to Claims of Intervening Patents 8,168,147 and 10,589,225***


Rule 1.57(d) provides that for applications filed on or after 9/21/2004 that “essential material”—which includes material that is “necessary to: provide a written description of the claimed invention”—“may be incorporated by reference, but *only* by way of incorporation by reference to a *U.S. patent or U.S. patent application publication.*” (emphasis added). The Provisional is neither, and thus

an “incorporation by reference” of the Provisional cannot provide written description support for a patent’s claims.

Two patents in the priority chain for the ‘430 Patent have claims for which the purported support derives from the Provisional.

First, claims 18-19 of U.S. Patent 8,168,147 require sorbent and bromine to be separately injected into a mercury-containing gas. The ‘219 application for the ‘147 Patent only describes combining sorbent and bromine in a transport gas such as air or nitrogen to promote the sorbent in-flight and then introduce the promoted sorbent into a mercury-containing flue gas. EX1020, [0055], Figure 3; EX1071, 29 (finding regarding the ‘147 Patent that “[t]here is no suggestion that bromine and the activated carbon are separately injected into mercury-containing flue gas”).

During prosecution, PO amended the ‘147 Patent’s Figure 1 to add the following highlighted brand-new line between activated carbon 10 and flue gas 50 without supporting description in the specification. EX1071, 30-32 (finding Figure 1 does not provide written description support for ‘147 Patent claims 18-19).



Purported support from Provisional Figure 2 would make the Provisional “essential material” to these ‘147 Patent claims in violation of 37 CFR 1.57(d), breaking the priority chain at the ‘665 Application’s 3/22/2012 filing date.

Second, claims 14 and 23 of U.S. Patent 10,589,225 require adding a promoter to coal, and adding an activated carbon (AC) sorbent free of contact with a promoter before addition to mercury-containing gas, respectively. As explained above, the ‘558 application for the ‘225 Patent does not describe adding a promoter to coal (*see* § VII.B.4.b) or adding unpromoted AC sorbent to mercury-containing gas (*see* amended ‘147 Figure 1 directly above). Purported support from Provisional Figure 2 would make the Provisional “essential material” to these ‘225 Patent claims in violation of 37 CFR 1.57(d), breaking the priority chain at the ‘970 Application’s 4/12/2018 filing date.

In sum, the ‘343 Application and its priority applications fail to provide written description support for adding any of the claimed promoters to coal as recited in the Challenged Claims. Also, breaks in priority preclude PO from proving a filing date before 4/12/2018. Accordingly, none of the Challenged Claims are entitled to a priority date before the ‘343 Application’s filing date. Each of the references relied upon in Grounds 1–5 thus qualify as prior art under the AIA and render the Challenged Claims unpatentable.

### **C. State of the Art**

The obviousness inquiry “necessarily depends on such artisan’s knowledge,” including an “assessment of the background knowledge possessed” by a POSITA. *Koninklijke Philips N.V. v. Google LLC*, 948 F.3d 1330, 1337 (Fed. Cir. 2020). The subjects below would have been “within the general knowledge of a skilled artisan” by 2004. *Id.* at 1338.

#### **1. Mercury and Halogens**

Halogens were known as Group VII elements, which include fluorine (F), chlorine (Cl), bromine (Br), and iodine (I), and are highly reactive oxidizing agents that cause other species to give up electrons (become more positively charged). EX1040, 788, 791, A.44. Halogens were known to exist naturally as diatomic molecules (*e.g.*, Br<sub>2</sub>), halides/halide compounds (*e.g.*, NaBr, CaBr<sub>2</sub>), and hydrohalides (*e.g.*, HBr).

Mercury was a known metal in an elemental/metallic ( $\text{Hg}^0$ ) form and as oxidized (either  $\text{Hg}_2^{2+}$  (mercurous) or  $\text{Hg}^{2+}$  (mercuric)). EX1002, ¶ 43; EX1041, 12.

## **2. Coal Combustion**

Pulverized-coal was commonly combusted in a combustion chamber known as a “boiler” and produced a mercury-containing flue gas. EX1042, 13–1, 18–1, 19–1. Coal emissions also included particulate matter (fly ash and unburned carbon), mercury (Hg), sulfur oxides ( $\text{SO}_x$ ), and nitrogen oxides ( $\text{NO}_x$ ). EX1043, 1.1–3 to 1.1–6. Downstream components used to control flue gas pollutants included electrostatic precipitators (ESP) and fabric filters (FF) for particulates, and wet or dry flue gas desulfurization (FGD) systems. EX1043, 1.1–6 to 1.1–9; EX1002, ¶¶ 44, 46.

## **3. EPA Regulations**

Mercury posed known health concerns. EX1046, 4–11 to 4–20. In 2000, the EPA announced plans to regulate mercury emissions from coal-fired power plants with rules to be proposed by December 2003 and finalized by December 2004. EX1044, 2, 7–9. The Clean Air Mercury Rule passed in 2005 and required 70% mercury removal. EX1045. The power-generation industry mobilized a massive response to develop mercury emissions control technologies in the early 2000s. EX1044; EX1002, ¶ 42.

#### **4. Activated Carbon and Halogens for Mercury Removal**

Adsorption is a process where adsorbate (*e.g.*, mercury) in a fluid (*e.g.*, flue gas) binds to a sorbent's surface (*e.g.*, activated carbon). “Reducing” mercury in flue gas results from adsorbing mercury to the sorbent surface and then removing the sorbent using particulate separators such as ESPs. EX1002, ¶¶ 45-56.

By 1934, it was shown that halogens improved the ability of activated carbon to remove mercury. *See* EX1049, 1:33–41. By 1970, bromine was known to adsorb up to a 31–38% saturation limit (adsorption equilibrium) in carbon materials. EX1050, 260. By 1988, bromine (Br) was shown to react with activated carbon to provide “carbon-bromine surface structures (surface compounds).” EX1051, 259.

By 1998, “[a]ctivated carbons ha[d] been the most thoroughly studied sorbent for the capture of mercury.” EX1041, 22. Indeed, two named inventors, Dr. Olson and Mr. Holmes, admitted, “activated carbon was the most common [or heavily] studied sorbent for mercury control.” EX1047, 114:21-25. EX1048, 41:5-9.

In 1999, researchers demonstrated that mercury from flue gas formed chemical bonds with halogen species on activated carbons. EX1052, 119. And researchers were investigating improving their effectiveness and cost. EX1001, 2:8-14; EX1046, 2–54 to 2–57; EX1041, 1.

By 2003, bromine was known to be more than 25 times more effective than chlorine for metallic mercury oxidation in coal combustion. EX1049, 2. In 2003, Vosteen's group was testing to achieve 95% mercury removal by combining bromine injection with powdered activated carbon ("PAC") injection and to reduce PAC consumption to one-fifth. EX1061, 96.

It was known that halogens, particularly bromine-containing species, improved the effectiveness of activated carbon in removing mercury. *See, e.g.*, EX1004; EX1012; EX1008; EX1066. EX1002, ¶ 52.

Calcium bromide was known to achieve the highest mercury removal at the lowest dosage rate as compared to other halogens tested in lignite coal combustion in March 2005. EX1057, 12; EX1054, 15.

It was also well known that adjusting the sorbent injection rate would control mercury emissions. EX1058, 14; EX1059; EX1060, 4676. EX1002, ¶ 52.

Coal-fired power plants used bromide compounds pre-combustion and activated carbon post-combustion to remove mercury from flue gas and sold the electric power generated in June 2004 at Holcomb Station (EX1062, 11, 15; EX1063, EX1064; EX1066), by March 2005 at Laramie River (EX1067, 11, 23), and by September 2005 at Meramec Station (EX1065, 17–18; EX1066, 16; EX1063; EX1064).

## **VIII. CLAIM CONSTRUCTION**

Petitioner does not contend that any term requires construction and has given all terms their plain and ordinary meaning consistent with the construction provided by Magistrate Judge Burke in the District of Delaware. EX1002, ¶¶ 104-110.

## **IX. THE CITED REFERENCES QUALIFY AS PRIOR ART**

Petitioner relies on six prior art references: Downs (EX1004); Altman (EX1007); Nelson (EX1008); Vosteen (EX1011); Blankinship (EX1012); and Olson-235 (EX1013). These references render the Challenged Claims unpatentable as anticipated or obvious.

### **A. Downs**

Downs was published as US2008/0107579 on 5/8/2008 before the ‘430 Patent’s 5/8/2018 effective filing date, and is prior art under 35 U.S.C. § 102(a)(1) (as of its 5/8/2008 publication date) and 102(a)(2) (AIA) (as of its 3/22/2004 provisional filing date). If the ‘430 Patent’s effective filing date is determined to be 8/30/2004, then Downs is prior art under 35 U.S.C. § 102(e) (pre-AIA) as of its 3/22/2004 provisional filing date because the provisional application has proper support for the subject matter relied upon as prior art and at least one Downs’ patent claim is supported by the provisional application’s written description under pre-AIA 35 U.S.C. 112, first paragraph. *In re Riggs*, 131 F.4<sup>th</sup> 1377, 1384-85 (Fed. Cir. 2025); *Dynamic Drinkware, LLC v. Nat’l Graphics, Inc.*, 800 F.3d 1375, 1378 (Fed. Cir. 2015); *Amgen Inc. v. Sanofi*, 872 F.3d 1367, 1380 (Fed. Cir. 2017) (*Dynamic*

applies to published patent applications). The PTAB previously found that Downs qualifies as prior art back to 3/22/2004. EX1045, 29, 32.

The disclosure of Downs is supported by Downs-Provisional, as illustrated by a redline comparison (EX1006) and confirmed by Dr. Vidic. EX1002, ¶¶ 111-138. At least Downs' claim 1 has written description support in Downs-Provisional, which describes: a “method of removing elemental mercury from coal combustion flue gases” (EX1005, Title, [0021]); providing a “bromine-containing reagent” to mercury-containing flue gas in the combustion chamber to “promote the oxidation of elemental mercury” and create an oxidized form (EX1005, Title, Fig. 2, [0002]-[0006], [0018]-[0019], [0021], [0027], claim 1); and removing “both oxidized and elemental mercury species” from the flue gas (EX1005, [0004]-[0005], [0018]-[0019]).

Downs explains, “[b]romine-containing compounds, added to the coal, or to the boiler combustion furnace, are used to enhance the oxidation of mercury, thereby enhancing the overall removal of mercury in downstream pollution control devices.” EX1004, Abstract, [0001], [0010]; EX1005, [0009], [0018]. Downs' schematic is reproduced below:




FIG. 2

EX1004, Figure 2 (annotations added in red); EX1005, Figure 2. Figure 2 shows adding bromine-containing reagent 10 to boiler 12 of combustion furnace 14 “either directly or by premixing with the incoming coal 16.” EX1004, [0015]; EX1005, [0018]. Downs describes injecting an aqueous solution of calcium bromide into furnace 14, and using “alkali metal and alkaline earth metal bromides, hydrogen bromide (HBr) or bromine (Br<sub>2</sub>)” as the bromine-containing reagent 10. EX1004, [0018], [0021]; EX1005, [0021], [0024]. Downs describes “downstream pollution control systems such as wet 22 and SDA 24 FGD systems, and PAC injection systems” with “powdered activated carbon (PAC)” as a sorbent. EX1004, [0015], [0025]; EX1005, [0018], [0028]. Wet 22 and SDA 24 FGD systems and ESP or FF particulate collectors 26 are shown in Figures 4 and 6, below:




FIG. 4




FIG. 6


EX1004, Figures 4 & 6; EX1005, Figures 4 & 6. Downs states, “experimental results indicate that bromine addition also results in an increased fraction of particulate-bound mercury,” enhancing mercury removal from particulate collectors 26 (FF or ESP). EX1004, [0015]; EX1005, [0018].

## B. Altman


Altman issued as US Patent 5,827,352 on 10/27/1998 and is a prior art patent under 35 U.S.C. §§ 102(a)(1) and 102(a)(2) (AIA) or 35 U.S.C. §§102(a) and 102(b) (pre-AIA) regardless of the '430 Patent's effective filing date.

Altman discloses that injection of activated carbon into flue gas was known to remove mercury in coal-fired boilers before April 1997. EX1007, 2:23–31, 1:41–2:22, 32–46.

Altman injects activated carbon sorbent into flue gas to remove mercury from the flue gas of a coal-fired boiler 12. EX1007, 1:5–9, 3:41–45, 4:57–58. Flue gas exiting boiler 12 is processed through ESP 19 to remove fly ash 21 and then through tower 24 and silo 27:



EX1007, Figure 1, 3:53–65 (annotations added in red). Tower 24 includes a particulate control device (wet ESP 51) located above internal chamber 34:



EX1007, Figure 2, 3:66–4:4, 17–20 (annotations added in red). The activated carbon sorbent is “injected into the flue gas” – either “injected into chamber 34” or into inlet duct 26 via line 41. EX1007, 4:53–61. Water or a water/sorbent mixture is injected into chamber 34 to lower the flue gas temperature such that temperature and sorbent injection rate provide “optimal mercury sorption” by activated carbon sorbent. EX1007, 4:62–5:5. Flue gas residence time within chamber 34 ranges from 1–20 seconds, preferably 5–10 seconds, to “allow a large portion of the mercury in the flue gas to be removed by the injected sorbent.” EX1007, 5:6–12. The flue gas rises through chamber 34 into wet ESP 51 where sorbent, remaining fly ash and condensed water are collected and either removed from tower 24 through drain 83 or partially recycled by recirculator 66. EX1007, 5:18–22, 41–49.

Instead of using complex packed beds with stationary sorbent, Altman injects activated carbon and lime sorbent particles into flue gas. EX1007, 1:30–40, 4:53–61, 5:50–61. EX1002, ¶¶ 139-147.

### **C. Nelson**

Nelson published as US Patent Application Publication US2004/0003716 on 1/8/2004, and is a prior art published patent application under 35 U.S.C. §§ 102(a)(1) (as of its 1/8/2004 publication date) and 102(a)(2) (AIA) (as of its 5/6/2002 provisional filing date). If the ‘430 Patent’s effective filing date is determined to be 8/30/2004, then Nelson is prior art under 35 U.S.C. §§ 102(a) (as of its 1/8/2004 publication date) and 102(e) (pre-AIA) as of its 5/6/2002 provisional filing date for the reasons provided in § IX.A, above. The disclosure of Nelson is supported by Nelson-Provisional, as illustrated by a redline comparison (EX1010) and confirmed by Dr. Vidic. EX1002, ¶¶ 148-168. At least Nelson’s claim 18 has written description support in Nelson-Provisional, which describes “exposing powdered activated carbon (PAC) to gaseous bromine, Br<sub>2</sub> (g), or gaseous hydrogen bromide, HBr (g), significantly increases its ability to remove elemental mercury when injected into coal-fired flue-gas compositions at high temperatures....By simply exposing PAC to concentrated bromine gas, a relatively large quantity of this gas appears to react with the carbon, forming surface compounds on the large surface-area of the carbon.” EX1009, 4.

Nelson describes exposing activated carbon sorbent to a bromine-containing gas before the sorbent is mixed with mercury-containing flue gas. EX1008, [0040]; EX1009, 4. Nelson indicates that exposure of sorbent to Br<sub>2</sub> or HBr gas “significantly increases the carbonaceous materials ability to remove mercury species.” EX1008, [0041]; EX1009, 4.


#### **D. Vosteen**

Vosteen published as US2004/0013589 on 1/22/2004, and is a prior art published patent application under 35 U.S.C. §§ 102(a)(1) (as of its 1/22/2004 publication date) and 102(a)(2) (as of its 7/24/2002 filing date) (AIA). If the ‘430 Patent’s effective filing date is determined to be 8/30/2004, then Vosteen is prior art under 35 U.S.C. § 102(a) (as of its 1/22/2004 publication date) and 102(e) (pre-AIA) (as of its 7/24/2002 filing date).

Vosteen describes “a process for removing mercury from flue gases of high temperature plants, in particular power stations” EX1011, [0001]. Vosteen discloses, “addition of bromine or bromine compounds to the furnace causes ... a substantial, essentially complete, oxidation of the mercury” allowing “substantially complete removal of mercury (Hg), from flue gases.” EX1011, [0005], [0007]. More than 90% mercury removal is reported. EX1011, Figure 5, [0028], [0042].

Vosteen reports adding sodium bromide (NaBr), a bromide compound, into coal-fired boilers 91 of a power plant to “demonstrate the effect of bromine on Hg oxidation.” EX1011, Example 5, [0047]. Vosteen describes a flue gas emissions

control system as known in the art “based either on wet scrubbing or dry cleanup or a combination of the two.” EX1011, [0017]. Vosteen exemplifies a boiler flue gas fed through air preheaters 93,93’ ESPs 96,96’ and FGD scrubber 97 as depicted below.



EX1011, Figure 9 (annotations added in red), Example 5, [0047]. Vosteen discloses activated carbon and alkaline materials such as lime for use in the flue gas emissions control system. EX1011, [0019]. EX1002, ¶¶ 169-178.

### E. Blankinship

Blankinship published on 6/2/2009, before the ‘430 Patent’s 5/8/2018 effective filing date, and is a prior art printed publication as of 6/22/2009 under 35 U.S.C. §§ 102(a)(1) (AIA) or 35 U.S.C. §§ 102(a) and 102(b) (pre-AIA).

“A reference is considered publicly accessible if it was disseminated or otherwise made available to the extent that persons interested and ordinarily skilled in the subject matter or art, exercising reasonable diligence, can locate it.” *Acceleration Bay, LLC v. Activision Blizzard Inc.*, 908 F.3d 765, 772 (Fed. Cir. 2018) (internal quotation omitted). Blankinship was in Volume 113, Issue 6 of Power Engineering magazine, as received by the University of Pittsburgh Libraries on June 22, 2009 (confirmed by date stamp) and made publicly available within days of receipt. EX1082, ¶¶ 1-4, 4a, Exhibit A. This Library subscribed to the print version of Power Engineering magazine from 1950 to 2018. *Id.*

Blankinship describes Alstom’s approach to removing 80–90% mercury from flue gases in coal-fired power plants burning subbituminous or lignite coal by using a bromide compound pre-combustion and activated carbon injection post-combustion “upstream of a particulate control device.” EX1012, 58. Alstom’s KNX™ calcium bromide solution is “added to the boiler or to the coal” pre-combustion in concentrations where it “enhances mercury oxidation without causing other concerns such as corrosion in the boiler.” *Id.*, 56, 58. A MER-CURE™ activated carbon sorbent injection system is used post-combustion to capture mercury on activated carbon particles injected into the flue gas upstream of the air heater to provide “more residence time for the sorbent to absorb the mercury,” reducing “sorbent usage about 50 percent compared to traditional activated carbon systems.” *Id.*, 58. EX1002, ¶¶ 179-184.

## **F. Olson-235**

Olson-235 issued as U.S. Patent 8,652,235 on 2/18/2014 before the ‘430 Patent’s 5/8/2018 effective filing date and is a prior art patent as of 2/18/2014 under 35 U.S.C. §§ 102(a)(1) and as of 4/23/2009 under 102(a)(2) (AIA).

Olson-235 discloses a method for removing mercury in flue gas by injecting a promoted sorbent into the gas. EX1013, 5:30–36. Olson-235 discloses that the promoted sorbent “comprises from about 1 to about 30 grams of promoter per 100 grams of base sorbent.” EX1013, 4:53–60, Claims 3, 17. Olson-235 also discloses an embodiment wherein “the injected sorbent is prepared in-flight by reacting a base sorbent (carbon, non-carbon or their combination) and a promoter within a pneumatic transport line from which the reaction product is injected to the mercury-containing flue gas stream.” EX1013, 5:43–48. In that embodiment, “the promoter is added at from about 1 to about 30 grams per 100 grams of the base sorbent.” EX1013, 6:17–31. EX1002, ¶¶ 185-188.

## **X. OBVIOUSNESS CONSIDERATIONS**

### **A. Reasons to Combine**

A POSITA would have been motivated to combine Downs/Altman or Downs/Altman/Nelson (Ground 2), Vosteen/Altman or Vosteen/Altman/Nelson (Ground 3), or Blankinship/Vosteen or Blankinship/Olson-235 (Ground 5) with reasonable expectation of success, because all of these references are directed towards the same goal (removing mercury from coal-combustion flue gases) and are

directed to using known techniques to improve similar devices. More particularly, these references (i) add a promoter to coal or a combustion chamber (Downs, Vosteen or Blankinship) to oxidize mercury and (ii) add (Vosteen) or inject (Downs, Blankinship, Altman, Nelson, Olson-235) sorbent post-combustion to adsorb the mercury and use a particulate control device (*i.e.*, an ESP) to collect the sorbent containing the mercury and remove it from the cleaned gas. It follows these references are analogous art to the '430 Patent, in the same field of endeavor, and reasonably pertinent to the problems the inventors faced. EX1002, ¶¶ 298-303, 379-386, 660-667.

#### **1. Downs/Altman or Vosteen/Altman**

Downs discloses using a PAC “sorbent injection system” and states that many “studies have focused on the injection of a carbonaceous sorbent (*e.g.*, powdered activated carbon, or PAC) into the flue gas .... The sorbent, and its burden of adsorbed mercury, are subsequently removed from the flue gases in a downstream particulate collector.” EX1004, [0004], [0025], claims 15–16.

Vosteen suggests using wet scrubbers, dry systems or both as known in the art. EX1011, [0017]. Vosteen describes wet scrubbing “performed, for example, in ... a packed-bed scrubber” without indicating what packing was used in the packed-bed. *Id.*

A POSITA had reason to select Altman’s wet flue gas emissions system (including tower 24 having chamber 34 and wet ESP 51) as Downs’ PAC sorbent

injection system or to substitute Altman's emissions system for Vosteen's packed bed wet scrubber because: (i) Altman's tower ensures "there is sufficient activated carbon mercury adsorption capacity at reasonable adsorption injection rates" to achieve "optimal mercury sorption" in a flue gas residence time of only 1 to 20 seconds; (ii) Altman discloses that activated carbon sorbent injection into flue gas entering a wet scrubber avoids the disadvantages of high pressure drop and sorbent regeneration associated with Vosteen's packed-bed wet scrubber; (iii) Downs describes its process as enhancing mercury removal in conventional particulate collectors<sup>26</sup> such as ESPs and in a PAC injection process due to "higher reactivity of oxidized mercury with PAC;" (iv) Downs and Altman disclose that activated carbon injection into flue gas was known for mercury removal by 1997; and (v) Altman's wet ESP captures sorbent particles for recycling or disposal. EX1007, 1:23–40, 2:23–31, 4:62–5:17, 59–61; EX1004, [0004], [0016]; EX1005, [0005], [0019]. EX1002, ¶¶ 298-303, 379-386.

A POSITA had reason to combine Downs or Vosteen with Altman with reasonable expectation of success because Altman describes activated carbon injection (ACI) into flue gas from a coal-fired combustion system having an ESP particulate control device as suggested by Downs or Vosteen. The combination represents prior art elements according to known ACI methods to yield predictable results in removing mercury. *See* § IX.B regarding Altman. EX1002, ¶¶ 302, 386.

## **2. Downs/Altman/Nelson or Vosteen/Altman/Nelson or Blankinship/Olson-235**

Regarding '430 Patent claim 20, a POSITA had reason to substitute Nelson's brominated-activated carbon sorbent for Altman's activated carbon sorbent in the Vosteen/Altman or Downs/Altman process, or Olson-235's brominated-activated carbon sorbent for Blankinship's activated carbon sorbent, with a reasonable expectation of success because Nelson indicates that exposure of sorbent to Br<sub>2</sub> or HBr gas "significantly increases the carbonaceous materials ability to remove mercury species" and Olson-235 states that it "increases the surface reactivity toward mercury." EX1008, [0041]; EX1009, 4; EX1013, 11:50-52. A POSITA would have known this approach would have increased overall mercury capture. EX1002, ¶¶ 336, 466, 610, 682. For example, mercury vapors were removed in the 1930s by injecting halogen-impregnated activated-carbon sorbents into a mercury-containing flue gas. EX1041, 1:33–41.

## **3. Blankinship/Vosteen**

Vosteen discloses "mercury content of the flue gas ... is measured continuously ... and on the basis of the measured mercury content the amount of bromine fed and/or bromine compounds . . . is controlled." EX1011, [0022], claim 10. If mercury is removed incompletely, additional bromine compound is fed. *Id.* Vosteen adds Br<sub>2</sub>, HBr, and bromide compounds (*e.g.*, NaBr) to the combustion

chamber and/or to the coal upstream of the combustion chamber as discussed in § XI.B.2.

A POSITA would have considered it obvious to optimize the amount of bromine additive in Blankinship since Vosteen describes this variable as affecting mercury removal from a flue gas. EX1011, [0022]. EX1002, ¶¶ 686-692.

### **B. Simultaneous Invention**

“Independently made, simultaneous inventions, made within a comparatively short space of time, are persuasive evidence that the claimed apparatus was the product only of ordinary mechanical or engineering skill.” *Geo. M. Martin Co. v. Alliance Mach. Sys. Int'l LLC*, 618 F.3d 1294, 1305 (Fed. Cir. 2010). *See also Medtronic, Inc. v. Teleflex Innov. SARL*, 70 F.4<sup>th</sup> 1331, 1339-40 (Fed. Cir. 2023) (“a competitor's independent and contemporaneous development of a similar product may, in some cases, even suggest the patented product *would* have been obvious.”). Notably, simultaneous invention(s) need not be prior to the purported ‘430 Patent invention date to be pertinent to the obviousness determination. *Trustees of Columbia Univ. v. Illumina*, 620 Fed.Appx 916, 920 (Fed. Cir. 2015).

In the Iowa MDL, PO emphasized that the ‘517 Patent (as well as each of the other patents asserted in the lawsuits) is directed to a straightforward two-step mercury capture process: (1) apply a halogen, and more specifically bromine, to coal and/or the combustion chamber; and (2) inject activated carbon into the flue gas as a sorbent. EX1077, 4-5. But this two-step process was developed, tested, and

implemented by many others at the time of the alleged invention. Such simultaneous invention is further evidence the Challenged Claims would have been obvious to a POSITA. EX1002, ¶¶ 736-743.

For example, Downs used such a two-step process before the Provisional filing date. *See* § IX.A. Alstom also developed a bromine-promotor added to coal or the combustion chamber for mercury control by 2004 that sold as KNX™. ADA-ES performed testing by the third quarter of 2004 under a Department of Energy Cooperative Agreement wherein Alstom's KNX product was applied to coal at Sunflower Electric's Holcomb Station and "enhance[d] the performance of standard activated carbon," achieving "[m]ercury removal of 86%." EX1063, 3, 25. Similar tests were also performed by ADA-ES in the fourth quarter of 2004 at Union Electric's Meramec Station using Alstom's KNX as a coal additive in combination with activated carbon. EX1064, 8, 21. Similar processes were also tested by EPRI and others at Texas Genaco's Limestone Electric Generating Station combusting lignite coal with injection of calcium bromide into the boiler and an ESP for particulate reduction and 81% mercury removal. EX1057, 12. These stations were in commercial operation supplying electricity to customers during the testing.

**XI. INDEPENDENT CLAIMS 1 AND 28–29 ARE UNPATENTABLE AS ANTICIPATED OR OBVIOUS**

This section addresses each limitation of claims 1 and 28–29 together since the independent claims are nearly the same.

**A. Element 1(Preamble), 28(Preamble), 29(Preamble) – “A method of separating mercury from a mercury-containing gas, the method comprising:”**

**1. Ground 1 – Downs**

Downs discloses processes for removing mercury from flue gas by adsorbing the mercury with PAC sorbent and separating the sorbent from the flue gas via particulate collectors. EX1004, [0007], [0018]; EX1005, [0009], [0021]; EX1002, ¶¶ 192-196, 277-281.

**2. Ground 2 – Downs/Altman**

*See* § XI.A.1. Altman discloses processes for removing/separating mercury from flue gas. EX1007, Abstract; EX1002, ¶ 342-349.

**3. Ground 3 – Vosteen/Altman**

*See* § XI.A.2 regarding Altman. Vosteen discloses processes for removing/separating mercury from flue gas. EX1011, Abstract. EX1002, ¶¶ 387-391, 498-504, 524-529.

**4. Ground 4 –Blankinship**

Blankinship discloses a process for removing 80–90% of mercury from a coal combustion flue gas. EX1012, 58. EX1002, ¶¶ 554-559, 640-645.

**5. Ground 5 – Blankinship/Vosteen**

*See* §§ XI.A.3–XI.A.4 regarding Blankinship and Vosteen. EX1002, ¶¶ 706-710.

- B. Element 1(a), 28(a), 29(a) – “combusting coal in a combustion chamber, to provide the mercury-containing gas, [wherein the mercury-containing gas comprises a halogen or halide promoter comprising HBr, Br<sup>-</sup>, or a combination thereof, –Cl. 28(a), 29(a)] wherein the coal comprises an additive comprising Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber, or the combustion chamber comprises an additive comprising Br<sub>2</sub>, HBr, a bromide compound, or a combination thereof;”**

**1. Grounds 1–2 – Downs, Downs/Altman**

Downs reports adding alkali metal or alkaline earth metal bromides (*i.e.*, bromide compounds), HBr or Br<sub>2</sub> as the bromine-containing reagent 10 that is premixed with the incoming coal 16. Downs also discloses calcium bromide injected into the combustion chamber through a coal burner. EX1004, [0002], [0007], [0011], [0021]; EX1005, [0003], [0009], [0018], [0021]; EX1002, ¶¶ 197-203, 282-287, 350-357.

Regarding the requirement that the mercury-containing gas comprises HBr, Br<sup>-</sup>, or a combination thereof in elements 28(a)-29(a), Julien discloses that when calcium bromide is added to a coal combustor, “[f]ree energy calculations suggest that complete decomposition of CaBr<sub>2</sub> to HBr and CaO in the presence of water vapour is favoured over the full range of temperatures in the [circulating fluidized bed combustor] CFBC.” EX1014, 1658. Thus, HBr is in vapor or gaseous form in the mercury-containing flue gas after combustion of a bromide compound such as calcium bromide or sodium bromide. EX1002, ¶¶ 286, 356.

## 2. Ground 3 – Vosteen/Altman

Vosteen discloses a “coal-fired power station, including a “combustion chamber.” EX1011, [0005]. Vosteen further discloses “addition of bromine or bromine compounds to the furnace causes . . . a substantial, essentially complete, oxidation of the mercury and therefore allows substantial removal of the mercury from flue gases.” EX1011, [0007]. Vosteen adds Br<sub>2</sub>, HBr, and bromide compounds (*e.g.*, NaBr) to the combustion chamber and/or to the coal upstream of the combustion chamber:

The invention relates to a process for removing mercury from flue gases of ... power stations ..., in which **bromine and/or a bromine compound and/or a mixture of various bromine compounds** is fed to the appropriate multistage furnace....

[A]n aqueous solution of **hydrogen bromide** [HBr] or an alkali metal bromide, in particular sodium bromide [NaBr], or an aqueous solution of the alkali metal bromide is used....

The bromine compound, ... can be added ... **to the ... coal or the like to be burnt, upstream of the furnace.... The compound can also be fed during the combustion process** ... [or] after the combustion...

EX1011, [0006], [0009], [0013] (emphasis added). EX1002, ¶¶ 392-395, 498-504, 530-537.

Vosteen describes “the mass ratio of bromine to mercury in the flue gas.” EX1011, [0025], [0028], [0031].

*See* § XI.B.1 regarding Julien for elements 28(a)-29(a). EX1002, 530.

### **3. Ground 4 – Blankinship**

Blankinship discloses “Alstom is attacking Hg from two different approaches that, in some cases, might be used simultaneously.” EX1012, 58. Blankinship explains Alstom’s KNX™ calcium bromide solution “can be added to the boiler or to the coal to oxidize the mercury and facilitate its capture in wet scrubbers” or in electrostatic precipitators (ESPs). EX1012, 56, 58; EX1002, ¶¶ 561, 647. Calcium bromide is a “bromide compound” because it is “a substance composed of atoms or ions of two or more elements in chemical combination” in which “constituents are united by bonds or valence forces.” EX1015, 291; EX1002, ¶¶ 560, 646. *See* § XI.B.1 regarding Julien. Thus, HBr is in vapor or gaseous form in the flue gas post-combustion. EX1002, ¶¶ 560-564, 646-650.

### **4. Ground 5 – Blankinship/Vosteen**

*See* §§ XI.B.2–XI.B.3 regarding Vosteen and Blankinship. EX1002, ¶¶ 674, 711-719. *See* § XI.B.1 regarding Julien for elements 28(a)-29(a).

- C. Element 1(b), 28(b), 29(b) – “injecting a sorbent comprising activated carbon into the mercury-containing gas downstream of the combustion chamber [such that the activated carbon reacts with the halogen or halide promoter in the mercury-containing gas to form a promoted sorbent—cl. 29(b)];”**

**Element 1(c), 28(c), 29(c) – “contacting mercury in the mercury-containing gas with the [promoted—cl. 29(c)] sorbent; and”**

**Element 1(d), 28(d), 29(d) – “separating the [promoted—cl. 29(d)] sorbent contacted with the mercury from the mercury-containing gas”**

**1. Ground 1 – Downs**

Downs discloses using a PAC sorbent injection system to remove mercury from coal combustion flue gas downstream from the combustion chamber via particulate collectors such as ESPs. EX1004, [0004], [0015]; EX1005, [0005], [0018]. EX1002, ¶¶ 204-212, 288-295. Further, the “increased fraction of oxidized mercury” resulting from bromine addition “enhances the removal of mercury across a PAC injection process, due to the higher reactivity of oxidized mercury with PAC.” EX1004, [0015]–[0016], EX1005, [0018]. Downs describes “injection of a carbonaceous sorbent (*e.g.*, powdered activated carbon, or PAC) into the flue gas ... to adsorb vapor-phase mercury” and the “sorbent, and its burden of adsorbed mercury, are subsequently removed from the flue gases in a downstream particulate collector.” EX1004, [0004]; EX1005, [0005].

## **2. Ground 2 – Downs/Altman**

*See* § XI.C.1 regarding Downs. Altman describes injecting PAC into flue gas to remove elemental and oxidized mercury using an ESP. EX1007, 1:30–2:46; 4:53–61, 5:6-12, 50–61.

Regarding element 29(b), it is obvious the activated carbon reacts with promoter in the mercury-containing gas to form a promoted sorbent when the HBr in the gas contacts the sorbent. It was well-known in the art that halogens (including bromine) “promoted” activated-carbon sorbents because they improved mercury removal by increasing the ability of the activated carbon to bind with the mercury. *See* § VII.C.4. Lead inventor Dr. Olson admitted, when bromides are added to coal “and activated carbon is injected downstream of the furnace,” then there would be “in-flight promotion.” EX1047, 231:3-9, 98:23-100:3. “[P]romotion” of activated carbon by halogens is a reaction. EX1083, 156 (labeled as limitation 24e, O’Keefe explaining how bromine containing ingredients added to coal would contact and react with sorbent), 160 (labeled as limitation 1c, O’Keefe explaining how activated carbon reacts with bromine), 179 (same analysis for limitation 29f, which is ‘430 element 29(c) above’); EX1002, ¶¶ 358-371.

## **3. Ground 3 – Vosteen/Altman**

*See* § XI.C.2 regarding Altman and element 29(b). Vosteen discloses “removal of mercury from the flue gases in a flue gas emission control system downstream of the combustion” EX1011, [0007]. One sorbent disclosed by Vosteen

is “finely pulverulent slaked lime/activated carbon.” *Id.*, [0019]. The mercury/sorbent composition is separated from the flue gas in an ESP. *Id.*, [0019], [0047]–[0049]. EX1002, ¶¶ 409, 518, 544.

#### **4. Ground 4 – Blankinship**

Blankinship discloses that KNX can be “applied in combination with another mercury control technology such as our Mer-Cure post-combustion technology or activated carbon injection.” EX1012, 58. Blankinship reports “[t]here are many cases where the combination of the two work very effectively together” because the “KNX applied to the coal provides better oxidation of the mercury at a lower cost than brominated sorbents, allowing the Mer-Cure system further downstream to capture the mercury more efficiently.” EX1012, 58. The Mer-Cure system “inject[s] the activated carbon into the duct work.” *Id.*

Blankinship further reports mercury removal of 80–90% for the Alstom process. EX1012, 58. A POSITA would understand the activated carbon sorbent in the Mer-Cure system collected the mercury from the flue gas. EX1002, ¶¶ 568, 571, 654, 657.

Blankinship describes using Alstom’s KNX process of calcium bromide addition “to the boiler or to the coal” and “injecting activated carbon upstream of the [flue gas desulfurization] FGD to improve its mercury capture performance even more. Power plants without an FGD would likely use sorbent injection, mostly an activated carbon, upstream of a particulate control device.” EX1012, 56. A POSITA

would have known that a particulate control device separates and removes the sorbent from the flue gas. EX1002, ¶ 46.

## **5. Ground 5 – Blankinship/Vosteen**

*See* §§ XI.C.3–XI.C.4 regarding Vosteen and Blankinship. *See* § XI.C.2 regarding element 29(b). EX1002, ¶¶ 720-729.

### **D. Element 29(e) – “measuring the mercury content of the mercury-containing gas; and”**

**Element 29(f) – “modifying, in response to the measured mercury content,**

**an injection rate of injecting the sorbent into the mercury-containing gas,**

**an amount of the Br<sub>2</sub>, HBr, the bromide compound, or a combination thereof, added to the coal or the combustion chamber, or**

**a combination thereof.”**

*See* § VII.C.3 regarding EPA Rules. It thus would have been obvious to a POSITA that the mercury content of the cleaned gas must be measured and must be maintained at a desired level—*e.g.*, 70% removal. EX1002, ¶ 374.

### **1. Ground 2 – Downs/Altman**

Downs describes use of an “on-line mercury analyzer” to detect “vapor-phase mercury species.” EX1004, [0018]; EX1005, [0021]. Downs measured vapor-phase mercury in flue gas and applied amounts of calcium bromide to the coal from 750 ppm to 1,000 ppm to 375 ppm in testing. EX1004, Figure 3; EX1005, Figure 3.

Altman describes achieving “optimal mercury sorption” and ensuring there is “sufficient activated carbon mercury adsorption capacity at reasonable adsorption injection rates.” EX1007, 4:62-5:5. Adjusting sorbent injection rates based on measured mercury content of a flue gas was known to a POSITA by at least 1995, as evidenced by EX1082, Abstract (“By adjusting ... the absorbent a permanent high Hg removal is achieved.”), 6:42-46 (The amount of ... activated carbon ... may be adjusted also on basis of the Hg content of the treated gas measured by means of a device 18 arranged in the duct 9.”)

A POSITA would have known that by 2004 the EPA put the industry on notice of requiring 70% mercury removal, including EPA’s Clean Air Mercury Rule (CAMR). EX1045. It would have been obvious to a POSITA that any mercury control system would have to comply with these laws and regulations.

A POSITA would have considered it obvious to optimize the sorbent injection rate in Altman and/or the amount of bromine additive in Downs since both variables affect mercury removal from a flue gas. EX1004, [0018], Figure 3; EX1005, [0021], Figure 3; EX1007, 4:62-5:5; EX1002, ¶¶ 376-377.

## **2. Ground 3 – Vosteen/Altman**

*See* § XI.D.1 regarding Altman. Vosteen discloses “mercury content of the flue gas, in particular the content of metallic mercury, is measured continuously . . . and on the basis of the measured mercury content the amount of bromine fed and/or bromine compounds . . . is controlled.” EX1011, [0022], claim 10. If mercury is

removed incompletely, additional bromine compound is fed. *Id.* Vosteen adds Br<sub>2</sub>, HBr, and bromide compounds (*e.g.*, NaBr) to the combustion chamber and/or to the coal upstream of the combustion chamber as discussed in § XI.B.2.

A POSITA would have considered it obvious to optimize the sorbent injection rate in Altman and/or the amount of bromine additive in Vosteen since both variables affect mercury removal from a flue gas. EX1011, [0022]; EX1007, 17, 20, Table 2, Figures 5-6. EX1002, ¶¶ 550-552.

### **3. Ground 5 – Blankinship/Vosteen**

*See* § XI.D.2 regarding Vosteen. EX1002, ¶¶ 701-735.

## **XII. CLAIMS DEPENDING FROM CLAIM 1 ARE UNPATENTABLE**

**A. Claim 2 – “the coal comprises the additive comprising the Br<sub>2</sub>, HBr, the bromide compound, or a combination thereof, wherein the additive is added to the coal before the coal enters the combustion chamber.”**

**Claim 3 – “the combustion chamber comprises the additive comprising the Br<sub>2</sub>, HBr, the bromide compound, or a combination thereof.”**

### **1. Grounds 1–2 – Downs, Downs/Altman**

*See* § XI.B.1. EX1002, ¶¶ 214-220, 314.

### **2. Ground 3 – Vosteen/Altman**

*See* § XI.B.2. EX1002, ¶¶ 412-417.

### **3. Ground 4 – Blankinship**

*See* § XI.B.3. EX1002, ¶¶ 573-579.

#### **4. Ground 5 – Blankinship/Vosteen**

*See* §§ XI.B.2-XI.B.3. EX1002, ¶ 674.

- B. Claim 4 – “the coal is combusted in the combustion chamber at a coal-combustion facility, wherein the additive comprising the Br<sub>2</sub>, HBr, bromide compound, or combination thereof, is added to the coal before the coal enters the combustion chamber, wherein the addition of the additive comprising the Br<sub>2</sub>, HBr, bromide compound, or combination thereof, to the coal is performed at the coal-combustion facility.”**

##### **1. Grounds 1–2 – Downs, Downs/Altman**

Downs describes “coal pulverizers 28 intimately mix the bromide reagent 10 with the coal 16, and the pulverized coal conveying system 30 to the several coal burners (not shown) ensures an even distribution of the reagent 10 across the boiler furnace 14.” EX1004, [0019], EX1005, [0022]. EX1002, ¶¶ 221-226.

##### **2. Ground 3 – Vosteen/Altman**

Vosteen describes “bromine compound, for example, sodium bromide, can be added ... as aqueous solution, **to the ... coal or the like to be burnt, upstream of the furnace.**” EX1011, [0013] (emphasis added). EX1002, ¶¶ 418-420.

##### **3. Ground 4 – Blankinship**

Alstom’s KNX pre-combustion offering applies calcium bromide to the coal prior to combustion to promote mercury oxidation” and Alstom installs the “equipment used to inject the [KNX] solution.” EX1012, 58. EX1002, ¶¶ 580-582.

#### **4. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.B.2-XII.B.3. EX1002, ¶ 676.

**C. Claim 6 – “the combustion chamber is an electric utility coal combustion chamber.”**

**Claim 7 – “the combustion chamber is a coal combustion furnace.”**

**Claim 22 – “the combustion chamber comprises a boiler”**

**1. Ground 1 – Downs**

Downs describes and depicts coal-fired electric utility plants having a boiler 12 and combustion furnace 14. EX1004, [0012]–[0015]; EX1005, [0014]–[0018].

**2. Ground 2 – Downs/Altman**

*See* § XII.C.1 regarding Downs. Altman discloses that injection of activated carbon into flue gas was known in the art for removing mercury in coal-fired boilers before April 1997. EX1007, 2:24–2:31.

**3. Ground 3 – Vosteen/Altman**

*See* § XII.C.2 regarding Altman. Vosteen describes its “process for removing mercury from flue gases of ... power stations” which have a furnace and boiler. EX1011, [0001], [0005], [0034], [0046]–[0047], Fig. 9.

**4. Ground 4 – Blankinship**

Blankinship describes reducing “mercury emissions from power plants and other industrial facilities.” EX1012, 56. Blankinship explains “[b]romide can be added to the boiler or to the coal ....” *Id.*

**5. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.C.3–XII.C.4.

**D. Claims 8–9 – “the coal comprises a [subbituminous–cl. 8; lignite–cl. 9] coal.**

**1. Grounds 1-2 – Downs, Downs/Altman**

Downs describes the coal-fired boiler fuel 16 can be subbituminous or lignite coals. EX1004, [0020]; EX1005, [0023].

**2. Ground 3 – Vosteen/Altman**

Vosteen’s process for “removing mercury from flue gases of high-temperature plants” includes “for example bituminous coal-fired or lignite-fired power stations.” EX1011, [0008].

A POSITA would have considered the types of coal burned in coal-fired power plants. It would have been obvious to a POSITA to use a subbituminous coal because it is a type of coal used in electricity generation and is intermediate to bituminous and lignite coals in terms of native-halogen content. EX1012, 58; EX1065, iv–viii; EX1002, ¶¶ 424-427.

**3. Ground 4 – Blankinship**

Blankinship discloses “Alstom says KNX is most attractive for a client burning sub-bituminous coal” and “[l]ignite can be a good candidate for the process as well.” EX1012, 58.

**4. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.D.2–XII.D.3 regarding Vosteen and Blankinship.

- E. Claims 10, 12 – “[measuring the mercury content of the mercury-containing gas; and—Cl. 10] modifying, in response to [a—cl. 12] [the—cl. 10] measured mercury content [of the mercury-containing gas—cl. 10], an injection rate of injecting the sorbent into the mercury-containing gas, an amount of the Br<sub>2</sub>, HBr, the bromide compound, or a combination thereof, added to the coal or the combustion chamber, or a combination thereof.”**

**Claim 11 – “the measuring of the mercury content comprises continuous measurement.”**

**1. Ground 2 – Downs/Altman**

*See* § XI.D.1. A POSITA would have continuously monitored mercury content and would have considered it obvious to optimize the sorbent injection rate in Altman in view of Felsvang and/or the amount of bromine additive added to the coal in Downs since both variables affect mercury removal from a flue gas. EX1004, [0018], Figure 3; EX1005, [0021], Figure 3; EX1007, 4:62-5:5; EX1080, Abstract, 6:42-46; EX1002, ¶¶ 320-321.

**2. Ground 3 – Vosteen/Altman**

*See* § XI.D.2 regarding Vosteen and Altman. EX1002, ¶¶ 434-435.

**3. Ground 5 – Blankinship/Vosteen or Blankinship/ Olson-235**

*See* § XI.D.2 regarding Vosteen. EX1002, ¶¶ 686-692.

Olson-235 describes “continuous measurement of mercury emissions as feedback to assist in control of the sorbent injection rate. Tighter control on the sorbent ... will ensure mercury removal requirements are met with minimal material requirements, thus minimizing the associated costs.” EX1013, 20:1-11, 14:20–29. Olson-235 discloses, “the rate at which the promoter is added and the rate of

promoted sorbent injection are determined by a digital computer based, at least in part, on the monitored mercury content of the cleaned flue gas.” EX1013, 6:15-31. Thus, Olson-235 measures the mercury content of the mercury-containing clean flue gas and modifies the injection rate of promoter into the combustion chamber and/or sorbent injection in response to the measured mercury content.

**F. Claim 13 – “the mercury-containing gas comprises about 1 g to about 30 g of the element bromine per 100 g of the sorbent.”**

This claim lacks written description support in the ‘343 application for the ‘430 Patent and all earlier priority applications because the promoted sorbent (not the mercury-containing gas) is described as comprising about 1-30g promoter per 100g base sorbent. EX1001, 3:19-21, 52-54; 4:40-45; 5:4-19; 11:1-3; 20:35-38; 24:52-54; 25:43-46, 62-65; 26:6-9, 24-26; 33:51-54. *See also* § XII.I.

Claim 13 claims a workable range for combining a conventional halogen (bromine) used in a conventional way (to promote a sorbent) with a conventional sorbent (activated carbon). Nothing in the ‘430 Patent indicates any criticality to the claimed range or establishes any “unexpected results.” The range presents nothing more than optimization of “result-effective” variables that would have been obvious to a POSITA. *In re Applied Materials, Inc.*, 692 F.3d 1297-98 (Fed. Cir. 2012); EX1002 ¶¶ 322-323, 436-437, 693-694; EX1089, 35 (PO does not dispute that the range is “nothing more than optimization of result-effective variables that would have been obvious to a POSITA”); EX1083, 153 (ratio is “necessarily” present for

‘114 claim 4 accordingly to PO’s expert), 170 (applying same analysis for ‘517 claims 19 and 21 which read the same as ‘430 claims 13 and 17).

**G. Claim 14 – “the sorbent contacted with the mercury comprises the element bromine and mercury”**

**1. Ground 2 – Downs/Altman or Downs/Altman/Nelson**

*See* § XI.C.2 regarding discussion of element 29(b). It follows the sorbent of Downs or Downs/Altman comprises bromine, sorbent and mercury when in-flight promotion occurs.

Nelson explains “in exposing PAC to concentrated bromine gas, ... the bromine reacts with the carbon, forming surface compounds on ... the carbon. When the PAC is then injected into the flue gas, the elemental mercury and oxidized mercury species there appear to react with at least one form of the bromine-carbon surface compounds .... When the carbon particles are removed from the flue gas ... the mercury is removed with them.” EX1008, [0043]; EX1009, 4. EX1002, ¶¶ 324-326.

**2. Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson**

*See* § XI.C.2 regarding discussion of element 29(b). It follows the sorbent of Vosteen/Altman comprises bromine, sorbent and mercury when in-flight promotion occurs. *See* § XII.G.1 regarding Nelson’s explanation of how the sorbent comprises bromine, sorbent and mercury. EX1002, ¶¶ 438-440.

### 3. Ground 5 – Blankinship/Vosteen or Blankinship/Olson-235

See § XI.C.2 regarding discussion of element 29(b). It follows the sorbent comprises bromine, sorbent and mercury when in-flight promotion occurs. EX1002, ¶¶ 695-696.

#### H. Claims 15–16 – “removing greater than 70 wt % of the mercury in the mercury-containing gas [with the sorbent–Cl. 16].”

##### 1. Ground 1 – Downs

Downs’ Figure 3 reports reducing vapor-phase mercury of flue gas by 77% from 9 µg/dscm mercury (red) at FF-inlet to 2 µg/dscm mercury (blue) at FF-outlet:




FIG. 3

EX1004, Figure 3, [0018]; EX1005, Figure 3, [0021] (red annotations added).

Downs describes “an increased-fraction of particulate-bound mercury” that

enhances removal across particulate collectors such as ESPs. EX1004, [0015]; EX1005, [0018]. EX1002, ¶¶ 233-243.

## **2. Ground 2 – Downs/Altman**

*See* § XII.H.1 regarding Downs. Altman describes 90% mercury removal using “an appropriate sorbent.” EX1007, 2:14-22. A POSITA would have reasonably expected the Downs/Altman combination of bromide and sorbent treatments would achieve greater than 70% mercury removal by the sorbent due to bromide’s ability to increase oxidized mercury and “higher reactivity of oxidized mercury with PAC.” EX1004, [0016]; EX1005, [0019]; EX1002, ¶ 310.

## **3. Ground 3 – Vosteen/Altman**

*See* § XII.D.2 regarding Altman. Vosteen reports mercury removal greater than 70 wt.% in that flue gas Hg<sub>met</sub> content was about 40 wt.% and was reduced to 10 wt.% at time 10:30. EX1011, Figure 8, [0049], Figure 5, [0042], [0015], [0037]. A POSITA would have reasonably expected the Vosteen/Altman combination of bromide and sorbent treatments would achieve greater than 70% mercury removal by the sorbent due to bromide’s ability to increase oxidized mercury and “higher reactivity of oxidized mercury with PAC.” EX1002, ¶¶ 441-451.

## **4. Ground 4 – Blankinship**

Blankinship reports mercury removal of 80–90% for the Alstom process, and the sorbent absorbs the mercury. EX1012, 58. A POSITA would have understood

the activated carbon sorbent of the Mer-Cure system collected the mercury from the flue gas. EX1002, ¶¶ 592-599.

## **5. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.H.3–XII.H.4 regarding Vosteen and Blankinship. EX1002, ¶ 679.

### **I. Claim 17 – “the sorbent in the mercury-containing gas comprises about 1 g to about 30 g of the added Br<sub>2</sub>, HBr, the bromide compound, or a combination thereof, per 100 g of the sorbent.”**

Claim 17 claims a workable range for a conventional halogen (bromine) used in a conventional way (to promote activated carbon) with a conventional sorbent (activated carbon) and is obvious. Nothing in the ‘430 Patent specification attributes any particular significance to the claimed range or establishes any “unexpected results” in mercury removal. Rather, the range presents nothing more than optimization of “result-effective” variables that would have been obvious to a POSITA. *See In re Applied Materials, Inc.*, 692 F.3d 1289, 1297–98 (Fed. Cir. 2012); EX1002 ¶ 327-333; EX1089, 35 (PO does not dispute that the range is “nothing more than optimization of result-effective variables that would have been obvious to a POSITA”).

A POSITA knew since the 1970s that the saturation limit of bromine in activated carbon was around 31–38 grams per 100 grams of activated carbon. EX1050, 260; EX1002, ¶ 51.

### **1. Ground 2 – Downs/Altman or Downs/Altman/Nelson**

Given its ordinary meaning, “the sorbent” in claim 17 is a promoted brominated activated carbon sorbent because it “has a composition comprising” both bromine and activated carbon. Nelson discloses brominated PAC sorbents having 1, 5, 9, 15, and over 30 wt.% loading of HBr or Br<sub>2</sub> (i.e., 1, 5, 9, 15 or over 30g bromine to 100g PAC). EX1008, [0054], Example 6; EX1009, 5 (15 wt.% loading for 500-1000% increase in mercury capacity). EX1002, ¶ 327-329.

If claim 17 is construed as not requiring “the sorbent” be a promoted sorbent, then a POSITA would look to the relative amounts of bromine to sorbent in the flue gas. Given the residence times in flue gas, a POSITA would have understood that bromine loaded onto activated carbon would be less than the 31-38g per 100g maximum. EX1002 ¶ 330; EX1050, 260. A POSITA would have recognized there would be sufficient bromine in the flue gas to provide a ratio of 1–30 g of bromine per 100 g of activated carbon. Indeed, PO’s expert in the Delaware lawsuit stated: “power plants employing bromine additives and activated carbon would necessarily produce a sorbent that is 1g to 30g bromine per 100g of activated carbon.” EX1083, 153. Claim 17 is obvious. EX1002, ¶ 330-333.

### **2. Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson**

If claim 17 is construed as requiring “the sorbent” be a promoted sorbent, then *see* Nelson discussion in § XII.I.1. EX1002, ¶¶ 452-454.

If claim 5 is construed as not requiring “the sorbent” be a promoted sorbent, then see the analysis in § XII.I.1. EX1002, ¶¶ 455-458.

### **3. Ground 5 – Blankinship/Olson-235**

If claim 17 is construed as requiring “the sorbent” be a promoted sorbent, then Olson-235 discloses the promoted sorbent “comprises from about 1 to about 30 grams of promoter per 100 grams of base sorbent.” EX1013, 4:53–60, Claims 3, 17. Olson-235 also discloses an embodiment wherein “the injected sorbent is prepared in-flight by reacting a base sorbent (carbon, non-carbon or their combination) and a promoter within a pneumatic transport line from which the reaction product is injected to the mercury-containing flue gas stream.” EX1013, 5:43–48. In that embodiment, “the promoter is added at from about 1 to about 30 grams per 100 grams of the base sorbent.” EX1013, 6:17–31. EX1002, ¶¶ 697-700.

#### **J. Claim 18 – “the Br<sub>2</sub>, HBr, or the bromide compound is contacted with the sorbent in vapor form, gaseous form, liquid form, or in an organic solvent.”**

##### **1. Grounds 1–2 – Downs, Downs/Altman**

Downs describes “gaseous, liquid or solid form” for the bromine-containing reagent 10, which can be HBr, Br<sub>2</sub> or a bromide compound such as a metal bromide. EX1004, [0021]–[0022]; EX1005, [0024]–[0025]. The bromine in the flue gas is contacted with the activated carbon sorbent when the activated carbon is injected into the flue gas. EX1004, [0016]; EX1005, [0019]; EX1002, ¶¶ 247-248. Thus, the bromide compound is contacted with the sorbent in gaseous form.

## **2. Ground 3 – Vosteen/Altman**

Vosteen describes “addition of a bromine compound ... leads to a gas-phase reaction between mercury and bromine.” EX1011, [0010]. At least a portion of Vosteen’s NaBr added to the coal would have vaporized during combustion and reacted to form HBr in the flue gas. EX1014, 1658. Thus, HBr is contacted with Altman’s sorbent in vapor form. EX1048, 98:23–100:3, 231:3–9; EX1083 154, 170; EX1007, 6; EX1002, ¶¶ 459-460.

## **3. Ground 4 – Blankinship**

*See* § XI.B.1 regarding Julien. Thus, HBr is in vapor or gaseous form in the flue gas post-combustion. The flue gas containing HBr from KNX decomposition as in Blankinship is contacted with the activated carbon in the Mer-Cure system when the activated carbon is injected into the flue gas. EX1012, 56; EX1002, ¶¶ 600-604.

## **4. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.J.2–XII.J.3. EX1002, ¶ 680.

**K. Claim 19 – “the activated carbon comprises powdered activated carbon, granular activated carbon, or a combination thereof.”**

### **1. Ground 1 – Downs**

Downs discloses using a PAC sorbent injection system. EX1004, [0004], [0015]–[0016], claims 15–16; EX1005, [0005], [0018]. EX1002, ¶¶ 249-250.

## **2. Ground 2 – Downs/Altman**

*See* § XII.K.1. Altman discloses that the activated carbon sorbents can be “particles.” EX1007, 5:59-61. EX1002, ¶ 308.

## **3. Ground 3 – Vosteen/Altman**

*See* § XII.K.2 regarding Altman. Vosteen describes granulated or pulverant activated carbon in its flue gas emission control systems. EX1011, [0019]; EX1002, ¶¶ 461-463.

## **4. Ground 4 – Blankinship**

Blankinship discloses that the Mer-Cure system differs from other post-combustion activated carbon sorbent systems because it “has an on line processor that keeps the resulting material from sticking together and de-agglomerates it to create smaller particle sizes and greater surface area.” EX1012, 58. Thus, small activated carbon particles are powdered or granular. Blankinship explains “[t]here are also variations of sorbent injection that provide ways to introduce activated carbon into flu[e] gas. ... There are also ways to agglomerate the carbon or grind it finer on site to achieve better mass transfer.” EX1012, 56.

## **5. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.K.3–XII.K.4 regarding Vosteen and Blankinship. EX1002, ¶¶ 605-608, 681.

- L. Claim 20 – “the sorbent injected into the mercury-containing gas is a sorbent obtained by contacting a sorbent with a halogen or halide promoter prior to the injection of the sorbent into the mercury-containing gas.”**

**1. Ground 2 – Downs/Altman/Nelson**

Nelson describes exposing activated carbon sorbent to a bromine-containing gas before the sorbent is mixed with mercury-containing flue gas. EX1008, [0040]; EX1009, 4. A POSITA had reason to substitute Nelson’s brominated-activated carbon sorbent for Altman’s activated carbon sorbent in the Downs/Altman process because Nelson indicates exposure of sorbent to Br<sub>2</sub> or HBr gas “significantly increases the carbonaceous materials ability to remove mercury species.” EX1008, [0041], Figures 12 & 14; EX1009, 4. A POSITA would have known this approach would have increased overall mercury capture. EX1002, ¶¶ 334-337. For example, it was known since the 1930s to remove mercury vapors by injecting halogen-impregnated activated-carbon sorbents into a mercury-containing flue gas. EX1049, 1:33–41.

**2. Ground 3 – Vosteen/Altman/Nelson**

*See* § XII.L.1 regarding Nelson. A POSITA had reason to substitute Nelson’s brominated-activated carbon sorbent for Altman’s activated carbon sorbent in the Vosteen/Altman process for the stated reasons. EX1002, ¶¶ 464-467.

### **3. Grounds 4–5 – Blankinship, Blankinship/Vosteen or Blankinship/Olson-235**

Blankinship describes use of a bromine-treated or untreated activated carbon sorbent and indicates both sorbent types are being “deployed at a number of power plants.” EX1012, 56. A brominated sorbent would have been brominated prior to injection of the sorbent to the mercury-containing gas. EX1002, ¶¶ 609-611.

Olson-235 describes contacting a base sorbent 10 with a halogen or halide promoter 20 prior to injection of the sorbent into flue gas 50. EX1013, Figure 1, 10:17-37. EX1002, ¶ 682.

#### **M. Claim 21 – “the sorbent injected into the mercury-containing gas is free of contact with a halogen or halide promoter prior to injection of the sorbent into the mercury-containing gas.”**

A POSITA had reason to select halogen-free activated carbon due to its lower cost as compared to halogen-activated carbons especially where sufficient mercury removal can be achieved without resorting to halogen-activated carbons. EX1002, ¶ 253, 311, 470, 614.

#### **1. Ground 1 – Downs**

Downs did not characterize the activated carbon sorbent as being pre-brominated or impregnated with halogens prior to injection. EX1004; EX1005.

#### **2. Ground 2 – Downs/Altman or Downs/Altman/Nelson**

*See* § XII.M.1 regarding Downs. Altman did not characterize the activated carbon sorbent as being pre-brominated or impregnated with halogens prior to

injection. EX1007. Nelson tests Norit DARCO FGD, which is not halogen- or halide-promoted. EX1008, Ex. 1; EX1009, 5.

A POSITA had reason to select halogen-free activated carbon due to its lower cost. EX1002, ¶ 311.

**3. Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson**

*See* § XII.M.2 regarding Altman and Nelson. EX1002, ¶¶ 468-471.

**4. Grounds 4–5 – Blankinship or Blankinship/Vosteen**

Blankinship explains “activated carbon and brominated activated carbon injection technology are being deployed at a number of power plants.” EX1012, 56. EX1002, ¶¶ 612-615.

**N. Claim 23 – “the mercury-containing gas is a flue gas.”**

**1. Grounds 1-2 – Downs, Downs/Altman or Downs/Altman/Nelson**

Downs describes “removal of mercury from flue gas.” EX1004, Title; EX1005, Title. Altman discloses “removal of ... mercury from the flue gas of a combustor.” EX1007, 1:5-9. Nelson describes “a sorbent material ... injected into a hot mercury-containing combustion gas, so that a significant portion of the mercury is adsorbed onto the sorbent and removed from the flue gas.” EX1008, [0019]; EX1009, 4. EX1002, ¶¶ 255-256.

## **2. Ground 2 – Vosteen/Altman or Vosteen/Altman/Nelson**

*See* § XII.N.1 regarding Altman and Nelson. Vosteen is titled “Process for Removing Mercury from Flue Gases.” EX1011, Title, Abstract, cl. 1. *See* § XII.N.1. EX1002, ¶¶ 472-473.

## **3. Grounds 4-5 – Blankinship or Blankinship/Vosteen**

*See* § XII.N.2 regarding Vosteen. Blankinship describes “variations of sorbent injection that provide ways to introduce activated carbon into flu[e] gas.” EX1012, 56. EX1002, ¶¶ 616-617.

**O. Claim 24 – “the injection of the sorbent into the mercury-containing gas occurs upstream of a particulate separator, a scrubber, or a combination thereof.”**


**Claim 25 – “the particulate separator comprises a baghouse, an electrostatic precipitator, a fabric filter, or a combination thereof.”**

### **1. Ground 1 – Downs**


Downs describes “sorbent ... removed from the flue gases in a downstream particulate collector” 26 such as an ESP or FF, or a wet FGD system 22. EX1004, [0004], [0015], [0023], Figures 4–6; EX1005, [0005], [0018], [0026], Figures 4–6. EX1002, ¶¶ 257-263.

### **2. Ground 2 – Downs/Altman or Downs/Altman/Nelson**

*See* § XII.O.1 regarding Downs. Altman’s Figure 2 depicts sorbent injection upstream of wet electrostatic precipitator (ESP) 51, which is a “particulate control device” that collects sorbent. EX1007, 4:17–21, 58–61; 5:27–29; Figure 2; EX1002, ¶¶ 312-313.



Nelson describes injecting sorbent from bin 71 upstream of ESP 32. EX1008, [0062], Figure 4.



### **3. Ground 3 – Vosteen/Altman or Vosteen/Altman/Nelson**

*See* § XII.O.2. EX1002, ¶¶ 474-480.

### **4. Grounds 4–5 – Blankinship or Blankinship/Vosteen**

Blankinship discloses “[p]ower plants without an FGD would likely use sorbent injection, mostly an activated carbon, upstream of a particulate control device. The particulate control can be either the plant’s existing device or a compact baghouse installed following the primary particulate control, with sorbent injection between the primary control and the new baghouse.” EX1012, 56.

Blankinship explains Mer-Cure systems are “targeted primarily to ESP configurations, [but] Alstom has also installed it on wet scrubber applications where the combination of Mer-Cure and KNX worked well.” EX1012, 58. EX1002, ¶¶ 618-625.

**P. Claim 26 – “a halide sorbent enhancement additive comprises the added Br<sub>2</sub>, HBr, bromide compound, or combination thereof.”**

**Claim 27 – “the sorbent enhancement additive comprises the bromide compound.”**

The ‘430 Patent does not define “sorbent enhancement additive.”

### **1. Grounds 1–2 – Downs or Downs/Altman**

Downs reports adding bromide compounds, HBr or Br<sub>2</sub> as the bromine-containing reagent 10 that is premixed with incoming coal 16. EX1004, [0015], [0021]; EX1005, [0018], [0024]. Downs also discloses calcium bromide injected

into the combustion chamber through a coal burner. EX1004, [0018]; EX1005, [0021]. EX1002, ¶¶ 264-273, 315.

## **2. Ground 3 – Vosteen/Altman**

Vosteen discloses “bromine compound, for example, sodium bromide, can be added in solid form, for example as salt, or liquid form, for example as aqueous solution, to the waste mixture, coal or the like to be burnt, upstream of the furnace. The addition can also be made to a plant section upstream of the furnace, for example ... to a coal mill.... The compound can also be fed during the combustion process.... [or] after the combustion, for example in a downstream waste-heat boiler.” EX1011, [0013]. EX1002, ¶¶ 481-488.

## **3. Ground 4 – Blankinship**

Blankinship explains Alstom’s KNX™ calcium bromide solution “can be added to the boiler or to the coal to oxidize the mercury and facilitate its capture in wet scrubbers” or in electrostatic precipitators (ESPs). EX1012, 56, 58. Calcium bromide is a “bromide compound” because it is “a substance composed of atoms or ions of two or more elements in chemical combination” in which “constituents are united by bonds or valence forces.” EX1015, 291; EX1002, ¶¶ 626-636.

## **4. Ground 5 – Blankinship/Vosteen**

*See* §§ XII.P.2-XII.P.3. EX1002, ¶ 683.

### **XIII. CONCLUSION**

Petitioner respectfully requests that the Petition be instituted and the Challenged Claims be cancelled as unpatentable.

Dated: July 18, 2025

Respectfully submitted,

By: /s/ Robert M. Evans, Jr.

Robert M. Evans, Jr., Reg. No. 36,794

Kathleen Markowski Petrillo, Reg. No. 35,076

Michael J. Hartley, Reg. No. 67,230

LEWIS RICE LLC

600 Washington Avenue, Suite 2500

St. Louis, MO 63101

T: 314-444-7784; F: 314-612-7784

Email: [revans@lewisrice.com](mailto:revans@lewisrice.com)  
[kpetrillo@lewisrice.com](mailto:kpetrillo@lewisrice.com)  
[mhartley@lewisrice.com](mailto:mhartley@lewisrice.com)

*Counsel for Petitioner*

## **CERTIFICATE OF COMPLIANCE**

Pursuant to 37 C.F.R. § 42.24(d), the undersigned certifies that the foregoing Petition, exclusive of the exempted portions as provided in 37 C.F.R. § 42.24(a), contains 13,993 words which is no more than 14,000 words and therefore complies with the type-volume limitations of 37 C.F.R. § 42.24(a). The word count was calculated by starting with Microsoft Word's total document word count and subtracting the words for the Table of Contents, the Exhibit List, the Mandatory Notices, the Certificate of Compliance, and the Certificate of Service.

This paper also complies with the typeface requirements of 37 C.F.R. § 42.6(a)(2)(ii) and the type style requirements of 37 C.F.R. § 42.6(a)(2)(iii) and (iv).

Dated: July 18, 2025

By: /s/ Robert M. Evans, Jr.  
Robert M. Evans, Jr., Reg. No. 36,794  
LEWIS RICE LLC  
600 Washington Avenue, Suite 2500  
St. Louis, MO 63101  
T: 314-444-7784; F: 314-612-7784  
Email: [revans@lewisrice.com](mailto:revans@lewisrice.com)

*Lead Counsel for Petitioner*

## **CERTIFICATE OF SERVICE**

In accordance with 37 C.F.R. §§ 42.6(e) and 42.105, the undersigned certifies that on July 18, 2025, a complete and entire copy of the PETITION FOR *INTER PARTES* REVIEW (“petition”), Power of Attorney, and related Exhibits were served on Patent Owner at the correspondence address of record for the subject patent,

SCHWEGMAN LUNDBERG & WOESSNER, P.A.  
P.O. Box 2938  
Minneapolis, Minnesota 55402

via Priority Mail Express or by means at least as fast and reliable as Priority Mail Express.

Further, a courtesy copy was served via electronic mail on the Patent Owner’s counsel at the following addresses:

CALDWELL CASSIDY CURRY PC  
2121 N. Pearl Street, Suite 1200  
Dallas, Texas 75201

Bradley W. Caldwell  
[bcaldwell@caldwellcc.com](mailto:bcaldwell@caldwellcc.com)

Justin T. Nemunaitis  
[jnemunaitis@caldwellcc.com](mailto:jnemunaitis@caldwellcc.com)

Dated: July 18, 2025

By: /s/ Robert M. Evans, Jr.  
Robert M. Evans, Jr., Reg. No. 36,794  
LEWIS RICE LLC  
600 Washington Avenue, Suite 2500  
St. Louis, MO 63101  
T: 314-444-7784; F: 314-612-7784  
Email: [revans@lewisrice.com](mailto:revans@lewisrice.com)

*Lead Counsel for Petitioner*