

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

DECLARATION (37 CFR 1.63) FOR UTILITY OR DESIGN APPLICATION USING AN APPLICATION DATA SHEET (37 CFR 1.76)

**Title of
Invention**

Power Source Load Control

As the below named inventor, I hereby declare that:

This declaration is directed to: ☒ The attached application, or

☐ United States application or PCT international application number _____
filed on _____.

The above-identified application was made or authorized to be made by me.

I believe that I am the original inventor or an original joint inventor of a claimed invention in the application.

I hereby acknowledge that any willful false statement made in this declaration is punishable under 18 U.S.C. 1001 by fine or imprisonment of not more than five (5) years, or both.

WARNING:

Petitioner/applicant is cautioned to avoid submitting personal information in documents filed in a patent application that may contribute to identity theft. Personal information such as social security numbers, bank account numbers, or credit card numbers (other than a check or credit card authorization form PTO-2038 submitted for payment purposes) is never required by the USPTO to support a petition or an application. If this type of personal information is included in documents submitted to the USPTO, petitioners/applicants should consider redacting such personal information from the documents before submitting them to the USPTO. Petitioner/applicant is advised that the record of a patent application is available to the public after publication of the application (unless a non-publication request in compliance with 37 CFR 1.213(a) is made in the application) or issuance of a patent. Furthermore, the record from an abandoned application may also be available to the public if the application is referenced in a published application or an issued patent (see 37 CFR 1.14). Checks and credit card authorization forms PTO-2038 submitted for payment purposes are not retained in the application file and therefore are not publicly available.

LEGAL NAME OF INVENTOR

Inventor: J. Carl Cooper Date (Optional) : _____

Signature: /J. Carl Cooper/

Note: An application data sheet (PTO/SB/14 or equivalent), including naming the entire inventive entity, must accompany this form or must have been previously filed. Use an additional PTO/AIA/01 form for each additional inventor.

This collection of information is required by 35 U.S.C. 115 and 37 CFR 1.63. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.11 and 1.14. This collection is estimated to take 1 minute to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

Privacy Act Statement

The **Privacy Act of 1974 (P.L. 93-579)** requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether disclosure of these records is required by the Freedom of Information Act.
2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.
3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.
4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).
5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.
6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).
7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (*i.e.*, GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.
8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspection or an issued patent.
9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.




Figure 1
Prior Art




Figure 2
Prior Art




Figure 3
Prior Art




Figure 4




Figure 5




Figure 6




Figure 7




Figure 8






Figure 9






Figure 12




Figure 13




Figure 14




Figure 15




Figure 16




Figure 17




Figure 18

ABSTRACT

A method and apparatus for controlling the total load presented to an AC power source such as a generator or inverter used to provide backup or portable power. The frequency of the output AC power is controlled in response to the loading on the power source, thereby providing information about that loading of the power source which is carried by the AC power itself, thus reducing or eliminating the need for traditional wired and wireless communications. By controlling the frequency of AC power, controllable loads and load control devices can determine the amount of remaining power available from the power source in order to determine if a given load can be connected without creating an overload. The frequency may also be controlled at the power source to indicate an overload, with the loads being responsive to that overload frequency to reduce the load and thereby alleviate the overload.

INVENTION TITLE

Power Source Load Control

DESCRIPTION

Heading

BACKGROUND OF THE INVENTION

[Para 1] This application is a division of, and incorporates herein by reference, application number 13/481,804 filed March 16, 2013 which in turn claims benefit of, and incorporates by reference in their entirety, provisional patent applications: Power Source Load Control, application number 61/490,253 filed May 26, 2011; Power Source Load Control, application number 61/552,722 filed October 28, 2011; Load Control, application number 61/598,564 filed February 14, 2012 and Genset Overload Control, application number 61/624,360 filed April 15, 2012, which provisional applications are also incorporated herein by reference.

[Para 2] The background of the invention, summary of the invention, brief description of the figures, detailed description of the preferred embodiment, claims and abstract are presented and described herein to a person having ordinary skill in the art to which the subject matter pertains, hereinafter sometimes referred to as person of ordinary skill or one of ordinary skill. Many people of ordinary or advanced skill in the art commonly use words, for example such as generator and load, to have language, location and context specific meaning. This usage works well for providing understanding and clarity to a person of ordinary skill, despite using words having several potential meanings. For example, valve is used in Europe in relation to vacuum tubes and in North America in relation to gaseous and fluid controls. Gas is used in the U.S. to mean gasoline and the gaseous state of a substance. One of ordinary skill will know from the language, location and context used which meaning of more than one possible meaning is intended.

[Para 3] As one example to demonstrate how the intended meaning is the known meaning to one of ordinary skill, consider a power generating device which is often referred to simply as a generator by one of ordinary skill, relying on the field of art and context of usage to supply specific meaning and limitations to the particular name generator. A person of ordinary skill writing a technical article about a backup generator used in the art of heating (or otherwise powering) a suburban home during loss of public utility power would know and intend generator to mean an electrical generator. A person of ordinary skill writing a technical article about a backup generator used in the art of heating a building in a large city during loss of public utility power would know that generator could be a steam generator. According to this example, depending on context, one of ordinary skill would know generator to mean a steam generator or an electrical generator. As another example, in the electrical power generating art generator is commonly meant to mean the generating device such as a motor or turbine and electrical alternator combination. As yet another example in the electrical art an electrical generator (often used in pre 1960's vehicles) outputs D.C. power and is distinguished from an alternator (often used in post 1960's vehicles) which creates A.C. power which is internally rectified to provide the needed D.C. power. Load may refer to the total load on a generator, or an individual load presented by a particular device, or may refer to the device itself which presents a load. The person of skill will recognize the meaning of generator and load from the context in which it is used.

[Para 4] As set forth in more detail in MPEP 2111.01 (July 2010 revision is referred to herein), Applicant, as his own lexicographer, intends the words and phrases used in the specification and claims to have their plain U.S. English meaning, unless it is clear from the specification that they have been given a different meaning. When a word or phrase for example such as a technical word or phrase has a meaning to one of ordinary skill from the location, context, usage, time frame and/or what is well known in the art to differ from the plain U.S. English meaning as of the pertinent date, Applicant intends that meaning which is

known to one of ordinary skill to be used. As set out in MPEP 2182 a patent specification need not teach, and preferably omits, what is well known in the art. Thus Applicant further notes that a meaning of a word or phrase which is well known in the art may not be specifically set forth in the instant specification other than by this note.

[Para 5] In a facility where a power source provides power to one or more devices which each present a load or loads to the power source there is a need to determine and control which and how many loads are connected in order that the total of the loads does not create an overload. Overloads are generally undesirable in that they may cause deviation from power output specifications, loss of power, damage or combinations thereof. In the above power source (generator) examples an overload could cause steam to not be hot enough, or electric voltage to be too low or have the wrong frequency. Additionally, management of the creation of power by the power source, as well as the loads connected thereto is desirable for efficient operation.

[Para 6] A given power source has a maximum load handling capability dictated by the power generation and delivery path (e.g. pressure, voltage, pipe size, wire size) or a maximum output (e.g. dictated by the design of the power source and the system it is used in). For simplicity, devices that may be connected to the power source are often referred to in the art and herein as loads. For a given group of loads that are available for connection, it may be desirable to inhibit a particular individual load from being connected to the power source at a given time (e.g. preventing connection or disconnecting an already connected load) or during a given time period or to restrict the power supplied to the load (e.g. by controlling coupling), or the power consumed by the load (e.g. by controlling the load). It may also be desirable to allow a given load to be connected at a given time or during a given time period. For example it may be desirable to inhibit the connection of a large load during times of high load demands, or to allow that load to be connected and operated only

during night hours when there is ample power available and/or when fuel or energy rates are cheaper.

[Para 7] One of ordinary skill will recognize from the teachings herein that the inventive concepts given by way of example may be utilized for many types of power systems, including but not limited to hydraulic, fluid or gaseous heating, mechanical, thermal, solar, wind, liquid fuel, gas fuel, solid fuel and combinations thereof. The use of the invention with various types of systems will be known to the person of skill and in particular by use of well known correlations between electrical, fluid, chemical and mechanical systems. For example a voltage in an electrical system correlates to pressure in a fluid system, amperage to flow rate, wire size to pipe size, switch to valve, etc. While the present invention will be known from the teachings herein to have applicability to many forms of power sources and loads the background and teachings will be given by way of example with respect to electrical generators and loads. The electrical generators used by example often include a rotating power source and AC alternator combinations and are often referred to in the art as generator sets, gensets or simply generators as well as by a host of other names which are frequently specific to the particular type of energy source, power output and/or alternator used.

[Para 8] The connection and disconnection of power from the power source to the load is in general controlled by one or more switch and it will be understood that there are many types of switching mechanisms that may perform such connection and disconnection. When speaking of switch, switching, connection or disconnection it will be understood that such action is not meant to be restricted to a particular type of switch or connection unless the type is specifically enumerated or is apparent from the context. For example when teaching connecting, coupling or switching power from an electrical generator to an electrical load it will be understood that the action is performed by an electrical circuit, for example a switch but the teaching is not otherwise limited to a particular type of electrical switch unless

specifically enumerated. If the teaching is with respect to controlling the amount of current or load (as compared to simply switching the current or load on or off) it will be known that a simple on/off type of switch is not meant and the switch must be some sort which can control the amount of current.

[Para 9] Often there are multiple types of electrical devices available to be connected to and powered by the power source. Some devices may simply be turned on and off and some devices have loads which will vary with time or environment. A maximum load can occur when all devices are powered at the same time and each device presents its individual maximum load to the power source. As a simple example, it is possible to turn on all of the lights and appliances in a house, but that rarely happens. In many systems maximum loads are rarely presented to the power source and the typical load is frequently much less than the maximum load. That causes a system design problem because it is necessary for the power source, in the present example an electric generator, to provide power to the maximum load to prevent overload but that capability generally makes powering the typical load inefficient.

[Para 10] By way of background one of ordinary skill will recognize that several factors are involved in both the amount of power that can be supplied by a power generator and the amount of power consumed by a particular device which is being powered. The output of a wind turbine is dependent on the amount of wind and the design of the turbine. A solar cell array is dependent on the amount of sunlight and the design of the array. An electrical generator is dependent on the mechanical power available to turn the alternator. For a typical liquid or gaseous fuel powered backup generator, the maximum output is dependent on the size of the internal combustion engine, the alternator and its operating conditions.

[Para 11] With respect to internal combustion engine powered electrical generators the maximum power available and transferred to a load for a given size generator is generally

dependent on many factors such as the generator's internal temperature, ambient temperature, humidity, altitude and barometric pressure, type of electrical connection (e.g. voltage and single or multiple phase), power factor of the load, fuel quality, fuel delivery rate and duration of the load. Generally the internal temperature of the engine is a factor in determining the safe maximum output of the engine and the internal temperature of the alternator is a factor in determining the safe maximum current output from the alternator. Internal temperatures of the engine and alternator are dependent on load, ambient temperature, altitude, barometric pressure and humidity, among other factors. Engine efficiency is also dependent on various fuel and air quality factors. A generator can usually withstand higher currents when it is cool but those currents will soon (often in the matter of a few minutes) cause additional internal heating which in turn limits the maximum output current. Electrical generators often have two maximum power ratings, one for generator use as a backup power source and one for use as a prime power source. The prime power maximum is usually lower in part due to the continuous operation.

[Para 12] Efficient operation of such generators is usually a consideration in the selection of the generator which in turn leads to a need for the present invention to manage the load presented to the generator. As an example, consider the specifications of a Cummins model GGHE 60 kW electric power generator which includes an AC alternator which is driven by a 6.8 liter V10 internal combustion engine using natural gas as fuel. Electric power generators of this type are commonly used for backup power in large homes and small businesses to provide power in the event utility company power fails. Assume for this example that this generator is chosen to power a home which can present a maximum load of 60 kW to the generator, but a typical load is only 15kW.

[Para 13] At the full load output of 60 kW the natural gas fuel consumption for this generator is 24.4 cubic meters per hour (m^3/hour). One might think that at $\frac{1}{4}$ load this generator would burn fuel at approximately $\frac{1}{4}$ of the full load rate or 6.1 m^3/hour . That

assumption is incorrect however because the generator is much less efficient at $\frac{1}{4}$ load. The fuel burn rate for a 15 kW load is actually 10.6 m³/hour or about 43% of the full load rate. Among the several reasons for the inefficiency at lower loads is that the alternator and the big V10 engine's entire cooling system must be sized to handle heat output at full load. The coolant pump is pumping coolant through the engine and radiator, the fans are pulling cooling air through the alternator, across the engine and blowing air through the radiator thus performing maximum alternator and engine cooling whenever the engine is running. This cooling causes a considerable drain of engine power, even though all of that cooling is not needed for the 15 kW load. Other efficiency robbing factors such as engine friction and alternator windage are higher than needed for the typical load because of the design to handle maximum load.

[Para 14] If instead a less expensive Cummins model GGMA four cylinder generator rated at 20 kW were used as the power source, the natural gas burn rate when powering the typical 15 kW load is only 7.6 m³/hour. Using the smaller 20 kW generator is less expensive to purchase and operate and thus more efficient for the typical load. Unfortunately the 20 kW generator is unable to handle the 60 kW maximum load, which if connected to the generator would cause the generator circuit breaker to trip and all power to the load would be lost. As will be described herein the present invention will find use in such applications where a generator is unable to power the maximum load which can otherwise be presented to it.

[Para 15] With respect to the power required by a particular load several factors may be involved depending on the load type. Several examples of varying load will be briefly described to aid in understanding the invention. It will be understood that for most devices the voltage applied from the generator is substantially constant and consequently the current drawn by the device is proportional to the load on the generator. When the voltage from the generator is substantially constant the current supplied directly corresponds to the

power supplied and vice versa and either may be measured to obtain the other as is well known to one of ordinary skill. Many electric motors have a large starting current for a few seconds followed by a running current which depends on the mechanical work the motor is doing. For a motor such as one powering a vacuum cleaner that work depends on the amount of suction being created at any particular time which in turn depends on the technique of the person operating the vacuum. Heating appliances such as ovens often require more current to initially heat up than to maintain temperature once it is heated. This change is due in part to temperature dependent resistance changes of the heating elements.

[Para 16] An air conditioner will require a large starting current for a few or many seconds depending on the head pressure of the compressor pump and mass of the armature of the compressor motor and the moving components of the compressor pump. Once the compressor is up to operating speed the amount of current necessary to maintain that speed depends on the head pressure which in turn is partially dependent on the temperature of the condenser coil which in turn is dependent on ambient temperature and air density. If a compressor loses power the built up head pressure will take several dozen seconds or even minutes to bleed off through the capillary tube or expansion valve in the evaporator and if an attempt is made to restart the compressor before that head pressure has dissipated the starting current will be very large. If the head pressure is too high it can cause the compressor motor to stall which in turn will cause one or more circuit breakers to trip and remove the voltage supply from the compressor, thus care must be taken to not start the compressor too quickly after it has stopped. This can be an issue when utility power is lost and a backup generator is started to replace that lost power.

[Para 17] A battery charger used for example to charge the batteries in an electric or hybrid vehicle or the like, can change its load to the power source based on a variety of factors including the internal temperature of the batteries and their amount of charge. Generally the charging current is decreased with increased temperature and as the batteries approach

full charge. The control of battery charging current, especially in large battery arrays used with electric and hybrid vehicles and the like is well known in the art. For example U.S. Patent Application Publication 2010/0134073 assigned to Tesla Motors, Inc. describes an elaborate manner in which battery charging current, temperature and various other factors are controlled, which Publication is incorporated herein by reference in respect to its prior art teachings. It may be noted that by controlling charging current, the maximum load drawn from the power grid or generator can be controlled.

[Para 18] Tesla Motors, Inc. offers a high power connector which allows its vehicle to be connected to common 240 volt AC power circuits to charge the batteries. The Tesla Motors High Power Connector, or HPC includes a maximum current selector switch that is manually set at the time of installation such that the maximum amount of current which the charger is allowed to draw from the 240 volt circuit is limited according to the capability of the circuit connection to the supply. For example if a 40 amp circuit is used, the switch on the HPC is set to limit the HPC current draw to 32 amps. This is an important feature of the HPC because even though the charger is capable of operating with a 240 volt, 90 amp circuit for fast battery charging, many homes only have a 100 amp service connection and thus are incapable of providing current to the HPC via a 90 amp circuit without risk of overloading the service and tripping the main circuit breaker.

[Para 19] Returning now to the operation of a system having a variety of loads, in order to prevent sustained overloads and decrease the possibility of a circuit breaker trip or damage to a generator, especially those used for backup power, there are prior art systems which detect when a generator is in an overload condition and switch off loads. This operation is known as load shedding. Load shedding is well known in the prior art, for example a system is described in the Rodgers et al. U.S. Patent Application Publication 2005/0116814 which Publication is incorporated herein by reference in respect to its prior art teachings.

Paragraphs 70 – 115 are particularly pertinent. Importantly load shedding takes place when the load is connected and overload detected as described in more detail in this Publication [Para 20] Load managers for load shedding are commercially available, for example the Generac Nexus automatic transfer switch used in conjunction with backup power generators has a load manager option. These devices, which will be explained further below in respect to Figures 1–3, operate to start a gaseous or liquid fueled backup generator to power homes and businesses whenever power from the local power company fails and transfer the load from the local power company to the generator. This Generac transfer switch contains multiple switches, a main high current switch (e.g. 400 amps) for switching between the power grid and generator as the source of power for the home or business. It includes additional low current secondary switches to provide control voltages which are used to disconnect low priority loads via load managers such as the Generac DLC load control Module (contactors) when the generator is overloaded.

[Para 21] Most generator engines utilized for North American home backup systems rotate at 1800 or 3600 RPM, that rotation being coupled to an alternator that provides AC power at a standard 60 Hz frequency. When overloaded the rotation of the engine slows because the engine can not produce enough torque to keep the alternator rotating at the correct speed. The slow engine in turn causes the frequency of the AC power to decrease. The rotation and corresponding AC power frequency may drop substantially in the presence of a large overload and the engine and alternator can even attempt to rotate against their mounts, much like an automobile engine attempts to rotate against its motor mounts during heavy acceleration. The Nexus transfer switch includes technology which monitors the frequency of the AC power from the generator and sheds all of the low priority loads after the generator has been overloaded. Nonessential circuits (low priority loads) are shed by opening the secondary switches when the frequency of the AC power provided by the generator drops below 58 Hz (for 60 Hz systems). The secondary switch is used to control a

circuit to apply or remove voltage to a contactor to control applying and removing a corresponding load on the generator thereby removing the overload when the contactor is opened. Importantly this load shedding takes place after the overload happens.

[Para 22] Frequency detectors have tolerances which must be accounted for to avoid false tripping so there is a tradeoff in the speed of detection of off frequency condition vs. false detection due to frequency detector error or allowable momentary frequency deviation. For example if the frequency threshold for disconnecting the load is set at 58 Hz, inaccuracies in frequency detection may cause an overload to be falsely detected and a load disconnected when no overload exists. It is possible that a combination of overload, say one which slows the frequency to 58 Hz and inaccurate frequency detection, can cause an actual overload to go undetected. Unfortunately the overload, and possibly damage to the generator or its load, may have already happened by the time the overload is detected. Despite the various shortcomings in using power frequency as an indicator of generator overload, it will be understood from the present teachings that this is nevertheless an inexpensive manner of detecting and removing overloads, as will be taught further in connection with load limit and load switch operations.

[Para 23] As another example if an oven is turned on at the same time a storm drain pump automatically starts, it is still possible that the generator circuit breaker will trip before the overload can be detected and the excess load removed, thus all power will still be lost. Turning on an oven at night during a storm and having all power go off because the generator circuit breaker improperly tripped can be extremely troublesome, not to mention the inconvenience of having to find and reset that circuit breaker. At the least, it is inconvenient for someone in the home to turn on a device, only to have it or some other device(s) automatically disconnected from power shortly thereafter. In a home backup system that device causing the overload might be something that is needed in a timely fashion such as a medical device, lighting, a cooking appliance, a television, garage door

opener or other important device. In most situations it would be better to have a non-essential load such as a vehicle battery charger turned off or limited to prevent any overload.

Heading

SUMMARY OF THE INVENTION

[Para 24] It will be understood from the present teachings that it is desirable to control the total load presented to a particular power source to keep that load at or somewhat below the maximum capability of the power source. Alternatively it may be desirable to control the total load to keep the power source at or near its optimum power output to achieve high or maximum efficiency. As part of controlling the load to the power source it is desirable to connect some or all loads according to a priority. It is also preferred to alert the user that power is not available to power a particular device and allow the user to decide what to turn off or leave off than to have the device (and possibly several others) turned off shortly after it is turned on due to actual or potential overload. If loads are available that may but do not need to be connected and operated, it may be desirable to wait and operate them when the power source is operating well below its optimum efficiency. By waiting an increase in the efficiency of the operation is achieved with the added benefit of avoiding having to disconnect loads when the power source is operating at or somewhat below its maximum capability and an unexpected additional load is applied. Thus at least these two modes of operation are desired to be provided to facilitate reliability and efficiency, operation at or somewhat below maximum output capability and operation at, near or closer to optimum power source output.

[Para 25] It will be understood by one of ordinary skill that short term large loads may be allowed in that many engine driven alternator systems are designed to permit short term increases in power output above the maximum power that can be continuously delivered. As used herein and in the claims, overload means a load that if not disconnected or otherwise

prevented will either cause a departure from specifications for the power output from the power source, for example such as a deviation of AC power voltage or frequency for longer than a specified time period, a loss of power such as from a tripped circuit breaker, or damage such as overheating or exceeding mechanical stress limits.

[Para 26] When making decisions which are aimed at efficiency, one substantial consideration is the cost of providing power. If power can be obtained from the electric utility or elsewhere at lower cost during certain times, for example during the night, the invention can be utilized to control loads in a manner to best take advantage of the lower cost power. This can be done while still ensuring that the devices presenting the loads are available for use at other times if needed. Such use can include the device's intended function or use by a user, or as a load to improve power source efficiency. For example a battery charger for charging an electric or hybrid vehicle or the like can charge the battery to a given level such as half full, immediately upon being connected. This will ensure the vehicle is quickly available for use. The remainder of the charging from half to full charge can be delayed until lower price electricity is available. The delay of the remaining charge can also be used to boost an under utilized power source such as a backup generator closer to its optimum output for improved efficiency. Thus it is desired to control a charger to charge at a given rate as soon as connected until a first level of charge is reached and then charge at the same or another rate starting at a later time and continuing until a second level of charge is reached.

[Para 27] The delay of operating a load can be coordinated with maintenance of the power source to provide a load for the maintenance without wasting power. Most backup generators are controlled in order that they are operated periodically, with or without a load, for example 30 minutes every week. This is known as exercising and it helps to keep fluids circulating, bearings oiled, moisture dried, etc. to improve reliability. A load such as a battery charger can be delayed until an upcoming scheduled exercising when the battery is

charged. Alternatively the battery can be charged at a convenient time by rescheduling the exercising. More generally loads may be supplied with current at a first known amount (which may be an amount to achieve a particular effect such as charge rate) starting at a known time (which may be upon connection or a clock time) for a known period of time (which may be the time to achieve a particular event or a particular clock duration) followed by one or more known combinations of the above known amount, known time and known period. As one example, charging a battery at full rate until half full upon connection upon return to home in the evening then charging at the maximum available current during the time period of generator exercise followed by charging at a most efficient charging rate during off peak hours when grid power is cheap with each of the times being terminated early if the battery reaches full or some other desired charge level.

[Para 28] The invention can also be configured to allow selection of the power source to power one or more loads from among a plurality of power sources, for example a load can be powered from a low cost source such as photovoltaic solar cell panels, a wind turbine, fuel cell, flywheel or powered from the utility company power if there is insufficient sun and wind or if more power is needed than the solar panel, wind turbine and/or fuel cell can provide. This operation may be coupled with efficient utilization of sources such as to charge a vehicle battery as described above. Changing to other power sources can be accomplished by any means or method known to the person of ordinary skill, e.g. via transfer switch, parallel input connections to the load, parallel power sources.

[Para 29] The invention described herein allows efficient matching of a total load made up of individual loads to one or more power sources without overloading the power sources. The present invention will allow sizing of power sources to accommodate less than the maximum possible load and can prevent overloading of the power source by preventing a load which would otherwise immediately cause or which could lead to a future overload from being connected or alternatively by restricting the power supplied to that load and/or

others. This operation is achieved by the intelligent connection and disconnection of individual loads as well as the control of the power drawn from power sources by connected individual loads and/or control of power supplied to connected individual loads as will be described in more detail below.

[Para 30] Most commercial generators are well characterized for operations under various conditions, including but not limited to loading and environmental conditions, and the maximum available output power is known for any particular set of such conditions. The present invention is preferred to sense one or more of the various conditions which affect that maximum available output power and use those conditions along with the characterization of the generator to determine precisely what that maximum available output power is at a given time, what the expected available power will be at one or more times in the future as well as the present and future effect the connection of a particular load may have on available power. In that fashion the present invention can select loads to be connected to the generator or other power source to power the maximum number of loads and/or to operate nearer to or achieve optimum efficiency while at the same time monitoring the present and expected future load thus ensuring that the generator will not be overloaded instantly or during the duration of any particular connection.

[Para 31] The description of the preferred embodiment of the invention herein is made by way of example as an improvement to an electrical backup generator system to provide power to a typical home or small business in the event power from the power grid (i.e. the municipal utility power or street power) is lost. The preferred embodiment may also be utilized with more than these two (grid and backup generator) power sources, for example wind and solar power sources may be incorporated with grid and engine driven power sources. It will be understood to one of ordinary skill from the teachings of the preferred embodiment that the invention as herein described is not limited to the particular embodiment and the invention may be practiced in a manner to be utilized with other types

and combinations of power sources and loads to achieve a desired level of performance for a particular system.

[Para 32] The elements and steps of the preferred embodiment are preferred to be implemented with electronic circuitry as will be well known to one of ordinary skill from the present teachings. As used in the description of the preferred embodiment, circuit is meant to be an electric or electronic circuit unless it is clear from the context that it is another type of circuit. Descriptions of, and nomenclature pertaining to, elements of the invention are given in respect to names of electrical and electronic devices or operations (e.g. switch, generator, processor or processor circuit, power grid, solar panel, wind turbine, fuel cell, communications, communications channel, interface or interface circuit) or a descriptive name of a function performed with respect to some device or condition (e.g. load monitor, generator monitor, load control, load switch, communications link) all as are well known to one of ordinary skill from the teachings of the preferred embodiment of the invention and context of usage. In some instances the name of the device is also descriptive as will be well known to one of ordinary skill.

[Para 33] The invention described herein is preferred to utilize intelligent timing for connecting and disconnecting of loads to one or more power sources including control of power supplied to or demanded by the loads in order that the total load on any one power source is kept at or below the maximum output capability of that power source, or alternatively at or near an optimum efficiency level, which may be at or below the maximum capability. The decision making used by the preferred embodiment of the invention for connecting, supplying and/or controlling a particular load to the power source is preferred to be responsive to the capabilities of the power source and the type of load to be connected (including one or more parameter of each), the priority or importance of the load to be connected, the timeliness of the load connection, environmental parameters which affect the power source and loads and the input of one or more persons desiring to use a

device presenting a particular load. As used herein and in the claims parameter means a quantity of one or more property or attribute (e.g. of a device, physical property, substance or environment) which is treated as a constant. A parameter may at times change or be adjusted. Examples of parameters of interest herein include various horsepower, mechanical load, temperature, pressure (including altitude), humidity, power, wattage, voltage, current, including maximums, minimums, safe, starting, limited, instant, real time, near real time and timely. Quantities pertaining to parameters may be in analog or digital form and expressed as numbers which are suitable for use by the device(s) using or responsive to such parameters.

BRIEF DESCRIPTION OF THE FIGURES

[Para 34] Figure 1 shows a simplified flow chart of a prior art transfer switch and generator controller having elements 1–11.

[Para 35] Figure 2 shows a simplified circuit diagram of a prior art power backup system having power grid 12, generator 13, generator and transfer switch controller 14, transfer switch 15a, load main panel 15b, load sub panel 15c and loads 16–20.

[Para 36] Figure 3 shows a simplified circuit diagram of a prior art power backup system having power grid 12, generator 13, generator and transfer switch controller 14, transfer switch 15, loads 16–20 and load manager elements 14a.

[Para 37] Figure 4 shows a simplified circuit diagram of a power backup system which incorporates a first embodiment of the present invention, the system having power grid 12, generator 13, transfer switch 15, loads 16–20, optional environmental, user & misc. sensors 21, load switches 22a–22c, load monitor 23a, generator monitor 24, load control 25a and communications links 26a – 26c, 27b and 28a and optional communications links 27a, 28b and 28c.

[Para 38] Figure 5 shows a circuit diagram of load control 25a with communications links 26a – 26N, 28a, 30, 31, 32, optional communications link 28b, interfaces 29a, 29c – 29h, optional interface 29b and processor circuit 33a.

[Para 39] Figure 6 shows loads 16 – 18, load switches 22b & 22c, load monitor 23b, communications links 26a – 26c, 36, 40a, optional communications link 38, 40b, interfaces 29i – 29k, 35, switches 34, and user input and user feedback module 39. Figure 6 also includes Load Limit 43 having current control circuit 44.

[Para 40] Figure 7 shows user input and user feedback module 39, display 41 and user input keys 42a – 42c.

[Para 41] Figure 8 shows a simplified circuit diagram of a power backup system similar to Figure 4 which is a more elaborate embodiment of the present invention, the system having power grid 12, generator 13, transfer switch 47, loads 16–19 and 48, environmental, user & misc sensors 21, load switches 22b and 22c, load monitors 23a and 23c, power source monitor 49, load control 25b, communications links 26a – 26c, 27a, 27b, 27d, 28a, 28c, 45, 46, optional communications links 27c, 28b, load limit 43 and third power source 50 having power output via 51.

[Para 42] Figure 9 shows a more detailed circuit diagram of load control 25b with communications links 26a – 26N, 28a, 30, 31, 32, 45, 46, optional communications link 28b, interfaces 29a, 29c – 29j, optional interface 29b and processor circuit 33b.

[Para 43] Figure 10 shows a simplified diagram of the embodiment of Figure 8 which includes elements 12, 13, 16, 17, 18, 19, 22b, 22c, 25b, 26a, 26b, 26c, 27a, 43, 45 and 47 as in Figure 8. Figure 10 also includes elements for recovering heat from generator 13 including heat exchangers 52 and 53, electrically controlled valves 54 and 55, valve control circuits 56 and 57, generator heat supply 58, generator heat return 59, domestic hot water supply 60, cold water supply 61, radiant heat supply 62, radiant heat return 63, domestic heat temperature sense link 64 and radiant heat temperature sense link 65.

[Para 44] Figure 11 shows a simplified diagram of a combination load and power source which the invention may be utilized with including battery 68, battery charger 66, DC to AC inverter 67, connection to transfer switch output 71a, communications connections to load control 69 and 70.

[Para 45] Figure 12 shows a simplified diagram of an embodiment of the invention which is used with an energy storage battery 68 and optional generator 72 communicating with load control 25b via optional communications link 73 with battery 68 usable as a backup power supply in the event of a power grid failure. Figure 12 includes power grid 12, loads 16–19 and 48, load control 25b, load switches 22b and 22c, load limit 43, communications links 26a – 26c, 45 and 46 and transfer switch 47, as in Figure 8 and including battery 68, communications links 69, 70 as in Figure 11. Battery charger 66 the same as in Figure 11 is connected to the output of the transfer switch 47 via 71c, and DC – AC inverter 67 the same as in Figure 11 is connected to an input of transfer switch 47 via 71b.

[Para 46] Figure 13 shows a simplified diagram of a combination of load coupler 80 shown by example configured with typical air conditioner load 18 for coupling the load to the power source, in this example power from the transfer switch. Load coupler 80, described further with respect to Figures 14 and 15, may be utilized for an implementation of any of the load switches 22 if desired and communicating with load control via link 26c. Load coupler 80 may also be configured with a current control circuit 44 (not shown), with or without a relay, to be utilized as a load limit 43 for those types of loads which may utilize controlled current, as described herein.

[Para 47] Figure 14 shows a detailed diagram of the preferred embodiment of load coupler 80 of Figure 13 having current sense 23d, relay 34 which may be latching or simple type, optional current control 44, relay position circuit 79, battery & charger 74 responsive to power from the transfer switch to provide backup power 75, wireless communications link circuit 29k receiving backup power and coupled to antenna 76 (which may be internal or

external to 80) to communicate wirelessly with load control via channel 26c. Also shown is microprocessor circuit 37 powered by backup power 75 and responsive to current monitor shown as sense 23d, transfer switch power voltage monitor 78, and relay position circuit 79, with 37 controlling relay 34 and interfacing with wireless communications link 29k and user interface 77 which may also receive backup power 75 if desired.

[Para 48] Figure 15 shows a commercially valuable embodiment of load coupler 80 which is physically separated into two sections, a high voltage section 80H and a low voltage section 80L having multiple and various circuit connections 82 for connecting internal circuits of each section to the other and/or external devices. High voltage section 80H is configured to controllably couple power from the transfer switch to a load 18 shown by example as via an externally controllable latching or simple relay 34 having relay position circuit 79, section 80H further including current monitoring shown as sense 23d. Figure 15 also shows a power supply 81 coupled to the power from the transfer switch, the power supply providing power, which is preferred to be a lower voltage safe for human contact, in response thereto. Figure 15 section 80L includes a battery and charger circuit 74 to receive AC (or DC) voltage from an external source 81 to provide regular and backup power 84 preferably made available to external devices via one or more connection 82, the battery and charger circuit 74 also providing regular and backup (DC or AC) power 75 (hereafter referred to as backup power) for internal use in 80L, a microprocessor circuit 37 is powered by backup power 75 and responsive to current sense 23d (located in 80H), voltage monitor 78 (from transfer switch power via supply 81) and relay position circuit 79 with microprocessor circuit 37 operative to provide control signals 85 via external connections 82 and with microprocessor circuit 37 also operating to control relay 83 which relay has connections 82 for external circuits. Connections to some external circuits are preferred to be protected via protection devices (circuits) 86. Microprocessor circuit 37 further interfaces with wireless communications link 29k (which is powered by backup power 75) having antenna 76 and

operating to communicate with load control(s) via wireless communications channel(s) 26c. Microprocessor circuit 37 is also coupled to user interface 77 (which may receive backup power 75 if desired) and to connections 82 via protection device 86

[Para 49] Figure 16 shows a further embodiment of a load limit 88 controlling an oven 16 wherein a load control 25c responsive to the input power via 87 is incorporated with 88 along with a current control circuit 44 and current sense 23d.

[Para 50] Figure 17 shows a further embodiment of a load switch 89 controlling a clothes dryer 17 wherein a load control 25d responsive to the input power via 87 is incorporated with 89 along with contactor 34.

[Para 51] Figure 18 shows the further embodiment of load control 25c including a transformer 81 responsive to the input power via 87, a power supply 74, frequency measurement circuit 90 responsive to the frequency of the incoming power, user display 90 for displaying messages to a user, user input 92 by which a user inputs information and/or commands, timebase 93 facilitating timing measurements, current measurement circuit 95 responsive to 23d, switch / limit driver 94 coupled to current control 44 (or alternatively 34).

Heading

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT

[Para 52] Figures 1–3 provide background for understanding of prior art electrical power backup power systems as they pertain to the present invention. One of ordinary skill will already know these systems and the Figures 1–3 are simplified to aid in understanding some of the shortcomings of the prior art which are overcome by the present invention. As just one example, it will be known that the connections shown in the various Figures 1–3 (and 4–18) often represent a plurality of actual circuits, such as the connection from the utility power grid 12 which may entail several conductors ranging from three for a single phase system to six or even more for multiple phase systems.

[Para 53] Figure 2 shows a prior art power backup system to power some of the loads 16–20 utilizing a service connection to a power grid 12 as the primary power source and a generator 13 as the backup power source. For the examples herein the power grid is subject to loss of power or power fluctuations (e.g. brownouts) and supplies power where the cost of the power varies from time to time. Generator 13 is used in the prior art and preferred embodiment examples with respect to an electric power generator having an internal combustion engine powering an alternator. It will be understood that power sources, loads and other elements of the described systems of the present disclosure have various parameters associated with them. Some parameters for example are the maximum output power of a source, which maximum output may change from time to time, the power output (e.g. timely, current or at the present time power output) of a source, the maximum power consumption of a load which maximum consumption may change from time to time, and the power consumption (e.g. timely, current or at the present time consumption) of a load. Such parameters may be a singular parameter for example such as a maximum voltage, wattage or current, or a plurality for example such as voltage and power, may include other factors such as a time or environment related factor, such as a maximum current at a given temperature or for a limited time. Load parameters, e.g. expected or maximum watts or current consumed by a load, and maximum output power parameters, e.g. maximum watts or current that can be provided by a power source, are of particular importance herein.

[Para 54] In typical installations the power grid 12 is connected via a service connection to the transfer switch 15a and distribution panels 15b and 15c all of which have a maximum rating. The service connection has a circuit breaker to prevent the total of the loads being powered (i.e. the total load) from exceeding that maximum rating of the service connection. In particular there is a circuit breaker (known as the main breaker) located on the power grid service, usually at the power meter, which will be known to disconnect all power to the transfer switch 15 and main panel 15b if it trips. There will also be a circuit breaker located

in the generator 13 to disconnect all power from the generator when it trips. Obviously, having either of these circuit breakers trip is a serious inconvenience, especially if it happens when there is nobody available to reset the breaker, or during a storm, at night or other inconvenient time. Additionally each panel has circuit breakers which will trip and protect individual loads if too much current is consumed.

[Para 55] It will be understood that generator 13 is intended to also represent other power source devices to provide power in a desired form from power in another form or from stored energy. Generator 13 may for example be a wind turbine, solar panel, fuel cell, flywheel, battery, water, wind or steam turbine and may incorporate a DC to AC inverter circuit, generator or alternator to provide electricity if that is the desired output. Stored or collected power may come from gaseous, liquid and solid sources (e.g. fuels) such as hydrocarbons like natural gas, gasoline and other petroleum or solid hydrocarbons like coal, biomass sources, water power such as tides, waves and reservoirs, wind, sunlight, chemical and nuclear energy such as batteries, fuel cells, reactors, mechanically stored energy such as stored heat, flywheels, weights and compressed gas, and other forms as will be known to one of ordinary skill. Some devices may be both power sources and power loads, and store energy which may be converted back to AC (or DC) power to provide backup power, heating, to store in another form or to sell back to the electric utility. For example in respect to battery storage of energy, it is noted that the batteries in an electric or hybrid vehicle or the like may be used as both loads and power sources.

[Para 56] When used with a primarily electrical circuit, generator will mean an electric generator which is compatible with that type of electrical circuit. Names such as electric generator (which primarily outputs at least electric power), AC generator (which primarily outputs at least AC electric power), steam generator (which primarily outputs steam power), solar panel (which uses solar energy as the source of output power), fuel cell (which uses liquid or gaseous fuel and a chemical reaction in a cell to output power), electric solar panel

or electric fuel cell (which additionally mean to output electricity). As an example of the type of generator being known from context, a generator which provides power to a transfer switch and thereby provides backup power in place of an electric power grid which has failed, will be understood from the context (i.e. to replace electric power) to be an electric power generator. Generally the type of device being referred to in the specification and claims will sometimes be specifically named, but when not specifically named will be generically named (e.g. generator) and if intended to refer to a specific device that device will be apparent from the context. As just one example, transfer switch may be any type of switch, e.g. electrical, gaseous (e.g. steam) or hydraulic but if used in an electrical system to transfer electric power will be known to be an electrical type of switch and if used with a steam system to transfer steam power will be known to be a gaseous type of switch, e.g. valve. The teachings herein with respect to the preferred embodiment of electrical systems will nevertheless be understood to be applicable to other types of power systems.

[Para 57] Figure 2 shows a simplified diagram of a prior art backup generator system of the type the preferred embodiment of the invention may be used with. Electrical power from power grid 12 is normally supplied via transfer switch 15a and main load panel 15b and load sub panel 15c to a home which consists of a group of electrical loads consisting of an oven 16, clothes dryer 17, air conditioner 18, selected lights 19 and selected miscellaneous load items 20. It is noted that the load 19 labeled lights is intended to represent high priority loads which are desired to always be connected to the power source including for example security lights, high priority lights, food storage appliances such as freezers and refrigerators, various alarms including intrusion and fire alarms, etc. A generator and transfer switch controller 14 is responsive to the grid power to control the setting of the transfer switch 15a to select either grid power 12 or generator power 13 to power the home, and to start and stop the generator 13 as needed. As is conventional in the art, transfer switch 15a is a break before make switch to prevent it from simultaneously

connecting both inputs (on the left) to the output (on the right) while switching and is shown with a dashed line connecting the moving portion, which will be referred to herein as the swinger, to communicate with 14 to indicate that the switch is controlled by 14. Practical devices called transfer switches incorporate both 15a and 14, and sometimes 15b and/or 15c in a single metal enclosure. It is noted that Figure 2 is a simplification for purposes of explanation of operation and one of ordinary skill will know that in practice prior art transfer switch 15a, panels 15b and 15c and the controlling mechanism will be much more elaborate and may incorporate solenoids, relays and multiple sets of contacts as well as mechanical safety and lockout features.

[Para 58] While Figure 2 shows a direct connection from the power grid 12 to the transfer switch 15a, it is common that that connection is taken from the main panel 15b which will include a power meter, circuit breakers and possibly other circuitry. Typical maximum service ratings for homes are set by the size of the wiring from the grid to the home and typically rated at 100, 200 or 400 amps depending on the size of the home. Similarly the generator connection via the transfer switch 15a and sub panel 15c will have a maximum rating, and the generator has a circuit breaker to prevent the total of the loads being powered from exceeding that maximum rating. Typical maximum ratings for backup generators are often substantially less than the service rating for the grid connection. To prevent the generator from being overloaded backup systems often include the distribution sub panel 15c and only high priority and low current loads such as 19 and 20 which are needed whenever the power is lost and whether the home is occupied or not are connected to that sub panel and powered by the backup generator. The rest of the high current loads which the generator is not capable of powering are connected to the main panel 15b and remain unpowered while the grid power is off and the backup generator is running. While transfer switch 15a, main panel 15b and sub panel 15c are individually shown in Figure 2, for purposes of simplifying the descriptions below main panel 15b and sub panel 15c will

not be shown and the transfer switch will be labeled as 15. One of ordinary skill will know that one or more distribution panel will be required for the systems described, even though they are not shown in the drawings.

[Para 59] Power grid is used herein in its common and ordinary meaning and refers to any commonly known and used sources of electrical power to homes and businesses, e.g. public and private electric utility companies. While such companies normally are part of a continent wide interconnection of power companies, that does not need to be the case. Further, while the preferred embodiment of the invention described herein with respect to a system having a power grid connection, it may also be practiced with only one power source such as generator 13, or with a plurality of power sources with none of them being a power grid. Such embodiments will find particular use where no power grid is available or is not desired to be used such as in transportation vehicles, mobile or remotely located applications.

[Para 60] Electrical device (or load) names oven, clothes dryer, air conditioner and lights are used in their common and ordinary meaning e.g. electrically powered devices found in the home. The miscellaneous electrically powered devices (or loads) found in the home, include but are not limited to entertainment devices, appliances and other modern, electrically powered conveniences. It will be understood that load devices are used herein by way of example and it will be understood by one of ordinary skill that the inventive teachings herein will apply to other devices as well.

[Para 61] Generator 13 usually includes a rotating power source, typically an internal combustion engine powered by a liquid or gaseous fuel, or a turbine powered by steam or water power, an electric motor powered by storage batteries, a flywheel powered by stored energy, a hydraulic motor powered by a compressed gas or a fluid stored with potential energy, or numerous other types of rotating power sources which convert mechanically or chemically stored energy to mechanical rotation as is known to one of ordinary skill. In addition the rotating power source is typically coupled to an AC alternator (as compared to

a DC generator) to provide AC power of the same voltage and phase configuration as that received from the power grid. In the U.S. the common power for homes is 240 volts single phase and will often be used in the examples of the Figures but it will be understood by one of ordinary skill that the invention may be utilized with many other power configurations.

[Para 62] The transfer switch 15 and the generator and transfer switch controller 14 are also somewhat simply referred to in these teachings. The transfer switch transfers power from the generator to the loads in the house in place of the failed grid power. The generator and transfer switch controller 14 controls starting and stopping of the generator and the position of the transfer switch. These elements are divided in this manner for ease of understanding the prior art and the present invention. This usage is somewhat different from the common use of these names in the art, wherein transfer switch generally refers to a device incorporating the generator and transfer switch control circuitry 14 (and often other circuitry) as well as the switch 15a to transfer the load from one power source to the other. In some instances, such as the previously mentioned Generac device, one or more additional switches are included to disconnect low priority loads during generator use. For ease of understanding the present invention these are all simply referred to herein as transfer switch numbered 15, and the controls for the switch and generator (and possibly other devices) are numbered 14.

[Para 63] Some backup systems operate to supplement power supplied by the power grid during heavy peak usage times such as very hot summer afternoons when the power grid approaches its maximum capability due to widespread use of air conditioning. In these instances the grid power may still be available but the generator is used to power some or all of the house loads, or the generator power may be synchronized to and paralleled with the power grid to provide part or all of the power to the house loads. When the house load is very small such paralleled generators may feed power back into the grid to in effect sell power to the utility company by causing the power meter to run backwards. These

operations require a more complex control, transfer switch and generator operation than shown in Figure 2. The inventive concepts disclosed herein will also be useful in such systems. It will be recognized however that in such paralleled systems when the power grid fails it is important to disconnect the power grid from the generator in order to prevent damage to the generator or possible harm to workers who are repairing the grid failure.

[Para 64] Figure 1 shows an abbreviated flow chart of the decision making process of the generator and transfer switch controller 14. Processing steps are represented by rectangles, input/output steps by parallelograms, conditional or decision steps are represented by diamonds and flow directions are shown by arrows. Basically the flow chart operates to start the generator and move the transfer switch to the generator when the grid power fails. The decision making starts at start 1, followed by sensing the grid power 2 to obtain information about the quality of the power, followed by a decision step 3 to decide if the quality of the grid power is sufficient (e.g. the power is on and within the range of expected voltage). If the power is on a next decision step 4 is entered to determine if transfer switch 15 is in the position to supply grid power to the home, if so the decision making returns to 2 and if not the transfer switch 15 is moved to the grid power position in 6. The loop normally remains in operation until the grid power goes off causing the timer off step 5 to be entered from decision 3.

[Para 65] If the grid power remains off for 5 seconds the process continues to the generator running decision 7. If the generator is not running it is started in 8 and another 5 second delay 10 is entered. At the end of the 5 second delay the process returns to the input of 7 to verify that the generator is running, if not another start is performed and if the generator is then running the process continues to check the transfer switch position in 9. If the transfer switch is in the position to provide generator power to the house the process returns to 2 to continue sensing grid power to see if it has returned to normal, and if the

transfer switch is not in the position to power the house from the generator it is switched in step 11 and then the process returns to wait for sensing the return of grid power 2.

[Para 66] Compared to an actual prior art device the flow shown in Figure 1 and accompanying description above is greatly simplified for convenience of understanding the basic operation of the system of Figure 2. For example for simplicity no step to stop the generator is shown, nor is the exit from 5 shown if power does not stay off for 5 seconds. Many additional steps, checks and considerations are usually found in commercially available systems to recognize and accommodate the many possible modes of short and long term power failure and to protect the generator. Such steps include for example a periodic (e.g. once a week) start and exercise of the generator and transfer switch to improve reliability and a delay in shutting down a generator which has been running in order to allow it to cool down without a load being applied. The timers 5 and 10 are greatly simplified and usually involve many other decision making subroutines and branches to avoid false starts of the generator during momentary power glitches and to allow the generator to attain proper speed, corresponding to proper AC power frequency and voltage, before confirming that it is running.

[Para 67] It will be understood from the description of Figures 1 and 2 that when power from the power grid is lost, the generator 13 is started and when it is operational the transfer switch 15 is moved so the power from 13 is coupled to the loads 16–20. Importantly, the generator 13 must be designed so that it is capable of powering all of those loads when they are simultaneously turned on, otherwise the generator will be overloaded and its internal circuit breaker will trip. In extreme cases of overloading the generator may be damaged before the internal circuit breaker can trip. Often generators are intentionally designed to only provide power to handle a part of the total load, and the occupants of the house must remember not to turn on certain large loads, for example the air conditioner and oven, which would cause an overload. In addition, if those large loads

are on at the time when power is lost, the occupants must quickly turn them off before the generator is started and transfer switch moved to prevent an overload. This all presents a substantial possibility of generator damage resulting from human error.

[Para 68] Figure 3 is a simplified example of an improved prior art version of the backup system in Figure 2 which provides power to a group of loads, including a set of uncontrolled loads and a set of controlled loads which may be simultaneously switched off if the generator becomes overloaded. After the controlled loads are simultaneously switched off they may then be automatically (and blindly) switched on in a sequential fashion according to priority, each additional load being switched a time period (e.g. 3 minutes) after the previous one. The previously mentioned Generac Nexus LTS Load Shed system is representative of a system of this type. Figure 3 additionally includes load managers 14a which are contactors to switch the high current load on and off in response to a control signal. A contactor is essentially a high current relay which switches the load completely on or off. The Generac DLM Load Control is a contactor of this type with a control input which is wired to and controlled by the Generac Nexus system. If during the reconnection sequence a certain priority load again overloads the generator (e.g. it is blindly switched on without knowing if it will again cause an overload), that load and all lower priority loads are disconnected for a period of time (e.g. 30 minutes) before the connection is tried again. When grid power is available the generator & transfer switch controller 14 operates (via control signal connections shown by arrowed lines) all of the load managers 14a connect their respective loads.

[Para 69] When the generator is running, the generator & transfer switch controller 14 operates to detect that the generator 13 is overloaded (by sensing the frequency of the AC power produced by the generator) and causes all of the load managers 14a to simultaneously disconnect their respective loads from the generator. Shedding the nonessential circuits when the generator is overloaded helps protect the generator of Figure

3 as compared to the system of Figure 2, however there are shortcomings in this approach. For example by detecting the power frequency the generator must already be overloaded to the point of not being able to supply enough rotating torque to the alternator to maintain proper speed. Short term speed variations resulting from momentary loads such as electric motor starting currents must also be accommodated. Most generators can handle significant excessive output currents for short periods of time and that is useful in providing large starting currents for motors, for example such as those required for starting air conditioner compressors. These large starting currents normally go away after a few seconds when the motor armature and its mechanical load have been accelerated to operating speed. Additionally, as will be recognized from the teachings herein, in some circumstances which will be described more fully below, it is unnecessary to simultaneously disconnect all of the low priority loads or to blindly reconnect them.

[Para 70] Accommodating such momentary high currents is common in the circuit breaker art, where circuit breakers are designed to trip according to a programmed load vs. time curve. For example a particular 10 amp breaker will trip with a 12 amp load after 30 seconds, may support a 15 amp load without tripping for 5 seconds, but will trip very quickly with a 20 amp load. Various thermal and magnetic technologies are utilized for such circuit breakers. For example a bimetallic strip may be used to trip with slightly high currents after those currents have persisted for enough time to cause the strip to heat and bend whereas an electromagnet is used to quickly pull a latch to disconnect for large currents. A generator will often have such a circuit breaker installed for protection. It is important that loads presented to the generator do not exceed the circuit breaker's load vs. time curve causing it to trip. Most such circuit breakers used in backup generators for homes and small businesses have to be manually reset.

[Para 71] The use of AC power frequency detection for control of load shedding is problematic. If the frequency detection is too sensitive unneeded shedding may occur, or if

it is not sensitive enough, slow or no load shedding may occur with the possible result of the generator's circuit breaker tripping thus removing all power. A one size fits all frequency threshold used to cause complete disconnect of the load from the generator may allow overheating or other damage to the generator 13 under some combination of time and load conditions. It is preferred that the present invention control of the load shedding be designed to accommodate varying loads of connected loads, determine if a load can be safely powered before the load is connected and otherwise operate such that it prevents an overload from happening, rather than attempting to detect and cure the overload after it has happened.

[Para 72] Another problem occurs when the transfer switch first switches from the power grid to the generator with too many loads connected. A similar condition exists when a connected load instantly or quickly increases its individual load causing the total generator load to exceed the generator's capability. In such situations if the generator has been sized such that it can not simultaneously power all of the loads which are connected, it will immediately go into overload. Depending on how fast the detection of the condition and disconnect of the loads takes the overload condition can continue for several seconds, or possibly even minutes. Most generators are designed to accept an instant 0 to 100% of its rated load change without damage (although not without serious speed and voltage fluctuations), however they may not be designed to accept an instant 0 to overload condition change which can happen when switching from grid to generator power, or a partial to overload condition which can happen when a connected load suddenly changes. Such overload conditions may damage the generator or, as with any closed loop system, cause the generator to become unstable, possibly even going into speed and/or power output oscillations if proper linearity and/or damping does not exist to make the loop stable for that overload condition.

[Para 73] The following Figures 4-18 are simplified diagrams given by way of example to enable one of ordinary skill to understand and practice the invention in small backup power systems, defined herein as those used for an individual home or business with a single or multiple phase service connection of 440 volts or less and 400 amps or less. It is often desirable to utilize a backup generator which is only capable of providing power for part of the maximum possible load which can be presented. In respect to Figures 4-18 the following brief descriptions will be useful. More detailed descriptions of these and other elements will be understood from the teachings below.

[Para 74] Environmental, User & Misc. Devices 21. User interface, e.g. an iPad or computer type display with interactive software, Environmental Sensors e.g. for home & outdoor such as temperature, sunlight, humidity, wind, generator operating conditions, Misc. Devices e.g. vehicle and battery sensors (e.g. usage time and distances, charge, temperature) appliance sensors (e.g. wine cooler, freezer and oven temperature), vehicle battery charger and battery, communications (e.g. telephone, internet, wireless, alarm), motion sensors to detect when areas of the property, particular rooms, or the home are vacant or occupied.

[Para 75] Power Source Monitor 49 and Load Control Processor 25b. The Power Source Monitor is preferred to be a separate module because of its need to monitor the power source(s) outside the home but may be part of the load control processor. The Power Source Monitor may be installed at the backup power source and monitors its operating parameters and conditions which may affect its operation, for example such as ambient temperature. The load control processor is the computing unit of the system and may be part of the user interface (e.g. iPad) which is preferred to be located in the home but may also be part of other equipment. The load control processor receives information about the various components of the system, receives user input, inputs from various monitors and sensors (including a time clock) and controls the Transfer Switch, Generator and Loads according to various pre-programmed parameters and those inputs.

[Para 76] Load Modules 43, 22b, 22c. Modules which communicate with the load control processor and which may provide information about the load, the load's environment and/or operate to permit control of the load. Load Modules include Load Limit Modules and Load Switch Modules.

[Para 77] Load Limit Module 43. Load limit modules limit the load presented by various devices by e.g. current limiting, power factor adjustment and/or time modulation of current. Load Limit Modules may include load condition sensors such as voltage, current and power factor sensors and the type of load operation for communication to the load control processor.

[Para 78] Load Switch Module 22b, 22c. Load Switch Modules switch power to loads on and off. Load Switch Modules may include load condition sensors such as current sensors and the type of load operation for communication to the load control processor.

[Para 79] Controllable Load(s) 48. These are loads which may be controlled directly without the need for a Load Module. Examples include electronically controlled devices such as heating and air conditioning systems, vehicle battery chargers, light dimmers & remotely controlled lights and internet and wirelessly controlled appliances.

[Para 80] Communications between the various system components 27, 28, 45, 46 may be wired or wireless. For ease of installation are preferred to be via bidirectional wireless data links, for example such as via IEEE Std. 802.1X. For those elements which communicate in one direction the associated receiver or transmitter circuitry may be omitted.

[Para 81] It will be understood that many elements that are necessary for an actual system have been omitted as they will be readily known to the person of ordinary skill from the present teachings. Additionally many inventive features and elements which are described with respect to one Figure will not be shown in another Figure but it will be recognized from the teachings herein that such omitted features and elements may still be incorporated.

[Para 82] Figure 4 shows a simplified diagram of the preferred embodiment of the invention in which the power grid 12 or a generator 13 may power a group of loads including set of uncontrolled loads and a set of individually switched loads. The invention may be utilized with the power grid alone, the generator alone, both, or with the generator serving as a backup during power grid failure. Heretofore overloads of the power grid service has typically been addressed by making the service, transfer switch and distribution panel(s) large enough to handle the maximum load that can occur. While that approach works well it is nevertheless expensive due to increased equipment costs and may become unworkable in the future. For consumers wishing to purchase electric and hybrid vehicles, having to upgrade their existing electric service to accommodate one or two vehicles and their associated high current chargers operating at the same time is an additional and costly consideration for such a purchase. In some instances the public utility may not be able to provide enough power via the existing grid to upgrade existing service and provide new service to everyone desiring such capability. Accordingly while using large service connections has worked well in the past, with the demand created by electric and hybrid vehicles may not allow larger capability service which effectively prevents overload from being used.

[Para 83] As an example, consider a family that wishes to purchase two new electric vehicles of the kind that could each use a 90 amp 240 volt charger circuit. If both drivers work during the day and wish to charge their vehicles when they come home from work that presents a substantial load to the electric service. Two of these circuits added to an existing 100 amp service would trip the service breaker if both chargers were simultaneously used. If only one charger was used any other high power load such as an electric stove or oven or air conditioner would trip the service breaker. Similar problems would exist for a 200 amp service. Upgrading to a 400 amp service would be costly, and might not even be possible if the utility company does not have an adequate transformer and grid wiring to the house.

The present invention will operate to intelligently manage the loads and prevent tripping the service breaker while at the same time allowing the family to set priorities for the use of power that can be safely delivered.

[Para 84] It is desired that the invention operate to ensure that the loads are controlled so that they do not overload the power grid service connection when power is provided by the power grid, or overload the generator when power is provided by the generator. One of the inventive features of the invention is that it may be determined whether or not an overload will occur, or is likely to occur at the time of connection or subsequently during that connection, before a load is connected. The inventive features of the preferred embodiment are described herein primarily in respect to preventing overloads of the generator 13 but it will be understood from these teachings that the invention may operate as well to prevent overloads to the power grid service connection. This feature of the invention will not only reduce possible damage or circuit breaker tripping during generator operation but will also reduce possible damage or circuit breaker tripping during power grid operation.

[Para 85] Figure 4 has the same power grid 12, generator 13, transfer switch 15 and loads 16–20 as with Figures 2 and 3. Generator and transfer switch controller 14 is not shown in Figure 4 for simplicity, however it is preferred that load control 25a communicates with either the 14 or 15 in order to verify the position of the transfer switch. In addition Figure 4 shows load monitor 23a to monitor the load on the generator (which is also the power supplied by the generator) and the timely power output from the generator is conveyed to load monitor 25a via generator monitor 24. Load monitor 23a also provides timely power output from (e.g. provided via) the service connection and thus the load on the power grid, when the transfer switch is in the power grid position. In that the invention finds applicability for preventing overloads it will be understood that it may be utilized for any power source or combination of sources, including off grid systems such as remote

terrestrial, aircraft, on and off road vehicles and marine applications with or without connection to the power grid.

[Para 86] It is preferred that the timely power output is an instantaneous measure of the current provided by the generator. Because most generators incorporate voltage sensing and correction circuitry, often by way of controlling the power applied to the exciter winding in the alternator, the output voltage is maintained nearly constant. Of course the voltage (and power factor if desired) may be measured and utilized as well. By knowing the output voltage of the generator is being held to a constant value, for example 240 volts in a single phase output, by measuring or sensing the instantaneous current flowing from the generator, an instantaneous measure of the output power may be had. It may also be desirable to utilize a measure which is not instantaneous. Examples of some non instantaneous measures include an average over time, a time related measure of output power, a measurement with reduced noise, an approximation of the average load provided to the generator, to provide a measure of the resulting heating of the alternator or engine, to provide a measure of fuel consumption by the generator, to provide a measure of the power consumption by the load(s).

[Para 87] A generator monitor 24 which receives data from load monitor 23a and communicates that load information to a load control 25a via communications link 28a. It is noted that load monitor 23a may be located in the circuit input to (to the left of) the transfer switch 15 in order to monitor the load only when power is provided by the generator. Monitoring the output of the transfer switch is preferred e.g. it is useful for characterizing load parameters e.g. current or wattage consumption, as individual loads are turned on and off (or turn on and off on their own) at any time, and for controlling the load presented to the grid so as not to exceed the service connection capability as will be explained below.

[Para 88] Figure 4 also shows load switch 22a is responsive to load control 25a via communications link 26a and operable to connect and disconnect oven 16 from power

coming from the transfer switch, load switch 22b via communications link 26b is operative to connect and disconnect the clothes dryer 17 and load switch 22c via communications link 26c is operative to connect and disconnect the air conditioner 18. It will be understood from the teachings of the present invention that one or more load switch 22 may be removed (for controllable devices or high priority devices as described herein) or replaced with a load control 43 or other types of control devices as will be described in more detail with respect to Figures 6–9. While load switches 22 have been described as being responsive to load control 25a, it will be preferred that they also include bidirectional communications capability in order that load control 25a may determine and/or verify the state of the switch (e.g. open, closed, dropped or other information) and further it is preferred that the switch include other functions as will be discussed below. In addition, it will be understood that load switches may be operated without a separate load control 25a, as that function may be incorporated within the load switch 22 (or load limit 23).

[Para 89] As used herein, communications and communications link is meant to encompass the conveyance of information from one point to another by one or a plurality of electronic circuits and may be the same or different for each type of information and each type of connection as desired. The communications links may be of any type suitable for communicating the particular information desired over the desired distance at an adequate speed and resolution with necessary reliability and may be continuous or not in order to fit a particular application of the invention. The information may be in, and may be communicated in, any suitable form, or forms e.g. analog, digital, optical, magnetic, electromagnetic waves, wired or wireless and may be communicated in single direction, bidirectional, singular or redundant form, and the communication may use handshaking, networking or broadcasting, may be multiplexed in any fashion, networked, daisy chained, point to point or otherwise as desired to fit a particular embodiment of the invention. For example if wired communications links are desired, RS–232, IEEE 1901 or USB may be used

or for wireless ZigBee, IEEE 802.1X, Bluetooth, or Wi-Fi may be used, all being well known to one of ordinary skill. The communications may be simply contained within a dedicated implementation of the invention or may utilize a network covering a larger area for communications, for example via the internet. The invention described herein and/or its communications circuits may be shared or included in other systems and devices such as for example a home control system. Communications theory is a broad but well known field of art readily available to one of ordinary skill wishing to practice the invention, accordingly the communications links will not be discussed extensively herein.

[Para 90] Communications between the load control 25a and load switches 22a – 22c (or load control 43 described below) are provided by communications links 26a, 26b and 26c respectively. In addition, communications between load monitor 23a and generator monitor 24 is provided by communications link 27b. Communications between generator monitor 24 and load control 25a is provided by communications link 28a. Additionally optional communications link 27a may be provided between generator 13 and generator monitor 24, and additional communications may be provided by optional communications link 28b between generator monitor 24 and load control 25a. These communications links are preferred to be utilized to provide generator monitor 24 and load control 25a with, inter alia, additional information about the operation of generator 13 and to communicate back to generator 13 and generator monitor 24. Various parameters of the connected devices may be communicated to load control 25a as well.

[Para 91] Many prior art generator systems incorporate digital engine and alternator control systems which incorporate monitoring of the performance of the generator. Such monitoring includes determining the engine and alternator temperature, engine overload, voltage output, RPM, AC power frequency, current and power output for each leg of the alternator, total current output from the alternator, power factor, and percent of true total available power being supplied to the load. These control systems often further include over

current warning, under frequency warning and overload warning (by measure of current and/or frequency). In many systems it is desirable to communicate with these control systems to provide some or all of the monitoring information and device parameters to the load control 15 for use in its load connection and other decision making. A load shed signal, responsive to a low frequency or over current condition or both, indicates the generator is overloaded, is also available on some systems. Assuming adequate information about the operation of the generator is available directly from the engine and alternator control systems, that information may be coupled directly to load control 25a via a communications link (not shown) making load monitor 23a, generator monitor 24 and their communications links redundant in respect to monitoring the generator so that they may be eliminated in that respect. Load monitor 23a is still desirable for use to characterize loads and for timely monitoring of the load presented to the power grid, which is also the timely power output from the service connection, as previously discussed. In the instance where the power grid output is desired, 23a may be located at any point on the power grid circuit, such as the input or output of the transfer switch 15.

[Para 92] It is preferred that load control 25a operate to provide power, either directly or indirectly e.g. via generator monitor 24, to all of the devices to which it is connected for purposes of communications and/or sensing operation. It is also preferred that load control 25a (as well as the devices with which it communicates wirelessly) include its own backup power source, such as a rechargeable battery, in order that it and the devices with which it communicates may continue to operate without interruption whenever its primary power source fails such as during the time interval between the failure of power from the power grid and the supply of power backup power from the generator. Of course for wireless communication links it is preferable that the various wireless devices have their own power source(s), including backup if the device is critical to operation during outages of that source.

[Para 93] One or more optional additional communication link(s) shown in Figure 4 by 28c, may be provided between load control 25a and other optional devices such as sensors, information sources, displays, feedback, etc. shown as environmental, user and misc, devices 21. The display and feedback elements used in respect to the user may be combined if desired, for example such as with a touchscreen. These devices can include various sensors, for example such as temperature sensors to monitor outside temperature useful in controlling air conditioner operation, engine or alternator cooling air inlet or exhaust temperature useful in determining genset load, refrigerator or freezer temperature to determine if additional cooling is needed. The sensors for example may be utilized by 25a in the setting of priorities for loads to be connected to the generator. Such devices are desired to communicate with the load control as will be described further by way of example below.

[Para 94] Sensors and other components suitable for interface with the processor of 25 and/or use in practicing the invention are available from Analog Devices of Norwood MA, Texas Instruments of Dallas TX, National Semiconductor of Santa Clara, CA, Sensirion of Westlake Village, CA and many other suppliers as will be known to the person of ordinary skill in the art from the present teachings. Additionally the load control of the invention herein may communicate with other devices or services within or outside of the home area such as via telephone, internet, long distance wireless and the like e.g. in order to provide and receive information as well as handle and generate requests regarding power consumption, the devices which are connected, available for connection and the like, as will be described in more detail below.

[Para 95] Generally the communications links which are considered desirable to practice the preferred embodiment (i.e. the best mode) of the invention are shown in Figures 4 and 5 with solid lines with solid arrows showing the primary direction of communications. For example the load information from load monitor 23a is communicated to load control 25a

by communications link 27b which is shown in a solid line with a solid arrow. Additional communications which may be desirable to practice advanced features of the invention are shown with dashed lines and arrows, for example the environmental, user and miscellaneous devices 21 communicating with load control 25a.

[Para 96] Load switches 22a – 22c are preferred to be of a latching, dropout type which will automatically open circuit when power to the load switch (from transfer switch 15) is lost and thereafter and must be subsequently directed to close their circuit (after generator power is available via transfer switch 15) to provide power to the load. Accordingly when power from the power grid is lost the load switches 22a – 22c will switch to open circuit and remain in that state until they are closed by load control 25a thus preventing a generator overload when the transfer switch selects the generator output. Other switch types, or load control circuits, e.g. such as 43, or load controls, discussed below, may be utilized as well as will be known to person of ordinary skill from the teachings herein. Additionally, while the load switches 22a – 22c and load control 43 below are shown as separate units they may be combined with, or incorporated in the transfer switch or its control or in particular loads. The parts or all of the invention are also suitable for being combined with or incorporated in the generator, and may also include transfer switch control and/or transfer switch as will be known to one of ordinary skill from the teachings herein.

[Para 97] After a grid power loss the generator 13 will be started and transfer switch 15 will be switched to couple generator power to the house under control of the generator and transfer switch controller 14 (not shown in Figure 4). At this time load monitor 23a will operate to measure the electrical load presented to the generator by the house, which at this point of this explanation is the load presented by the lights 19 and miscellaneous loads 20 since load switches 22a – 22c are preferred to have switched, and remain open when grid power was lost and thereafter until turned on. Accordingly, 23a provides the timely power output of the generator.

[Para 98] Because the voltage out of the generator is known, for example 240 volts, the load monitor 23a may simply be a current sense coil, inductor, transformer, sensor or integrated circuit which provides an analog voltage output that is proportional to the electrical current supplied to the loads by the generator. Rogowski coils such as that described in US Patent 6,313,623 to Kojovic et al. are particularly useful in that they can respond to fast changing currents and are not prone to saturation as are iron core transformers and coils and are reasonably immune to electromagnetic interference. The output of 23a is coupled to generator monitor 24 where it is preferred to be converted to digital with the digital value of the current being coupled to load control 25a via communications channel 28a. Various other types of known load monitors are readily available and may be utilized and coupled to load control 25a as will be apparent to one of ordinary skill from the teachings herein.

[Para 99] As previously described, load (and other generator) information may be taken directly from the generator. For example the aforementioned Cummins model GGHE generator includes their PowerCommand control module which provides a wealth of information about the operation of the engine and alternator over RS-232 and other communications links. Many other generator manufacturers provide similar modules and functionality. It should be kept in mind however that the information provided by these modules may not always be accurate due to cost savings and tolerances. For example an overload indication may respond only to electric power output but not measure engine or alternator temperature. If the generator is operated at significant altitude, or on a hot and humid day, the cooling system may not be able to prevent an over temperature type of overload from occurring even though the power output is otherwise below that which would generate an overload signal. Accordingly it is desirable that load control 25a be capable of sensing several parameters of the generator, and that it may be programmed or otherwise set to operate in response to those parameters and the particular generator and environment.

[Para 100] Load Monitor 23a may be used to determine the actual kilowatt output by measuring both voltage and current and may also be used to determine the power factor (the ratio of active power to the arithmetic apparent power) of power being supplied to the load. Calculations may be performed in load monitor 23a, or generator monitor 24 or load control 25a as desired, however in this example it is preferred that 23a sense active and apparent power by sensing or measuring the present voltage and current in real time (or near real time), transmit those values to generator monitor 24 in real time (or near real time) where they are converted to digital in near real time with the digital values being communicated to load control 25a in near real time where the calculations of power factor and load are performed. By using real time or near real time values of voltage and current the relative phase of the two is preserved and that phase information can be used in the calculations to timely determine the power output of the generator which is used to determine the available power for other loads. As used herein, timely will be used to mean instant, real time, close to real time or a suitable time. In particular timely voltage, current, wattage, power or other quantity or parameter will mean the quantity of, or value representing the quantity of, the parameter existing at a time which is suitable to be useful in the operation of the invention. For example timely voltage output or power output values may be measured and transmitted to the load control with some time delay which delay is not long enough to impair the proper operation of the load control.

[Para 101] For this explanation, load control 25a will be assumed to know at least one maximum output power parameter e.g. maximum wattage or current of generator 13 (or a plurality of parameters e.g. its maximum output current vs. time capability). The maximum output power parameter is compared against the actual output at the time as measured by 23a and the remaining available power at the time is then calculated. Other parameters may be utilized to determine the projected power available at a future time or over a future time period may also be calculated. It is also desired that the power parameters e.g. initial

current requirements and current vs. time curve(s) of each load 16 – 18 are known to the load control 25a. It is desired that each of the loads 16 – 18 has associated with it one or more known priority parameter(s). As used herein, know and known mean to have been previously stored in a memory and available e.g. having been previously manufactured with, programmed with or measured. All such parameters are preferred to be manually or automatically changeable as will be described below. In reality it may be that one or more parameters is not know at the time and must be determined or estimated as will be described further below.

[Para 102] After generator power is made available via the transfer switch, load control 25a operates to determine if the highest priority load 16 – 18 can be supported by the available power of generator 13 and if so load control 25a causes the load switch associated with that load to be closed via commands conveyed to the switch by its corresponding communications channel. Next load control 25a operates in response to the new power measurement from 23a to determine if the next highest priority load 16 – 18 can be supported by the available power from the generator. If so that load is connected by command sent via its switch's corresponding communications channel. Likewise the third priority load requirement (in this case the last load of the three) is checked against available generator power and the load connected if sufficient power available. While only three controlled loads are shown in Figure 4, it will be known from the present teachings that the number of loads which may be controlled is not so limited and additional controlled loads and corresponding communication links (e.g. 26d – 26N) may be utilized. In the event one or more of the loads cannot be connected because of insufficient available power from the generator, the load control 25a will periodically compare the available power supplied by the generator to the power required by the load and if possible connect the load. It may be that available power for a load results from one or more previously connected loads no longer requiring power, for example the clothes dryer is finished and that load may be

disconnected to prevent it from being turned on and creating an overload. Or, the air conditioner may require less power to run because outside air has cooled and that additional information may be utilized by load control 25a to determine it is safe to connect another load.

[Para 103] Load control 25a is preferred to operate in substantially continuous mode to constantly compute load requirements and generator capabilities to connect and disconnect loads according to priorities as a result of changing loads and priorities. Lower priority loads may be disconnected to accommodate higher priority loads. Environmental, user and other parameters may be utilized by load control 25 in order to determine that it is safe (or that there is a high probability that it is safe) to connect a particular load. It is preferred that load control 25a ensure that loads such as air conditioners which should not be cycled too quickly remain disconnected and/or remain connected for appropriate amounts of time. Load control 25a also monitors the generator 13 for overloads, and other parameters such as minor equipment failures such as slight overheating and chooses which loads to disconnect, or in the event of a significant failure may change the transfer switch 15 back to the grid power position (even though there is no grid power). Of course load control 25a will monitor grid power and change the transfer switch 15 back to the grid power position when power returns, meets expected parameters and is expected to continue meeting those parameters. It is preferred that after the transfer switch returns to grid power that loads are reconnected one at a time in order to prevent a large instantaneous power demand surge.

[Para 104] Although continuous operation is preferred, the invention may be practiced with other types of operation as well, especially when power consumption of the load control is intended to be kept to a minimum. It may be operated at periodic intervals or may be caused to operate only when one or more parameter of the system changes appreciably. In one alternative, load control 25a may operate in a low power standby mode, only checking for the presence of power from power grid 12 and remain in standby as long as

grid power is present, but change to a more active or fully active mode if grid power experiences problems such a fluctuations in voltage or frequency (outside of expected parameters), or failure.

[Para 105] It will be appreciated from these teachings that load changes on the generator 13 may occur during operation because the switched loads 16 – 18 (if connected) or the unswitched loads 19 and 20 may change, and those changes may be communicated by the generator monitor 24 via 27b or otherwise to provide data via generator monitor 24 to load control 25a which may use this data to characterize and store load characteristics. For example if a request is made of load control 25a to turn on clothes dryer 17 via load switch 22b, the change in current sensed by load monitor 27b over the next few minutes can be stored and used as some of the parameters, e.g. starting and current after initial warm up, for that load. In this fashion unknown parameters may be determined or estimated and known parameters may be updated. While this type of measurement might be interfered with by other loads changing, if several consistent measurements and some inconsistent measurements are made for a number of dryer requests, it is probable that the consistent measurements are reasonably accurate. The consistent and inconsistent measurements may be determined by correlation or other statistical matching techniques. The consistent measurements may then be averaged to remove small variations due to dryer load, ambient temperature and other such changes. Of course more accurate measurements may be made by directly monitoring the dryer load as will be discussed below.

[Para 106] Figure 5 shows a more detailed diagram of load control 25a. Communication links provide for communications between a processor circuit 33a and various devices as discussed herein. Load control 25a contains interface circuits 29a – 29h to interface communications channels 28a, 28b (optional), 30, 31, 32 and 26a – 26N to a processor circuit 33a.

[Para 107] The processor circuit will include a processor, e.g. a digital machine performing logic, computing and/or program execution operations which machine accepts data and runs (i.e. executes) logic operations, computing operations and/or program steps to produce results. The processor circuit will also include supporting circuitry to facilitate the processor accepting data, executing one or more logic operations, computing operations and/or program(s), produce and utilize the necessary results and communicate with other components and devices. The processor circuit and its various elements may be of any of the types suitable for performing the various desired ones of control, monitoring, storage, communications, calculation and decision making operations described herein which are necessary to implement a particular version of the invention. The processor circuit may be implemented with any type(s) of circuit devices currently known or which will become to be known in the electronic control systems art including but not limited to analog and digital circuits, LSI, VLSI, ASIC, PLD, CPLD, FPGA, DSP, IP Core, Array, microcontroller, microprocessor, Multicomputer, RISC or CPU integrated circuits.

[Para 108] Processor circuit 33a may also include one or more interface circuits similar to 29 (thus eliminating one or more interface circuits 29 which are external to 33a). A particular processor circuit may be chosen for use in implementing the present invention by one of ordinary skill from the teachings herein in view of other considerations as well, e.g. power consumption, cost, complexity, ease of use, speed of operation and flexibility of operation. Examples of such computer circuits include PCs using Windows, Linux or other operating systems, Apple products such as iPhone, iPad, iPod, Android product such as the Asus Eee Pad tablet, various RISC, parallel microcomputer and embedded devices. While the processor circuit 33a has been described in the singular, it may be implemented by multiple circuits or devices as desired.

[Para 109] Communications links 26a – 26N, 28a and 28b operate as described previously and in further detail below. Communication links 30, 31 and 32 (in Figure 4 as part of 28c)

communicate with one or more environmental, user and miscellaneous devices (shown in Figure 4 as part of 21). Communication link 30 is used to supply data from a user input module(s) to processor circuit 33a of load control 25a and if desired communication link 31 operates to supply data from the processor circuit 33a of load control 25a to the same or different user module(s). It is of course possible that such data may be supplied by a single bidirectional communications link as indicated by the dashed arrow on 30 and 31. Data to and from other auxiliary devices may be communicated to and from processor circuit 33a of load control 25a by one or more communications link(s) 32 as will be discussed further below. Processor circuit 33a communicates via communications links 26a – 26N to communicate with load switches or replacement devices 1 – N respectively to cause loads to be connected to the power source (via transfer switch 15) and if desired to receive data from one or more load switches or replacement devices. It will be understood that the preferred embodiment of Figures 4 and 5 may utilize a particular processor circuit 33a, for example the Asus Eee Pad tablet wherein various other elements of Figures 4 and 5 are provided by 33a. In the present example all of the user inputs and feedback devices are preferred to be provided by the Asus Eee Pad touch screen and communications links 26a – 26N, 28a, 28b and 32 being provided via its IEEE 802.11 and/or Bluetooth wireless communications capability.

[Para 110] As a simplified example to aid in understanding the operation of the load monitor and load control of the preferred embodiment, consider a generator which because of its existing load and internal temperature can provide 30 amps for up to 5 seconds and 20 amps for 5 minutes and 18 amps after 10 minutes. Now consider an air conditioner which requires 30 amps for 4 seconds to start, 20 amps to run after that for 1 minute and then increasing to 21 amps as the condenser coil heats thereby causing the head pressure and compressor current to increase. Starting the air conditioner and running it for 1 minute would be possible without overloading the generator. After 1 minute the condenser coil

heats and the air conditioner would overload the generator by 1 amp and disconnecting it would be advisable. After 10 minutes the generator would be overloaded by 3 amps and would need to be disconnected because of the substantial overload of the generator. It is desirable that the load control also keep track of the operating characteristics of the other loads which are connected. By knowing the characteristics of the generator and load(s), the load control can make a decision of whether to connect the load, which in this example would not be advisable.

[Para 111] As a further example, add to the above example an ambient temperature monitor to provide an environmental parameter. Assume the load control 25a records a decrease of the ambient temperature due to cold rainfall with the internal temperature of the generator decreasing for a given load which in turn will allow a somewhat larger load to be accommodated. As used in this context records means to store a plurality of values of the same changing parameter, in this instance temperature, over a time period. The rainfall may also be sensed and recorded, For the air conditioner compressor a decreasing ambient temperature will lead to a reduced condenser coil temperature, decreased compressor head pressure and decreased compressor current draw. In this instance, depending on the rate of temperature drop, the expected increase of generator capacity and expected decrease of compressor current, it may be possible to predict that the air conditioner may be safely connected to the generator.

[Para 112] Adding a further environmental parameter to the example, it is likely that humidity will increase due to the rain and the higher humidity air will decrease the maximum torque output of the generator's motor. This additional environmental parameter may be sensed and recorded for utilization by the load control 25a in determining the maximum output power which will be available in the near future. Because humidity also affects the cooling of the condenser coil by airflow across the coil, this may be taken into account by load control 25a as well. It will be understood that timely determinations of

generator maximum output power as well as load power consumption for a given load may be made by using various environmental parameters. It will be further understood that determinations of upcoming generator maximum output power as well as upcoming load power consumption for a given load may be made by using various changing environmental parameters, upcoming meaning over at least the next hour unless otherwise specified.

[Para 113] To continue the above example, consider the same generator capability as above, i.e. 30 amps for up to 5 seconds and 20 amps for 5 minutes and 18 amps after 10 minutes. Consider a different load, an oven which will draw 25 amps for 5 seconds, 20 amps decreasing to 15 amps over 3 minutes and 15 amps intermittently thereafter as the oven thermostat switches the heating element on and off. This load can be safely connected to the generator since it will not exceed the generator's capacity at any time.

[Para 114] Of course, in the above examples it is assumed that when a connection to the air conditioner or the oven is made that device will be in operation and will immediately begin loading the generator. It would be useful to know if each device would in fact be in operation or could be in operation at some time after connection. As an added factor in the decision making it would be useful to input the status of the device (e.g. on or off as a parameter), or otherwise determine the likelihood that the device would present a load if connected. This consideration relates to establishing a priority for a load, for example if the oven or the air conditioner is turned off then it would not present a significant load if it is connected. If the indoor or outdoor air temperature were low it is unlikely the air conditioner would present a load if connected. If the oven were operating before loss of grid power the thermostat will likely power the heating element when the oven is connected or within a few minutes thereafter. It is desirable for load control 25a to record and use these parameters in its load connection decision making.

[Para 115] As a further example of the operation of the load control 25a consider the priority of the loads. If the time of day (sunset) is after the normal time that dinner is

prepared in the oven then the oven has a relatively low priority. If the temperature in the house is hot, the air conditioner has a high priority. If generator capacity is available the air conditioner would be connected instead of the oven. On the other hand, if the oven is in use when the grid power fails it is reasonable to assume food is being prepared. The interruption of power while food is being prepared can cause a serious problem for the occupants of the house making the oven a very high priority load. If the inside temperature of the house is at a reasonably comfortable level, and if generator capacity is available the oven would be connected instead of the air conditioner. The oven use likely will end within an hour or two and at that time it may be possible to connect the air conditioner, meanwhile the inside temperature of the house will likely not rise to uncomfortable levels. It is thus preferred that load control 25a include a real time clock and calendar feature, coupled with calendar factors such as sunrise and sunset, identification of local temperature norms, highs and lows for each calendar day and other information such as load usage habits, as will be useful in managing generator operation and loads.

[Para 116] If the oven was operating in a self cleaning mode instead of food preparation mode when grid power failed as detected by steady and higher than normal current draw. It is preferred that the oven current draw be recorded by the load control 25a and used to determine that the oven was in cleaning mode. That determination is preferred to be incorporated into the assignment of priority to reconnecting the oven. Since oven cleaning is not as important as preparing food, that cleaning can be delayed while other higher priority loads such as the air conditioner are connected. Of course it will be desirable to allow the occupants of the house to make the decision as to applying power to the oven or the air conditioner as will be explained further below. A temperature sensor, part of 21, may be provided for a refrigerator or freezer and that temperature is used in determining the priority of connecting the associated load. For example if the freezer temperature is well below the safe limit the freezer would be determined to be a low priority load whereas if the

temperature rises to be near the safe limit the freezer would be determined to be higher or high priority load.

[Para 117] Secondary factors, such as the time of day and decreasing ambient temperature of the above example are also preferred to be taken into account in deciding to connect a particular device to or disconnect it from the power source. Such factors include, but are not limited to, calendar data, load usage habits, one or more parameter of the load for the particular device e.g. maximum possible load, expected load for current conditions, projected changes in the load with time or conditions, starting and surge currents (e.g. the starting current of an electric motor), power factor of the load such as resistive, capacitive or inductive type loads, the probability that a load will need to be connected or disconnected during the near and distant future, damage done by failing to connect a load or by disconnecting a load once connected. The short and long term ability of the power source to supply power in known or projected amounts, environmental factors such as ambient temperature, humidity, altitude, quantity of fuel available, fuel delivery rate, quality of fuel, cost of fuel, cost of supplying power from a given power source vs. cost of purchasing or supplying power from another power source and environmental effects of supplying power from a given power source.

[Para 118] In order to evaluate various factors and parameters used by the load control 25a for decisions to connect or disconnect loads, information will need to be available to the load control. It is preferred that the load control be programmable in order to store such information, however that information may be incorporated at manufacture, or may be learned by the load control by monitoring and recording parameters e.g. the operation of various loads, as will be explained further in respect to Figure 6. As a simple example the current and time parameters of the oven may be recorded to compute current vs. time curves from initial turn on until reaching temperature for both cooking at different temperatures and cleaning operation of the oven can be used in subsequent decision

making. The higher the oven thermostat is set, the longer it takes for the thermostat to reach its first cycle and the more frequently it cycles, which information may be utilized to characterize the oven operation.

[Para 119] Of course those time and cycling parameters are also influenced by the mass and initial temperature of the food being cooked but about half way into the cooking time when the surface temperature of the food approaches the oven setting, that influence is greatly decreased. Curves for different temperatures as determined by the time from turn on until first thermostat cycle and then the cycle time thereafter can be recorded. When the oven is first started in a new cooking cycle, the temperature the oven thermostat is set to may be estimated from the time of turn on to first several thermostat cycles and comparison to the curves computed for previous operations. While such determinations are not absolutely accurate they will nevertheless provide an approximation which load control 25a may use in determining whether or not to connect a load. In some applications the oven may be configured to communicate directly with load control 25a, to provide useful information such as thermostat setting, cooking time and/or oven temperature.

[Para 120] Figure 6 shows the preferred embodiment of the invention with various embodiments of load switches 22b and 22c (note load switch 22a of Figure 4 is replaced with load limit 43) and a combination user input and user feedback module 39. Load limit 43 includes a current control 44 to control current supplied to load 16 which control may, if desired, include complete disconnect of load 16 (an electric oven in this example) to/from the power source selected by the transfer switch 15. As just one example of a load limit device which may be utilized for 43, consider a remotely controlled light dimmer switch commonly found in the home and connected to a 250 watt incandescent light bulb. The light bulb will draw a full load of 250 watts of power if connected directly to the 120 volt power but a load limit circuit which in this example is the dimmer will limit the amount of power supplied to the light bulb.

[Para 121] Such load limiting circuits are well known in the art and include current limit circuits which operate to prevent a current from exceeding its prescribed limit, which in the present example is set in response to load control 25a. Constant current circuits may be also used for 44 and operate to maintain a preset current through a range of a variable load, which current in this example will be set in response to load control 25a. For clarity, as used in the present specification and claims a load limit (or current control) device limits the power supplied to a device which if connected directly to the power source under the same conditions is capable of consuming more power than that the power delivered via the load limit. This usage is in contrast to a controllable load for which the load itself is controlled so that the amount of power that is consumed when connected directly to the power source is controlled. As a simple example, remote controlled room heaters are such a controllable load.

[Para 122] It will be further understood to one of ordinary skill from the teachings herein that other types of control circuits may be utilized for 44 to control the power supplied to the load, e.g. phase vector drive circuits, variable frequency circuits, direct torque control, SCR and thyristor circuits, pulse width modulation and chopper circuits, and various soft start circuits, many of which are commonly used as drive circuits for electric motors. Some of the other circuits which may be utilized operate by reducing the amplitude of the supplied voltage, or by reducing the duty cycle of supplied current or altering the phase of the voltage and current applied to the load, and various combinations thereof. One of ordinary skill will be able to select a particular type of circuit for use with a particular load type.

[Para 123] Load limit 43 communicates with load control 25a via communication links 26a and 36 in order to send and receive data. Interface 29i couples the communication link 26a to current control 44 to allow the load control 25a to operate current control 44. While shown in respect to an electric oven in this example, it will be understood from the

teachings herein that load limit 43 may be utilized with other types of loads, and will be particularly useful with high demand loads, for example heating and other resistive loads, battery chargers, electrolysis and other electro-chemical loads, in order to limit the maximum amount of power the load draws. One of ordinary skill will also understand that many types of high demand loads do not lend themselves to operation with particular load control circuits, for example many large constant speed rotating machinery loads which are desired to operate synchronously with relatively fixed voltage AC power and thus are difficult to use with variable voltage control circuits.

[Para 124] Load control 25a may cause the load to be controlled in discrete levels, for example full, 75%, 50% etc. or may cause the load to be controlled in essentially continuous fashion, for example 1% or smaller increments from 0 to 100%. It is desirable however that many loads such as the oven be continuously provided with some minimum amount of power to power clocks, timers, control circuits and the like in order that they do not have to be reprogrammed after power is completely interrupted for a longer period of time. Many ovens and other high demand loads include switching power supplies to power their clocks, timers, control circuits and the like with these supplies being capable of operating with reduced voltages. Alternatively the clocks, timers and the like may be provided power via a continuously connected circuit, or may incorporate backup power such as battery operation.

[Para 125] Load monitor 23b is preferred to be included in load limit circuit 43 but may, as well as 35, be omitted if their capabilities are not desired for operation of load control 25a. Load monitor 23b is similar to 23a except for possible changes to match it to the current controlled and different maximum load. 23b monitors the electric power supplied to load 16 and communicates via interface 35 and communication channel 36 with load control 25a. This monitor may be utilized to send load power (e.g. current) information to load control 25a for several purposes. For example full power oven load characteristics such as initial heating current and current to maintain temperature when heated to provide current

vs. time parameters as previously discussed will allow load control to predict future load. Also 23b may be used to enable load control 25a to determine that the current actually being used has dropped below the value the current is set to by current controlled 44. This will allow load control 25a to further adjust current to thus guarantee a lower maximum load without adversely affecting oven performance. It is also desirable that communications link 26a and/or 36 operate bidirectionally to provide information to load control 25a thus allowing verification and monitoring of the operation of load limit 43.

[Para 126] The oven load information may be used by load control 25a to detect when the oven heating element has just been turned off by the oven thermostat (and thus expected not to turn on again for several seconds or longer). This will allow load control 25a to use the resulting extra generator capacity for other purposes, for example to provide additional starting current such to as an air conditioner compressor. As a safety precaution load control 25a may also lower the current supply to the oven to a very low value for a short time. This lowering will not impair oven operation while guarding against an unintentional overload of generator 13 in the event the oven thermostat unexpectedly closes due to an unforeseen event such as an opened door. Oven load information may be used to cycle another load out of phase with the oven heating element, that is to only turn on or increase another load such as a battery charger for a time period after the oven heating element is turned off. Alternatively the other load can be turned on or increased when the oven heating element is turned off and turned off or decreased immediately after the oven heating element is turned on, the momentary overlap of the two being handled by the short term higher current capability of the generator. These operations will generally be possible with any type of load which cycles on and off.

[Para 127] It will be recognized from the teachings herein that the operation of load limit 43 may be partially or completely incorporated within a particular load as desired. For example the current control 44 and/or load monitor 23b may be incorporated within the

oven 16. Alternatively other loads which are capable of being limited, for example the battery charger for an electric or hybrid vehicle or the like discussed above, may be connected in a fashion to provide current limit and/or load monitoring interconnection to load control 25a as desired. If the load has internal control of its current available, for example such as the battery charger for an electric or hybrid vehicle or the like, it may be connected to load control 25a without an additional current limit circuit. As with the additional current control 44, load control 25a may cause the load to be controlled in discrete levels or may cause the load to be controlled in essentially continuous fashion. As with the separate current control circuit, for loads which have internal clocks, timers or the like which require some small amount of current to operate it is desirable not to completely disconnect them from the power source for long times which will cause these circuits to need to be reset, or alternate continuous circuit power or backup capability can be provided.

[Para 128] Control of individual loads to limit the power supplied to them or power consumed by them (one controls the other) under control of load control 25a is desired, particularly during times when the power grid is in heavy use and during times when generator 13 is supplying power. For example heavy current loads like ovens and chargers may still be operated at reduced current in order to prevent overload of the power source, as compared to their being entirely disconnected. An oven for example will take longer from initial turn on to heat to its thermostatically controlled temperature, but once at that temperature the thermostat will be able to control the temperature, assuming a reasonable amount of current less than the maximum is still available to the heating element. In a situation where a power failure occurs after oven use is started, limiting the current to the oven may allow the oven to be powered from the generator, thus allowing the cooking to be completed, as compared to an oven which is not so limited and thus can not be connected to the generator because it will cause an overload.

[Para 129] Figure 6 also shows load switch 22b including a switch 34 to connect and disconnect load 17, an electric clothes dryer, to/from the power source selected by the transfer switch 15. Load switch 22b communicates with load control 25a via communication links 26b. Interface 29j couples the communication link 26a to switch 34 to allow the load control to operate switch 34. Load 17 may optionally communicate with load control 25a via communications link 40b. The switch may be operated in a normally closed or a normally open configuration or a latching condition as known to one of ordinary skill, however it is preferred that load control 25a simulate any of those switch types for a given switch. It is also desirable that communications link 26b operate bidirectionally to provide information to load control 25a thus allowing verification and monitoring of the operation of load switch 22b.

[Para 130] Figure 6 further shows load switch 22c which includes a switch 34 to connect and disconnect load 18, an electric air conditioner, to/from the power source selected by the transfer switch 15. Load switch 22c communicates with load control 25a via communication links 26c. Interface 29k and switch logic circuit 37 couple the communication link 26c to switch 34 to allow the load control 25a to operate switch 34 via logic circuit 37. Logic circuit 37 is preferred to be configurable by communications from load control 25a to cause it to operate in response to power from the transfer switch as a normally open, normally closed, latching or special function switch. It is preferred that 37 normally be configured by load control 25a to operate the switch to open when power to the switch from the transfer switch is lost and to stay open until a command to close is received and thereafter as a latching switch (until power from the transfer switch is lost again). In this fashion the load is automatically removed from the transfer switch when power is lost, thus eliminating the need to have it disconnected by the load control. It is further preferred that 37 include a time delay function to prevent power from being applied to the air conditioner for a time period after it has been removed in order that the

compressor head pressure can bleed off thus avoiding the possibility of excessive compressor starting currents. It is also desirable that communications link 26c operate bidirectionally to provide information to load control 25a thus allowing verification and monitoring of the operation of load switch 22c.

[Para 131] Figure 6 still further shows a combination user input and user feedback module 39 which communicates with load 16 via communications link 38 and communicates with load control 25a via communications link 40. As previously discussed 39 may be incorporated into or supplied by processor circuit 33. While shown as a combination input and feedback module, the two operations may be separated into different devices using common or different communications. In the present example, a user desiring to operate the oven may be alerted that insufficient power capability exists for such operation, thereby allowing further user interaction with load control 25a.

[Para 132] While the load switches 22, load limit 43, controllable loads e.g. 16, 17 and 48 are most commonly described herein as being preferred to be separate from the load control 25, one of ordinary skill will recognize that the invention may very well be practiced with load control circuitry, especially that circuitry corresponding to controlling a particular switch, limit and/or load, being incorporated within or specific to a particular switch, limit and/or load, or small number thereof, which will be referred to herein as load specific control circuitry. In this respect the communications which sense overloads and other load related parameters and user inputs e.g. generator monitor 24 and environmental, user & miscellaneous devices 21, as well as particular user interfaces, may be contained within the load or load controlling device, and/or communicate directly with load specific control circuitry.

[Para 133] In particular, in low cost systems, the aforementioned use of power frequency may be utilized directly within a load or load control device to sense an overload and disconnect the load. One of skill in the art will recognize that it will be useful to establish

priorities for each such device which priorities may be established by incorporating circuitry to determine the degree or level of overload, various time delay operations or combinations thereof in one or more of load switches 22, load limit 43, controllable loads e.g. 16, 17 and 48 such that some loads are shed or prevented from connecting more readily than others. For example the power frequency detector may be set to detect degrees or levels of frequency change, with some loads being disconnected, transferred, limited or prevented from being connected to a particular source at a small frequency change and others being disconnected, limited or prevented from being connected with larger frequency changes or combinations thereof being utilized with a particular load. As described herein, particular loads may be switched from one power source to another to facilitate a desired optimization or operation of the system.

[Para 134] As one example a low priority load may be prevented from being connected if the power frequency makes more than normal excursions, if even momentary, below a given frequency threshold. Such excursions would have a high probability of indicating the generator is close to an overload and is momentarily overloaded by small and/or short term load increases for example such as the starting current of a small motor in a kitchen appliance such as a refrigerator. When a larger or longer term power frequency deviation is detected a delay may be incorporated in one or more of load switches 22, load limit 43, controllable loads e.g. 16, 17 and 48, with lower priority loads being disconnected faster than higher priority loads. In this example a low priority load such as an air conditioner may be quickly disconnected which could very well eliminate the overload and return the power frequency to normal and thus eliminate the need to disconnect more loads.

[Para 135] A load circuit may be part of or otherwise incorporated to control one or a small number of loads, load switches, transfers and/or load limits in order to sense power frequency to determine the probability of nearing an overload, being in a small overload, a moderate overload or large overload with this information being utilized to control limiting

the current supplied to one or more load, disconnecting or transferring one or more load and/or preventing the connection of one or more load. In addition other features of the invention described herein may be incorporated, such as preventing the reconnection of a load for a time period after it normally turns off or is disconnected. It will be understood that the individual features, e.g. those of 22b, 22c, 43 and 39 described with respect to the Figures may be rearranged to operate with a particular load, set of loads or sets of loads as desired to provide a particular combination of inventive features for a particular system as will be known to the person of ordinary skill from the teachings herein.

[Para 136] With systems where load specific control circuitry is utilized to control the connection of one or a small number of loads in response to the power frequency, it is desirable to know the loading vs. frequency of the power source or sources. In particular the characteristics of the frequency versus load are preferred to be programmed into the microprocessor either at manufacturer or by the user during installation in order that the microprocessor may know if the load being supplied by the generator is below, near, slightly overloaded, significantly overloaded or highly overloaded. In this respect it is also useful to control the frequency of the A.C. power provided by the power source in response to the load on the power source in order that the frequency may be more accurately utilized by the load specific control circuitry to prevent or remove overloads. This frequency control may be accomplished by sensing the load on the source and controlling the power frequency by feedback to the frequency control, e.g. the rotational speed of a genset or frequency reference of an A.C. inverter.

[Para 137] Figure 7 shows an example of a mechanical layout of the combination user input and user feedback module 39, including a display 41 for displaying messages from load control 25a to the user and switches 42a – 42c to allow the user to (among other capabilities) provide commands to the load control 25a. User commands and messages are conveyed to and from the load control 25a via communications link 40a, and to and from

load 16 via communications link 38. Load 16 and load control 25a may also communicate with each other via 39 (and communications links 38 and 40a). For example if the user wants to turn on the oven it can instruct the load control to provide power for the oven to be operated in a particular mode such as full power or at some level of reduced power as described herein. The load control 25a can offer a set of options to the user including options to chose the level of operation of the desired load and corresponding decreases in the level of, or termination of, operation of other loads. In this fashion the user may communicate with the load control in order to change priorities to enable the user to obtain power for the desired device. It will be understood that one or more user input and/or user feedback modules may be provided with any of the loads in order to allow the user to communicate with the load control in order to enable the user to operate a desired device, or to allow communications with the load control in order for the user to operate multiple devices. The feedback and input capabilities may be combined if desired, for example by use of a touch screen as is well known in the art.

[Para 138] For example, a user desiring to use the oven to bake for 45 minutes at 400 degrees can enter that information to load control 25a via 39 and keys 42. The load control will then determine options available to allow oven operation and provide them to the user. The user then selects one or more (or none) of the options and the load control puts the user's desired operation into effect. For example the load control might offer the user the following options: a) operate the oven at full power by turning off an air conditioner; b) operate the oven at full power by turning off a vehicle battery charger; c) operate the oven at 75% power by reducing the battery charger current by 50% with an increase of 7 minutes to preheat the oven to 400 degrees; d) operate the oven at 65% power by turning off a hot water heater, with an increase of 10 minutes to preheat the oven; e) select option d) and in addition reduce the battery charger power by 75% and operate the water heater only while the oven heating element is turned off by the oven thermostat. It will be understood from

the above example that there are numerous capabilities and options which may be determined by the load control 25a and presented to a user to assist the user to achieve a desired operation. This assistance may be provided in several manners with menu selection, interactive querying and graphical user interface being just a few.

[Para 139] Accordingly it will be understood that the system of Figure 4 as implemented with the various features of Figures 6 and 7 will be capable of operation to power ones, which will be understood to include some or all, of a group of loads. The group of loads may include loads which may be individually switched on and off, loads for which the power supplied to the load is limited to a known maximum amount, loads which may be controlled to limit the amount of power they take from the power source and loads which are not controlled. It is noted that practice of the invention will virtually always include loads which are not controlled, which for example will most probably include the generator and transfer switch controller 14 as well as the power supply for the load control 25, lighting and electrical outlets for consumer electronic devices. It will be understood that the invention may be practiced as needed in a particular system with only one load comprising any one or more particular type of loads and/or without any combination of the above described types of loads.

[Para 140] Figure 8, similar to Figure 4 shows a simplified diagram of another embodiment of the invention which includes operation with a third power source 50 which by way of example is shown as a solar panel and controllable load(s) 48. Elements 12, 13, 16, 17, 18, 19, 21, 22b, 22c, 23a, 26a, 26b, 26c, 27a, 27b, 28a, 28b and 28c are shown, the same as in Figure 4 except that 21, 27a and 28c are changed from optional in this embodiment. Load limit 43 is the same as described in respect to Figure 6. Figure 8 further includes load control 25b similar to 25a of Figure 4 but having increased capabilities including controlling the generator and transfer switch instead of 14, as will be described below by way of example. Figure 8 also includes transfer switch 47, similar to switch 15 except that it is an

on-off-on type switch (as compared to break before make on-on type for prior art switch 15) which can connect its output to either power grid 12, or generator 13 or neither, thus leaving only the third power source (solar panel) 50 to power the loads. Transfer switch 47 is controlled by load control 25b via communications link 45 (shown at the top of the transfer switch and bottom of the load control) and controllable load(s) 48 communicating with load control 25b via load control communications link 46. One of ordinary skill will understand that in order to simplify the description of the invention Figure 8 does not show many elements, e.g. circuit breakers, safety features and the like that are required of an actual system and as with transfer switch 15, one of ordinary skill will know that transfer switch 47 will be much more complex in practice and is shown herein in simplified form for purposes of explanation.

[Para 141] One of ordinary skill will know from the present teachings, to practice the invention utilizing the on-off-on type of transfer switch 47. As with Figure 4, the embodiment of Figure 8 may be utilized to prevent overload of any combination of the power grid service 12, generator 13 and third power source 50. It will also be understood that third power source 50 may be operated while the power grid is connected in order to reduce the power supplied by the power grid, or even to sell power back to the power utility, however it will be recognized that in such paralleled systems when the power grid fails it is important to disconnect the power grid from the generator in order to prevent damage to the generator or possible harm to workers who are repairing the grid failure. Additionally, when the generator is connected by transfer switch 47 to power the loads it is likewise important not to transfer substantial (i.e. damaging) amounts of power from the third power source to the generator to prevent damage to the generator. Because of this it is important to monitor the generator current output or otherwise to connect an additional load or disconnect the generator when the third power source 50 can provide enough current to power the loads.

[Para 142] Communications link 27a is utilized for communications between generator 13 and load control 25b via power source monitor 49 in order that load control 25b may start and stop the generator in response to power grid failure (sensing link to power grid is not shown) or as otherwise needed. Note that communications link 27a may connect directly from generator 13 to load control 25b as previously described. One of ordinary skill will understand from the present teachings that the third power source, solar panel 50 is representative of one or more additional individual power sources which may be utilized with the invention. A solar panel which is made up of individual photovoltaic cells that convert sunlight to electricity is chosen in Figure 8 by way of example with the teachings of the inventive concepts being applicable to individual and combinations of other types and numbers of power sources, e.g. stored energy, wind, water and geothermal types of power sources in addition to solar. As with communications link 27a, the solar panel communications link 27c may be connected directly to load control 25b if desired. When solar panel 50 and generator 13 are connected directly to load control 25b power source monitor 49, load monitors 23a and 23c and their associated communications links may become redundant and may be eliminated with respect to monitoring the generator and solar panel respectively.

[Para 143] Solar panel 50 has a power output via connection 51 which is connected with the output of transfer switch 47 to provide power to the loads as is well known in the art, e.g. it is synchronized to and paralleled with the power from transfer switch 47. The power output from the solar panel is measured via load monitor 23c and communicated to power source monitor 49 via communications link 27d. Load monitor 23c is similar to 23a except for possible changes to match it to the maximum output power of the solar panel. Power source monitor 49 functions in a manner similar to generator monitor 24, receiving generator and power grid load information from 23a via communications link 27b and

optionally communicating via communications link 27a. As explained with respect to Figure 4, load monitor 23a may also monitor power supplied by the grid.

[Para 144] Additionally power source monitor 49 receives solar panel power output information via 23c and communications link 27d and optionally communicates with solar panel 50 via communications link 27c. The power source monitor 49 communicates with load control 25b via communication link 28a and optionally 28b as previously described in respect to Figures 4 and 5 but additionally includes information and communications with respect to solar panel 50. As will be known to one of ordinary skill from the teachings herein, the power source monitor and load control may be expanded or duplicated to handle more power sources than the generator 13 and solar panel 50. Connection of those extra power sources to the system may be via extra transfer switch circuits as with generator 13, or via paralleling as with solar panel 50, and will be accommodated by load control 25b for control of the loads being powered. As previously explained with respect to generator 13, if the power source(s) provide information about their operating parameters from their own control and/or monitoring systems that information may be communicated directly to load control 25b and power source monitor 49 along with its sensors and communications link may be eliminated with respect to those power sources.

[Para 145] The operation of the embodiment of Figure 8 is similar to that of Figure 4, however additional capabilities of powering loads 16 – 19 and 48 from the solar panel 50 are provided as well as interacting with and controlling load(s) 48 directly by load control 25b to set its maximum load presented to the power source(s). For example a controllable load 48 may be a Lasko Model 5350 room heater which can be remotely switched from off to 900 watts to 1500 watts via wireless communications link via load control 25b. Solar panel 50 is connected to the output of the transfer switch 47 to provide additional power to the loads when environmental conditions permit, thereby reducing the amount of power required from the other power source(s). In particular, during periods of low load demand

when power is available from 50 the load control 25b is preferred to communicate via 45 to cause transfer switch 47 to switch to its off position in order to power those of the loads 16 – 19 and 48 which are consuming power to receive that power from 50.

[Para 146] Controllable load(s) 48, such as the aforementioned room heater may be powered by solar panel 50 and controlled to either heat at 1500 watts if there is enough power available and heating is desired because of a cold room or outdoor temperature (sensed by sensors 21), or may be reduced to 900 watts if a higher priority load needs power or the solar panel 50 is incapable of providing power for the high setting, or may be switched off if the room temperature is high enough or solar panel 50 can not provide 900 watts. It will be recognized in this example that when the room temperature reaches the thermostat temperature of the heater 48 (which may be set by load control 25b or directly on the heater by a user), the heater will turn off its heating element thereby drawing minimal power. Load control 25b may nevertheless turn off the heater to avoid a sudden overload of the solar panel 50 should the room temperature cool to the point where the heater's thermostat turns the heating element on again.

[Para 147] Accordingly to the present example, low cost power is selected by load control 25b to power the loads while at the same time the load control will communicate to various components of the system to monitor (e.g. via load monitor 23c) and control power supplied to several loads each of differing types including high priority loads such as lights 19, switchable loads such as by load switch 22b to clothes dryer 17, limitable loads such as via load limit 43 to oven 16 and controllable loads such as the heater 48 to allow loads of various priorities to be powered by the low cost power source while at the same time preventing overload of that source. Load control 25b will monitor and control power demands by the various loads so as to not exceed the available power from a given power source or set of power sources. If demand increased beyond what a power source such as the solar panel 50 is capable of providing, the load control will decide to either not connect

the additional load(s), or to connect but control power supplied to the additional load(s), or to connect additional power source(s) such as grid power 12, or start and connect the generator 13, or other power sources (not shown) thus providing additional power for the additional loads. The decision making by load control 25b is preferred to be based on one or more of user input, load priorities, load parameters, power source parameters, power cost and environmental parameters in order to prevent overload of the power source(s) powering the loads.

[Para 148] In particular, the decision to connect to additional power sources is preferred to be made according to the priority of the load(s) to be connected, availability and cost of the power from the various power sources which are available to provide additional power, or according to other decision making criteria which is provided to the load control during manufacture, installation or afterward by an operator, either by the operator's changing and storing priorities or by the operator's instant override of stored priorities. It will be understood that more than the three power sources may be accommodated. There may be one or more wind turbines, solar panels, fuel cell, generators and the like provided in the system in addition to the grid power as one of ordinary skill will find desirable to fit a particular application. In systems requiring high reliability there may also be multiple connections to the power grid, the multiple connections being provided by different grid service paths, or even to multiple power grids provided by different utilities. Such multiple connections are known in the art to be used in broadcasting and medical facilities. Of course as previously described there may also be many loads of different types to be controlled by load control 25b using the devices, capabilities and features described herein.

[Para 149] A controllable load 48 may be of any type where control of the power consumed by the load is provided within the load, e.g. those described in respect to Figure 6 or those which include any of the various circuits described with respect to current control 44 of Figure 6, and those which are otherwise controllable without requiring a separate load

limit 43 or load switch 22b or 22c as previously discussed. A three way light bulb is such a controllable load. Other such controllable loads include the above mentioned low and high power oven and clothes dryer and the Tesla Motors vehicle High Power Connector and battery charger. Controllable load 48 communicates with load control 25b via communications link 46 to provide load control communications, which may be single direction or bidirectional as desired.

[Para 150] Figure 9 shows a diagram of load control 25b, similar to Figure 5 with the same elements 26a – 26N, 28a, 28b, 29a – 29h, 30, 31 and 32. In addition, load control 25b has additional interface circuits 29i and 29j and communications links 45 and 46 to provide communications with transfer switch 47 and controllable load(s) 48 respectively. One of ordinary skill will understand that processor circuit 33b of 25b is preferred to have additional capabilities as compared to processor circuit 33a of Figure 5 in order to accommodate the additional capabilities such as may be needed in relation to solar panel 50, transfer switch 47 and controllable load(s) 48. Implementation of such additional capabilities will be within the ability of one of ordinary skill from the teachings herein.

[Para 151] It is preferred that the operation of the embodiment of Figures 8 and 9 be such that power is provided to each individual load at times and in amounts, and from one or more of a plurality of available sources as are desirable to minimize cost and maximize reliability for a given set of circumstances, as controlled by load control 25b. It is further preferred that the operation of load control 25b be performed at least in part by taking into account established priorities for one or more individual loads, established parameters for one or more loads, established parameters for one or more power sources and monitoring parameters for one or more power sources and one or more loads. It is further preferred that the operation of load control 25b be performed to allow input from one or more user in order to allow changing of priorities of loads and changing of the operation of one or more load so as to change at least that load's current in operation.

[Para 152] Figure 10 shows a simplified diagram of the embodiment of Figure 8 which includes additional capabilities for management of loads presented to a power source wherein the power source provides power in one or more form, and the loads consume power in more than one form, e.g. electric and heat. Figure 10 includes elements 12, 13, 16, 17, 18, 19, 22b, 22c, 25b, 26a, 26b, 26c, 27a, 43, 45, and 47 as in Figure 8. Other elements of Figure 8 are omitted from Figure 10 for simplicity. Additional elements are included in Figure 10 for the purpose of recovering power in the form of heat from generator 13 as controlled by load control 25b. The elements of Figure 8 which are not shown in Figure 10 will be known to be available for inclusion in Figure 10 as desired. Generator 13 is assumed for the teachings herein given by way of example and in particular with respect to the instant explanation of heat transfer with respect to Figure 10, as being of a type such as a fuel cell, internal combustion engine, battery or battery array, or the like having significant heat generation as a byproduct of its operation. Generator 13 will further be assumed to have a liquid or gaseous coolant system which may utilize glycol, water, steam or any other coolant suitable for use with generator 13, along with a radiator or other heat exchanger for removing such heat thereby cooling the generator. As used herein the coolant will be referred to as a fluid, even though it may be in a gaseous or mixed state form. In the system of Figure 10, the coolant is supplied from the generator's cooling system via piping (piping shown by heavier lines) 58 to electrically controlled valves 54 and 55 to heat exchangers 52 and 53 where the coolant loses heat to the fluid on the other side of the heat exchangers. The cooler fluid (which may change phase from gaseous to liquid due to cooling in the heat exchanger), is then returned to the generator via piping 59 (and change phase from liquid to gaseous in the generator). Circulation of the coolant may be provided by the cooling pump in generator 13, or externally by an additional pump or pumps (not shown). In this manner the excess heat from 13 will be removed and utilized to heat other needed devices and/or systems. As noted Figure 10 is a simplified diagram and

one of skill will know there are several operation details and considerations which will be pertinent to the proper operation of the generator, load control and heat exchangers in a particular system. For example it is desirable that additional flow control, mixing and safety valves, temperature and pressure sensors and/or pumps are included in the systems. These are not shown but nevertheless necessary as will be known to one of ordinary skill.

[Para 153] Heat exchanger 52 operates to transfer heat in the coolant from 13 to heat cold water 61 from a supply such as a well or municipal water utility to be used as domestic hot water 60. Heat exchanger 52 is preferred to be a double wall construction type to prevent leakage of coolant into domestic hot water. The domestic hot water may be heated to proper temperature, usually around 125° F directly by heat exchanger 52 or may be only partially heated to its desired temperature with heating to the desired temperature accomplished by another heating stage (not shown) as is well known in the hot water heating industry. Similarly, heat exchanger 53 operates to heat returning glycol or other fluid 63 used in a radiant heating system to the proper temperature, usually around 150 ° F to provide a supply of radiant heat fluid 62 or only partially with heat to the desired temperature accomplished by another heating stage (not shown) as is well known in the hydronic heating industry. Temperature sensors (e.g. RTD and other resistive sensors, thermocouple, silicon junction, silicon bandgap, thermostats or aquastats) inside the heat exchangers 52 and 53 sense the temperature of the domestic hot water supply and radiant heat supply respectively and convey those temperatures to load control 25b via domestic heat sense link 64 and radiant heat sense link 65 respectively as known in the respective industries. Load control 25b operates to adjust the opening of one or both of valves 54 and 55 to maintain radiant heat supply and/or domestic hot water supply at or near a desired and preferably constant temperature. Valve opening may be controlled such that the valve is either fully open or closed with heating controlled by the time of opening, or partially opened with heating controlled by the amount of opening, or a combination of the two.

[Para 154] Figure 10 elements 52 – 65 will be understood to be common and ordinary components of hydronic and hot water heating systems as are known to the person of ordinary skill. In some systems it may be desired that temperature sensors be omitted (but not relief valves) where the heat exchanger 52 or 53 can only partially heat to desired temperature and another heating stage is used. It is desired that both the domestic hot water system and radiant heat system include additional heating stages to ensure both systems operate when generator 13 is not running. When generator 13 is running and at operating temperature, if the domestic hot water temperature and/or radiant heat temperature as sensed via 64 and 65 respectively is below the desired temperature load control 25b causes opening of the corresponding valve. Generator temperature will be made available to the load control via communications link 27a. It is desired that the radiant heat system be controlled so that when generator 13 is not running the radiant heat fluid is not circulated through heat exchanger 53 which might lead to some inefficiencies due to heat loss in 53. Other arrangements of the system and its components will be possible from the teachings herein.

[Para 155] As another example, one or more battery pack(s) in an energy storage system such as that utilized in an electric or hybrid vehicle, or wind turbine, and in particular a battery pack stored in an unheated location, may be heated by connection to radiant supply 62 or by a separate heat exchanger in order to prevent excessive cooling and/or to maintain the temperature of the batteries at or near optimum temperature for the type and intended use of the battery. In addition, during charging the excess heat from the battery may be removed by the same system and used to heat other devices or systems, for example such as the radiant heat supply or domestic hot water. The integration and operation of such additional heating and cooling connections and control thereof by the load control 25b will be within the skill of one of ordinary skill from the teachings herein.

[Para 156] Also, it will be desirable to regulate the cooling of the generator 13, which is provided by its own radiator, in order that sufficient heat is available to the heat exchangers when needed, and when heat is not needed by the heat exchangers the generator radiator dissipates sufficient heat to keep the generator properly cooled. This heat management may be had by proper choice of the generator's cooling thermostat temperature, somewhat above the highest output temperature of the heat exchangers. In the above example if the generator's thermostat is chosen to be 160 ° F it will open and cool the generator independent of the heat exchangers if sufficient heat is not drawn away from the generator by the heat exchangers. The proper handling of these operation details and considerations will be apparent to one of ordinary skill from the present teachings.

[Para 157] It may be desirable that the system of Figure 10 be used with a fuel cell which has its electrical output connected to the output of the transfer switch in the same fashion as the solar panel 50 of Figure 8. This will provide more continuous heat for use by the heat exchangers 52 and 53. Alternatively, because most fuel cells include one or more internal heat exchanger that heat exchanger may be used to heat the domestic hot water and/or the radiant heat. As with the generator example above provisions must be made to ensure proper cooling of the fuel cell in the event sufficient heat is not drawn away by the heat exchanger. The proper handling of operation details and considerations will be apparent to one of ordinary skill from the present teachings.

[Para 158] The coupling of a second form of energy (heat) from generators and other power sources such as fuel cells for use in the heating of domestic hot water and radiant heat supply is given by way of example and one of ordinary skill will recognize from the present teachings that other forms of energy may be produced, recovered, transmitted, stored and/or utilized to power devices or systems for which it is desirable to utilize that energy. Such systems may utilize the teachings and features of the preferred embodiment of the present invention to benefit from improved management of energy therein as will be

known to one of ordinary skill. For example, some vehicles are known to utilize stored compressed air for power and energy may be managed in a gaseous form utilizing the inventive concepts disclosed herein.

[Para 159] Figure 11 shows a simplified diagram of a load which may also be utilized as a power source which the present invention may be used with. In this example the load is shown as a battery (or battery array) which may be charged to store power. Such batteries may be part of a green power system such as a solar panel, wind or water turbine and may be permanently located or otherwise such as installed in an electric or hybrid vehicle, described in more detail with respect to Figure 12. Other forms of energy storage may be utilized in place of the battery, as long as suitable interface devices to store and recover stored energy are used as will be known to one of ordinary skill from the teachings herein. For example energy storage forms using compressed air in a container, heat in a vessel, fluid pumped to an elevated reservoir, mechanical such as a flywheel or spring, and many other suitable forms may be resorted to by the person of ordinary skill.

[Para 160] In Figure 11 a connection 71a from the transfer switch (preferred to be made via a circuit breaker which is not shown), for example a high current 240 volt connection such as discussed herein with respect to a vehicle battery charger, is made to the input of battery charger 66 and output of DC to AC inverter 67. The output of the battery charger 66 is connected to the battery 68 and the battery 68 is also connected to the input of DC to AC inverter 67 which when it operates is preferred to synchronize with and parallels power (if any) available at the transfer switch output. U.S. Patent 7,338,364 describes this type of power inverter. It is possible that both charger 66 and inverter 67 will be in close proximity to the battery 68 in order to minimize wiring costs and it is possible that both charger 66 and inverter 67 will be combined into one instrument. Both charger 66 and inverter 67 are connected to load control 25 (not shown) via communications links 69 and 70. The communications may be combined in one communications link if desired. In this fashion

power from the transfer switch may be utilized to charge the battery or the battery may be used to power the inverter 67 to provide AC power to the other loads or to the power grid, all under control of load control 25. In particular the battery array of an electric or hybrid vehicle may be utilized in order to provide backup power to one or more loads in the event of a failure of the power grid.

[Para 161] Recalling that many homes only have a 100 amp service from the grid it normally would be unwise to use a 90 amp connection from the transfer switch to the battery charger due to the risk of overloading the service connection. When, as in this example, the charger can be controlled by the load control to keep its maximum load to the service at a much lower level, for example 20 amps, or to otherwise prevent overload of the service connection, a larger capacity connection may be utilized as will be understood from these teachings. The load control may at any time monitor the charge of the battery 68 via the charger 66 and communications link 69. If the battery has a sufficient charge and the load control needs to have additional power available, such as during a grid outage or during a high load conditions, the load control may turn off the battery charger 66 and turn on the DC to AC inverter 67, thereby taking power from the battery to be used elsewhere.

[Para 162] In this example, having the 90 amp connection to the battery inverter 67 will allow a significant amount of power to be supplied, almost enough to replace the entire 100 amp service in the event of a grid power failure. Of course the power taken from the battery may be utilized for other applications as previously discussed, including supplementing grid power during heavy loads or expensive power rates or even selling power back to the utility. One will recognize that it is also possible to charge the battery with cheap power from another source such as solar panel 50 or at a time of availability of cheap power from the grid 12 such as at night. That cheap power which is stored in the battery may then be used when power from the grid (or other sources) is more expensive, or may even be sold at a profit. Control of charging and discharging of the battery 68 by load control 25 may also

take into account the timing and need of power for other uses as well, such as driving the vehicle which the battery is installed in.

[Para 163] Figure 12 shows a diagram of an embodiment of the invention which is used with an energy storage battery 68, optional communications link 73 and charging generator 72. Battery 68 and DC to AC inverter 67 are configured as a backup power supply to be used in the event of a power grid failure. Power grid 12, loads 16–19 and 48, load control 25b, load switches 22b and 22c, load limit 43, communications links 26a – 26c, 45 and 46 and transfer switch 47 are described above as in Figure 8. Battery 66, DC – AC inverter 67, battery 68, communications links 69 and 70 operate as described above in respect to Figure 11, except that the battery charger 66 is connected to the output of the transfer switch via 71c whereas the output of DC to AC inverter 67 is connected to an input of the transfer switch 47 instead of to the output of the transfer switch as in Figure 11. If it is desired to provide power from 67 to the power grid, synchronization with and parallel operation may be obtained with the connection moved to the output of the transfer switch. It will be recognized that it will be necessary to disconnect the power grid in the event it fails.

[Para 164] The embodiment of Figure 12 will find use as a home backup system and in particular where the battery (or battery array) 68 is contained within an electric vehicle which is charged by battery charger 66 or a hybrid vehicle which may be charged by battery charger 66 or by a generator 72. It will be known that generator 72 may be of any type suitable for use with the battery 68, or with a vehicle which contains the battery, for example an internal combustion engine or more preferably a fuel cell. It will be understood that when the battery 68 is part of a vehicle that battery charger 66 detect and convey to load control 25b when it is connected to the battery and similarly DC to AC inverter 67 communicate to load control 25b when it is connected to the battery. Of course when the two are configured to be connected simultaneously, e.g. by a single connector, either charger 66 or inverter 67 may convey the communications via a single connection. When the

vehicle includes an on board generator operable to charge the battery, load control 25b may communicate with generator 72 as desired via 73, it being preferred that 73 be wireless, or included in the communications link 69 or 70. DC to AC Inverter 67 may also be located in the vehicle. When the vehicle includes an operating system to manage those of 66, 67, 68 and/or 72 which are located in the vehicle, communications between those element and load control 25b may be handled via a communications link with that operating system.

[Para 165] Battery charger 66 will be turned off by load control 25b whenever inverter 67 is selected by transfer switch 47. Generator 72 is preferred to be utilized to charge battery 68 whenever the battery is being used as an energy source for backup power and the battery becomes discharged from that operation or is already in a discharged state when needed for backup power. It is preferred that load control 25b operate to determine the level of charge of battery 68 at or below which it is desirable to start the generator 72 to charge the battery in order to maintain or extend the amount of energy which is available to power DC to AC inverter 67 to be utilized as backup power in the event of failure of the power grid 12. It is additionally preferred that in normal operation battery charger 66, under control of load control 25b, operate to charge battery 68 with low cost power, for example during night hours or from a low cost power source such as solar, wind or water power as previously discussed. Thus battery 68 may be kept at or near a fully charged state using low cost energy and used to power inverter 67 during power outages. Although the battery 68 and related elements of Figures 11 and 12 are not shown in Figures 4–10 the teachings related thereto generally may be incorporated with respect to any of Figures 4–10. Figure 11 does not show a battery charger other than 66, however it will be understood that the teachings of Figure 12 and in particular with respect to generator 72 will also be applicable to the system of Figure 11.

[Para 166] If battery 68 is discharged to a predetermined level due to extended use for backup power or lack of initial charge, generator 72 may be started by load control 25b (or

otherwise by the vehicle's own operating system) to recharge the battery. Load control 25b is preferred to manage loads in order to minimize the discharge of battery 68 while maintaining a user preferred level of power to various loads, either during normal backup operation or during charging by generator 72 or both. As an additional consideration, while generator 72 is preferred to be a fuel cell with no dangerous or annoying emissions, if generator 72 is an internal combustion engine or similar generating device which emits dangerous or annoying emissions it is preferred that the facility such as a garage in which it is housed (if any) include provisions for suitable ventilation and other protection against such emissions. Such protection is desired to be controlled by or otherwise monitored by load control 25b in order to ensure safe operation of generator 72. In an example of such protection, a garage will be fitted with an exhaust fan and monitor for potentially dangerous emissions (e.g. a carbon monoxide monitor) which fan is started when or near the time which the generator is started with the fan not being shut off by load control 25b until after generator 72 is stopped and carbon monoxide levels (and any other potentially dangerous emissions) are verified via the monitor(s) to be at or below safe levels. The exhaust fan is preferred to be otherwise controlled by load control 25b to run whenever the level of any emission is above safe levels.

[Para 167] Figure 13 shows a simplified diagram of a combination of load coupler 80 configured with a load 18 shown as a typical air conditioner and communicating with load control via link 26c in order to control the coupling of power from the transfer switch to the load as taught above and as will be explained further in respect to Figures 14 and 15. Control link 26c may be of any type previously described but will be shown by way of example in Figures 14 and 15 below as a wireless link. As described herein the power and loads may take on various forms however for purposes of explaining the invention description will be given by way of single or multiple phase electrical power in commercial voltage and currents available to homes powering loads which are relatively heavy as

compared to the utility service, for example electric air conditioners. Accordingly, 80 may also be configured as a load limit 43 if desired to provide control of suitable loads as discussed herein.

[Para 168] Figure 14 shows a detailed diagram of a commercially valuable embodiment of load coupler 80. Power from the transfer switch is controllably coupled to the load 18, shown in this example via controllable relay 34 which may be a latching or a simple type as desired. If desired, relay 34 may be replaced by or combined with a current control circuit 44 which communicates unidirectionally or bidirectionally with microprocessor 37 to control or limit current to the load as an implementation of load limit 43 previously discussed. It is preferred that by using microprocessor 37 and user interface 77, load coupler 80 may be manufactured as a standard device with each of multiple devices configured via the user interface 77 at the time of installation in a particular system to match the particular load being controlled.

[Para 169] Additionally the load coupler 80 may be designed such that optional features, for example such as the aforementioned current control, or different size latching or simple relays, may be installed after manufacture as desired. For example it will be desirable for the installer to have the ability to install a current control and/or relay of proper current rating to match the load. Once a unique name or other identifier is assigned to a particular coupler 80 via the user interface (or in manufacture), other configuration and test settings may be made via the user interface 77 or via a load control 25 or both. It is further desired that the installer have the capability to operate current control 44 and/or relay 34 and to operate, calibrate, test and/or check other functions such as battery charge, communications integrity and operation of sensing functions from either the user interface 77 or the load control 25 or both.

[Para 170] A latching relay which operates independent of external control from 37 to drop out and latch open when the voltage from the transfer switch rises above drops below

known levels (setting a range of permissible voltage) is useful in protecting the load. This type of operation achieves high immunity from momentary disconnection due to over and under voltage conditions which frequently accompany power loss situations. Utilizing a relay which automatically drops out and latches provides a degree of protection which is independent of the other control circuitry, e.g. the relay will drop out independent of the control circuitry but the aforementioned capabilities may also be provided via microprocessor circuit 37 if desired.

[Para 171] If utilized, the latching operation may be configured to latch open only, or latch open and closed. Additional protection including noise and spike filters, snubbers, limiters or absorbers such as transient voltage suppressors (e.g. TVS diodes) may be utilized (not shown) to protect the load from such unwanted occurrences as will be known to the person of ordinary skill in the art from the teachings herein. For example, when a simple relay is used momentary high voltage spikes may be passed to the load causing unwanted operation or damage and momentary disconnection of the load due to brown out or other low voltage conditions may cause unwanted operation or damage. For example a short disconnection during a brownout may cause an attempt to restart an air conditioner compressor with a high head pressure as previously discussed. By use of a latching relay operating to drop out and latch independent of control circuitry an extra degree of load protection is provided.

[Para 172] Because microprocessors are low voltage and low current devices a current driver and/or voltage translator must often be used to provide a higher voltage and/or current to energize the coil of relay 34 than the microprocessor alone can provide. Such current driver (or voltage translator) may be incorporated in the microprocessor circuit 37, or the relay 34 or elsewhere. Accordingly the energizing the coil of relay 34 may be dependent on power from the transfer switch (which would directly or indirectly power the relay coil) thus allowing short voltage transients to cause the current to the relay 34 coil to

lower to the point of allowing the relay to briefly disconnect the load. That brief disconnection can happen even though microprocessor circuit 37 maintains a constant command to the relay coil driver circuit intending to keep the load energized. In this example the use of a latching relay which will latch off in the event of a momentary dropout will avoid a relatively quick restart of the load and the resulting damage. Other types of relays and disconnect and connect operations may be utilized to prevent or reduce such problems if desired as will be known to the person of ordinary skill in the art from the teachings herein.

[Para 173] If a latching type relay or other circuit more complex than a standard relay is used, it is preferred that relay position circuit 79 be included in order that the microprocessor may know which position the relay or other circuit is in and in particular may know when the relay drops out. Such knowledge will be useful for example when voltage transients not timely sensed (or not sensed at all) by the microprocessor 37 occur. The relay position information will also be useful in the event the microprocessor is not programmed to store the relay setting when a change is made, or when the microprocessor is caused to reboot such as might happen in response to a monitoring routine, or as a failsafe to verify that the relay actually switches to the position commanded by the microprocessor.

[Para 174] The control of the relay is provided by the microprocessor 37 in response to various inputs and programming as described elsewhere herein. In particular a current monitor 23d provides a measure of current provided to the load to 37 and a voltage monitor 78 provides a measure of the transfer switch voltage to 37. While the control of the coupling of power from the transfer switch to the load is shown in Figure 14 by way of example as a relay, it may also be performed by other circuits as well, for example by way of current control, current limiting or otherwise as will be known to the person of ordinary skill from the teachings herein.

[Para 175] A battery & battery charger 74 provides backup power to the various elements of 80 as desired in order that they may continue to operate in the absence of power provided by the transfer switch. The output of 74 may be AC and/or DC at any voltage desired to fit a particular use and application of 80 as will be known to the person of ordinary skill in the art from the teachings herein. In the preferred embodiment of Figure 14 it is desired that the battery be a rechargeable type and that it be charged whenever AC power is available from the transfer switch. It is further preferred that 74 include a switching type power supply to provide the desired DC and/or AC power at various voltages (and frequencies) which are needed by the various circuits within 80 in order that all desired circuits are operational whether AC power is available from the transfer switch or not. In this manner 80 may operate to provide control of the coupling of power to the load as taught herein. In particular, in the event grid power is lost and there is a delay before power is restored via the transfer switch, microprocessor 37 will have recorded the state of power consumption by the load immediately before power loss, will have a timer to determine the amount of time power has been lost and will have available load characteristics and/or other data which is used to determine the manner in which backup power may be coupled to the load when available. As one example, when an air conditioner compressor was running when the power is lost the microprocessor will know not to couple backup power from the transfer switch to the air conditioner until sufficient time has passed to allow head pressure to bleed off thus preventing excessive starting current or compressor stall. The user interface 77 may operate to provide various interaction between the user and microprocessor, and via the microprocessor to the load control as described elsewhere herein and in addition allows an installer to configure 80 to operate with a particular load.

[Para 176] In particular, it is desired that the microprocessor and/or load control may be accessed via user interface 77 in order to identify the particular load (and its characteristics) to the system and configure the system and/or microprocessor 37 to the particular load at

the time load control 80 is installed in the system, or at subsequent times for example such as when the load or its characteristics are changed. This user capability will facilitate physical installation of 80 in near proximity to the load, for example at an outside air conditioner compressor and will reduce the number of trips between the load (and 80) and the load control which likely will be located near the transfer switch, the utility service entrance or a location convenient to the home owner.

[Para 177] Figure 15 shows a commercially valuable embodiment of load control 80 like that of Figure 14 but which is physically separated into two sections, a high voltage section 80H and a low voltage section 80L. The two sections will facilitate design and manufacture to meet a particular application, including various testing and regulatory approvals. The low voltage section may be configured to provide a desired level of features and functionality for a particular system or level of systems and the high voltage section may be configured to provide a desired level of features and/or type of control of the load. Both sections may for example have options which may be installed after manufacture, such as the aforementioned capability of having relay and/or current control options installed at the time of installation to match operation of 80 with a particular load. It is desired that the interface between the low and high voltage sections be compatible for all combinations thereof. For example, the low voltage section may be configured in several models starting with a basic, low cost model with wired communications and a simple user interface to allow the user to only assign an identifier to each device in a small system with advanced, higher cost models (or installation of options) providing more features such as keypads, LCD displays, additional configuration and advanced programmability capabilities, wireless communications, etc.

[Para 178] The high voltage section may likewise be configured in several models from low cost basic to higher cost advanced models (or installation of options) to accommodate various power sources and loads such as particular operating voltages, maximum load

currents and multiple power phases. In this fashion a manufacturer may sell a small number of low voltage section models and a small number of high voltage section models with a particular system installer choosing the type and number of each model and options to match the particular system being installed. Additionally separate high voltage models may be utilized for relay or current control or a single model may incorporate both relay and current control or may incorporate multiple relays and/or current control devices. The high voltage devices may be controlled by a lesser number of low voltage sections or even a single low voltage section if desired, the latter being particularly well suited for utilizing the invention with, or incorporating the invention into, the transfer switch, power entrance service panel, a power sub-panel or any of the various local power generating devices taught herein, for example with respect to Figure 8.

[Para 179] As an example of the usefulness of separate sections and options, a manufacturer might offer only one low voltage section with options for: user keypad, LCD display, relay 83 and wireless communications link 29k and two high voltage sections, one for single phase and one for multiple phase power, each with options for: current sensing, latching or simple relays of differing voltage and current ratings, current control circuits for differing voltage and current ratings.

[Para 180] The physically separated sections 80H and 80L will also facilitate installation and operation of the invention. For example by keeping all of the high voltage components in the 80H section safety is enhanced by only having a minimum number of circuits which are potentially exposed to high voltages and to electrical interference and noise created by controlling high voltages and currents. Additionally physical size is kept to a minimum thereby facilitating installation of that section near to or within the enclosure which houses the load. On the other hand, the low voltage section may be designed without overdue attention to high voltage, high current, interference, noise, regulatory and safety

considerations. For example, by utilizing only low voltages in the 24 volt and below range various regulatory approvals will not be needed for the 80L section.

[Para 181] Figure 15 shows an embodiment of the invention where high voltage and high current (e.g. a 240 VAC 50 amp supply) from the transfer switch is coupled to the load 18 via a relay with a 24 VAC control (coil). In addition a class 2 (dry environment) or class 3 (wet environment) 240 volt to 24 volt transformer 81 is utilized to provide low voltage for the 80L section. It is desired that 81 be connected to the 240 volt power physically close to 80H in order that the 24 volt output may be used by microprocessor 37 (via 78) to monitor the 240 volt power from the transfer switch. For example in a simple form the 24 volt AC output of 81 is monitored by the microprocessor circuit 37 to determine and compare the RMS voltage to a high and a low limit. If desired, the amount of time that voltage exceeds the high limit or falls below the low limit may be monitored as well. If the voltage falls outside of either acceptable limit for more than a predetermined time then the microprocessor circuit 37 may actuate relay 83, which in turn causes relay 34 to open thus disconnecting the load 18 from the transfer switch. The parameters for the high and low voltage limits as well as the aforementioned time duration are preferred to be programmable in order to protect load 18 from damage as well as to prevent it from contributing to overload and possible damage of the backup power source during a power outage as will be known to one of ordinary skill in the art from the teachings herein. If desired a current monitor 23d, such as the aforementioned current transformer may be incorporated, as well as a relay position circuit 79 may be included to facilitate microprocessor circuit 37 control of power coupling to load 18.

[Para 182] Supply 81 is preferred to be a 24 volt AC transformer to provide low voltage power to section 80L and is chosen because it is a readily available standard device used in home heating and air conditioning controls, doorbells and elsewhere. Other AC or DC supplies may be utilized if desired, for example plug in 120 volt to low voltage AC or DC

power supplies frequently referred to as “wall warts” may be utilized. In addition, the battery charger and/or battery of 74 may be incorporated as well. It will be noted that if a power supply which incorporates a voltage regulation circuit is utilized, the regulation will prevent monitoring of the voltage of the power from the transfer switch except for the loss of power causing the output of 81 to shut down. If a simple voltage presence is all that is desired then that may be monitored via microprocessor circuit 37 but if a more accurate indication of the actual voltage is needed other provisions will be required as discussed elsewhere herein.

[Para 183] Relay position circuit 79 is simply shown in the drawings as a connection from the relay 34 to the microprocessor circuit 37. The relay position circuit is preferred to incorporate a switch or switches which are coupled to the position of the movable portion of the relay, e.g. its armature, or to otherwise respond to its state, in order to open or close electrical circuitry in response to that position or state. Coupling may be by mechanical, magnetic, optical, electrical or other well-known coupling and the switch action itself may be mechanical, magnetic, optical, solid state or other well-known action. For a two state (open/closed) relay the switching action may indicate the relay closed or open or both as desired. For example, a switch may close a two wire circuit when the relay is closed, or may close a two wire circuit when the relay is open, or may include a three wire circuit with a common, first wire and second wire with the switch closing the common to first wire circuit with the relay in a first position (e.g. closed) and close the common to the second wire circuit when the relay is in another position (e.g. open).

[Para 184] Relays may incorporate more than two positions or states, e.g. the open, latched open, closed, latched closed of one type of latching relay, and the position circuit 79 may be configured to indicate all or a portion of the possible positions or states. Additionally, as discussed herein the relay 34 may be replaced by or augmented with other load control functions, circuits or devices, for example such as a circuit breaker capability or

an electronic current limit with or without a switch, and the relay position circuit 79 may be configured to indicate such operation(s). For example 79 may indicate breaker open, breaker closed, breaker tripped open in response to excessive current, or 79 may indicate relay open, relay closed, relay closed with a first current limit, relay closed with a second current limit. The relay position circuit 79 may also be combined with other operations as desired, for example the relay position 79 and current sense 23d may be combined to report to the microprocessor 37 over a shared or common communications channel. As another example the relay position 79 may be shared by a relay and a separate circuit breaker with 79 reporting relay open, relay closed and breaker tripped conditions (note it may be possible for the breaker to be tripped or closed while the relay is open or closed). The selection of particular circuit(s), action(s) and coupling(s) to fit a particular load and application will be well known to the person of ordinary skill in the art from the teachings herein and may be resorted to without departing from the spirit and scope of the invention as claimed.

[Para 185] Various circuit connections 82 for connecting the 24 VAC supply from 81, 24 VAC relay control, relay position and current circuit circuits to 80L are provided and it is desired that these connections be selected to facilitate installation of the sections via low voltage wiring, e.g. screw terminals, punch terminals or the like. Accordingly the implementation of 80H may be performed with many off the shelf components, e.g. a U.L. approved class 2 transformer and relay mounted in a U.L. approved enclosure (which may be the air conditioner housing) and in a large number of air conditioners and other loads the relay and transformer are already present such that only 80L needs to be added to provide a controllable load 48. The low voltage portion 80L may then be installed nearby the load, but in a location convenient to the installer, for example mounted in a waterproof plastic case mounted to the outside of the load housing or an adjacent building wall. In such an installation the connections from the load housing (or 80H) to 80L may be achieved

by use of an 8 conductor cable such as common 20 gauge thermostat wire. If the current transformer and relay position elements are not needed, such as in many air conditioners, a 4 or 3 wire (one side of the 24 VAC line will usually be common) thermostat cable may be used. Other AC or DC voltages may be utilized as well.

[Para 186] Figure 15 section 80L includes a battery and charger circuit 74 to receive the AC (or DC) voltage from an external source. In this example power supply 81 serves as the external source, however power may be received from other sources as desired including via one or more wired communications link. The 24 volt AC power is preferably also made available to external devices via connections 82, and shown in this drawing as being used to control relay 34 via relay 83 and dashed connections. Connections 82 which are preferred to be readily available, low cost and easy to use terminals and can for example be spade lugs, screw, press fit or quick connect terminals and may be assembled on open or enclosed terminal blocks. The battery and charger circuit 74 provide backup (DC) power 75 with microprocessor 37, wireless link 29k having antenna 76 (which may be internal or external to 80L), user interface 77 and other circuits if desired, powered thereby. As with 74 of Figure 14 a switching power supply may be incorporated to provide multiple output DC and/or AC voltages as desired including power 84 to external connectors 82.

[Para 187] While DC voltage 75 could be coupled to external connectors, it is preferred that 84 be a separate DC output which is isolated from 75 in order to protect 75, and the circuits it powers, from any adverse effects which would be experienced if some external device failed in a short circuit mode. In that event, power 84 might be shut down due to the short circuit however 75 will continue unaffected. In the embodiment of 80L it is desired for reasons of installation flexibility that the section includes a relay 83 which is controlled by the microprocessor and that the relay contacts are made available for external connection and further that one or more of these connections be current limited or otherwise protected, in this instance shown by the use of 86 in the relay swinger circuit. DC voltage

output(s) 85 from the microprocessor circuit are also preferred to be made available for external connection as shown, including protection 86.

[Para 188] For example a microprocessor output may control a 12 volt DC supply connected to a screw terminal as shown by 85. Connections to external connection terminals, if not otherwise protected (e.g. as with class 2 or 3 transformers) are preferably made via protection 86. Positive temperature coefficient (PTC) resettable fuses are particularly useful choices for such protection but other means of protection including for example current limiting circuits and devices, standard or other automatically resettable fuses or standard or automatically resettable circuit breakers may be utilized if desired. In this fashion 80L may be easily connected to 80H. 80L may as well be connected to various types of systems and devices by providing DC and/or AC voltage sources as well as normally open and normally closed relay contacts via screw terminal or other convenient types of connections 82. As shown via dashed lines between 80L and 80H in Figure 15 these connections may be configured to control the coupling of power to the load in 80H.

[Para 189] In addition it is desired that the type and number of circuits and their connections 82 be chosen in order to facilitate commonality of connections between various models of high voltage and low voltage sections and in particular any circuits unused in a particular installation be designed such that having any unconnected terminal(s) will not have an adverse effect on the system. For example if a highly featured low voltage section 80L provides for a number of connections 82 to the high voltage section 80H and external devices such as 81, and it is desired that if a basic high voltage section 80H is connected to that 80L, any unused circuits (or circuits which are intended to be used but are miswired or defective) are automatically detected by 80L such that they are reported to the user interface and/or load control, disregarded or the circuits are otherwise designed to accommodate the lack of connection.

[Para 190] One example in understanding this feature may be given in respect to current sense 23d. If the low voltage section 80L is designed to accept a connection to 23d but the high voltage section 80H is a basic model which does not include a current sense then 80L is desired to operate to detect the lack of a connection to a current sense and operate without it. This operation may be achieved via sensing the voltage, resistance or other characteristic (for example such as impedance or capacitance) between the connections and detecting a high resistance if there is no connection to 23d and a known resistance if 23d is connected. The microprocessor circuit 37 may operate to perform this sensing or to respond to other sensing circuitry. Multiple types of current sense devices may be detected and accommodated in this fashion, assuming each type has a different resistance or other characteristic. Previously present circuits which become disconnected, silent or otherwise inoperative or suspect (e.g. because of unusual readings) may be detected via the microprocessor circuit 37 and reported via the user interface 77, via communications link 29 to load control 25 or otherwise.

[Para 191] Another manner of accommodating unconnected circuits is via circuit design of the particular circuit. For example a resistor or other component may be connected between two current sense connections on the low voltage section 80L or the high voltage section 80H to ensure little or no static charge or noise will build up on the circuits and thus zero current will be sensed and reported in the microprocessor circuit 37 if no current sense 23d is connected. The resistor or other component may also be used to signify the presence of the current sense 23d. If the current sense circuit 23d is connected the microprocessor circuit 37 will eventually be able to detect or respond to a voltage on the circuit (corresponding to a current flow in the load) when the relay 34 is closed and thus detects that the current source is connected. The microprocessor circuit 37 may also detect or respond to a voltage on the circuit (corresponding to a current flow in the load) and that voltage (load current flow) going to zero immediately after the relay 34 opens and know the

current sense is connected. At initial installation or other times the microprocessor circuit 37 may be caused to energize relay 34 to determine if a load sensor is connected, or to energize an alternative voltage or current circuit in the high voltage section 80H to simulate a current flowing to the load and thereby detect if the current sense circuit 23d is connected, which may also be used to calibrate the current sense circuit. These and other circuit operations and/or designs may be incorporated at either or both ends of the circuit communications between the two modules or the connections themselves to allow detection of connected or unconnected circuits, effectively communicating the configuration of one section or device to another. Microprocessor circuit 37 may also be programmed by an installer via user interface 77 and/or communications link 29 to identify the presence or absence of particular models, devices, features, options and the like.

[Para 192] It is envisioned in the commercially valuable embodiments of Figures 14 and 15 (as well as those of the of the preceding Figures) that for cost reduction reasons the microprocessor circuit 37 will be configured to perform many of the functions and features described, with the relays 83 and 34, current control 44, wireless communications link 29k and associated antenna, user interface 77 and battery and charger 74, current sense 23d, and power supply 81 being separate circuits for reasons of their diverse physical and/or electrical requirements. For example relay 34 is required to handle high voltages and currents which with present technology make it difficult to incorporate that relay function into the microprocessor circuit 37. In keeping with the teachings herein, the load control 80 (or 80H and/or 80L) of Figures 14 or 15 and their individual circuits and functions may be configured by the person of ordinary skill in the art to fit particular needs and sets of requirements It is envisioned however that in the practice of the invention for particular applications and their requirements that combining various of the individual circuits and functions, and/or further separating of combined functions, removing features and functions as well as adding additional features and functions may be useful. Additionally,

for higher volume applications it is envisioned that ARM and RISC types of processors, along with embedded designs and even ASIC devices will become attractive technologies for implementing portions of the present invention.

[Para 193] Figure 16 shows a simplified diagram of a further load control embodiment 88 which is coupled to power from the genset which is supplied via a transfer switch and controlling the power supplied to a load 16 with a current control 44. The load control circuit 25c, senses one or more parameter of the power, in this example the A.C. power frequency via connection 87 as well as the current drawn by the load via a current sense 23d and controls the current delivered to the load via control of current control 44. Load control 25c may also sense the voltage, distortion or other parameter of the power via 87 and incorporate those measurements into the control. In this embodiment the load control circuit 25c will operate to sense the power frequency (and/or voltage or other parameter) via 87 or otherwise and when the load in the genset nears or enters an overload condition the power to the oven will be reduced or limited or even turned off, thereby preventing or removing a genset overload.

[Para 194] Figure 17 shows a simplified diagram of a further load control embodiment 89 which is coupled to power from the genset and connecting or disconnecting the power supplied to the load via switch 34. The load control circuit 25d senses one or more parameter of the power, in this example the A.C. power frequency (and/or voltage or other parameter) via connection 87 and controls the connection of the load. In this embodiment a clothes dryer 17 is shown as the load by way of example and it will be recognized that if the voltage to the dryer were to be reduced by any substantial amount the electric motor which provides rotation of the dryer drum could overheat and be damaged. Otherwise, any slowing of the electric motor caused by reduced voltage (even for synchronous motors) could cause reduced airflow through the dryer and create a fire hazard. For these reasons it is more desirable to simply switch the dryer on and off via switch 34 than to attempt to limit

the current supplied to the dryer. The embodiments of Fig. 16 and 17 may operate with power inputs from any power source known in the art in which one or more parameter of the power changes as the load on the power source approaches maximum or enters overload, or a novel power source in which one or more parameter of the power is controlled in response to the load thereon as will be described in more detail below.

[Para 195] Figure 18 shows a more detailed diagram of the preferred load control circuit 25c having a transformer 81 which is connected to the A.C. power via 87, a frequency measurement circuit 90 responsive to the A.C. power via transformer 81 and supplying frequency information to microprocessor 37. A power supply 74 receives low voltage A.C. power from transformer 81 and supplies power to the circuitry of 25c as necessary. A user display 91 and user input 92 allow a user to communicate with the microprocessor 37 and a timebase 93 provides time information to 37. A current measurement circuit 95 is responsive to a current sensor 23d (not shown in Fig. 18) to provide load current information to 37 with 37 operating to communicate with a switch and/or limit driver circuit 94 to control the associated load. Microprocessor 37 may also be configured to sense one or more parameter of the power for example such as the voltage at 87 either directly or from the output of transformer 81 by using a voltage measurement circuit or otherwise as will be known from the present teachings. It will be recognized that the circuit may also be used as the load control 25d and if desired may eliminate or not utilize the current measurement circuit 95. Additionally the circuit of Fig. 18 may also be utilized to control a parameter of the power for example such as by control of the frequency and/or voltage of the A.C. power supplied by the genset in response to the load on the genset as will be described further below.

[Para 196] Load control circuit 25c may include a transformer 81 coupled to the A.C. power from the genset (e.g. which is supplied for a particular load) and to provide a safer low voltage for use by the circuitry. In particular it is desired that 81 be the aforementioned

Class 2 (dry) or Class 3 (wet) transformer having an input voltage matching the genset voltage (e.g. 120 volts) and an output voltage of 24 volts as is well known in the genset industry. Other types of transformers may be utilized as well to fit particular needs. Power supply 74 is preferred to receive the A.C. voltage from the transformer and provide battery backed up D.C. power out at a voltage, or voltages, utilized by the circuitry of 25c. In particular 5 or 3.3 volt outputs for powering the various circuits 90–92, 37 and 93–95 are desired.

[Para 197] A microprocessor circuit 37 is provided which operates to interface with the circuits 90–92 and 93–95 to receive A.C. power frequency information from frequency measurement circuit 90, optionally receives parameters such as voltage information from 87 or otherwise, receives timebase information from timebase 93 (which may be provided by the crystal oscillator for the microprocessor clock and internal circuitry), current information from current measurement circuit 95, and user information from a user input 92, and to provide messages to the user via user display 91 and control of the current control 44 of Fig. 16 or load switch 34 of Fig. 17. Optionally the circuitry may provide control of the speed of the genset engine or voltage of the generator output (not shown) via an electronic switch/limit driver circuit 94. User display 91 may be of any type well known in the art suitable to display messages to the user as taught herein and may also be utilized to facilitate user input, to display operating conditions, provide fault warnings and to display other messages as will be known to the person of ordinary skill from the teachings herein. User input 92 may be of any type well known in the art suitable for input by the user as will be known to the person of ordinary skill from the teachings herein. User display 91 and user input 92 may be combined if desired, e.g. via a touchscreen.

[Para 198] It is preferred that 25c be mechanically configured in order that it may be physically located next to current control 44, load switch 34, the controlled load, e.g. 16 or 17. In particular it is desired that it be incorporated with those components within their

enclosures for ease of installation. In particular, by incorporating the elements as shown in Fig. 16 and 17, or within the load, or within the genset the additional wiring necessary for connection of the load, or the genset is kept to a minimum. In this fashion control of individual loads may be provided without the need for a more complex load control communicating via links to a plurality of load limits and load switches thus providing flexible and cost effective overload protection, but at the potential cost of accuracy due to reliance on power parameters measured at that load as compared to the embodiments of the earlier figures which may operate with accurate measurement of the total power output of the power generator.

[Para 199] In operation 25c or 25d is preferred to monitor power parameters for example the A.C. frequency (and/or voltage) of the supplied power and control the load accordingly. In particular the characteristics of the frequency (and/or voltage) versus load are preferred to be programmed into the microprocessor either at manufacture or by the user during installation in order that the microprocessor may know if the load being supplied by the generator is below overload, near overload, slightly overloaded, significantly overloaded or highly overloaded. It is also preferred that the microprocessor be programmed in order to know the type of load being controlled and its priority and to control the load, via driver 94 according to the amount of overload, the time that amount of overload has existed and particular characteristics of the load.

[Para 200] As one example if the genset is nearing overload the load control circuit will operate to prevent a low priority load from being connected to prevent additional loading of the genset, or to disconnect or limit the current supplied to a low priority load in order to reduce the load already coupled to the genset. As another example if the genset suddenly becomes significantly or highly overloaded a low priority load would be prevented from being connected or immediately disconnected if it is connected. Lower priority loads are preferred to be connected only when the genset is below overload, or if a high priority load

is relatively small it may be connected when the genset is only slightly overloaded. If already connected when the genset goes into any overload condition the higher priority load would be disconnected only after a time delay (set by the user) in order to give other lower priority loads time to be disconnected by their controllers. In this respect it may be recognized that a plurality of Fig. 16 and/or 17 load controls may be utilized with each one programmed with a different time delay in order that the lowest priority load is disconnected first, thus avoiding the prior art problem of disconnecting all lower priority loads simultaneously. In addition a low priority load may be disconnected or left unconnected with no attempt to reconnect the load being made until the genset is below (or well below) overload thus preventing the prior art problem of blindly connecting low priority loads. Of course multiple driver 94 and/or current measurement circuits 95 may be incorporated within load control 25c in order to monitor and control multiple loads according to the teachings herein.

[Para 201] Additionally in 25c or 25d current measurement 95 may be utilized to monitor the current drawn by a load and to control that or other loads accordingly. For example if the load is one that should not be connected immediately after is disconnected, such as an air conditioner compressor, 95 may be utilized by the microprocessor 37 to determine when the load was last drawing current and a timer used to prevent reconnection before it is safe. It is preferred that the microprocessor 37 have stored parameters pertaining to at least the frequency at which the genset is exhibiting an overload, and may also have stored parameters pertaining to time durations versus overload and parameters pertaining to the load being controlled, priorities and desired system operation. The stored parameters may be stored at the time of manufacture, at the time of installation or later, e.g. via user input 92, or may be determined by the microprocessor during operation and stored for future use.

[Para 202] A novel feature of load control circuit 25c is that it may be utilized to control one or more parameter of the power output from the genset in order to convey load

information to load controls 88 and 89. For example the speed of the genset engine and thus the power frequency, and/or the alternator control and thus the voltage, of the output A.C. power may be controlled as a measure of the loading of the genset. In this fashion this reasonably accurate measure is coupled to individual load controls for control of those individual loads without the need for separate communications therebetween. In this fashion the prior art need to hard wire communications from the transfer switch to the load contactor is eliminated while at the same time improving the accuracy of overload detection. This capability is particularly useful with typical gensets which have an engine sized such that the alternator will overload before the engine slows down, but is also useful for gensets where the engine will slow down first. The current supplied by the genset is preferred to be sensed with a current sense such as 23d which is coupled to current measurement 95. That current is then utilized by the microprocessor 37 to generate a control signal (or a plurality of control signals) via driver 94 which is coupled to the genset engine's engine control module, or otherwise to the throttle of the engine in order to control the engine speed and thus the power frequency by known amounts in response to the load.

[Para 203] The driver 94 or another driver may also be coupled to the alternator to control the voltage output if desired, either in addition to frequency control or in place of frequency control. For example if the genset is at 95% of its rated load the power frequency can be lowered from a steady state 60 Hz to for example a steady state 59.5 Hz. If voltage adjustment is used the voltage may be lowered from a steady state 120 volts to 115 volts. These are relatively small amounts but may be measured by frequency measurement circuits 90 and/or voltage measure function of 37 in individual load controls to signify that the genset is nearing full output capability. It is preferred that a microprocessor 37 which is utilized for such frequency and/or voltage control have stored parameters related to current levels relative to overload and desired frequency and/or voltage relative to current or loading levels. The stored parameters may be stored at the time of manufacture, at the time

of installation or later, e.g. via user input 92, or may be determined by the microprocessor during operation and stored for future use.

[Para 204] If the genset goes into overload, for example 105% of its rated load, the microprocessor can then operate to adjust the frequency and/or voltage to a different amount, for example 59 Hz and 110 volts. This will let the individual load control circuits know that the genset is slightly overloaded in order that they can control their loads accordingly. For example at this value one or more low priority loads can be limited or disconnected, preferable in sequence according to their priority with the lowest priority loads being disconnected first, until the genset load returns to an acceptable amount which would result in the genset control returning the frequency to 60 Hz and 120 volts. For very low loads the frequency could also be increased, for example if the genset is only loaded at 50% the frequency could be set at 60.5 Hz and the voltage set to 125 volts.

[Para 205] Of course setting engine RPM and/or frequency accurately in response to load is useful in the preferred embodiment and the microprocessor 37 may operate to sense that RPM indirectly by monitoring the power frequency via 13 and sense voltage via its voltage circuit. In this fashion highly accurate settings may be established with any inaccuracies being sensed and removed or reduced via adjustment of the control provided to the engine via 90. It is noted that the use of frequency measurement circuit 90 and voltage sensing circuitry in 37 are provided by way of example and one of ordinary skill will know to practice the invention with many variations of circuitry and microprocessor types 37. For example separate voltage and frequency circuits may be utilized with their outputs coupled to 37, a combined voltage and frequency circuit may be utilized with its output coupled to 37, or for some microprocessors having analog input capabilities, e.g. one with an analog to digital converter, a low voltage version of 87 (e.g. the output of transformer 81 coupled via a resistor divider or otherwise) may be coupled to 37 as known in the art and any desired power parameter or combination thereof may be determined directly thereby.

[Para 206] It is preferred to accurately control engine RPM and many gensets already incorporate a frequency control circuit so that the driver 94 should be coupled to that frequency control instead of the engine control module or throttle. It is also possible to modify some frequency control circuits to accomplish a known relationship between power frequency and genset load without the use of the full circuitry of 25c. It is still further possible that the voltage regulator or other circuitry of the alternator which controls output voltage may be coupled to be controlled via 37 utilizing a driver circuit 94 or otherwise or that that control circuitry may be modified to provide a known relationship between output voltage and power without utilizing the full circuitry of 25c as will be known from the teachings herein. Further, both voltage and frequency control of a genset may be utilized to convey load information to load controls.

[Para 207] Whether there is a dedicated control of genset frequency or voltage in response to the load, or merely a simple engine speed or alternator control without any controlled response to load (e.g. via a circuit 25c), it is possible for the microprocessor of a load control 25c to operate to infer load conditions by measurement of one or more parameters of the output power. One or more of frequency, voltage, distortion and noise changes which take place as loads are connected and disconnected as previously described may be utilized. Performance of a genset generally decreases as it approaches overload and that decreased performance often results in measurable changes in one or more parameter such as frequency, voltage, distortion and noise which may be utilized to sense loading. As an example, when the genset is lightly loaded a refrigerator motor starting might cause the frequency to only dip .1 Hz for 3 seconds and when the genset is near maximum load the same motor starting would cause a .3 Hz dip for 3 seconds. The voltage might dip one volt if lightly loaded and 5 volts if near maximum. Distortion, such as sine wave distortion of the power might not increase at all if lightly loaded but jump to 5% if near maximum output and noise might increase by 10 Db.

[Para 208] More generally, for a particular genset the parameters such as frequency and/or voltage variations of the output power may be known to increase in size or duration as the genset approaches full load or enters overload conditions. By monitoring these parameter changes which take place with the somewhat random normal load changes during operation the microprocessor may estimate the amount of load. In particular by utilizing the aforementioned circuitry to perform current and voltage measurements combined with either a known connection of a load such as an air conditioner compressor or the somewhat random changes of normal operation it will be possible to estimate the total load on the genset. Such monitoring is particularly useful for controlling large loads where it is undesirable to allow those loads to impart large step loads to an already heavily loaded genset.

[Para 209] The above described feature of determining genset loading from output power parameters such as the frequency, voltage, distortion or noise resulting from a particular load change is particularly useful when multiple loads are controlled by a given load control circuit. In this fashion differing loads of differing priority may be controlled to optimize powering those loads without overloading the genset, according to information about the loads, genset, priorities and desired performance of the system as programmed in the load control operation time of manufacture, or manually or automatically at time of installation, or later via automated monitoring of power parameters or manually via the user display and input.

[Para 210] One example of an embodiment of the invention described above which will find particular usefulness in modern homes and businesses is the incorporation of the load control 25b and various communications links within, or combined with, a more extensive home control system in order to provide flexible backup power in the event of a power grid failure and to manage the cost of power consumed by the loads. It is preferred that the a home control system (or part of the system) will automatically manage the operation of the

home as is well known in the home control industry, e.g. to set temperatures, provide home operating modes such as away and occupied, operate lighting and entertainment appliances, operate door locks and control access to the home, monitor the home for failures and intrusions, all of which may be performed automatically or as commanded or programmed directly or remotely by the home owner. U.S. Patent 7,379,778 describes one such home control system. Of particular advantage in such a combination is the relative ease of adjusting load priorities. For example if the home control is programmed for unoccupied operation various loads such as hot water heaters, air conditioners, ovens and other devices which are primarily used for comfort of the occupants can be assigned low priorities.

[Para 211] Additionally the present invention is desired to be incorporated in or otherwise combined with the home (or business) control system to include not only control of power consumption during times of limited available power or failure, such as when the grid power goes into brownout or fails, but also to facilitate reduced waste and lowered cost. Additionally the incorporation in a home control system allows the invention to respond directly or remotely via telephone, internet or other communications link(s) as described herein to provide the home (or business) owner with information about the home, including grid, generator and load operations and to additionally respond to desired priorities for powering devices and otherwise operating the home (or business). In particular as explained above several types of power sources generate excess heat in their operation, which excess heat may be utilized under control of load control 25b to provide heating, e.g. water heating or radiant heating as requested by the automation system.

[Para 212] Exemplary Small Backup Power System Embodiment

[Para 213] An embodiment of the invention as used with small backup power systems, which is believed to achieve a commercially desirable tradeoff of performance and cost is given by way of example. This embodiment is described with respect to Figure 8 as used in

a home and is explained in more detail below and may operate to prevent overloading of one or more of the power sources 12, 13 and 50 and in particular may be utilized to allow the use of distribution panels having amperage ratings higher than the service or backup power source rating. The explanations below may depart from the more general explanations given above under the description of the preferred embodiment in specific areas.

[Para 214] This small backup power systems utilizes a backup generator which is only capable of providing power for part of the maximum possible load which can be connected when the power grid fails and the total load must be controlled to prevent an overload. With some prior art systems such as that of Figure 2 this limit is hard wired, that is, only certain higher priority loads are connected to the backup generator and those lower priority loads which are not connected simply go without power. In other prior art systems such as that of Figure 3 certain lower priority loads are connected but are all immediately disconnected if the frequency of the AC power from the generator drops as a result of an overload. Those disconnected loads are then reconnected after a time delay without regard to whether the generator will be able to power it and thus a high probability that another overload may be created.

[Para 215] Neither of these systems is capable of a high degree of utilization of the power available from the generator with high overload immunity, in the first low priority loads are never powered and the generator may run well below its load capability and in the second a low priority load may be powered part of the time but when it is disconnected after an overload it will not be reconnected until after a time delay which is unrelated to the generator's ability to power that load at that later time, i.e. it is blindly reconnected which may result in an instant overload and possible damage or circuit breaker tripping. In addition when utilizing prior art gensets (i.e. those which do not have an active control of

frequency in response to loading) and relying on power frequency as a measure of overload the detection of overloads has less that desired reliability in many cases.

[Para 216] Recognizing the above faults, this embodiment of Figure 8 controls the total load presented to the generator 13 to connect some or all loads 16–19 & 48 according to a priority, which priority may be changed manually or automatically. In particular the load control 25b is programmed with parameters pertaining to the power sources and loads, which parameters are necessary to achieve the desired mode(s) of operation of the system. For example 25b is preferred to be programmed with the maximum current output of the solar panel 50 (if utilized), the maximum current output of the generator 13, the current output for optimum efficiency of the generator 13 and the current drawn (e.g. load) by each load which 25b is capable of controlling (e.g. connecting). A group of high priority loads 19 such as selected lights, home controls, alarms, food storage appliances and the like which are desired to be powered whether the home is occupied or not are always connected and receive power from the transfer switch 47 upon loss of grid power, it being preferred that these high priority loads are selected to ensure that they are not capable of overloading the generator at their maximum current demand.

[Para 217] When operating with the solar panel 50 (if provided) and/or generator 13 it is preferred that load control 25b operate a) to prevent overloading the generator 13 or solar panel 50 by preventing or limiting the connection of loads which would cause an overload, b) to immediately cure an overload by promptly disconnecting or limiting one or more connected load, c) to maximize efficiency of solar panel 50 and/or generator 13 by allowing operation of loads which the generator and/or solar panel are capable of powering when they are operating below their optimum capability, d) to alert the home owner that power is not available to power one or more particular device(s) which the home owner may wish to operate and e) allow the home owner to decide what to turn off (or limit or leave off) in order to prevent having a device (and possibly several others) turned off shortly after the

desired device turned on due to an overload. Selected loads that may but do not need to be connected are preferred to be connected when the generator and/or solar panel is operating below its optimum capacity or efficiency in order to provide operation closer to that optimum. These operations are performed by the load control 25b in response to the loads currently connected to the solar panel 50 and generator 13 as measured via current sense devices 23a and 23c and the herein described stored parameters for the generator and solar panel, as well as stored parameters for loads which can be connected or otherwise controlled by 25b.

[Para 218] When the generator is operating well below optimum, either during exercising or during outages, an increase in the efficiency of the operation is achieved by connecting lower priority loads such as battery chargers, water heaters, heat and air conditioning units. Accordingly, different modes of operation may be assigned to the backup system by the user via 21 or otherwise, with the user selecting priority of connection of the loads and the system automatically connecting and disconnecting loads to best achieve the priority based modes of operation under control of load control 25b operating in conjunction with the other elements of the load control system shown in Fig. 8.

[Para 219] Importantly, the priority of one or more load(s) is preferred to be changed automatically, or by the user if needed with the changed priority being permanently stored, at least until it is updated, for an amount of time selected by the user, or for other conditions selected by the user. For example to cook a meal which has already been started when the grid power goes off. The load priority for the oven may be changed automatically by 25b recognizing that the oven was in use when power failure occurred, with the priority of the oven being returned to its previous value when the cooking ends as sensed by the current being drawn by the oven or otherwise. Alternatively, if the priority is not automatically changed by 25b the user may assign a higher priority to the oven for a time period such as an hour to allow completion of the cooking, or in response to the condition

of the oven no longer utilizing a large current for 15 minutes indicating the cooking is completed. Thermal sensors may also be utilized to provide oven temperature to 25b as part of the miscellaneous devices 21, which temperature may be utilized to set priority.

[Para 220] Priorities may be automatically changed, temporarily, permanently or repeatedly in response to environmental or other conditions via 21 or otherwise. For example some lights are more important at night than in the daytime and heating is more important when it is cold outside than when it is hot, but this importance is tempered by whether or not anybody is home and thus priorities for such items are preferred to be set at a first value when the home is not occupied and/or during daylight hours and a second value when the home is occupied and/or during night hours. As another example a temperature sensor may be provided for a food storage appliance such as a freezer, refrigerator or wine cooler as part of 21 and if the temperature should approach a dangerous level (high or low) that food storage appliance can be made a high priority until a safer temperature is reached. If the problem of the food appliance approaching a dangerous temperature occurs often during power loss events its priority may be automatically changed to a higher priority by 25b whereas the priority may be automatically lowered if the problem infrequently or never occurs. Such automatic changes will serve to adjust operation to a more optimum condition.

[Para 221] Decisions can also be aimed at efficiency. One substantial consideration which can be utilized is the cost of providing power from the grid vs. cost from the generator, for example for a homeowner having one or more electric vehicle. If power can be obtained from the electric utility or elsewhere at lower cost during certain times, for example during the night, the load control can be utilized to control loads in a manner to best take advantage of the lower cost power. Load control 25b may receive the cost of grid power at various times and the cost of generator fuel (e.g. natural gas) automatically via the internet or otherwise and calculate the best time to charge the vehicle's batteries from the grid or

alternatively from the generator even though grid power is available, depending on the cost. The load control 25b may also take into account the need to exercise the generator and delay battery charging until an upcoming scheduled exercise, advance the exercise time once to charge the battery or change the exercise time schedule to accommodate the home owner's changing vehicle usage.

[Para 222] The load control is preferred to utilize intelligent timing for connecting and disconnecting loads to one or more power sources in order that the total load on any one power source is kept at or below the maximum output capability of that source, or alternatively at or near an optimum efficiency level, which may be at or below the maximum output capability. It is preferred that at all times the home owner has the opportunity to interact with the load control processor in order to facilitate any out of the ordinary power needs the home owner may desire or require and which are not automatically provided for by the load control. For example the home owner may choose to turn off an air conditioner or vehicle charger for 30 minutes in order to allow normally low priority clothes dryer to be used. As another example the home owner may want to limit the current supplied to an oven (causing the heating element to be on for longer periods of time) to allow an air conditioner to be used.

[Para 223] More generally, the present invention described herein may also be utilized to communicate with a power utility to allow that utility to manage power consumption, for example to cause partial or total removal of loads from the power grid as the utility deems desirable or necessary during times of high power consumption, lack of grid capacity or grid failure. The power company may notify the load control of possible or scheduled events pertaining to the supply of power from the grid, e.g. poor power quality (i.e. power not meeting specifications set by for example the utility, the home owner or a regulatory agency) or rolling blackouts. The load control will then cooperate with the utility to accomplish the desired degree of power consumed from the grid.

[Para 224] It may be desired that the utility company may interact with the load control to negotiate sending power to the grid from one or more power sources or loads e.g. during times of peak load. For example the power company could request that the load manager send power from the power sources 13, or 50 or from the battery 68 via inverter 67 (Figure 11) or the like into the grid. The load manager may be configured to negotiate pricing with the electric utility for the power which it wishes to be delivered. In such negotiations the load manager is preferred to take into account the cost of power available from various sources which are available to it to transfer power back to the grid.

[Para 225] The several simplifications and operational related examples and exemplary descriptions used herein in conjunction with the descriptions of the prior art and the teachings of the preferred embodiment of the invention are not to be considered limiting of the inventive concepts which are herein disclosed. Although this invention has been described in its preferred embodiment with a certain degree of particularity, it is understood that the invention is not so limited and the present disclosure of the preferred embodiment with its various benefits, features and capabilities has been made by way of example and numerous changes in the details of construction and the combination and arrangement of parts may be resorted to in order to meet a particular level of performance, reliability and cost without departing from the spirit and the scope of the invention as hereinafter claimed.

Claims

Claim 1. An electric power source with load related output power frequency control, the power source comprising:

- a) a power source which provides output A.C. power having a known frequency which is controlled in response to a frequency control signal, the power source comprising one or both of an alternator or inverter circuit and at least one maximum output power parameter;
- b) a power sensing circuit which provides an output power signal which representative of the timely amount of A.C. power being output from the power source;
- c) a processor circuit comprising an input responsive to the output power signal, a timebase circuit and operating to provide the frequency control signal, the processor thereby operating to control the frequency of the output A.C. power to be a known standard first frequency when the output A.C. power is less than the maximum output power parameter and a known second frequency when the power source is overloaded.

Claim 2. The power source as claimed in claim 1 wherein the processor circuit operates to control the frequency of the output A.C. power to be a known frequency different than the known standard frequency corresponding to a first known remaining amount of power which can be taken from the power source to power a load without causing an overload.

Claim 3. The power source as claimed in claim 1 wherein the processor circuit operates to control the frequency of the output A.C. power to be a known third frequency corresponding to a first known amount of power which is being taken from the power source and a different fourth frequency corresponding to a second known amount of power which is being taken from the power source.

Claim 4. The power source as claimed in claim 1 wherein the processor circuit operates to control the frequency of the output A.C. power to be a known third frequency corresponding to a first known remaining amount of power which can be taken from the power source without causing an overload and a different fourth frequency corresponding to a second known remaining amount of power which can be taken from the power source without causing an overload.

Claim 5. A load coupler device operating to control the connection of one or more loads to a power source to relieve an overload of the power source, the load coupler device comprising:

- a) an enclosure within which a load switch and a load control circuit are physically located;
- b) the load switch comprising at least one control connection for electrically opening and closing the load switch, at least one A.C. power line connection, and at least one A.C. power load connection via which line connected A.C. power may be supplied to a corresponding load when the load switch is closed;
- c) the load control circuit additionally comprising a power supply responsive to the A.C. power to provide power to a processor circuit;
- d) the load control circuit further comprising a user input configured to provide information from a user to the processor circuit and a user output configured to provide information to a user from the processor circuit;
- e) the processor circuit operating to timely sense one or more parameter, including the frequency, of the A.C. power and executing a program whereby in response to the frequency of the A.C. power, the processor performs a load shed by causing the load switch to open, thereby relieving an overload of the power source.

Claim 6. The load coupler device of claim 5 wherein the processor circuit is responsive to the amount of overload as represented by the frequency of the A.C. power, as well as the time that amount of overload has existed, to open the load switch.

Claim 7. The load coupler device of claim 5 wherein the processor circuit determines when to cause a load shed in response to the amount of an overload as represented by the frequency of the A.C. power and the time duration of the overload with the load shed occurring faster for relatively large overloads as compared to other, relatively small overloads.

Claim 8. The load coupler device of claim 5 wherein the load coupler determines beforehand in response to the frequency of the A.C. power, if the corresponding load can be connected to the power source without an overload.

Claim 9. The load coupler device of claim 5 wherein the processor circuit is programmed to operate in response to the frequency of the A.C. electric power being output from the power source, which frequency represents the remaining amount of power which can be output from the power source without creating an overload, to determine if the load can be connected without creating an overload.

Claim 10. The load coupler device of claim 5 wherein the priority of the first load can be assigned to the load coupler via the user input circuit.

Claim 11. A load control device operating to control the connection of one or more loads to a power source to prevent or relieve an overload of the power source, the load control device comprising:

- a) a contactor comprising one or more each of; a control connection via which the contactor can be opened and closed, a line connection rated to connect A.C. Power from a power source, and a load connection rated to connect a corresponding load and thereby supply the load with A.C. power when the contactor is closed;
- b) a load control circuit comprising a power supply having an input connected to the line connection of the contactor to thereby receive the A.C. electric power, the power supply providing power to power a processor circuit;
- c) the load control circuit additionally comprising a user input and a user output, both communicating with the processor circuit;
- d) the processor circuit comprising a timebase circuit and executing a program to timely sense the A.C. electric power at the contractor line connection and in response to the timebase circuit monitor the frequency of the sensed A.C. electric power, the processor further operating in response to a frequency drop of a known amount for a known amount of time to cause a load shed by opening the contactor to relieve an overload or causing the contactor to remain open to prevent a possible overload or additional overload of the power source;
- e) the processor, following the load shed by a known time period, closes the contactor to resupply power to the load, the known time period being responsive to the configuration of the load coupler.

Claim 12. The load control device of claim 11 wherein the load control circuit and the contactor are physically adjacent to one another, both of which are contained in a U.L. approved plastic electronic enclosure.

Claim 13. The load control device of claim 11 wherein when the frequency of the A.C. electric power received at the contactor line connection is controlled to drop by at least one known

amount, the processor control operates in response to the frequency drop to determine the presence of an overload.

Claim 14. The load control device of claim 11 wherein the priority of the load can be assigned to the load coupler via the user input circuit by the installer at the time of installation of the load control device.

Claim 15. The load control device of claim 11 wherein the priority of the first load and the amount of power the first load draws, can be stored in the load control via the user input circuit by the installer at the time of installation of the load control device.

Claim 16. The load control device of claim 14 wherein when the power received at the contactor line connection is controlled by a power source to have a frequency corresponding to an amount of remaining available output A.C. electric power, the processor operates to prevent closing the contactor when the load would draw more power from the power source than the power source has available.

Claim 17. The load control device of claim 11 wherein the processor circuit determines when to cause a load shed in response to the amount of an overload and the time duration of the overload with the load shed occurring faster for large overloads as compared to small overloads.

Claim 18. A load module device operating to control the coupling of a load to an electric power source to relieve an overload of the power source, the load module comprising:

- a) a load switch and/or load limit having a control connection via which the power supplied to a load is controlled, a plurality of power connections for A.C. power including one connection suitable for connecting to A.C. power received from a power source, and another connection suitable for supplying the A.C. power to a load when controlled via the control connection;

- b) a load control circuit comprising a power supply, the input connected to the A.C. power and the output to provide operating power to a processor circuit;
- c) the processor circuit executing a program and operating in response to a timebase circuit to timely monitor the A.C. power frequency, the processor further operating to cause full power to be provided to the load when the A.C. power frequency is substantially a standard frequency, and to remove or reduce power provided to the load when: the A.C. power frequency deviates from the standard frequency to a known first frequency, corresponding to a first amount of overload, for a first time period; or when the frequency deviates from the standard frequency by a larger amount to a different known second frequency, corresponding to a second amount of overload, for a second time period.

Claim 19. The load module of claim 18 wherein the load control circuit additionally comprises user input and user output circuits which are coupled to the processor circuit, with a load priority being established via the user input, and after removing all power from the load in response to an overload, the processor circuit operates a known amount of time later to restore power to the load, the known amount of time being set by the priority of the load.

Claim 20. The load module of claim 18 wherein the load control circuit additionally comprises user input and user output circuits which are coupled to the processor circuit, with a load priority being established via the user input, and after removing all power from the load in response to an overload, the processor circuit operates a known amount of time later to restore power to the load if the A.C. power is the standard frequency.

Claim 21. The load module of claim 18 wherein the load control circuit additionally comprises user input and user output circuits which are coupled to the processor circuit, with a load priority being established via the user input, and after removing all power from the load in response to an overload, the processor circuit operates a known amount of time later to determine if the A.C.

power frequency indicates that there is sufficient remaining available power from the power source to power the load without creating an overload, and if so then providing full power to the load.

Claim 22. The load module of claim 18 wherein the load control circuit and load switch and/or load limit are mechanically configured to be physically located next to each other, and are contained in a U.L. approved plastic electronic enclosure.

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

Application Data Sheet 37 CFR 1.76		Attorney Docket Number	JCC_5-12_Div_2020
		Application Number	
Title of Invention	Power Source Load Control		
The application data sheet is part of the provisional or nonprovisional application for which it is being submitted. The following form contains the bibliographic data arranged in a format specified by the United States Patent and Trademark Office as outlined in 37 CFR 1.76. This document may be completed electronically and submitted to the Office in electronic format using the Electronic Filing System (EFS) or the document may be printed and included in a paper filed application.			

Secrecy Order 37 CFR 5.2

☐ Portions or all of the application associated with this Application Data Sheet may fall under a Secrecy Order pursuant to 37 CFR 5.2 (Paper filers only. Applications that fall under Secrecy Order may not be filed electronically.)

Applicant Information:

Applicant 1		Remove	
Applicant Authority • Inventor		Legal Representative under 35 U.S.C. 117	Party of Interest under 35 U.S.C. 118
Prefix	Given Name	Middle Name	Family Name
Mr. ▾	J.	Carl	Cooper ▾
Residence Information (Select One) • US Residency Non US Residency Active US Military Service			
City	Reno	State/Province	NV
Country of Residence	US		
Citizenship under 37 CFR 1.41(b)	US		
Mailing Address of Applicant:			
Address 1	2730 Tobiano Drive		
Address 2			
City	Reno	State/Province	NV
Postal Code	89521	Country	US
All Inventors Must Be Listed - Additional Inventor Information blocks may be generated within this form by selecting the Add button.			
Add			

Correspondence Information:

Enter either Customer Number or complete the Correspondence Information section below.
For further information see 37 CFR 1.33(a).

☐ An Address is being provided for the correspondence Information of this application.

Customer Number	57131		
Email Address	videoengr@sbcglobal.net	Add Email	Remove Email
Email Address	videoengr@sbcglobal.net	Add Email	Remove Email

Application Data Sheet 37 CFR 1.76		Attorney Docket Number	JCC_5-12_Div_2020
		Application Number	
Title of Invention	Power Source Load Control		

Application Information:

Title of the Invention	Power Source Load Control		
Attorney Docket Number	JCC_5-12_Div_2020	Small Entity Status Claimed	☒
Application Type	Nonprovisional		
Subject Matter	Utility		
Suggested Class (if any)		Sub Class (if any)	
Suggested Technology Center (if any)			
Total Number of Drawing Sheets (if any)	9	Suggested Figure for Publication (if any)	8

Publication Information:

☐	Request Early Publication (Fee required at time of Request 37 CFR 1.219)
☒	Request Not to Publish. I hereby request that the attached application not be published under 35 U.S.C. 122(b) and certify that the invention disclosed in the attached application has not and will not be the subject of an application filed in another country, or under a multilateral international agreement, that requires publication at eighteen months after filing.

Representative Information:

Representative information should be provided for all practitioners having a power of attorney in the application. Providing this information in the Application Data Sheet does not constitute a power of attorney in the application (see 37 CFR 1.32). Enter either Customer Number or complete the Representative Name section below. If both sections are completed the Customer Number will be used for the Representative Information during processing.			
Please Select One:	☒ Customer Number	☐ US Patent Practitioner	☐ Limited Recognition (37 CFR 11.9)
Customer Number	57131		

Domestic Benefit/National Stage Information:

This section allows for the applicant to either claim benefit under 35 U.S.C. 119(e), 120, 121, or 365(c) or indicate National Stage entry from a PCT application. Providing this information in the application data sheet constitutes the specific reference required by 35 U.S.C. 119(e) or 120, and 37 CFR 1.78(a)(2) or CFR 1.78(a)(4), and need not otherwise be made part of the specification.			
Prior Application Status	Pending	Remove	
Application Number	Continuity Type	Prior Application Number	Filing Date (YYYY-MM-DD)
	Division of	13481804	2012-05-26
Prior Application Status	Expired	Remove	
Application Number	Continuity Type	Prior Application Number	Filing Date (YYYY-MM-DD)
13481804	non provisional of	61490253	2011-05-26
Prior Application Status	Expired	Remove	

Application Data Sheet 37 CFR 1.76		Attorney Docket Number	JCC_5-12_Div_2020
		Application Number	
Title of Invention	Power Source Load Control		

Application Number	Continuity Type	Prior Application Number	Filing Date (YYYY-MM-DD)
13481804	non provisional of	61552722	2011-10-28
Prior Application Status	Expired	Remove	
Application Number	Continuity Type	Prior Application Number	Filing Date (YYYY-MM-DD)
13481804	non provisional of	61598564	2012-02-14
Prior Application Status	Expired	Remove	
Application Number	Continuity Type	Prior Application Number	Filing Date (YYYY-MM-DD)
13481804	non provisional of	61624360	2012-04-15
Additional Domestic Benefit/National Stage Data may be generated within this form by selecting the Add button. Add			

Foreign Priority Information:

This section allows for the applicant to claim benefit of foreign priority and to identify any prior foreign application for which priority is not claimed. Providing this information in the application data sheet constitutes the claim for priority as required by 35 U.S.C. 119(b) and 37 CFR 1.55(a).			
Remove			
Application Number	Country ¹	Parent Filing Date (YYYY-MM-DD)	Priority Claimed
			Yes No
Additional Foreign Priority Data may be generated within this form by selecting the Add button. Add			

Assignee Information:

Providing this information in the application data sheet does not substitute for compliance with any requirement of part 3 of Title 37 of the CFR to have an assignment recorded in the Office.				
Assignee 1 Remove				
If the Assignee is an Organization check here. ☐				
Prefix	Given Name	Middle Name	Family Name	Suffix
Mailing Address Information:				
Address 1				
Address 2				
City		State/Province		
Country		Postal Code		
Phone Number		Fax Number		
Email Address				
Additional Assignee Data may be generated within this form by selecting the Add button. Add				

Signature:

A signature of the applicant or representative is required in accordance with 37 CFR 1.33 and 10.18. Please see 37 CFR 1.4(d) for the form of the signature.

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

Application Data Sheet 37 CFR 1.76		Attorney Docket Number		JCC_5-12_Div_2020		
		Application Number				
Title of Invention		Power Source Load Control				
Signature		/J. Carl Cooper/			Date (YYYY-MM-DD)	2020-11-18
First Name	J. Carl	Last Name	Cooper	Registration Number	34568	

This collection of information is required by 37 CFR 1.76. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 23 minutes to complete, including gathering, preparing, and submitting the completed application data sheet form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. **SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.**

Privacy Act Statement

The Privacy Act of 1974 (P.L. 93-579) requires that you be given certain information in connection with your submission of the attached form related to a patent application or patent. Accordingly, pursuant to the requirements of the Act, please be advised that: (1) the general authority for the collection of this information is 35 U.S.C. 2(b)(2); (2) furnishing of the information solicited is voluntary; and (3) the principal purpose for which the information is used by the U.S. Patent and Trademark Office is to process and/or examine your submission related to a patent application or patent. If you do not furnish the requested information, the U.S. Patent and Trademark Office may not be able to process and/or examine your submission, which may result in termination of proceedings or abandonment of the application or expiration of the patent.

The information provided by you in this form will be subject to the following routine uses:

1. The information on this form will be treated confidentially to the extent allowed under the Freedom of Information Act (5 U.S.C. 552) and the Privacy Act (5 U.S.C. 552a). Records from this system of records may be disclosed to the Department of Justice to determine whether the Freedom of Information Act requires disclosure of these records.
2. A record from this system of records may be disclosed, as a routine use, in the course of presenting evidence to a court, magistrate, or administrative tribunal, including disclosures to opposing counsel in the course of settlement negotiations.
3. A record in this system of records may be disclosed, as a routine use, to a Member of Congress submitting a request involving an individual, to whom the record pertains, when the individual has requested assistance from the Member with respect to the subject matter of the record.
4. A record in this system of records may be disclosed, as a routine use, to a contractor of the Agency having need for the information in order to perform a contract. Recipients of information shall be required to comply with the requirements of the Privacy Act of 1974, as amended, pursuant to 5 U.S.C. 552a(m).
5. A record related to an International Application filed under the Patent Cooperation Treaty in this system of records may be disclosed, as a routine use, to the International Bureau of the World Intellectual Property Organization, pursuant to the Patent Cooperation Treaty.
6. A record in this system of records may be disclosed, as a routine use, to another federal agency for purposes of National Security review (35 U.S.C. 181) and for review pursuant to the Atomic Energy Act (42 U.S.C. 218(c)).
7. A record from this system of records may be disclosed, as a routine use, to the Administrator, General Services, or his/her designee, during an inspection of records conducted by GSA as part of that agency's responsibility to recommend improvements in records management practices and programs, under authority of 44 U.S.C. 2904 and 2906. Such disclosure shall be made in accordance with the GSA regulations governing inspection of records for this purpose, and any other relevant (i.e., GSA or Commerce) directive. Such disclosure shall not be used to make determinations about individuals.
8. A record from this system of records may be disclosed, as a routine use, to the public after either publication of the application pursuant to 35 U.S.C. 122(b) or issuance of a patent pursuant to 35 U.S.C. 151. Further, a record may be disclosed, subject to the limitations of 37 CFR 1.14, as a routine use, to the public if the record was filed in an application which became abandoned or in which the proceedings were terminated and which application is referenced by either a published application, an application open to public inspections or an issued patent.
9. A record from this system of records may be disclosed, as a routine use, to a Federal, State, or local law enforcement agency, if the USPTO becomes aware of a violation or potential violation of law or regulation.

Electronic Patent Application Fee Transmittal				
Application Number:				
Filing Date:				
Title of Invention:		Power Source Load Control		
First Named Inventor/Applicant Name:		J. Carl Cooper		
Filer:		J. Carl Cooper		
Attorney Docket Number:		JCC_5-12_Div_2020		
Filed as Small Entity				
Filing Fees for Utility under 35 USC 111(a)				
Description	Fee Code	Quantity	Amount	Sub-Total in USD(\$)
Basic Filing:				
UTILITY FILING FEE (ELECTRONIC FILING)	4011	1	80	80
UTILITY SEARCH FEE	2111	1	350	350
UTILITY EXAMINATION FEE	2311	1	400	400
Pages:				
Claims:				
CLAIMS IN EXCESS OF 20	2202	2	50	100
Miscellaneous-Filing:				
Petition:				

Description	Fee Code	Quantity	Amount	Sub-Total in USD(\$)
Patent-Appeals-and-Interference:				
Post-Allowance-and-Post-Issuance:				
Extension-of-Time:				
Miscellaneous:				
Total in USD (\$)				930

Electronic Acknowledgement Receipt	
EFS ID:	41163880
Application Number:	16952007
International Application Number:	
Confirmation Number:	3658
Title of Invention:	Power Source Load Control
First Named Inventor/Applicant Name:	J. Carl Cooper
Customer Number:	57131
Filer:	J. Carl Cooper
Filer Authorized By:	
Attorney Docket Number:	JCC_5-12_Div_2020
Receipt Date:	18-NOV-2020
Filing Date:	
Time Stamp:	20:54:19
Application Type:	Utility under 35 USC 111(a)

Payment information:

Submitted with Payment	yes
Payment Type	DA
Payment was successfully received in RAM	\$930
RAM confirmation Number	E2020AHK55121338
Deposit Account	505365
Authorized User	Carl Cooper
The Director of the USPTO is hereby authorized to charge indicated fees and credit any overpayment as follows: 37 CFR 1.21 (Miscellaneous fees and charges)	

File Listing:					
Document Number	Document Description	File Name	File Size(Bytes)/ Message Digest	Multi Part /.zip	Pages (if appl.)
1	Oath or Declaration filed	aia0001_oath.pdf	176402	no	2
			91b210b107b427ef8f1ae9fc48da3e81a7fca36e		
Warnings:					
Information:					
2	Drawings-only black and white line drawings	Figs_1-18_as-filed.pdf	1747155	no	9
			c8e2630f99e24963deb9c621ddf3c54792466166		
Warnings:					
Information:					
3	Abstract	JCC_5-12_Div_2020_ABSTRACT_as_filed.pdf	15836	no	1
			4e1e20827a30e0170b19e3b34b3cc3720b6e3485		
Warnings:					
Information:					
4	Specification	JCC_5-12_Div_2020_spec_as_filed.pdf	281424	no	108
			d0b3f7bd64c351edee4535790953a6f263ec0e1b		
Warnings:					
Information:					
5	Claims	JCCC_5-12_Div_2020_claims_as_filed.pdf	91442	no	7
			ebabde26280195c8f4bc5c9a4026c41f751f4038		
Warnings:					
Information:					
6	Application Data Sheet	sb0014_JCC_5-12_Div_2020.pdf	1595722	no	5
			0503ca47121af28c59db062cbcd873a55852c18		
Warnings:					
Information:					

7	Fee Worksheet (SB06)	fee-info.pdf	36617	no	2				
			d79d5a938efa1026d3e07a1abbf84c6e16be9a88						
Warnings:									
Information:									
Total Files Size (in bytes):			3944598						
This Acknowledgement Receipt evidences receipt on the noted date by the USPTO of the indicated documents, characterized by the applicant, and including page counts, where applicable. It serves as evidence of receipt similar to a Post Card, as described in MPEP 503. <u>New Applications Under 35 U.S.C. 111</u> If a new application is being filed and the application includes the necessary components for a filing date (see 37 CFR 1.53(b)-(d) and MPEP 506), a Filing Receipt (37 CFR 1.54) will be issued in due course and the date shown on this Acknowledgement Receipt will establish the filing date of the application. <u>National Stage of an International Application under 35 U.S.C. 371</u> If a timely submission to enter the national stage of an international application is compliant with the conditions of 35 U.S.C. 371 and other applicable requirements a Form PCT/DO/EO/903 indicating acceptance of the application as a national stage submission under 35 U.S.C. 371 will be issued in addition to the Filing Receipt, in due course. <u>New International Application Filed with the USPTO as a Receiving Office</u> If a new international application is being filed and the international application includes the necessary components for an international filing date (see PCT Article 11 and MPEP 1810), a Notification of the International Application Number and of the International Filing Date (Form PCT/RO/105) will be issued in due course, subject to prescriptions concerning national security, and the date shown on this Acknowledgement Receipt will establish the international filing date of the application.									